

Financial Management Department Purchasing Division 1112 Manatee Ave W Suite 803 Bradenton, FL 34205 Phone: (941) 749-3074

www.mymanatee.org

<u>Email</u> July 28, 2016

TO: All Interested Bidders

SUBJECT: Invitation for Bid #16-1928DC

Satellite Lift Station R&R 2015 Group 2

ADDENDUM #3

Bidders are hereby notified that this Addendum shall be acknowledged on the Bid Form and made a part of the above named bidding and contract documents.

1. Bid Form, electronic copy and hard copy revised to correct formula and delete entry from unit price.

If you have submitted a bid prior to receiving this addendum you may request <u>in writing</u> that your original, sealed bid be returned to your firm. All sealed bids received will be opened on the date stated.

Bids will be received at Manatee County Purchasing, 1112 Manatee Avenue West, Suite 803, Bradenton, Florida 34205 until **August 3, 2016 at 3:00 P.M.**

Sincerely,

Deborah Carey-Reed, CPPB

Contracts Specialist

/dcr

Attachment - Downloadable copy and Hard copy.

HORSESHOE COVE 1 - RTU 315 (5200 60th Street East - Bradenton)

Item No.	Line Item	U/M	Qty		Unit Price	Extended Price
1	Wetwell Cleaning	SF	380	\$	-	\$0.0
2	6" DR-11 HDPE Discharge Piping	LF	59	\$	-	\$0.0
3	BPIU.14 Base Ells	EA	2	\$	-	\$0.0
4	Base Ell Mounting Plate	EA	2	\$	-	\$0.0
5	S.S. Pipe Bracing - 6' Diameter	EA	2	\$	-	\$0.00
6	Raise existing Wetwell Rim	VF	0.30	\$	-	\$0.00
7	Replace existing Wetwell Top Slab	EA	1	\$	-	\$0.0
8	4" PVC Vent - Schedule 80	EA	1	\$	-	\$0.0
9	Aluminum Hatch Cover - 36" x 48" Single Door (Wetwell)	EA	1	\$	-	\$0.0
10	2" S.S. Pump Gide Rail System	LF	35	\$	-	\$0.0
11	Left Intentionally Blank					
12	Wetwell Liner - Spray-On	SF	351	\$	-	\$0.0
13	Grout Fill existing Drain - Abandon	EA	1	\$	-	\$0.0
14	6" Flanged Gate Valve	EA	3	\$	-	\$0.00
15	6" Flanged Swing Check Valve	EA	2	\$	-	\$0.0
16	6" Gate Valve - MJ	EA	1	\$	-	\$0.0
17	6" D.I. Flanged Pipe	LF	5	\$	-	\$0.0
18	6" PVC Pipe (C900)	LF	10	\$	-	\$0.0
19	Ductile Iron Fittings	LB	381	\$	-	\$0.0
20	6" D.I. Flanged Adapters	EA	1	\$	-	\$0.0
21	6" Male Aluminum Quick Coupler Adapter	EA	1	\$	-	\$0.0
22	S.S. Adjustable Valve Supports - Flange Attachment	EA	2	\$	-	\$0.0
23	Saw Cut Valve Vault Wall - Demo & Removal	EA	1	\$	- 1	\$0.0
24	Complete Removal of Valve Vault	EA	1	\$	-	\$0.0
25	Concrete Slab - Valve Assembly	EA	1	\$	-	\$0.0
26	8" Influent Line Plug	EA	1	\$	-	\$0.0
27	By-Pass Pumping	LS	1	\$	-	\$0.0
28	Relocate existing Backflow, Meter & Hose Bib Assembly	LS	1	\$	- 1	\$0.0
29	Remove & Replace Electric Meter Can	EA	1	\$	-	\$0.0
30	Left Intentionally Blank			Ė		
31	Left Intentionally Blank	TU U				
32	Remove & Replace Schedule 80 PVC Conduit	LF	30	\$	-	\$0.0
33	Left Intentionally Blank					
34	Remove & Replace Electrical Mounting Structure	EA	1	\$	-	\$0.0
35	Left Intentionally Blank			Ť		
36	Left Intentionally Blank					
37	Left Intentionally Blank					
38	Left Intentionally Blank					
39	Left Intentionally Blank					
40	Concrete Repair - 2" Thick	SF	95	\$	-	\$0.0
41	Left Intentionally Blank			Ť		40.0
42	Driveway, 6" Thick Reinforced Concrete	SY	42	\$	_	\$0.0
	Left Intentionally Blank	-		#		Ψ0.0
44	Left Intentionally Blank					
_	Mobilization	LS	1	\$		\$0.00
_	Miscellaneous Work and Cleanup	LS	1	\$		\$0.00
_	Record Drawings	LS	1	\$		\$0.00
-71		Lo	-	Ψ	-	\$0.00
48	Subtotal Construction Cost Contract Contingency (Used only with County Approval)	%	10			\$0.00

MANASOTA INDUSTRIAL PARK - RTU 318 (4414 18th Street East - Bradenton)

Item No. Line It	em	U/M	Qty		Unit Price	Extended Price
1 Wetwe	oll Cleaning	SF	476	\$	-	\$0.00
2 4" DR-	11 HDPE Discharge Piping	LF	66	\$	-	\$0.00
3 BPIU.1	4 Base Ells	EA	2	\$	-	\$0.00
4 Base B	Ell Mounting Plate	EA	2	\$	-	\$0.00
5 S.S. P	ipe Bracing - 6' Diameter	EA	3	\$	-	\$0.00
6 Raise	existing Wetwell Rim	VF	1.20	\$	-	\$0.00
7 Replac	e existing Wetwell Top Slab	EA	1	\$	-	\$0.00
8 4" PVC	Vent - Schedule 80	ΕA	1	\$	-	\$0.00
9 Alumin	um Hatch Cover - 36" x 48" Single Door (Wetwell)	EA	1	\$	-	\$0.00
10 2" S.S	Pump Gide Rail System	LF	45	\$	-	\$0.00
11 Left In	entionally Blank					
12 Wetwe	Il Liner - Spray-On	SF	447	\$	-	\$0.00
13 Grout	Fill existing Drain - Abandon	EA	1	\$	-	\$0.00
14 4" Flar	ged Gate Valve	EA	3	\$	-	\$0.00
15 4" Flar	ged Swing Check Valve	EA	2	\$	-	\$0.00
16 4" Gat	a Valve - MJ	EA	1	\$	-	\$0.00
17 4" D.I.	Flanged Pipe	LF	5	\$	_	\$0.00
_	C Pipe (C900)	LF	10	\$	-	\$0.00
_	Iron Fittings	LB	210	\$	-	\$0.00
	Flanged Adapters	EA	1	\$	_	\$0.00
	e Aluminum Quick Coupler Adapter	EA	1	\$	-	\$0.00
_	djustable Valve Supports - Flange Attachment	EA	2	\$	_	\$0.00
_	ut Valve Vault Wall - Demo & Removal	EA	1	\$	-	\$0.00
	rentionally Blank			Ť		4010
	ite Slab - Valve Assembly	EA	1	\$	_	\$0.00
_	uent Line Plug	EA	1	\$	_	\$0.00
	ss Pumping	LS	1	ļ s		\$0.00
	te existing Backflow, Meter & Hose Bib Assembly	LS	1	\$		\$0.00
	re & Replace Electric Meter Can	EA	1	\$		\$0.00
_	re & Replace Fused Safety Switch (Disconnect)	EA	1	\$		\$0.00
_	re & Replace Control Panel	EA	1	\$		\$0.00
	e & Replace Schedule 80 PVC Conduit	LF	30	\$		\$0.00
_	· · · · · · · · · · · · · · · · · · ·	LF	20	\$		
	e & Replace Electrical Service			H		\$0.00
	e & Replace Electrical Mounting Structure	EA	1	\$	-	\$0.00
_	entionally Blank	0)/	05	6		60.00
_	d Shell with Weed Barrier	SY	25	\$	-	\$0.00
— <u>I</u> —	Galvanized Fence	LF	36	\$	-	\$0.00
—— <u> </u>	Galvanized Fence Gate - Swing Type	EA	2	\$	-	\$0.00
	Galvanized Corner / Gate Post	EA	4	\$	-	\$0.00
	entionally Blank			_		
	entionally Blank					
_	entionally Blank			Н		
_	entionally Blank			^		4.5
	tenna concrete Base, Remove & Disponse	LS	1	\$	-	\$0.00
45 Mobiliz		LS	1	\$	-	\$0.00
_	aneous Work and Cleanup	LS	1	\$	-	\$0.00
	Drawings	LS	1	\$	-	\$0.00
_	tal Construction Cost					\$0.00
	ct Contingency (Used only with County Approval)	%	10			\$0.00
Total	for Manasota Industrial Park					\$0.00

SUGAR RIDGE - RTU 361 (3107 37th Terrace East - Samoset)

Item No.	Line Item	U/M	Qty		Unit Price	Extended Price
1	Wetwell Cleaning	SF	389	\$	-	\$0.00
2	4" DR-11 HDPE Discharge Piping	LF	54	\$	-	\$0.00
3	BPIU.14 Base Ells	EA	2	\$	- 1	\$0.00
4	Base Ell Mounting Plate	EA	2	\$	- 1	\$0.00
5	S.S. Pipe Bracing - 6' Diameter	EA	2	\$	- 1	\$0.00
6	Left Intentionally Blank					
7	Replace existing Wetwell Top Slab	EA	1	\$	- 1	\$0.00
8	4" PVC Vent - Schedule 80	EA	1	\$	- 1	\$0.00
9	Aluminum Hatch Cover - 36" x 48" Single Door (Wetwell)	EA	1	\$	-	\$0.00
10	2" S.S. Pump Gide Rail System	LF	36	\$	-	\$0.00
11	Remove existing Liner - Fiberglass	SF	360	\$	-	\$0.00
12	Wetwell Liner - Spray-On	SF	360	\$	-	\$0.00
13	Grout Fill existing Drain - Abandon	EA	1	\$		\$0.00
14	4" Flanged Gate Valve	EA	3	\$		\$0.00
15	4" Flanged Swing Check Valve	EA	2	\$	-	\$0.0
16	4" Gate Valve - MJ	EA	1	\$	- 1	\$0.0
17	4" D.I. Flanged Pipe	LF	5	\$	-	\$0.0
18	4" PVC Pipe (C900)	LF	10	\$	-	\$0.0
19	Ductile Iron Fittings	LB	280	\$	- 1	\$0.0
20	4" D.I. Flanged Adapters	EA	1	\$	-	\$0.0
21	4" Male Aluminum Quick Coupler Adapter	EA	5	\$	-	\$0.0
22	S.S. Adjustable Valve Supports - Flange Attachment	EA	2	\$	-	\$0.0
23	Saw Cut Valve Vault Wall - Demo & Removal	EA	1	\$	-	\$0.0
24	Left Intentionally Blank					
25	Concrete Slab - Valve Assembly	EA	1	\$	-	\$0.00
26	10" Influent Line Plug	EA	1	\$	-	\$0.0
27	By-Pass Pumping	LS	1	\$	- 1	\$0.0
28	Left Intentionally Blank				-	
29	Remove & Replace Electric Meter Can	EA	1	\$	-	\$0.00
30	Remove & Replace Fused Safety Switch (Disconnect)	EA	1	\$		\$0.00
31	Remove & Replace Control Panel	EA	1	\$	-	\$0.0
32	Remove & Replace Schedule 80 PVC Conduit	LF	40	\$	- 1	\$0.00
33	Left Intentionally Blank		Inchi.			
34	Remove & Replace Electrical Mounting Structure	EA	1	\$	-	\$0.00
35	Left Intentionally Blank					
36	Washed Shell with Weed Barrier	SY	82	\$		\$0.00
37	6' High Galvanized Fence	LF	97	\$	-	\$0.00
38	6' High Galvanized Fence Gate - Swing Type	EA	2	\$	-	\$0.00
39	6' High Galvanized Corner / Gate Post	EA	6	\$	-	\$0.00
40	Concrete Repair - 2" Thick	SF	195	\$	-	\$0.00
41	Left Intentionally Blank			Ť		75101
42	Driveway, 6" Thick Reinforced Concrete	SY	29	\$	-	\$0.00
43	Left Intentionally Blank		770	Ť		72101
44	Left Intentionally Blank					
45	Mobilization	LS	1	\$	-	\$0.00
46	Miscellaneous Work and Cleanup	LS	1	\$	- 1	\$0.00
47	Record Drawings	LS	1	\$	-	\$0.00
	Subtotal Construction Cost			Ť		\$0.00
48	Contract Contingency (Used only with County Approval)	%	10	-		\$0.00
	Total for Sugar Ridge	,,,	1.0			\$0.00

RED LOBSTER - RTU 407 (5715 14th Street West - U.S. 41)

1 Wetwell Cleaning 2 4" DR-11 HDPE Discharge Piping 3 BPIU.14 Base Ells 4 Base Ell Mounting Plate 5 S.S. Pipe Bracing - 5' Diameter	SF LF EA EA	196 36 2	\$	-	\$0.00
3 BPIU.14 Base Ells 4 Base Ell Mounting Plate 5 S.S. Pipe Bracing - 5' Diameter	EA EA		\$		
4 Base Ell Mounting Plate 5 S.S. Pipe Bracing - 5' Diameter	EA	2		-	\$0.00
5 S.S. Pipe Bracing - 5' Diameter			\$	-	\$0.00
	EA	2	\$	-	\$0.00
C I off Intentionally Disale		2	\$	-	\$0.00
6 Left Intentionally Blank			178		
7 Replace existing Wetwell Top Slab	EA	1	\$	-	\$0.00
8 4" PVC Vent - Schedule 80	EA	1	\$	-	\$0.00
9 Aluminum Hatch Cover - 30" x 48" Single Door (Wetwell)	EA	1	\$	-	\$0.00
10 2" S.S. Pump Gide Rail System	LF	20	\$	-	\$0.00
11 Left Intentionally Blank					
12 Wetwell Liner - Spray-On	SF	176	\$	-	\$0.00
13 Grout Fill existing Drain - Abandon	EA	1	\$	-	\$0.00
14 4" Flanged Gate Valve	ΕA	3	\$	-	\$0.00
15 4" Flanged Swing Check Valve	EA	2	\$	-	\$0.0
16 4" Gate Valve - MJ	EA	1	\$	-	\$0.0
17 4" D.I. Flanged Pipe	LF	5	\$	-	\$0.0
18 4" PVC Pipe (C900)	LF	10	\$	-	\$0.0
19 Ductile Iron Fittings	LB	210	\$	-	\$0.0
20 4" D.I. Flanged Adapters	EA	1	\$	-	\$0.0
21 4" Male Aluminum Quick Coupler Adapter	EA	1	\$	_	\$0.00
22 S.S. Adjustable Valve Supports - Flange Attachment	EA	2	\$	-	\$0.0
23 Left Intentionally Blank	4		Ť		
24 Complete Removal of Valve Vault	EA	1	\$	-	\$0.00
25 Concrete Slab - Valve Assembly	EA	1	\$	-	\$0.00
26 8" Influent Line Plug	EA	1	\$	-	\$0.00
27 By-Pass Pumping	LS	1	\$	_	\$0.0
28 Left Intentionally Blank		_	Ť		40.0
29 Remove & Replace Electric Meter Can	EA	1	\$		\$0.0
30 Remove & Replace Fused Safety Switch (Disconnect)	EA	1	\$		\$0.00
31 Remove & Replace Control Panel	EA	1	\$		\$0.00
32 Remove & Replace Schedule 80 PVC Conduit	LF	30	\$		\$0.00
33 Left Intentionally Blank			Ψ		Ψ0.00
34 Remove & Replace Electrical Mounting Structure	EA	1	\$	-	\$0.00
35 Left Intentionally Blank			<u> </u>		ψ0,00
36 Left Intentionally Blank		-		_	
37 Left Intentionally Blank			-		
38 Left Intentionally Blank					
39 Left Intentionally Blank					
40 Left Intentionally Blank					
	ΕA	2	\$		\$0.00
41 Phase Converter - Single Phase to 3 Phase 42 Driveway, 6" Thick Reinforced Concrete	EA SY	13	\$	-	\$0.00
42 Driveway, 6" Thick Reinforced Concrete 43 Left Intentionally Blank	οī	13	Φ	-	\$0.00
44 Left Intentionally Blank	10	4	o		60.00
45 Mobilization	LS	1	\$	-	\$0.00
46 Miscellaneous Work and Cleanup	LS	1	\$	-	\$0.00
47 Record Drawings	LS	1	\$		\$0.00
Subtotal Construction Cost	-	15	-		\$0.00
48 Contract Contingency (Used only with County Approval)	%	10			\$0.00
Total for Red Lobster					\$0.0

PALM LAKES ESTATES - RTU 414 (808 53rd Avenue East - Lot 26 - Bradenton)

Item No.	Line Item	U/M	Qty		Jnit rice	Extended Price
1	Left Intentionally Blank					
2	Left Intentionally Blank					
3	Left Intentionally Blank					De N
4	Left Intentionally Blank					
5	Left Intentionally Blank					
6	Left Intentionally Blank					
7	Left Intentionally Blank					
8	Left Intentionally Blank					
9	Left Intentionally Blank					
10	Left Intentionally Blank					
11	Left Intentionally Blank					
12	Liner, Spray-On - Converted Manhole	SF	114	\$	-	\$0.00
13	Left Intentionally Blank	i ba				
14	Left Intentionally Blank					
15	Left Intentionally Blank					
16	Left Intentionally Blank					
17	Left Intentionally Blank					
18	4" PVC Pipe (C900)	LF	10	\$	-	\$0.00
19	Ductile Iron Fittings - Downstream of Isolation Valve	LB	35	\$	-	\$0.00
20	Left Intentionally Blank					
21	Left Intentionally Blank					
22	Left Intentionally Blank					
23	Left Intentionally Blank					
24	Complete Removal of Valve Vault	EA	1	\$	-	\$0.00
25	Left Intentionally Blank					
26	8" Influent Line Plug	EA	3	\$	-	\$0.00
27	By-Pass Pumping	LS	1	\$	-	\$0.00
28	Relocate existing Meter, Backflow & Hose Bib Assembly	LS	1	\$	-	\$0.00
29	Remove & Replace Electric Meter Can	EA	1	\$	-	\$0.00
30	Remove & Replace Fused Safety Switch (Disconnect)	EA	1	\$	- 1	\$0.00
31	Remove & Replace Control Panel	EA	1	\$	- 1	\$0.00
32	Remove & Replace Schedule 80 PVC Conduit	LF	30	\$	-	\$0.00
33	Remove & Replace Electrical Service	LF	20	\$	-	\$0.00
34	Remove & Replace Electrical Mounting Structure	EA	1	\$	-	\$0.00
35	New 6' Diameter Wetwell & Above Ground Valve Assembly	LS	1	\$	- 1	\$0.00
36	Left Intentionally Blank			H		
37	Left Intentionally Blank					
38	Left Intentionally Blank					
39	Left Intentionally Blank		-			
40	Concrete Repair - 2" Thick	SF	50	\$	-	\$0.00
41	Left Intentionally Blank					
42	Driveway - 2" Thick Asphalt	SY	104	\$	- 1	\$0.00
43	Convert extisting Lift Station to Concentric Manhole	LS	1	\$	-	\$0.00
44	Left Intentionally Blank					Ψυ.υι
45	Mobilization	LS	1	\$	-	\$0.00
46	Miscellaneous Work and Cleanup	LS	1	\$	-	\$0.00
47	Record Drawings	LS	1	\$	-	\$0.00
41	Subtotal Construction Cost	2.0		Ψ	-	\$0.00
48	Contract Contingency (Used only with County Approval)	%	10			\$0.00
40	Total for Palm Lakes Estates	70	,0			\$0.00