IFB#15-0660-OV / Addendum #1 Whitfield Avenue, 16-Inch Water Main, Project No. 6040970

BID "A" Based on Completion time of 210 Calendar Days

ITEM	212 / 2000 01	7 3		of 210 Calendar Da	TOTAL BID
#	DESCRIPTION	U/M	QTY.	PER UNIT	PRICE
1	Mobilization & Demobilization	LS	1	\$	\$
2	Maintenance of Traffic	LS	11	\$	\$
3	Furnish & Install 16-inch Flex-Ring Ductile Iron Pipe and Fittings by Open Cut	LF	1,650	\$	\$
4	Furnish & Install 16-inch Flex-Ring Ductile Iron Pipe by HDD	LF	550	\$	\$
5	Furnish & Install 16-inch Gate Valve Assembly	EA	3	\$	\$
6	Furnish & Install Concrete Valve Vault	EA	1	\$	\$
7	Furnish & Install Ductile Iron Mechanical Joint Fittings and Restraints	TON	3	\$	\$
8	Furnish & Install Manual Air Release Valve Assembly	EA	1	\$	\$
9_	Furnish & Install Fire Hydrant Assembly	EA	1	\$	\$
10	Connect to Existing Water Main	EA	2	\$	\$
11	Furnish & Install Concrete Sidewalk	SY	600	\$	\$
12	Milling of Existing Asphalt (1-inch Average Thickness)	SY	1,600	\$	\$
13	Furnish & Install Superpave Asphaltic Concrete, SP 9.5	TON	900	\$	\$
14	Furnish & Install Settlement Monitoring Points	LS	1	\$	\$

Bidder:	
Authorized	
Signature:	Bid "A"

Bid Form - 2 Whitfield, 16-Inch Water Main (210 Calendar Days) Addendum #1

IFB#15-0660-OV / Addendum #1 Whitfield Avenue, 16-Inch Water Main, Project No. 6040970

BID "A" Based on Completion time of 210 Calendar Days

ITEM				BID PRICE	TOTAL BID
#	DESCRIPTION	U/M	QTY.	PER UNIT	PRICE
15	Unsuitable Material Removal	CY	100	\$	\$
16	Additional Select Fill Material	CY	100	\$	\$
17	Miscellaneous Concrete	CY	50	\$	\$
	TOTAL BASE BID				\$
40	CONTRACT CONTINGENCY (Used only with County Approval)	%	10		œ.
18	TOTAL CONTRACT AWARD (including Contract Contingency) - Whitfield Avenue, 16-Inch Water Main (Bid "A" Based On Completion				\$
	Time of 210 Calendar Days)				\$

Bidder:	
Authorized	
Signature:	Bid "A"

Bid Form - 3 Whitfield, 16-Inch Water Main (210 Calendar Days) Addendum #1

IFB#15-0660-OV / Addendum #1 Whitfield Avenue, 16-Inch Water Main, Project No. 6040970

BID "B" Based on Completion time of 270 Calendar Days

ITCM	DID B Based Oil	COIII	pietion time	e of <u>270 Calendar Da</u>	TOTAL BID
ITEM #	DESCRIPTION	U/M	QTY.	PER UNIT	PRICE
- т	DESCRIPTION				
_1	Mobilization & Demobilization	LS	1	\$	\$
2	Maintenance of Traffic	LS	11	\$	\$
3	Furnish & Install 16-inch Flex-Ring Ductile Iron Pipe and Fittings by Open Cut	LF	1,650	\$	\$
4	Furnish & Install 16-inch Flex-Ring Ductile Iron Pipe by HDD	LF	550	\$	\$
5	Furnish & Install 16-inch Gate Valve Assembly	EA	3	\$	\$
6	Furnish & Install Concrete Valve Vault	EA	_1	\$	\$
7	Furnish & Install Ductile Iron Mechanical Joint Fittings and Restraints	TON	3	\$	\$
8	Furnish & Install Manual Air Release Valve Assembly	EA	11	\$	\$
9	Furnish & Install Fire Hydrant Assembly	EA_	1	\$	\$
10	Connect to Existing Water Main	EA	2	\$	\$
11	Furnish & Install Concrete Sidewalk	SY	600	\$	\$
12	Milling of Existing Asphalt (1-inch Average Thickness)	SY	1,600	\$	\$
13_	Furnish & Install Superpave Asphaltic Concrete, SP 9.5	TON	900	\$	\$
14	Furnish & Install Settlement Monitoring Points	LS	11	\$	\$

Bidder:	
Authorized	
Signature:	Bid "B"

Bid Form - 4 Whitfield, 16-Inch Water Main (270 Calendar Days) Addendum #1

IFB#15-0660-OV / Addendum #1 Whitfield Avenue, 16-Inch Water Main, Project No. 6040970

BID "B" Based on Completion time of 270 Calendar Days

ITEM				BID PRICE	TOTAL BID
#	DESCRIPTION	U/M	QTY.	PER UNIT	PRICE
15	Unsuitable Material Removal	CY	100	\$	\$
16	Additional Select Fill Material	CY	100_	\$	\$
17	Miscellaneous Concrete	CY	50	\$	\$
	TOTAL BASE BID				\$
	CONTRACT CONTINGENCY				
	(Used only with County				
18	Approval)	%_	10		\$
	TOTAL CONTRACT AWARD (incl.				
	TOTAL CONTRACT AWARD (including Contract Contingency) - Whitfield Avenue, 16-Inch Water Main (Bid "B" Based On Completion				
	Time of 270 Calendar Days) (Add	\$			
	Time of all of control of the contro				

Bidder:	
Authorized	
Signature:	Bid "B"

Bid Form - 5 Whitfield, 16-Inch Water Main (270 Calendar Days) Addendum #1