



1112 Manatee Avenue West
Bradenton, FL 34205
purchasing@mymanatee.org

Solicitation Addendum

Addendum No.: 1
Solicitation No.: 22-TA004390LP
Project No.: 6108460
Solicitation Title: 75th ST W Rebase from Cortez RD to Bridge #134094
Addendum Date: November 30, 2022
Procurement Contact: Leslie Peer

IFBC No. 22-TA004390LP is amended as set forth herein. Responses to questions posed by prospective bidders are provided below. This Addendum is hereby incorporated in and made a part of IFBC No. 22-TA004390LP.

The deadline to submit all inquiries concerning interpretation, clarification or additional information pertaining to this IFBC was November 21, 2022.

REPLACE:

SECTION B, BID FORMS, APPENDIX K, BID PRICING FORM

Replace Appendix K Bid Pricing Form, with Appendix K Bid Pricing Form Revised issued with this Addendum 1 and available for download as a separate attachment.

SECTION C, BID ATTACHMENTS, BID ATTACHMENT 3, PROPOSED ROADWAY PLANS FOR 75TH ST W REBASE

Replace Bid Attachment 3 Proposed Roadway Plans for 75th St W Rebase issued with this Addendum 1 and available for download as a separate attachment.

QUESTIONS AND RESPONSES:

Q1. Why is there a 4000 SY difference between cold in place and milling? The plans seem to show that all areas getting milled are also getting cold in place. There is no differentiation.

- R1. There is 3933SF bridge deck area that does not need cold in place base. The quantity of cold in place base has been updated. Please see Appendix K, Bid Pricing Form Revised.
- Q2. Type S-3 Asphalt quantity also seems off. No additional areas are shown getting a 1” overlay. At 51015 SY and 110lbs/SY, there should only be about, 2805 tons.**
- R2. The asphalt quantities for both S-1 and S-3 have been adjusted. Please see Appendix K, Bid Pricing Form Revised.
- Q3. Please identify the lane closure restrictions for this project.**
- R3. Due to high traffic volumes, lane closures are ONLY permitted from 9 AM – 2 PM.
- Q4. Please expand on the extent of the bridge repairs. It is being assumed that the county will be doing the joint repair themselves.**
- R4. The bridge joint repair will be handled by Manatee County maintenance crew. Please coordinate with County before the construction.
- Q5. Pay item number 35 appears to be mislabeled. The pay item number coincides with FDOT pay item “PULL & SPLICE BOX, F&I, 13” x 24” COVER SIZE”, yet it is labeled as “Polymer Concrete Adjustment Ring” please confirm.**
- R5. Item 35 is for Pull & Splice Box, PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE. The label is a TYPO. Please see Appendix K, Bid Pricing Form Revised.
- Q6. Can you please provide a bid form in excel format for submission?**
- R6. Excel format of Appendix K Bid Pricing Form Revised (Fillable) is available for download as a separate attachment.
- Q7. Please expand on the County’s intent about “add 2 warning signs and striping” to the traffic separators. There is no requirement or standard for signs and markings on a traffic separator, so the contractor will need clarification on what the county wants.**
- R7. The intent is to hatch out the extra room left between the lane and the traffic separator and provide the warning sign at each end. See below picture as an example.



Q8. Please identify on the plans where the patterned textured pavement is to go.

R8. Pay Item 523-3 Patterned Pavement is in relation to the Green-Colored Pavement Markings for use in the bicycle lanes as identified on the plans as a grey colored hatch, shown adjacent to right-turn lanes and at intervals along the roadway. Length of patterned pavement to be determined from stationing shown on the plans.

Q9. Will bituminous liquid adjustment be applied to this project?

R9. No adjustment.

Q10. Please confirm if the side streets on this project will get milled and resurfaced?

R10. Limits will be as shown per plan.

Q11. Will we be required to provide a signed and sealed MOT plan for this project?

R11. If the FDOT standards are followed, no signed & sealed plan is required. If there is any deviation from those standards, then a signed & sealed plan is required.

Q12. The file “22-TA004390LP Bid Attachment 3 100% Plans – 75th St W – Cortez Rd – Bridge- 134094 – 8-31-22.pdf” is missing the utility adjustment sheet and details. Will you please provide these missing plan sheets?

R12. Revised Bid Attachment 3, Proposed Roadway Plans for 75th St W Rebase is available for download as a separate attachment.

NOTE:

Deleted items will be ~~struck through~~, added or modified items will be underlined. All other terms and conditions remain as stated in the IFBC.

INSTRUCTIONS:

Receipt of this Addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the response being deemed non-responsive.

END OF ADDENDUM

AUTHORIZED FOR RELEASE

APPENDIX K, BID PRICING FORM (REVISED)									
75TH ST WEST - REBASE									
COUNTY PROJECT NO. 6108460									
Bidders must provide prices for each available line item on each tab for their bid to be considered responsive.									
LINE NUMBER	FDOT ITEM NO.	DESCRIPTION	ESTIMATED QUANTITY	U/M	UNIT PRICE BID A 150 CALENDAR DAYS	EXTENDED PRICE BID A	UNIT PRICE BID B 240 CALENDAR DAYS	EXTENDED PRICE BID B	
MOBILIZATION & MAINTENANCE OF TRAFFIC									
1.	101-1	MOBILIZATION	1.00	LS					
2.	102-1	MAINTENANCE OF TRAFFIC	1.00	LS					
SUBTOTAL MOBILIZATION & MAINTENANCE OF TRAFFIC									
ROAD WORK									
3.	104-18	INLET PROTECTION SYSTEM	41.00	EA					
4.	MC-1	COLD-IN-PLACE RECYCLE 8" DEPTH	50,466.00	SY					
5.	327-70-6	MILLING EXIST ASPH PAVT. 1" TO 2" AVG DEPTH	51,015.00	SY					
6.	334-MC	TYPE S-I ASPHALT CONCRETE W/TACK COAT, 2"	5,599.00	TN					
7.	334-MC	TYPE S-III ASPHALT CONCRETE W/TACK COAT, 1"	2,800.00	TN					
8.	520-1-10	CONCRETE CURB & GUTTER, TYPE F (INCLUDING CONCRETE FLUMES)	40.00	LF					
9.	522-1	CONCRETE SIDEWALK, 4" THICK (INCLUDING HANDICAP RAMPS)	342.00	SY					
10.	522-2	CONCRETE DRIVEWAYS, 6" THICK	149.00	SY					
11.	527-2	DETECTABLE WARNINGS	360.00	SY					
SUBTOTAL ROAD WORK									
SIGNING AND PAVEMENT MARKINGS									
12.	0523-3	PATTERNED PAVEMENT	585.00	SY					
13.	700-1-11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	38.00	AS					
14.	700-1-60	SINGLE POST SIGN, REMOVE	11.00	AS					
15.	704-1-2	TUBULAR MARKER, DURABLE, 36" YELLOW POST	8.00	EA					
16.	0710-11290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	144.00	SF					
17.	711-11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	522.00	LF					
18.	711-11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	14.00	LF					
19.	711-11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE & CROSSWALK	560.00	LF					
20.	711-11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	0.50	GM					
21.	711-11-160	THERMOPLASTIC, STANDARD, WHIT, MESSAGE OR SYMBOL	23.00	EA					
22.	711-11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	74.00	EA					
23.	711-11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	252.00	LF					
24.	711-11-241	THERMOPLASTIC, STANDARD, YELLOW, 2'X4' SKIP GUIDELINE	0.23	GM					
25.	711-11-15101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	2.69	GM					
26.	0711-15102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	0.02	GM					
27.	0711-15131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	2.45	GM					
28.	0711-15201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	2.63	GM					
29.	0711-15231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	0.99	GM					
SUBTOTAL SIGNING AND PAVING									
PAY ITEM NO. UTILITY IMPROVEMENTS									
30.	U1	MANHOLE FRAME & COVER (INCLUDING RAINWATER INSERT)	5.00	EA					
31.	U2	POLYMER CONCRETE ADJUSTMENT RING(S) (PER MANHOLE)	5.00	EA					
SUBTOTAL UTILITY IMPROVEMENTS									
PAY ITEM NO. LIGHTING									
32.	0630 2 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH (2" HDPE)	40.00	LF					
33.	0630 2 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE (2" HDPE)	370.00	LF					
34.	0633 8 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	1,720.00	LF					
35.	0635 2 11	POLYMER CONCRETE ADJUSTMENT RING(S) (PER MANHOLE) PULL & SPLICE BOX, F&I, 13"X24" COVER SIZE	4.00	EA					
36.	0660 3 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	1.00	EA					
37.	0660 3 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	7.00	EA					
38.	0660 3 60	VEHICLE DETECTION SYSTEM - MICROWAVE, REMOVE, COMPLETE SYSTEM	1.00	EA					
39.	0670 5111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	1.00	AS					
40.	0670 5400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	1.00	AS					
41.	0682 1113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	1.00	EA					
42.	0684 1 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	1.00	EA					
43.	0685 1 12	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION	1.00	EA					
44.	0685 2 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	1.00	EA					
SUBTOTAL MOBILIZATION & MAINTENANCE OF TRAFFIC, ROAD WORK, SIGNING & PAVEMENT MARKINGS, SIGNALIZATION, AND UTILITY IMPROVEMENTS									
CONSTRUCTION CONTINGENCY COUNTY AUTHORIZED USE ONLY (10% OF SUBTOTAL PRICE)									
GRAND TOTAL									
NO. ALTERNATE BID A									
45.	520-5-46-MC	TRAFFIC SEPARATOR CONCRETE - TYPE IV, 8.5' WIDE (Include signs and striping as necessary)	120.00	LF					

UPDATED
UPDATED
UPDATED
UPDATED

UPDATED

Bidder: _____

Signature: _____

*To be considered responsive, it is the sole responsibility of the bidder to correctly calculate and manually enter all sub-total, contingency and total bid price fields.