



MANATEE COUNTY

December 20, 2013

All Interested Quoters

SUBJECT: Request for Quotation #14-0502-OV
Langdon Hall Master Meter Improvements
Location: Langdon Hall, 1120 33rd Avenue West
Bradenton, FL (Project No.: 402.0019607)

ADDENDUM #2

Quoters are hereby notified that this Addendum shall be acknowledged on page 20 of the Quote Form and made a part of the above named bidding and contract documents. Quotes submitted without acknowledgement of the Addendum will be considered incomplete.

The following items are issued to add to, modify, and clarify the quote and contract documents. These items shall have the same force and effect as the original quoting and contract documents, and cost involved shall be included in the quoted prices. Quotes to be submitted on the specified quote date, shall conform to the additions and revisions listed herein.

Quoters Note 1: The reply date for RFQ #14-0502-OV has been revised as follows:

FROM: January 3, 2014

TO: January 9, 2014 at 4:00 PM

Quoters Note 2: Addendum No. 2 is issued in reply to the following questions received on December 19, 2013.

Question 1:

Is the intent to only replace / upgrade the above ground assembly to current standards as stated in response to question 1? If so, thrust blocks would not be needed per item 5 or the 6" gate valve per item 4 on the bid form. Please clarify.

Financial Management Department – Purchasing Division
1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205
Phone: 941-749-3055 – Fax: 941-749-3014
www.myanatee.org

LARRY BUSTLE * MICHAEL GALLEN * JOHN R. CHAPPIE * ROBIN DiSABATINO * VANESSA BAUGH * CAROL WHITMORE * BETSY BENAC
District 1 District 2 District 3 District 4 District 5 District 6 District 7

ADDENDUM #2

Response 1:

Yes, there are above ground meters on this site, but they are not to current standards. They need individual assemblies as shown on the standard details, dedicated vertical risers for each meter assembly through the slab with each meter assembly per current standards. A new slab, thrust blocks at the underground T's and 90's, etc are all require.

Question 2:

Does the county have an idea on how long this assembly can be out of service, and does this work need to be performed after daylight hours?

Response 2:

This is a residence facility, so water outage needs to be minimized which means the assemblies will need to be pre-assembled and put in place during low flow time - typically at night / early morning hours.

Question 3:

Do we need to make provisions for temporary service to Langdon Hall while this work is being performed?

Response 3:

Temporary service during construction has not been needed in any of the other master meter upgrades we have done thus far. The Contractors have been able to coordinate with the property owners and make the transition in a timely manner. Should your means and methods have the property owners out of water for an unacceptable time period, then temporary service may be needed.

Question 4:

Assuming this is to be painted once installed; do we include painting of the assembly in bid item 13?

Response 4:


Painting is required as indicated on the referenced details. Payment for the painting should be included in the line item for "Master Meter Assembly", quote item #1.

END OF ADDENDUM #2

All quotes will be received at the **Manatee County Purchasing Division, 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205 until 400 P.M. on January 9, 2014.**

Quotes may be submitted via Email or via Fax.

Sincerely



Melissa M. Wendel, CPPO, Purchasing Official
Manatee County Purchasing Division

Ov