

May 3, 2013

TO: All Interested Bidders

SUBJECT: Invitation for Bids #13-1195CD

Manatee County Historic Courthouse 2nd Floor Remodel and Outside Air

Project

ADDENDUM #2

Bidders are hereby notified that this Addendum shall be acknowledged on page <u>00300-1</u> of the Bid Form and made a part of the above named bidding and contract documents. Bids submitted without acknowledgment of the Addendum will be considered incomplete.

The following items are issued to add to, modify, and clarify the bid and contract documents. These items shall have the same force and effect as the original bidding and contract documents, and cost involved shall be included in the bid prices. Bids to be submitted on the specified bid date, shall conform to the additions and revisions listed herein.

1. **CHANGE** Article C.03, Completion of Work, on page 00030-1of the bid documents to read as follows:

The Work will be completed and ready for final inspection within the specified calendar days from the date the Contract time commences to run. Only one Bid shall be considered based on **260 calendar days**. Only one Award shall be made.

2. **ADD** the following paragraph to Article D.01, The Work, on page 00100-1 of the Bid Documents:

The Work shall also include asbestos abatement that is to be performed by a licensed Asbestos Contractor pursuant to the terms of Florida Statutues Chapter 469. If the General Contractor licensed pursuant to the terms of Article B.03 of these Bid Documents is not also licensed as an Asbestos Contractor pursuant to the terms of Florida Statutues 469, then they shall subcontract this portion of the work to an Asbestos Contractor who is licensed pursuant to the terms of Florida Statutues 469 and list the name of the Asbestos Contractor with their license number in question #11 of the Contractor's Questionnaire.

3. **ADD** the Limited NESHAP Asbestos Renovation Survey dated May 8, 2012 that is attached to this Addendum #2 to the Bid Documents.

Financial Management Department -Purchasing Division 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205 PHONE: 941.749.3014 * FAX: 941.749.3034

www.mymanatee.org

IFB #13-1195CD Addendum #2 Page 2

- 4. **ADD** the Pre-Renovation Asbestos Inspection Report for Second Floor Flooring and Walls dated April 7, 2011 that is attached to this Addendum #2 to the Bid Documents.
- 5. **CLARIFICATION** of Article's 1.6 and 1.8, Access to Site and Work Restrictions, on pages 2 thru 4 of Section 011000 of the Contract Documents:

Every employee of the General Contractor and Sub-Contractors shall be required to go thru background screening before being allowed unsupervised access to the building. It shall be the responsibility of the Contractor to submit a Judicial Center Background Waiver (attached to this Addendum #2) for every employee or subcontractor employee to the Project Manager before that person is allowed onto the job site. All employees and subcontractor employees shall wear identifying apparel that clearly identifies the company they are working for.

After successful background screening, a limited number of access cards will be issued to the General Contractor's resident superintendent for the purpose of escorting all employees and subcontractors to and from the job site work area. Failure to abide by security protocols will result in suspension of access cards and building access before 8:30 am.

Contractors shall use the Contractor Staging Sketch ASI-2 that is attached to this Addendum #2 for their staging activities.

- 6. **ADD** the following Article 1.10, Sequence of Operations, to Section 011000 of the Contract Documents:
 - 1.10 SEQUENCE OF OPERATIONS

In order to meet the overall objectives of the project, the work will proceed at the site in the following general sequence of activities:

- 1. The Contractor shall complete all fire sprinkler work in the historic courtroom and obtain the inspection and approval of the City of Bradenton and Engineer;
- 2. After fire sprinkler system in the historic courtroom has passed inspection, the Contractor shall move all of the pews into the historic courtroom;
- 3. The Contractor shall then proceed and perform the asbestos abatement;
- 4. After the asbestos abatement has been performed, the Contractor shall perform the remaining remodeling activities in accordance with the construction schedule that they will submit at the pre-construction meeting.
- 7. **DELETE** all of Section 012000 Payment Procedures that are in the Contract Documents, and **INSERT** the Section 012000 Payment Procedures Revision 4 pages 1 thru 10 that are attached to this Addendum #2.

Financial Management Department –Purchasing Division 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205 PHONE: 941.749.3014 * FAX: 941.749.3034

www.mvmanatee.org

LARRY BUSTLE * MICHAEL GALLEN * JOHN R. CHAPPIE *ROBIN DISABITINO * VANESSA BAUGH * CAROL WHITMORE * BETSY BENAC District 1 District 2 District 3 District 4 District 5 District 6 District 7

- 8. **DELETE** Bid Form pages 00300-1 thru 00300-3, and **INSERT** the REVISED bid Form pages 00300-1 thru 00300-3 that are attached to this Addendum #2.
- 9. CHANGE the Due Date and Time to Thursday, May 23, 2013 at 3:00 PM.

An additional Addendum will issued in the near future that will address all questions submitted prior to the deadline for clarifications.

END OF ADDENDUM #2

Bids will be received at Manatee County Purchasing, 1112 Manatee Avenue West, Bradenton, Florida 34205 until **Thursday, May 23, 2013 at 3:00 PM.**

Sincerely,

Melissa M. Wendel, CPPO

Purchasing Official

Financial Management Department –Purchasing Division 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205 PHONE: 941,749.3014 * FAX: 941,749.3034

www.mvmanatee.org

SECTION 00300- REVISED ADDENDUM #2

BID FORM (SUBMIT IN TRIPLICATE)

For: IFB #13-1195CD- MANATEE COUNTY HISTORIC COURTHOUSE 2ND FLOOR REMODEL AND OUTSIDE AIR PROJECT

TOTAL BID PRICE (BID "A"):
Based on a Completion Time of 260 calendar days
· · · · · · · · · · · · · · · · · · ·

Only one schedule for Completion of the Work shall be considered. Only one Award shall be made.

We, the undersigned, hereby declare that we have carefully reviewed the Bid documents, and with full knowledge and understanding of the aforementioned herewith submit this Bid, meeting each and every specification, term, and condition contained in the Invitation for Bids.

We understand that the Bid package, in its entirety, including but not limited to, all specifications, terms, and conditions in their entirety shall be made a part of any Agreement or Contract between Manatee County and the successful Bidder. Failure to comply shall result in Contract default, whereupon, the defaulting Contractor shall be required to pay for any and all re-procurement costs, damages, and attorney fees as incurred by the County.

Communications concerning this Bid shall be addressed as follows: (Complete all fields) Person's Name: Phone: Address: _____ Date: _____FL Contractor License#____ License in the Name of: Bidder is a WBE/MBE Vendor? _____ Certification _____ COMPANY'S NAME: AUTHORIZED SIGNATURE(S): Name and Title of Above Signer(s) CO. MAILING ADDRESS: STATE OF INCORPORATION ______ (if applicable) TELEPHONE: (____) _____ FAX: (____) ____ Email address: _____on [date]____attest that I have visited the project site(s) to familiarize myself with the full Scope of Work required for the Bid. Acknowledge Addendum No.____ Dated: _____ Acknowledge Addendum No.____ Dated: _____ Acknowledge Addendum No.____ Dated: _____ Acknowledge Addendum No.____ Dated: ____ Acknowledge Addendum No.____ Dated: _____ Acknowledge Addendum No.____ Dated: ____

BID FORM

(Submit in Triplicate) Section 00300

MANATEE COUNTY HISTORIC COURTHOUSE 2ND FLOOR REMODEL AND OUTSIDE AIR PROJECT Bid "A" Based on Completion Time of 260 Calendar Days

ITEM	Bid "A" Based on Completion	EST.	Lou Call	andar Days	EXTENDED
NO.	DESCRIPTION	QTY.	U/M	UNIT PRICE	PRICE
		Q 111.		OIIII I IIIOL	TRIOL
1	MOBILIZATION	1	LS	\$	\$
2	STRUCTURAL REPAIRS	1	LS	\$	\$
3	ASBESTOS ABATEMENT	1	LS	\$	\$
4	SELECTIVE DEMOLITION	1	LS	\$	\$
5	CONCRETE	1	LS	\$	\$
6	FRAMING & DRYWALL	1	LS	\$	\$
7	DOORS AND DOOR FRAMES	1	LS	\$	\$
8	DOOR HARDWARE	1	LS	\$	\$
9	ROOFING TIE IN / REPAIR	1	LS	\$	\$
10	ACOUSTIC CEILINGS AND GRID	1	LS	\$	\$
11	FLOORING	1	LS	\$	\$
12	CASEWORK	1	LS	\$	\$
13	PAINTING	1	LS	\$	\$
14	SIGNAGE	1	LS	\$	\$
15	BATHROOM PARTITIONS AND ACCESSORIES	1	LS	\$	\$
16	MISCELLANEOUS ITEMS	1	LS	\$	\$
17	FIRE PROTECTION SYSTEMS	1	LS	\$	\$
18	HVAC DEMOLITION	1	LS	\$	\$

Bidder Name:		


BID FORM

(Submit in Triplicate) Section 00300

MANATEE COUNTY HISTORIC COURTHOUSE 2ND FLOOR REMODEL AND OUTSIDE AIR PROJECT Bid "A" Based on Completion Time of 260 Calendar Days

ITEM	Bid "A" Based on Completio	EST.		l au suyo	EXTENDED
NO.	DESCRIPTION	QTY.	U/M	UNIT PRICE	PRICE
	NEW HVAC SYSTEMS AND COMPONENTS	1	LS	\$	\$
20	HVAC CONTROLS	1	LS	\$	\$
21	IT ROOM DX SYSTEM	1	LS	\$	\$
22	HVAC TEST AND BALANCE	1	LS	\$	\$
23	PLUMBING	1	LS	\$	\$
24	PLUMBING FIXTURES	1	LS	\$	\$
25	ELECTRICAL SWITCHGEAR, PANELS, CIRCUIT BREAKERS, TRANSFORMERS	1	LS	\$	\$
26	LIGHTING	1	LS	\$	\$
	ELECTRICAL CONDUIT FOR FIRE PROTECTION, LIFE SAFETY, SECURITY AND DATA	1	LS	\$	\$
28	ELECTRICAL SYSTEMS AND COMPONENTS	1	LS	\$	\$
29	SECURITY SYSTEMS- QUALIFIED SYSTEMS CONTRACTING				\$50,000.00
30	FIRE ALARM SYSTEMS	1	LS	\$	\$
31	DISCRETIONARY WORK (USED ONLY WITH COUNTY APPROVAL)				\$250,000.00
	TOTAL PRICE FOR BID "A" - Based on Completion Time of <u>260</u> Calendar Days				\$

Bidder Name:	



SECTION 012000 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section specifies administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Sections include the following:
 - 1. Division 1 Section "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
 - 2. Division 1 Section "Construction Progress Documentation" for administrative requirements governing preparation and submittal of Contractor's Construction Schedule and Submittals Schedule.
 - 3. Refer to County Purchasing requirements for additional directives and clarification.

1.3 DEFINITIONS

A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

1.4 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the Schedule of Values with preparation of Contractor's Construction Schedule.
 - 1. Correlate line items in the Schedule of Values with other required administrative forms and schedules, including the following:
 - a. Application for Payment forms with Continuation Sheets.
 - b. Submittals Schedule.
 - 2. Submit the Schedule of Values to Engineer and Project Manager at earliest possible date but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
- B. Format and Content: Use the Project Manual table of contents as a guide to establish line items for the Schedule of Values. Provide at least one line item for each Specification Section.
 - Identification: Include the following Project identification on the Schedule of Values:
 - a. Project name and location.

- b. Name of Engineer.
- c. Engineer's project number.
- d. Contractor's name and address.
- e. Date of submittal.
- 2. Arrange the Schedule of Values in tabular form with separate columns to indicate the following for each item listed:
 - a. Related Specification Section or Division.
 - b. Description of the Work.
 - c. Name of subcontractor.
 - d. Name of manufacturer or fabricator.
 - e. Name of supplier.
 - f. Change Orders (numbers) that affect value.
 - g. Dollar value
 - Percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent.
- 3. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with the Project Manual table of contents. Provide several line items for principal subcontract amounts, where appropriate.
- 4. Round amounts to nearest whole dollar, total shall equal the Contract Sum.
- 5. Provide a separate line item in the Schedule of Values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
- 6. Differentiate between items stored on-site and items stored off-site. Include evidence of insurance or bonded warehousing if required.
- 7. Provide separate line items in the Schedule of Values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
- 8. Each item in the Schedule of Values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.
- 9. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the Schedule of Values or distributed as general overhead expense, at Contractor's option.
- 10. Schedule Updating: Update and resubmit the Schedule of Values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

1.5 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.
 - 1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.

- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction Work covered by each Application for Payment is the period indicated in the Agreement.
- C. Payment Application Forms: Use AIA Document G702 and AIA Document G703 Continuation Sheets as form for Applications for Payment.
- D. Transmittal: Submit 3 signed and notarized original copies of each Application for Payment to Engineer and Project Manager by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
 - 1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- E. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from every entity who is lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.
 - 1. Submit partial waivers on each item for amount requested, before deduction for retainage, on each item.
 - 2. When an application shows completion of an item, submit final or full waivers.
 - 3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
 - 4. Waiver Delays: Submit each Application for Payment with Contractor's waiver of mechanic's lien for construction period covered by the application.
 - a. Submit final Application for Payment with or preceded by final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
 - 5. Waiver Forms: Submit waivers of lien on forms, executed in a manner acceptable to Owner.
- F. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
 - List of subcontractors.
 - 2. Schedule of Values.
 - 3. Contractor's Construction Schedule (preliminary if not final).
 - 4. Products list.
 - 5. Schedule of unit prices.
 - 6. Submittals Schedule (preliminary if not final).
 - 7. List of Contractor's staff assignments.
 - 8. List of Contractor's principal consultants.
 - 9. Copies of building permits.
 - 10. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
 - 11. Initial progress report.

- 12. Report of preconstruction conference.
- 13. Certificates of insurance and insurance policies.
- 14. Performance and payment bonds.
- 15. Data needed to acquire Owner's insurance.
- G. Application for Payment at Substantial Completion: After issuing the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
 - 1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
 - 2. This application shall reflect Certificates of Partial Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
- H. Final Payment Application: Submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
 - 1. Evidence of completion of Project closeout requirements.
 - 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 - 3. Updated final statement, accounting for final changes to the Contract Sum.
 - 4. AIA Document G706, "Contractor's Affidavit of Payment of Debts and Claims."
 - 5. AIA Document G706A, "Contractor's Affidavit of Release of Liens."
 - 6. AIA Document G707, "Consent of Surety to Final Payment."
 - 7. Evidence that claims have been settled.
 - 8. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
- I. Separate Pricing and Lump Sum Payments Separate pricing and lump sum payments shall follow the following payment schedule below and meet the required specifications, meet the requirements of the Engineer's plans, and must be accepted by the Owner's Representative and the Engineer.

J. SCOPE:

1. The scope of this section of the Contract Documents is to further define the items included in each Bid Item in the Bid Form section of the Contract Documents. Payment will be made based on the specified items included in the description in this section for each bid item. All contract prices included in the Bid Form section will be full compensation for all shop drawings, working drawings, labor, materials, tools, equipment and incidentals necessary to complete the construction as shown on the Drawings and/or as specified in the Contract Documents to be performed under this Contract. Actual quantities of each item bid on a unit price basis will be determined upon completion of the construction in the manner set up for each item in this section of the Specifications.

Payment for all items listed in the Bid Form will constitute full compensation for all work shown and/or specified to be performed under this Contract.

K. GENERAL

1. All contract lump sum prices included in the Bid Proposal section will be full compensation for all labor, equipment, and incidental to construct the 2nd Floor Remodel and Outside Air Project of the Manatee County Historic Courthouse as specified in the Contract Documents under this contract.

L. WORK OUTSIDE AUTHORIZED LIMITS

 No payment will be made for work constructed outside the authorized limits of work.

M. LUMP SUM PAYMENT

- 1. Where payment for items are shown to be paid for on a lump sum basis, no separate payment will be made for any item of work required to complete the lump sum items.
- 2. Lump sum contracts shall be complete, tested and fully operable prior to request for final payment. Contractor may be required to provide a break-down of the lump sum totals.
- 3. Payment shall be made for the items listed on the Bid Form on the basis of the work actually performed, completed, and accepted by the Engineer. Such work includes but is not limited to the furnishing of all necessary labor, materials, equipment, transportation, clean up, restoration of disturbed areas, all other appurtenances to complete the construction and installation of the work as shown on the drawings, as described in the specifications, and as directed by the Engineer. Measurement and Payment for Lump Sum bid items will be based on a percentage of completion, as approved by the Owner and recommended by the Engineer, on a monthly basis for the Lump Sum bid items listed on the Bid Form of the Contract Documents. Partial payments will be based on the breakdown of the Bid Item in accordance with the Schedule of Values submitted by the Contractor and approved by the Engineer. Payment shall also include full compensation for project photographs, as-built record drawings, project signs, rubbish and spoil removal, repair, replacement or relocation of all signs, walls, and any and all other items required to complete the project in accordance with Contract Documents.
- 4. No separate payment will be made for the following items and the cost of such work shall be included in the applicable pay items of work. Final payments shall not be requested by the Contractor or made by the Owner until as-built (record) drawings have been submitted and approved by the Engineer.
 - a. Shop Drawings, Working Drawings.
 - b. Cleanup and miscellaneous work.
 - c. Testing and placing system in operation.
 - d. Any material and equipment required to be installed and utilized for the tests.

- e. Pipe, structures, pavement replacement, asphalt and shell driveways and/or appurtenances included within the limits of lump sum work, unless otherwise shown.
- f. Maintaining the existing quality of service during construction.
- g. Appurtenant work as required for a complete and operable system.
- h. As-built Record Drawings.

N. BID ITEMS

- Mobilization Provide mobilization for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the project requirements. See the plans for an exact scope of work.
- 2. Structural Repairs Provide for all Structural Repairs for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Structural Repairs shall be inspected and accepted by the Engineer and City of Bradenton.
- 3. Asbestos Abatement Perform Asbestos Abatement for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the "Limited NESHAP Asbestos Renovation Survey" prepared by PSI dated May 8, 2012 and "Pre-Renovation Asbestos Inspection Report for Second Floor Flooring and Walls" prepared by EEG Environmental Services, LLC, dated April 7, 2011, for an exact scope of work
- 4. Selective Demo Perform Demolition for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work.
- 5. Concrete Provide and install all Concrete for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Concrete work shall be inspected and accepted by the Architect and the City of Bradenton.
- 6. Framing & Drywall Provide and install all Framing & Drywall for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Framing & Drywall shall be inspected and accepted by the Architect and the City of Bradenton.
- 7. Doors and Door Frames Provide and install all Doors and Door Frames for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final

- payment is completed the Doors and Door Frames shall be inspected and accepted by the Architect and the City of Bradenton.
- 8. Door Hardware Provide and install all Door Hardware for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Door Hardware shall be inspected and accepted by the Architect.
- 9. Roofing Tie In / Repair Provide and install all Roofing Tie In / Repair for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Roofing Tie In / Repair shall be inspected and accepted by the Architect and the City of Bradenton.
- 10. Acoustic Ceilings and Grid Provide and install all Acoustic Lay-In Ceiling and Ceiling Grid for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Ceiling Grid and Lay-In Ceiling shall be inspected and accepted by the Architect and the City of Bradenton.
- 11. Flooring (Ceramic Tile, VCT, Carpet) Provide and install all Flooring for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Flooring shall be inspected and accepted by the Architect.
- 12. Casework Provide and install all Casework for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Casework shall be inspected and accepted by the Architect.
- 13. Painting Provide and install all Painting for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Painting shall be inspected and accepted by the Architect.
- 14. Signage Provide and install all Signage for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Signage shall be inspected and accepted by the Architect and the City of Bradenton.
- 15. Bathroom partitions and Accessories Provide and install all Bathroom partitions and Accessories for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Build-

- ing Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Bathroom partitions and Accessories shall be inspected and accepted by the Architect.
- 16. Miscellaneous items Provide and install miscellaneous items (this item is for all items that do not fit in another category, list all items included under this category) for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Miscellaneous items shall be inspected and accepted by the Architect and where applicable by the City of Bradenton.
- 17. Fire Protection Systems Provide and install all fire protection systems for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and all local codes. See the fire protection plans and specifications for an exact scope of work. Demolition and replacement of items may be required. Install the systems as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed fire protection systems shall be inspected and accepted by the Engineer and the City of Bradenton.
- 18. HVAC Demos Perform Demolition for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work.
- 19. HVAC Systems and Components Provide and install all mechanical systems for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and all local code requirements. Demolition and replacement of items may be required. Check the mechanical plans and specifications for an exact scope of work. Install the systems and check the HVAC air balance of the building after the construction of the building is completed. Before final payment is completed the Manatee County Project Manager, the Engineer and the City of Bradenton Inspector shall inspect and accept the HVAC systems.
- 20. HVAC Controls Provide and install all temperature controls for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and all local codes. Demolition and replacement of items is required. See the HVAC plans and specifications for the exact scope of work. New controls shall be provided and installed. The controls shall be connected to the existing building controls if required. Before final payment is completed the Manatee County Project Manager, the Engineer and the City of Bradenton Inspector shall inspect and accept the HVAC systems.
- 21. IT Room DX System Provide a price for the provision of an HVAC unit for cooling the computer room 217, and the complete installation of the provided unit. See the mechanical plans and specifications for the DX air handler for a specific scope. Provide and install all items required for the installation of the

DX air handler unit for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and all local code requirements. Install the systems and check the HVAC air balance of the building after the construction of the building is completed. Before final payment is completed the Manatee County Project Manager, the Engineer and the City of Bradenton Inspector shall inspect and accept the HVAC systems.

- 22. HVAC Test and Balance Perform HVAC Test and Balance for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the HVAC Test and Balance Report shall be provided by the General Contractor and inspected and accepted by the Engineer of Record.
- 23. Plumbing Provide and install all Plumbing for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Plumbing shall be inspected and accepted by the Engineer and the City of Bradenton.
- 24. Plumbing Fixtures Provide and install all Plumbing Fixtures for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Plumbing Fixtures shall be inspected and accepted by the Architect and the City of Bradenton.
- 25. Electrical Switchgear, panels, circuit breakers, transformer(s) Provide and install all Electrical Work for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Electrical Work shall be inspected and accepted by the Engineer and the City of Bradenton.
- 26. Lighting– Provide and install all Lighting for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and the City of Bradenton requirements. See the plans for an exact scope of work. Before final payment is completed the Lighting shall be inspected and accepted by the Engineer and the City of Bradenton.
- 27. Electrical Conduit Provide and install all conduits and wiring required for the Fire Protection, Life Safety, Security, Data and electrical connections per the National Electrical Code (NEC) and all local codes. See the mechanical, electrical, security and fire protection plans and specifications for the exact scope of work. Before final payment is completed all conduit shall be inspected and accepted by the Engineer and the City of Bradenton.
- 28. Electrical Systems and Components Provide and install all electrical items: conduits, wiring, and all items required to make a complete functioning electri-

cal system for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as to meet the requirements of the National Electrical Code (NEC) and all of the local codes. See the electrical design plans and specifications for an exact scope of work. The wiring and conduits in bid Item # 24 are not included. Excluding lighting for bid item #23. Excludes items in the electrical switchgear items #22, the security systems bid items #26, the fire alarm systems items #27. Before final payment is completed electrical systems shall be inspected and accepted by the Engineer and the City of Bradenton.

29. Security Systems - Provide and install all security system items of the Project at the Manatee County Historic Courthouse and tie into the existing building security as required. See the contact documents for the exact scope of work. The conduit for security systems is a separate bid item (bid item # 24) and is not part of the allowance. Before final payment is completed security systems shall be inspected and accepted by the Engineer and the City of Bradenton.

General Contractor shall use an allowance of \$50,000.00 to contract with the Manatee County Security Continuing Services Contractor listed below.

Qualified Systems Contracting, Inc.

6996 Anderson Road

Tampa, FL 33634 Larry Phillips
Office: 813-885-3705 Branch Manager
Fax: 866-306-1799 Cell: 813-523-8685

30. Fire Alarm Systems - Provide and install all fire alarm systems for the 2nd Floor Remodel and Outside Air Project at the Manatee County Historic Courthouse as required to meet the Florida Building Code and all local codes. The wiring and conduit installation are in another bid item (bid item # 24). See the contract documents for the exact scope of work. Limited demolition shall be required. Provide and install new systems and connect to the existing building system. Before final payment is completed fire alarm systems shall be inspected and accepted by the Engineer and the City of Bradenton.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012000



LIMITED NESHAP ASBESTOS RENOVATION SURVEY MANATEE COUNTY HISTORIC COURTHOUSE SECOND FLOOR and LIMITED MEZZANINE AREA LOCATED AT 1115 MANATEE AVENUE WEST BRADENTON, MANATEE COUNTY, FLORIDA

PSI PROJECT NO. 0552903



May 8, 2012

Mr. John Rowland

Manatee County Government

Property Management Construction Services
1112 Manatee Avenue West

Bradenton, Florida 34205

Re: Limited NESHAP Asbestos Renovation Survey
Manatee County Historic Courthouse
Second Floor and Limited Mezzanine Area
Located at 1115 Manatee Avenue West
Bradenton, Manatee County, Florida
PSI Project Number 0552903

Dear Mr. Rowland:

Professional Service Industries, Inc. (PSI) was contracted by Manatee County Government per IFAS #W1200092 referencing Work Assignment No. 22PE to perform a limited National Emissions Standard for Hazardous Air Pollutants (NESHAP) asbestos renovation survey. On April 17, 18 and 19, 2012, PSI representatives Mr. Manuel Porras and Kevin Callahan conducted the limited asbestos survey of suspect asbestos-containing materials associated with the Manatee County Historic Courthouse on the second floor and the limited mezzanine located at 1115 Manatee Avenue West in Bradenton, Manatee County, Florida.

At the request of the client, the survey was limited to the interior areas on the second floor, and the mezzanine. The roof and exterior areas are not a part of this survey.

Numerous cuts were made in carpet, floor tile and ceramic tiled areas throughout each space to access and observe the underlying substrates. All areas above the ceiling panels were accessed to view the plenum space. Fireproofing material was observed between the walls.

This survey is limited to the materials referenced in the table on the following page. If additional materials not listed in the table are observed during renovation activities and are scheduled to be impacted, then those materials must first be laboratory tested prior to being disturbed.

During the limited NESHAP asbestos renovation survey, the inspectors collected a total of one hundred thirty-six (136) samples from eighty-nine (89) homogeneous areas of suspect asbestos-containing materials. Samples were laboratory analyzed by Polarized Light Microscopy (PLM). The following chart lists the materials sampled, sample locations, approximate quantity of materials located throughout the surveyed area and percentage of asbestos fibers found in the materials sampled. The results of our analytical testing are discussed in the table on the following page.

Homo.	SAMPLE No.	MATERIAL DESCRIPTION	SAMPLED LOCATION	APPROX. QUANTITY ⁽¹⁾	% ASBESTOS Type	NESHAP CATEGORY
-1101			North Side – Pl			
01	01	Terrazo flooring	North room, center	11,900 sq. ft.	NAD ⁽²⁾	N/A ⁽³⁾
		· ·	area			
01	02	Terrazo flooring	Middle west courtroom, center area		NAD	N/A
02	03	Black floor mastic	Northwest room, west area	8,900 sq. ft.	10 % Chry. ⁽⁴⁾	Category I ⁽⁵⁾
02	04	Black floor mastic	Middle east courtroom, center area		10 % Chry.	Category I
03	05	Yellow floor glue	Northeast courtroom, center area	6,800 sq. ft.	NAD	N/A
03	06	Yellow floor glue	Middle west courtroom, west area		NAD	N/A
04	07	White window caulk	North room, west corner	600 lin. ft.	NAD	N/A
04	08	White window caulk	Southeast courtroom, south window		NAD	N/A
05	09	Red fire caulk	North room, center window	600 lin. ft.	NAD	N/A
05	10	Red fire caulk	Southeast hallway, upper wall area		NAD	N/A
06	11	12" x 12" Beige vinyl floor tile and yellow glue	Northeast hallway	2,500 sq. ft.	NAD	N/A
06	12	12" x 12" Beige vinyl floor tile and yellow glue	South hallway, upper layer		NAD	N/A
07	13	12" x 12" Pink vinyl floor tile and yellow glue	Northeast hallway	500 sq. ft.	NAD	N/A
07	14	12" x 12" Pink vinyl floor tile and yellow glue	South hallway		NAD	N/A
08	15	12" x 12" Light Gray vinyl floor tile and black glue	Northeast office, west office area	110 sq. ft.	NAD	N/A
08	16	12" x 12" Light Gray vinyl floor tile and black glue	Northeast office, east office area		NAD	N/A
09	17	12" x 12" Beige vinyl floor tile and black glue	Northwest lobby hallway, center area	2,500 sq. ft.	Floor Tile- 4% Chry. Mastic- 8% Chry.	Category I
09	18	12" x 12" Beige vinyl floor tile and black glue	South hallway, west side		Floor Tile- 4% Chry. Mastic- 8% Chry.	Category I
10	19	Sheet vinyl flooring and glue	Southeast restroom, east corner	200 sq. ft.	NAD	N/A
10	20	Sheet vinyl flooring and glue			NAD	N/A



NESHAP Номо. SAMPLE MATERIAL SAMPLED APPROX. **% ASBESTOS** QUANTITY⁽¹⁾ No. **DESCRIPTION CATEGORY** No. LOCATION TYPE 11 21 Tan wallpaper and glue | Southeast restroom, 800 sq. ft. NAD N/A west wall Tan wallpaper and glue Southwest restroom, 11 22 NAD N/A east wall Middle courtroom, 12 23 Black baseboard and 600 sq. ft. NAD N/A west area glue 12 24 Black baseboard and Northwest hallway, NAD N/A south wall glue 13 25 Northeast office. 30 sq. ft. Tan baseboard and NAD N/A glue east wall 14 26 Gray baseboard and Northeast office, 30 sq. ft. NAD N/A south wall glue 27 15 Red baseboard and Northwest 990 sq. ft. NAD N/A glue courtroom, north wall 15 28 Red baseboard and North hallway, north NAD N/A glue wall 16 29 Tan glue North room, west 80 sq. ft. NAD N/A wall 17 30 NAD Black glue North room, 240 sq. ft. N/A northeast wall Category II⁽⁶⁾ Black HVAC duct 6% Chry. 18 31 Middle courtroom. 30 sq. ft. mastic west wall 18 32 Black HVAC duct Middle hallway 6% Chry. Category II mastic 19 33 White HVAC duct Middle east 1,150 sq. ft. NAD N/A mastic courtroom 19 34 White HVAC duct NAD N/A Middle west mastic courtroom 20 35 Black and pink duct 1,100 sq. ft. NAD N/A Middle west insulation courtroom, south end duct 21 36 Black and pink duct Middle east 1,100 sq. ft. NAD N/A insulation courtroom, north end duct 22 37 Tan HVAC duct mastic NAD North hallway 10 sq. ft N/A 23 38 Brown HVAC duct Northeast room, east 60 sq. ft. NAD N/A mastic wall 39 24 Gray concrete slab Southeast HVAC 200 sq. ft. NAD N/A room 24 40 Gray concrete slab Southeast HVAC NAD N/A room 25 41 12" x 12" Light green South side stairs 300 sq. ft. Floor Tile- 3% Chry. Category I vinyl floor tile and landing Mastic- 5% Chry. black glue 25 42 12" x 12" Light green North side stairs 300 sq. ft. Floor Tile-3% Chry. Category I vinyl floor tile and landing Mastic- 5% Chry. black glue



Manatee County Government

PSI Project No. 0552903 (WA #22PE, IFAS #W1200092)

Homo. No.	SAMPLE No.	MATERIAL DESCRIPTION	SAMPLED LOCATION	APPROX. QUANTITY ⁽¹⁾	% ASBESTOS TYPE	NESHAP CATEGORY
26	43	1" x 1" White tile with gray floor grout and white thin set	Men restroom, main hallway	800 sq. ft.	NAD	N/A
26	44	1" x 1" White tile with gray floor grout and white thin set	Southeast side hallway		NAD	N/A
27	45	Yellow liquid nail	South hallway, east side wall	2,000 sq. ft.	NAD	N/A
28	46	White caulk	Middle hallway, east side wall	800 sq. ft.	NAD	N/A
29	47	Brown insulation	Middle west courtroom, west side wall	13,000 sq. ft.	NAD	N/A
29	48	Brown insulation	Middle hallway, east side wall		NAD	N/A
29	49	Brown insulation	Southwest hallway, west side wall		NAD	N/A
30	50	White pyrobar block	Middle Hallway, west side wall	6,500 sq. ft.	NAD	N/A
31	51	White pyrobar block	North room, south side wall		NAD	N/A
32	52	Black vapor barrier	Middle west courtroom, west side wall	16,400 sq. ft.	NAD	N/A
32	53	Black vapor barrier	Middle east courtroom, east side wall		NAD	N/A
33	54	White plaster	North room, south side wall	21,500 sq. ft.	NAD	N/A
33	55	Peach plaster	Middle east courtroom, east side wall		NAD	N/A
33	56	White plaster	Middle hallway, east side wall		NAD	N/A
34	57	White/Orange drywall and white joint compound	North hallway, west side wall	12,560 sq. ft.	NAD	N/A
34	58	White drywall and white joint compound	Middle hallway, east side wall		NAD	N/A
35	59	4" Black pipe insulation and black mastic	Middle courtroom, north side wall	120 sq. ft.	Black insulation – NAD Mastic- 3% Chry.	Category II
35	60	4" Black pipe insulation and black mastic	Middle hallway, west side wall		Black insulation – NAD Mastic- 3% Chry.	Category II
36	61	2" White pipe insulation with white wrap	Middle east courtroom, north side wall	120 lin. ft.	Pipe insulation – 10% Chry. Wrap – NAD	Friable RACM ⁽⁷⁾
36	62	2" White pipe insulation with white wrap	Middle hallway, west side wall		Pipe insulation – 10% Chry. Wrap – NAD	Friable RACM



Номо.	SAMPLE	MATERIAL	SAMPLED	APPROX.	% ASBESTOS	NESHAP
No.	No.	DESCRIPTION	LOCATION	QUANTITY ⁽¹⁾	TYPE	CATEGORY
37	63	4" Black pipe insulation	Southeast HVAC	500 lin. ft.	NAD	N/A
		with white mastic	room			
38	64	4" Black pipe insulation	South hallway HVAC		NAD	N/A
		with white mastic	room			
39	65	4" Yellow insulation	Southeast HVAC	500 lin. ft.	NAD	N/A
		with white mastic	room	_		
39	66	4" Yellow insulation	South hallway HVAC		NAD	N/A
40	07	with white mastic	room	40 #	NAD	NI/A
40	67	Black HVAC damper	Middle east	16 sq. ft.	NAD	N/A
40	68	White HVAC damper	courtroom South hallway HVAC	30 sq. ft.	NAD	N/A
40	00	Writte HVAC damper	room	30 Sq. ii.	INAD	IN/A
41	69	Black pipe mastic	Hallway, north side	950 lin. ft.	3% Chry.	Category II
7.	00	Black pipe mactic	4" steel cast pipes	000	0 /0 Omy.	outogory ii
41	70	Black pipe mastic	Hallway, north side		3% Chry.	Category II
			4" steel cast pipes		•	
			South Side - Ph	nase II		
42	71	Gray concrete slab	Southeast room,	8,000 sq. ft.	NAD	N/A
		-	center area			
42	72	Gray concrete slab	Middle hallway,		NAD	N/A
			center area			
43	73	Gray concrete ceiling	Southeast room,	8,000 sq. ft.	NAD	N/A
		deck	south side area			
43	74	Gray concrete ceiling	Middle courtroom,		NAD	N/A
44	75	deck Black HVAC duct	center area Southeast room,	100 sq. ft.	9% Chry.	Category II
44	73	mastic	west wall	100 Sq. 1t.	9 /0 Ciliy.	Category
44	76	Black HVAC duct	Middle hallway,		9% Chry.	Category II
	. •	mastic	west side wall		070 C y .	Janeger, ii
45	77	Tan HVAC duct mastic	Middle courtroom,	105 sq. ft.	NAD	N/A
			center area			
45	78	Tan HVAC duct mastic	North hallway, center		NAD	N/A
			area			
46	79	Black baseboard with	Southeast hallway,	90 lin. ft.	2% Chry.	Category I
		Brown mastic	center side wall	100 !! 6	NAD	21/2
47	80	Red baseboard with	Northeast office, east	120 lin. ft.	NAD	N/A
40	01	mastic	side wall Southeast room,	0.000.00 ft	NAD	N/A
48	81	Gray plaster over gray coat	southwest side area	9,000 sq. ft.	NAD	IN/A
48	82	Gray plaster over gray	Northeast hallway,	9000 sq. ft.	NAD	N/A
70	02	coat	north wall	3000 3q. it.	TVID	14// (
48	83	Gray plaster over gray	West courtroom,		NAD	N/A
		coat	west wall			
49	84	White pyrobar block	Southeast room,	5,500 sq. ft.	NAD	N/A
		1,7	southwest side area	'		
49	85	White pyrobar block	North hallway, center		NAD	N/A
			area			
50	86	Yellow carpet glue	Southeast room,	7,000 sq. ft.	NAD	N/A
			center area	<u> </u>	N1.5	
50	87	Yellow carpet glue	Northwest room,		NAD	N/A
		1	center area			



Номо.	SAMPLE	MATERIAL	SAMPLED	APPROX.	% ASBESTOS	NESHAP
No.	No.	DESCRIPTION	LOCATION	QUANTITY ⁽¹⁾	TYPE	CATEGORY
51	88	Gray/beige sheet vinyl flooring material	Southwest restroom, south side	120 sq. ft.	NAD	N/A
52	89	Tan/white wallpaper	Southwest restroom, south wall	720 sq. ft.	NAD	N/A
53	90	Gray drywall and white joint compound	Southwest courtroom, east side wall	13,000 sq. ft.	NAD	N/A
53	91	Gray drywall and white joint compound	South corridor, north wall		NAD	N/A
54	92	White window caulk	Southwest courtroom, southwest window	600 lin. ft.	NAD	N/A
55	93	Red fire caulk	Southwest courtroom, west center window	600 lin. ft.	NAD	N/A
56	94	Yellow liquid nail	North hallway, south wall	6,000 sq. ft.	NAD	N/A
57	95	Black sink undercoat	Southeast room, southwest area	4 sq. ft.	2% Chry.	Category II
58	96	Black vapor barrier	South corridor, south wall	1,800 sq. ft.	NAD	N/A
59	97	12" x 12" Beige vinyl floor tile and yellow glue	North hallway, south side	500 sq. ft.	NAD	N/A
60	98	12" x 12" Pink vinyl floor tile and yellow glue	North hallway, north side	150 sq. ft.	NAD	N/A
61	99	12" x 12" Light green vinyl floor tile and black glue	Middle courtroom, center area	4,000 sq. ft.	Floor Tile- 3% Chry. Mastic- 7% Chry.	Category I
62	100	Tan insulation	South corridor, south wall	13,000 sq. ft.	NAD	N/A
63	101	Gray/Yellow HVAC duct mastic	Southwest courtroom, center area	60 sq. ft.	NAD	N/A
64	102	4" Black pipe insulation with white mastic	Southwest HVAC room	80 lin. ft.	NAD	N/A
65	103	Black/Yellow HVAC duct insulation	Middle courtroom, west area	4,500 sq. ft.	NAD	N/A
66	104	Tan caulk	North hallway, north wall	100 lin. ft.	NAD	N/A
67	105	Black pipe mastic	Hallway, north side 4" steel cast pipes	300 lin. ft.	3% Chry.	Category II
			Mezzanine	•		
68	106	2' x 2' Gray/White ceiling panel	Lobby area	1,200 sq. ft.	NAD	N/A
68	107	2' x 2' Gray/White ceiling panel	Room 301, center area		NAD	N/A
68	108	2' x 2' Gray/White ceiling panel	Room 303, north area		NAD	N/A



Homo.	SAMPLE No.	MATERIAL DESCRIPTION	SAMPLED LOCATION	APPROX. QUANTITY ⁽¹⁾	% ASBESTOS TYPE	NESHAP CATEGORY
	400	0 7 1 11 1			NAD	
69	109	Gray/Tan drywall and	Lobby area, northeast corner	3,000 sq. ft	NAD	N/A
69	110	white joint compound Gray/Tan drywall and	Room 303,	-	NAD	N/A
09	110	white joint compound	southeast corner		INAL	IN/A
69	111	Gray/Tan drywall and	Restroom, northwest		NAD	N/A
00		white joint compound	corner		TVAD	14// (
70	112	Gray/Beige sheet vinyl flooring	Restroom, southwest corner	36 sq. ft.	NAD	N/A
71	113	Black/Yellow carpet mastic	Room 304, southwest area	700 sq. ft.	5% Chry.	Category I
71	114	Black/Yellow carpet	Room 303,		5% Chry.	Category I
		mastic	northwest corner		0,0 Ciii yi	category :
73	115	White plaster over gray coat	Room 301, northwest corner	3,000 sq. ft.	NAD	N/A
73	116	White plaster over gray coat	Room 303, northwest corner		NAD	N/A
74	117	White window caulk	Lobby, southwest window	200 lin. ft.	NAD	N/A
75	118	Black baseboard and white glue	Lobby, west wall	50 lin. ft.	NAD	N/A
76	119	Red baseboard and white glue	Room 352, south center wall	200 lin. ft.	NAD	N/A
77	120	Yellow carpet over gray leveling compound and black mastic	Main entrance hallway	230 sq. ft.	6% Chry.	Category I
77	121	Yellow carpet over gray leveling compound and black mastic	Lobby, center area		6% Chry.	Category I
78	122	White pyrobar block	Room 302, west wall	200 sq. ft.	NAD	N/A
79	123	White/Yellow pipe insulation	Room 302, south wall	15 lin. ft.	NAD	N/A
80	124	4" Black pipe insulation and black mastic	Room 301, center area	50 lin. ft.	Insulation – NAD Mastic - 6% Chry.	Category II
81	125	4" Black pipe insulation with foil paper and black mastic	North storage area, west side	50 lin. ft.	Insulation – NAD Foil paper - NAD Mastic - 6% Chry .	Category II
82	126	2" White pipe insulation and white mastic	Room 302, southwest wall	10 lin. ft.	NAD	N/A
83	127	Black HVAC damper	Room 301, northwest area	16 lin. ft.	NAD	N/A
84	128	White HVAC duct mastic over green mastic	Lobby, southwest area	50 sq. ft.	NAD	N/A
85	129	Gray HVAC duct mastic	Room 301, north area	50 sq. ft.	NAD	N/A
86	130	Yellow interior HVAC insulation	Room 301, north area	300 sq. ft.	NAD	N/A
87	131	White ceiling plaster	Room 301, southwest corner	60 sq. ft.	NAD	N/A
88	132	Black vapor barrier	Room 301, south wall	200 sq. ft.	NAD	N/A



Homo. No.	SAMPLE No.	MATERIAL DESCRIPTION	SAMPLED LOCATION	APPROX. QUANTITY ⁽¹⁾	% ASBESTOS TYPE	NESHAP CATEGORY
89	133	Peach plaster	Room 301, south wall	200 sq. ft.	NAD	N/A
89	134	Peach plaster	Room 301, south wall	•	NAD	N/A
90	135	12" x 12" Green vinyl floor tile with yellow and black glue	Hallway room 301	400 sq. ft.	Floor Tile - 3% Chry. Black Mastic - 7% Chry. Yellow Mastic- NAD	Category I
90	136	12" x 12" Green vinyl floor tile with yellow and black glue	Room 301, northwest corner		Floor Tile - 3% Chry. Black Mastic - 7% Chry. Yellow Mastic- NAD	Category I

- (1) Approximate quantity located throughout the surveyed area; sq. ft. = square feet; lin. ft. = linear feet
- (2) NAD = No asbestos detected
- (3) N/A = Not applicable
- (4) Chry. = Chrysotile Asbestos
- (5) Category I = Non-friable ACM are asbestos-containing resilient floor coverings, asbestos tile, asphalt roofing products, packing and gaskets
- (6) Category II = All non-friable asbestos-containing materials not Category I
- (7) RACM = Friable Regulated Asbestos Containing Material

Reference attachment for laboratory analytical results.

The U.S. Environmental Protection Agency (EPA) and the Occupational Safety and Health Administration (OSHA) define asbestos containing material as any material which contains greater than one percent asbestos. When friable samples analyzed by Polarized Light Microscopy contain asbestos in amounts less than ten percent (< 10%), a more exact method of analysis called point counting may be performed at the client's request. The EPA point count method allows a friable sample in which asbestos was visually detected, but which is visually estimated to have 10% or less asbestos, to be quantified using a point count procedure. If not point counted, a friable sample in which asbestos was visually detected and estimated (including trace to \leq 1%) must be assumed to be greater than 1% and treated as an asbestos-containing material (ACM).

The EPA point counting procedure is as follows: an ocular reticule (cross hair or point array) is used to superimpose visually a point or points on the microscope field of view. A total of 400 points superimposed on either asbestos fibers or non-asbestos matrix material must be counted over at least eight different preparations of representative sub-samples. If an asbestos fiber and matrix particle overlap so that a point is superimposed on their visual intersection, a point is scored for both categories. Point counting provides a quantification of the area percent asbestos.

Per EPA's regulations, materials which have been point-counted and, therefore, quantitatively determined to have less than or equal to one percent (≤ 1%) asbestos, can be treated as non-ACM. None of the samples collected were point counted during this survey.



This report may not be used by the client to claim product endorsement by NVLAP or any agency of the U.S. Government. Method used: EPA Method for the Determination of Asbestos in Bulk Building Materials (EPA/600/R-93/116, July 1993).

Seventeen (17) of the eighty-nine (89) homogeneous materials collected and analyzed during the limited NESHAP asbestos renovation survey were found to contain asbestos mineral fibers.

MATERIAL DESCRIPTION	% ASBESTOS – TYPE
North Side – Phase I	
HA: 02 Approximately 8,900 square feet of black floor mastic asbestoscontaining (Located throughout the north space). This mastic material is adhered to the floor deck.	10% Chrysotile Asbestos
HA: 09 Approximately 2,500 square feet of asbestos-containing 12" x12" Beige floor tile with asbestos-containing black floor mastic (Located throughout the north to south hallway and the southeast and southwest courtrooms). This material is the lower 12" x 12" floor tile layer.	Floor Tile 4% - Chrysotile Asbestos Mastic 8% - Chrysotile Asbestos
HA: 18 Approximately 30 square feet of asbestos-containing black HVAC duct mastic (located mainly in the middle east courtroom and inside the mechanical north HVAC room). This material was observed on the seams of the foil wrap duct insulation over bare metal duct.	6% Chrysotile Asbestos
HA: 25 Approximately 300 square feet of asbestos-containing 12" x12" Light Green floor tile with asbestos-containing black floor mastic (Located throughout the north and south stairs and landings). This material is a single layer.	Floor Tile 4% - Chrysotile Asbestos Mastic 8% - Chrysotile Asbestos
HA: 35 Approximately 120 linear feet of 4" Pipe stink rock insulation with asbestos-containing black duct mastic (located in the middle east and west pipe chases between the partitions areas on the seams). This material was observed on the black wrap pipe insulation.	3% Chrysotile Asbestos
HA: 36 Approximately 120 linear feet of friable asbestos-containing 2" Pipe insulation with white wrap (located in the middle east and west pipe chases between the partitions areas). This material was observed inside the white wrap.	10% Chrysotile Asbestos
HA: 41 Approximately 950 linear feet of asbestos-containing 4" pipe black mastic (located on the steel cast pipe lines). This remaining black mastic spots were observed over these 4" steel cast pipes along the entire hallway; the insulation material was already removed.	3% Chrysotile Asbestos
South Side – Phase II	
HA: 44 Approximately 200 square feet of asbestos-containing black HVAC duct mastic (located mainly in the southeast to east office areas on the upper wall). This material was observed on the HVAC duct insulation lines over bare metal duct.	10% Chrysotile Asbestos
HA: 46 Approximately 90 linear feet of asbestos-containing black baseboard mastic (observed at the southeast corridor and east office area). This mastic material is adhered to the lower base wall areas.	2% Chrysotile Asbestos
HA: 57 Approximately 4 square feet of asbestos-containing black sink undercoat (located in the southeast room). This material is associated with a former kitchen cabinet area.	5% Chrysotile Asbestos
HA: 61 Approximately 4,000 square feet of asbestos-containing 12" x12" light green floor tile with asbestos-containing black floor mastic (located throughout the east to west hallway and the center courtrooms). This material is the lower 12" x 12" floor tile layer.	Floor Tile 4% - Chrysotile Asbestos Mastic 8% - Chrysotile Asbestos



MATERIAL DESCRIPTION HA: 67 Approximately 300 linear feet of asbestos-containing 4" pipe black mastic (located on the steel cast pipe lines). This remaining black mastic spots were	% ASBESTOS – TYPE 10% Chrysotile Asbestos
observed over these 4" steel cast pipes along the entire hallway, the insulation material was already removed.	
Mezzanine	
HA: 71 Approximately 700 square feet of black/yellow floor mastic asbestos-containing (located throughout room 304, room 352 and room 303). This mastic material is adhered to the floor deck.	5% Chrysotile Asbestos
HA: 77 Approximately 230 square feet of green/yellow and black floor mastic asbestos-containing (located throughout the lobby space). This mastic material is adhered to the floor deck mixed with the leveling compound.	6% Chrysotile Asbestos
HA: 80 and 81 Approximately 100 linear feet of asbestos-containing black pipe mastic (located in room 301 and inside room 302). This material was observed on the seams of the foil wrap pipe insulation.	15% Chrysotile Asbestos
HA: 90 Approximately 400 square feet of asbestos-containing 12" x12" light green floor tile with asbestos-containing black floor mastic (located throughout room 301) This material is a single layer.	Floor Tile 3% - Chrysotile Asbestos Mastic 5% - Chrysotile Asbestos

*All quantities are estimated and are not for bidding purposes and must be verified by the abatement contractor.

The black floor mastic (HA-02, HA-09, HA-25, HA-46, HA-61, HA-71, HA-77 and HA-90) are considered to be a Category I non-friable asbestos-containing material per EPA NESHAP 40 CFR Part 61, Subpart M. This material does not pose a significant exposure problem unless sawn, drilled, sanded, or structurally altered in a way which could make it become friable.

The black duct mastic (HA-18, HA-35, HA-41, HA-44, HA-67, HA-124 and HA-125) and black sink undercoat mastic (HA-57) are considered to be Category II non-friable asbestos-containing materials per EPA NESHAP 40 CFR Part 61, Subpart M. These materials do not pose a significant exposure problem unless sawn, drilled, sanded, or structurally altered in a way which could make it become friable.

The white pipe insulation (HA-36) is considered RACM, i.e. friable asbestos containing materials. Prior to demolition, above referenced RACM material should be removed by an experienced Florida Licensed Asbestos Abatement Contractor, utilizing proper abatement procedures as per OSHA 29 CFR Part 1926.1101 with documentary air monitoring performed by and independent Florida Licensed Asbestos Consulting Firm to verify compliance with EPA NESHAP 40, CFR Part 61, Subpart M.

If there are plans to disturb the above referenced Category I and II non-friable asbestos-containing material during renovation activities, then this material should be removed by an experienced Florida Licensed Asbestos Contractor, utilizing proper abatement procedures as per OSHA 29 CFR Part 1926.1101 with documentary air monitoring performed by an independent Florida Licensed Asbestos Consulting firm.



If renovation activities expand into other areas not referenced in this survey, or if during renovation activities, any additional materials are found which have not been tested, or any materials are found in any of the areas that were not visible at the time of the survey, they should be assumed to be asbestos containing until laboratory testing proves otherwise. The renovation contractor should provide oversight to ensure that additionally found suspect materials are properly tested. The contractor must keep a copy of the asbestos survey onsite.

Warranty

PSI warrants that the findings contained herein have been prepared in general accordance with accepted professional practices at the time of this preparation, as applied by similar professionals in the community. Changes in the state of the art or in applicable regulations cannot be anticipated and have not been addressed in this report.

This report was prepared pursuant to authorization received by Manatee County Government per IFAS #W1200092. That contractual relationship included an exchange of information about the property that was unique and between PSI and its client and serves as the basis upon which this report was prepared. Because of the importance of the communication between PSI and its client, reliance or any use of this report by anyone other than Manatee County Government for whom it was prepared, is prohibited and therefore not foreseeable to PSI.

Reliance on or use by any such third party without explicit authorization in the report does not make said third party a third party beneficiary to PSI's contract with Brixmor Property Group. Any such unauthorized reliance on or use of this report, including any of its information or conclusions, will be at the third party's risk. For the same reasons, no warranties or representations, expressed or implied in this report, are made to any such third party.

The survey and analytical methods have been used to provide the client with information regarding the presence of the parameters tested in the facility at the time of study. Test results are valid only for the locations sampled. There is a distinct possibility that conditions may exist which could not be identified within the scope of the study or which were not apparent during the site visit. This inspection covered only those areas that were physically accessible to the inspector. The study is also limited to the information provided by the client at the time the survey was conducted.

As directed by the client, PSI did not provide any service to investigate or detect the presence of moisture, mold or other biological contaminates in or around any structure, or any service that was designed or intended to prevent or lower the risk of the occurrence of the amplification of the same. Client acknowledges that mold is ubiquitous to the environment with mold amplification occurring when building materials are impacted by moisture. Client further acknowledges that site conditions are outside of PSI's control, and that mold amplification will likely occur, or continue to occur, in the presence of moisture. As such, PSI cannot and shall not be held responsible for the occurrence or recurrence of mold amplification.



Manatee County Government Limited NESHAP Asbestos Renovation Survey Manatee County Historic Courthouse, Second Floor & Limited Mezzanine Area 1115 Manatee Avenue West in Bradenton, Florida PSI Project No. 0552903 (WA #22PE, IFAS #W1200092)

After your review of this information, if you have any questions or concerns, please do not hesitate to contact Mr. Keith R. Kartovicky at (813) 886-1075.

Respectfully submitted,

PROFESSIONAL SERVICE INDUSTRIES, INC.

Manuel Porras

AHERA Certified Asbestos Inspector

Keith R. Kartovicky

AHERA Certified Asbestos Inspector

Kuth B Kattorice

Senior Project Manager

Michael W. Rothenburg, P.E.

Principal Consultant

Florida Licensed Asbestos Consultant

License No. EA41

P:\552-Env\A-Reports 2012\0552903 Historic Courthouse-Manatee County\0552903 Bradenton.doc



PLM ANALYTICAL LABORATORY RESULTS





19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202002 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst
PSI (Miami)
7950 NW 64th St.
Miami, FL 33166

Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/18/12 10:00 AM

Analysis Date: 4/19/2012 Collected: 4/17/2012

Project: Manatee County Historic Courthouse - 3rd FL - Phase I - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Sample Description **Appearance Fibrous** % Non-Fibrous % Type **None Detected** Terrazo Flooring 100% Non-fibrous (other) Gray/White Non-Fibrous 171202002-0001 Homogeneous Terrazo Flooring **None Detected** 2 Gray/White 100% Non-fibrous (other) Non-Fibrous 171202002-0002 Homogeneous 3 Floor Mastic Black 90% Non-fibrous (other) 10% Chrysotile Non-Fibrous 171202002-0003 Homogeneous Floor Mastic Stop Positive (Not Analyzed) 171202002-0004 Carpet Mastic 100% Non-fibrous (other) None Detected Yellow Non-Fibrous 171202002-0005 Homogeneous 6 Carpet Mastic Yellow 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0006 Homogeneous Caulk White 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0007 Homogeneous Caulk White 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0008 Homogeneous

Analyst(s)	
Natasha Montova (50)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Emberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202002 CustomerID: PSI59

CustomerPO: ProjectID:

in: Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166 Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/18/12 10:00 AM

Analysis Date: 4/19/2012 Collected: 4/17/2012

Project: Manatee County Historic Courthouse - 3rd FL - Phase I - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Sample Description **Appearance Fibrous** % Non-Fibrous % Type Fire Caulk **None Detected** 3% Glass 97% Non-fibrous (other) Red Non-Fibrous 171202002-0009 Homogeneous Fire Caulk **None Detected** 10 Red 3% Glass 97% Non-fibrous (other) Non-Fibrous 171202002-0010 Homogeneous Floor Tile Beige 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0011 Homogeneous Mastic 100% Non-fibrous (other) None Detected 11A Yellow Non-Fibrous 171202002-0011A Homogeneous 12 Floor Tile 100% Non-fibrous (other) **None Detected** Beige Non-Fibrous 171202002-0012 Homogeneous 12A Mastic 100% Non-fibrous (other) **None Detected** Yellow Non-Fibrous 171202002-0012A Homogeneous Floor Tile None Detected 13 Pink 100% Non-fibrous (other) Non-Fibrous 171202002-0013 Homogeneous 13A Mastic Yellow 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0013A Homogeneous

Analyst(s)	
Natasha Montova (50)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Emberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

miamilab@emsl.com http://www.emsl.com

EMSL Order: 171202002 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166

Phone: (305) 471-7721 Fax: (305) 593-1915 04/18/12 10:00 AM Received:

Analysis Date: 4/19/2012 Collected: 4/17/2012

Project: Manatee County Historic Courthouse - 3rd FL - Phase I - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

			Non-Asbestos		<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
14 171202002-0014	Floor Tile	Pink Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
14A 171202002-0014A	Mastic	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
15 171202002-0015	Floor Tile	Grayish Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
15A 171202002-0015A	Mastic	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
16 171202002-0016	Floor Tile	Grayish Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
16A 171202002-0016A	Mastic	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
17 171202002-0017	Floor Tile	Beige Non-Fibrous Homogeneous		96% Non-fibrous (other)	4% Chrysotile
17A 171202002-0017A	Mastic	Black Non-Fibrous Homogeneous		92% Non-fibrous (other)	8% Chrysotile

Analyst(s)	
Natasha Montoya (50)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Emberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

miamilab@emsl.com http://www.emsl.com

EMSL Order: 171202002 PSI59 CustomerID:

CustomerPO: ProjectID:

Glenn Potharst **PSI (Miami)** 7950 NW 64th St. Miami, FL 33166

Phone: (305) 471-7721 Fax: (305) 593-1915 04/18/12 10:00 AM Received:

Analysis Date: 4/19/2012 Collected: 4/17/2012

Project: Manatee County Historic Courthouse - 3rd FL - Phase I - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Sample Description **Appearance Fibrous** % Non-Fibrous % Type Floor Tile Stop Positive (Not Analyzed) 18 171202002-0018 Stop Positive (Not Analyzed) 18A Mastic 171202002-0018A 19 Sheet Vinyl Gray/Beige 15% Synthetic 75% Non-fibrous (other) **None Detected** Fibrous 5% Cellulose 171202002-0019 Heterogeneous 5% Glass 19A Mastic Cream 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0019A Homogeneous 20 Sheet Vinyl Gray/Beige 5% Cellulose 75% Non-fibrous (other) **None Detected** Fibrous 15% Synthetic 171202002-0020 Heterogeneous 5% Glass 20A Mastic Cream <1% Synthetic 100% Non-fibrous (other) None Detected Non-Fibrous 171202002-0020A Homogeneous 21 Wallpaper Tan/Beige 95% Cellulose 5% Non-fibrous (other) **None Detected Fibrous** 171202002-0021 Heterogeneous Mastic Insufficient Material 21A 171202002-0021A Limberly a Wallace Analyst(s)

Natasha Montoya (50)

Kimberly Wallace, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202002 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166 Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/18/12 10:00 AM

Analysis Date: 4/19/2012 Collected: 4/17/2012

Project: Manatee County Historic Courthouse - 3rd FL - Phase I - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Sample Description **Appearance Fibrous** % Non-Fibrous % Type **None Detected** Wallpaper 5% Non-fibrous (other) 22 Tan/Beige 95% Cellulose Fibrous 171202002-0022 Homogeneous Insufficient Material 22A Mastic 171202002-0022A Baseboard Black 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0023 Homogeneous 23A Mastic 100% Non-fibrous (other) **None Detected** Beige Non-Fibrous 171202002-0023A Homogeneous 24 Baseboard 100% Non-fibrous (other) **None Detected** Black Non-Fibrous 171202002-0024 Homogeneous 24A Mastic Beige 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0024A Homogeneous 25 Baseboard Tan 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0025 Homogeneous 25A Mastic Tan 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0025A Homogeneous

Analyst(s)	
Natasha Montova (50)	

Kimberly G Wallace
Kimberly Wallace, Laboratory Manager

or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202002 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166 Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/18/12 10:00 AM

Analysis Date: 4/19/2012 Collected: 4/17/2012

Project: Manatee County Historic Courthouse - 3rd FL - Phase I - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Description **Appearance** Sample **Fibrous** % Non-Fibrous % Type Baseboard **None Detected** 100% Non-fibrous (other) 26 Gray Non-Fibrous 171202002-0026 Homogeneous Mastic **None Detected** 26A Beige 100% Non-fibrous (other) Non-Fibrous 171202002-0026A Homogeneous 27 Baseboard Red/Purple 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0027 Homogeneous Mastic 100% Non-fibrous (other) None Detected 27A Beige Non-Fibrous 171202002-0027A Homogeneous Baseboard Red/Purple 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0028 Homogeneous 28A Mastic Beige **None Detected** 100% Non-fibrous (other) Non-Fibrous 171202002-0028A Homogeneous None Detected 29 Mastic Tan 100% Non-fibrous (other) Non-Fibrous 171202002-0029 Homogeneous 30 Mastic Black 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0030 Homogeneous

Analyst(s)	
Natasha Montova (50)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Emberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202002 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn PotharstPSI (Miami)7950 NW 64th St.Miami, FL 33166

Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/18/12 10:00 AM

Analysis Date: 4/19/2012 Collected: 4/17/2012

Project: Manatee County Historic Courthouse - 3rd FL - Phase I - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos <u>Asbestos</u> Description **Appearance** Sample **Fibrous** % Non-Fibrous % Type A/C Duct Mastic 94% Non-fibrous (other) 6% Chrysotile 31 Black Non-Fibrous 171202002-0031 Homogeneous A/C Duct Mastic 32 Stop Positive (Not Analyzed) 171202002-0032 A/C Duct Mastic White 5% Wollastonite 95% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0033 Homogeneous A/C Duct Mastic White Wollastonite 95% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0034 Homogeneous 35 A/C Duct Insulation Black/Pink 97% Glass 3% Non-fibrous (other) **None Detected** Fibrous 171202002-0035 Heterogeneous 36 A/C Duct Insulation Black/Pink 97% Glass 3% Non-fibrous (other) **None Detected** Fibrous 171202002-0036 Heterogeneous A/C Duct Mastic 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0037 Homogeneous 38 Mastic Brown <1% Wollastonite 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202002-0038 Homogeneous

Analyst(s)	
Natasha Montoya (50)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Emberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0





Asbestos Chain of Custody EMSL Order Number (Lab Use Only):

17/202002

EMSL ANALYTICA., INC. 19501 NE 10^T AVE BAY A NORTH MIAM BEACH FL 33179

> PHONE: (305) 650-0577 FAX: (305) 650-0578

company: +SI, Miami			EMSL-Bill to: Same Different If Bill to is Different note instructions in Comments*				
Street: 795	DNW	64th	Street			requires written author	
city: Miam	1		ovince: Fla	Zip/Postal Co			ountry:
Report To (Name):	Glenn	1 1 1 1		Fax #:			ountry.
Telephone #: 78				Email Address			
Project Name/Num	ber: Mano	too Co	mto 1/stacio	Courthouse		-1 Fl - Fl	7 T
Please Provide Re	sults: 🔲 Fa:		Purchase Orde	or:		S. State Samples T	aken:
	***	Tuma	round Time (TAT				
*For TEM Air 3 hr through	6 Hour	24 Hour	V 48 Hour	72 Hour		96 Hour 1 1 W	eek 2 Week
	form for this serv	ice. Analysis co	impleted in accordance	e with EMSL's Term	s and Co	nera or EPA Level II TA anditions located in the Al	 You will be asked to sign nelytical Price Guide.
FUNI - AIF			TEM-AIT 44	.5hr TAT (AHERA	only)	TEM- Dust	
NIOSH 7400			AHERA 40 CF	R, Part 763		☐ Microvac - AST	TM D 5755
W/ OSHA 8hr. TV	and the second s		☐ NIOSH 7402			☐ Wipe - ASTM [
PLM Bulk (reporting			EPA Level II			☐ Carpet Sonicat	ion (EPA 600/J-93/167)
PLM EPA 600/R-9			☐ ISO 10312	4,511		Soil/Rock/Vermic	
PLM EPA NOB (<	1%)	1 3	TEM - Bulk				5 - A (0.25% sensitivity)
Point Count 400 (<0.25%)	1000 (10 10/)	1 7	TEM EPA NOB				5 - B (0.1% sensitivity)
Point Count w/Gravin			NYS NOB 198.	4 (non-friable-NY)		TEM CARB 43	5 - B (0.1% sensitivity)
☐ 400 (<0.25%) ☐ 1		1 2	Chatfield SOP	konta TDA DDD			5 - C (0.01% sensitivity)
☐ NYS 198.1 (friable		Parent.	EM - Water: EPA	-	sis-EPA 600 sec. 2.5 EPA Protocol (Semi-Quan		
☐ NYS 198.6 NOB (_ 1 =			ina	☐ EPA Protocol (Quantitative) Other:	
☐ NYS 198.6 NOB (non-friable-NY) Fibers >10µm ☐ Waste ☐ Drinkin ☐ NIOSH 9002 (<1%) All Fiber Sizes ☐ Waste ☐ Drinkin		4	1 73 77				
11100110002 (-17	The state of the same		itive Stop - Cle				
140	11 /	7/)	iure otop – ote	any lacitaly in	omoge	shous Group	
Samplers Name: /	Januel.	Dona	1+K.C.	Samplers Sign	ature:	7-1	
Sample #		Sa	mple Description			Volume/Area (Air HA # (Bulk)	Date/Time Sampled
1-38	B.11.	· Malaria	1.	*		2	11/-1
	Zwiain	2/14/5/19	7.5			0	4/17/2012
							
				10 to			
				V.()			
	AT A		··· / · · · · · · · · · · · · · · · · ·				
-44	ANaly	ze wh	at's only	in the			
		,	1			£	
	asbesti)> She	(4).				
Client Sample # (s):						Total # of Samples:	<u> </u>
Relinquished (Client):			Date:	1 1		Time	a•
Received (Lab):	-emst-	TED CM		nution			11.400
Comments/Special In:	structions,		Date:	111111		Time	e: 10/411
- Frank Ald	*	First	Stop	Positiv	-	*	
	9.5		Record T	1643/11/4	Winter.	713	



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

miamilab@emsl.com http://www.emsl.com

EMSL Order: 171202028 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166

Phone: (305) 471-7721 (305) 593-1915 Fax: Received: 04/19/12 10:15 AM

Analysis Date: 4/19/2012 Collected: 4/18/2012

Project: Manatee Courthouse - 3rd Floor - Phase 1 - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Description **Appearance** Sample **Fibrous** % Non-Fibrous % Type **None Detected** Concrete 100% Non-fibrous (other) 39 Gray Non-Fibrous 171202028-0001 Homogeneous **None Detected** 40 Concrete 100% Non-fibrous (other) Gray Non-Fibrous 171202028-0002 Homogeneous 41 Floor Tile Green 97% Non-fibrous (other) 3% Chrysotile Non-Fibrous 171202028-0003 Homogeneous 41A Mastic Black 95% Non-fibrous (other) 5% Chrysotile Non-Fibrous 171202028-0003A Homogeneous 42 Floor Tile Stop Positive (Not Analyzed) 171202028-0004 42A Mastic Stop Positive (Not Analyzed) 171202028-0004A Tile **None Detected** 43 White 100% Non-fibrous (other) Non-Fibrous 171202028-0005 Homogeneous Grout 100% Non-fibrous (other) **None Detected** 43A Gray Non-Fibrous 171202028-0005A Homogeneous Limberly a Wallace

Analyst(s)

Kim Wallace (43)

Kimberly Wallace, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202028 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst
 PSI (Miami)
 7950 NW 64th St.
 Miami, FL 33166

Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/19/12 10:15 AM

Analysis Date: 4/19/2012 Collected: 4/18/2012

Project: Manatee Courthouse - 3rd Floor - Phase 1 - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Description **Appearance** Sample **Fibrous** % Non-Fibrous % Type Thin Set **None Detected** 100% Non-fibrous (other) 43B White Non-Fibrous 171202028-0005B Homogeneous Tile **None Detected** White 100% Non-fibrous (other) 44 Non-Fibrous 171202028-0006 Homogeneous 44A Grout Gray 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202028-0006A Homogeneous 44B Thin Set 100% Non-fibrous (other) None Detected Gray Non-Fibrous 171202028-0006B Homogeneous 45 Liquid Nail Yellow 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202028-0007 Homogeneous White 46 Caulk 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202028-0008 Homogeneous 90% Cellulose None Detected 47 Insulation 10% Non-fibrous (other) Brown Fibrous 171202028-0009 Homogeneous Cellulose 48 Insulation Brown 90% 10% Non-fibrous (other) **None Detected** Fibrous 171202028-0010 Homogeneous

Analyst(s)	
Kim Wallace (43)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Limberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202028 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst
PSI (Miami)
7950 NW 64th St.
Miami, FL 33166

Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/19/12 10:15 AM

Analysis Date: 4/19/2012 Collected: 4/18/2012

Project: Manatee Courthouse - 3rd Floor - Phase 1 - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos <u>Asbestos</u> Description **Appearance** Sample **Fibrous** % Non-Fibrous % Type **None Detected** Insulation 10% Non-fibrous (other) 49 90% Cellulose Brown Fibrous 171202028-0011 Homogeneous Block **None Detected** 50 White 2% Cellulose 98% Non-fibrous (other) Non-Fibrous 171202028-0012 Homogeneous 2% Cellulose 51 Block White 98% Non-fibrous (other) **None Detected** Non-Fibrous 171202028-0013 Homogeneous 52 Vapor Barrier 100% Non-fibrous (other) None Detected Black Non-Fibrous 171202028-0014 Homogeneous Vapor Barrier Black 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202028-0015 Homogeneous White 54 Plaster **None Detected** 100% Non-fibrous (other) Non-Fibrous 171202028-0016 Homogeneous None Detected 55 Plaster Peach 100% Non-fibrous (other) Non-Fibrous 171202028-0017 Homogeneous Plaster 56 White 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202028-0018 Homogeneous

Analyst(s)	
Kim Wallace (43)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Limberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202028 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166 Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/19/12 10:15 AM

Analysis Date: 4/19/2012 Collected: 4/18/2012

Project: Manatee Courthouse - 3rd Floor - Phase 1 - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Sample Description **Appearance Fibrous** % Non-Fibrous % Type Drywall White/Orange **None Detected** 10% Cellulose 90% Non-fibrous (other) 57 Fibrous 171202028-0019 Heterogeneous **None Detected** 57A Drywall White 100% Non-fibrous (other) Non-Fibrous 171202028-0019A Homogeneous 10% Cellulose 58 Drywall White 90% Non-fibrous (other) **None Detected** Fibrous 171202028-0020 Heterogeneous 58A Drywall White 100% Non-fibrous (other) None Detected Non-Fibrous 171202028-0020A Homogeneous Insulation Black 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202028-0021 Homogeneous 59A Mastic Black 3% Chrysotile 97% Non-fibrous (other) Non-Fibrous 171202028-0021A Homogeneous None Detected 60 Insulation 100% Non-fibrous (other) Black Non-Fibrous 171202028-0022 Homogeneous 60A Mastic Stop Positive (Not Analyzed) 171202028-0022A

Analyst(s)	
Kim Wallace (43)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Limberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202028 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166 Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/19/12 10:15 AM

Analysis Date: 4/19/2012 Collected: 4/18/2012

Project: Manatee Courthouse - 3rd Floor - Phase 1 - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Sample Description **Appearance Fibrous** % Non-Fibrous % Type **None Detected** 100% Cellulose 0% Non-fibrous (other) 61 Wrap White Fibrous 171202028-0023 Homogeneous Insulation 10% Chrysotile 61A White 90% Non-fibrous (other) Fibrous 171202028-0023A Homogeneous 62 Wrap White 100% Cellulose 0% Non-fibrous (other) **None Detected** Fibrous 171202028-0024 Homogeneous Insulation Stop Positive (Not Analyzed) 62A 171202028-0024A 63 Insulation Black 100% Non-fibrous (other) None Detected Non-Fibrous 171202028-0025 Heterogeneous 63A Mastic White 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202028-0025A Homogeneous Insulation Black 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202028-0026 Homogeneous 64A Mastic White 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202028-0026A Homogeneous

Analyst(s)	
Kim Wallace (43)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Limberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202028 CustomerID: PSI59

CustomerPO: ProjectID:

tn: Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166 Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/19/12 10:15 AM

Analysis Date: 4/19/2012 Collected: 4/18/2012

Project: Manatee Courthouse - 3rd Floor - Phase 1 - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Description **Appearance** Sample **Fibrous** % Non-Fibrous % Type **None Detected** Insulation 100% Glass 0% Non-fibrous (other) 65 Yellow Fibrous 171202028-0027 Homogeneous **None Detected** 65A Mastic White 100% Non-fibrous (other) Non-Fibrous 171202028-0027A Homogeneous 100% Glass 66 Insulation Yellow 0% Non-fibrous (other) **None Detected** Fibrous 171202028-0028 Homogeneous Mastic White 100% Non-fibrous (other) None Detected 66A Non-Fibrous 171202028-0028A Homogeneous A/C Damper Black 20% Synthetic 80% Non-fibrous (other) **None Detected** Fibrous 171202028-0029 Homogeneous 68 A/C Damper White 30% Glass **None Detected** 70% Non-fibrous (other) Fibrous 171202028-0030 Homogeneous 69 Pipe Mastic 97% Non-fibrous (other) 3% Chrysotile Black Non-Fibrous 171202028-0031 Homogeneous 70 Pipe Mastic Stop Positive (Not Analyzed) 171202028-0032

Analyst(s)	
Kim Wallace (43)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Emberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0

171202028



Asbestos Chain of Custody EMSL Order Number (Lab Use Only):

EMSL A DETTICAL AT 19501 NE 10 TAVE BAY A NORTH MIAM BEACH FL 33179

PHONE. (805) 650-6577 FAX: (305) 650-0578

Company: PSI, Street: 7950 11	Miami	EMS	L-Bill to: Same sis Different note instructions i	Different	
L CONTRACTOR	W 64th Street				
City: Miami	Mami State/Province: Flo		ng requires written authorit		
Report To (Name): Gle	ny tothouse	Zip/Postal Code:		ountry:	
Telephone #: 786-2	36-0102				
Project Name/Number		Email Address:			
Please Provide Results:		- 3/2 Floor - Phys	el-05529	03	
	The state of the s	497.	I State Camerine T.	ken:	
☐3 Hour ☐ 6 Hour	24 Hour 48 Hour	T) Options* – Please Cr	neck		
an authorization form for the	The same of the sa	nium charge for 3 Hour TEM	96 Hour 1 We	ek 2 Week	
PCM - Air	is service. Analysis completed in accorder TEM - Air 14	nce with EMSL's Terms and C	Conditions located in the Ani	You will be asked to significal Price Guide	
☐ NIOSH 7400	j	men the function office	TEM- Dust	- Jacob Frice Galloe,	
WOSHA 8hr. TWA	AHERA 40 C	FR, Part 763	☐ Microvac - AST	VID 5755	
PLM - Bulk (reporting limit)	☐ NIOSH 7402		☐ Wipe - ASTM De		
□ PLM EPA 600/R-93/116 (<1)	☐ EPA Level II			on (EPA 600/J-93/167	
☐ PLM EPA NOB (<1%)	100 10012		Soil/Rock/Vermicu	lite	
Point Count	TEM - Bulk		TPIM CARR 435	- A (0.25% sensitivity	
☐ 400 (<0.25%) ☐ 1000 (<0.1	☐ TEM EPA NOE		TPIM CARR 435	P (0.23% Sensitivity	
Point Count w/Gravimetric	1 11 14 14 190 190	.4 (non-friable-NY)	PLM CARB 435 - B (0.1% sensitivity)		
1400 (<0.25%) [] 1000 (=0.4	☐ Chatfield SOP		TEM CARB 435 - B (0.1% sensitivity)		
☐ 400 (<0.25%) ☐ 1000 (<0.1	%) TEM Mass Ana	lysis-EPA 600 sec. 2.5	☐ TEM CARB 435 - C (0.01% sensitivity ☐ EPA Protocol (Semi-Quantitative) ☐ EPA Protocol (Quantitative)		
NYS 198.1 (friable in NY)	TESS INC.	A 100.2			
NYS 198.6 NOB (non-friable	Fibers >10µm	Waste Drinking	Other:	rarillative)	
NIOSH 9002 (<1%)	All Fiber Sizes	Waste Thrinking			
	Check For Positive Stop - Cle	arty Identify Homos	100		
omniam M. All	1/20/	T TOTAL TOTAL OF THE PARTY OF T	enous Group		
ampiers Name: //amu	Lorras	Samplers Signature:	1		
Sample #	Sample Description		Volume/Area (Air)	Date/Time	
29-70 P	Outspie Description		HA # (Bulk)	Sampled	
21 70 100	Valley Marina		R	minol.	
			2	7/18/12	
		122270000000000000000000000000000000000			
- HI	<u> </u>				
AND	lyze what's only	. 11			
		in the			
asbes	stos sheet "				
nt C					
nt Sample # (s):	•	Tr	otal # of Samples:		
nquished (Client):	D-4		tar w or Samples:		
eived (Lab): AF-EM W	Date:	itatio	Time:		
ments/Special Instructions:	Date: 0	1119112	Time: /	0:15Am	
	1 1	Lymn &	ilme: /	<u> </u>	
*	First Stop	Pasitive >	¥		
			**		
				The same of the sa	

Information I To Build On Engineering • Consulting • Testing	SBESTOS BULK SA)G	**************************************	
Homogeneous Area Sample Number Material Description	Sample Location	Approximate Quantity	% Asbestos Type	NESHAP Category	Comments
Terrazo Flooring	North Area	11, 900'50			
1 2	Middle West Court Room				man subscients and to describe the control of the c
Black Floor Mastic	North Area	8,9cosq	7		
2) 4	Middle Est Room				
3 5 Yellow Carpet Mastic	N.E. Room	6.800'sq	AND CONTROL OF THE PROPERTY OF		
3 6	Middle West Court Room		NAME AND ADDRESS OF THE PARTY O		
ly z		600 Line	20/		
White Window Caulk	Northwest Area		2000		
4 8	Southeast Court Room				
5 9 Red Fire Caulk	"North Room	600 Line			

Engineering •	Inform ITo Build Consulting • 1	ation d On A esting	ASBESTOS BULK SA	AMPLE LO)G		
Homogeneous Area	Sample Number	Material Description	Sample Location	Approximate Quantity	% Asbestos Type	NESHAP Calegory	Comments
5 Red	Fire	as/K	Southeast Wall				
6 12"412 Mastir	" Beige	erfyellm	Northeast Hallway	2, 500kg			
<u> </u>	12		South Hallway				ngambalaki king napi kao napandaki king napan napan kao napangamba taur na ka king
12" × 12" Modic	13 Buk F Turper	I It tyellow Layer	North Hallway	500 ¹ 39			
F			South Hallway				
8 12'412' Yelow 1	15 1246 Tastic	I way Ff t Opper Jayon	Northeat Room	110'59			
	16		North east Room			,	
121/x12 Bbok	Martin	Lowerlage	Northwest Hallway	2,500se	3		
9	78		South Hallway				

Information
To Build On ASBESTOS BULK SAMPLE LOG NESHAP Approximale Comments % Asbestos Type Sample Location Material Description Sample Number Homogeneous Area Quantity Category 200/59 10 Sheet Vinyl of mastic Southeast Restmon 10 Southwest Restroom 800\$g 21 Southeast Wall Paper + Mastic Restroom Southwest Restroom 600 Lineal 23 Black baseboard of Yastis Middle West 12 Northwest Halwary 30 Lineal Northeast Office Tan basebonnot/ bastic 30 Lineal Northeast Gray baseboard + Mastic Office 990 Live al Northwest Burgandy baseboard + Courtroom

Them at of house thouse I was to to to to the - the see I

Harriet De Continues 311 Floor And Co Information
To Build On
Engineering • Consulting • Testing ASBESTOS BULK SAMPLE LOG NESHAP Approximate Comments % Asbestos Type Sample Number Material Description Sample Location Homogeneous Area Quantity Category Morth Hallway Burgandy Baseboard + Rolineal Northwest Tan Mastic w/out baseboard Arrea 240 Lind 20 North Area Black Mostic what baseboard 30'sq! Black Ale Duct Hastic Middle East Courtroom Middle Halway Remaining "Spoks" on the Metal A/C duet 1,150/2/20 White A/C Duct Mastic Middle East Courtroom Middle West Court room 35 20 Black & ANK AIK Duck Middle West This material is inside the A/C duct. Interior Insulation Court room Middle East Courtroom

Information
To Build On ASBESTOS BULK SAMPLE LOG Engineering . Consulting . Testing Approximate **NESHAP** Comments % Asbestos Type Homogeneous Area 🛭 Sample Number Material Description Sample Location Category 10'sa1 North Halway Tan Ale Duct Mastic 60'Lineal Dark Brown Mastic Wort baseboard Northeast Room 200'59 Dew A/C Room Base Graele New A/C Room 300'sq 12 1/2" Life Green Ft. of South Stairs Landind North Stairs Landing 80050 26 Men Restroom 1"x 1" Tile w/ Grout + thinset (Multicolor) 26 Southeast Hallway South 2000 30 Liquid Nail Hallway 3' feet Design Panel (Hallway + Courtnoon)
"non asbestos suspect" one sample-

Manager Son Chare - 3rd Han - 171085 de

Information ASBESTOS BULK SAMPLE LOG Engineering • Consulting • Testing					
Hornogeneous Area Sample Number Material Descr	ption Sample Location	Approximate % Asbestos T	ype NESHAP Category	Comments	
28 46		800'5g			
Wood Trim Caulk	Hallway	All around the	e wood wo	rk ectore <i>sample</i>	
29 47	основного в противо общения общения общений в поставлений в поста	13,000/54		ama mantan ara on peru arawa arawa mana menjengah pengengan pengengah pengengan pengengan pengengan pengengah p	
Wall Insulation	Middle West Courtroom				
29 48					
	Middle Hallway				
29 49					
7	Southwest Hallway				
30 50		6,50050			
Ryrobar Block	Middle Hallung				
31 5/	9,000000000000000000000000000000000000	·		Pikitakaiki 1944-ki - kikus Pikitak in 1944-ki kitak Antan Annas an monkoo ki na macaa casaa sabira a	
	Northeast Avea				
<i>32 5</i> 2		16,400'sg	iootekkomobioassa usoioanessa intimiettiini		
Black Vapor Barrier	Middle West Court room	- 4			
32 53					
V	Middle East Court room				
33 54 Ceilina		21,500sg			
33 54 Ceiling White Plaster over Heach Coat	Northeast Wall				

Information Inform	ion On A	ASBESTOS BULK S	AMPLE LO	OG		
Homogeneous Area Sample Number	Material Description	Sample Location	Approximate Quantity	% Asbestos Type	NESHAP Category	Comments
33 55	Uhii					
white Plaster c	over Gat	Middle Est Wall	akopia selakika kanda			
33 56		одну мустом подосто на под				
		Middle Hallway	ooleen jade op anderstande op anders			
34 57			12,5605	J.		
Drywall Mudt	Tape	Northwest Hallway		7		·
34 58	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\					
		Center Hallway				·
85) 59			120 Lin	eu/	***********************	
4" Stink Rock Pil yo black Masi	PeInsulation tic	Center East n Courtroom				
(3分) (40)	[:	110-4			TTO CENTED COMMON THE SECOND CO.	
		Hallway west Side				
(36) [6]			120'Linee			
2" White Rap	N TOB	Center Est				
Insulation		Gurtroom				
<u> </u>		Middle (West Hallmay Side)				
37 63			500' Line	e/		
4" Stink Bock Pipe & White Mastic	E Tusuladion	Southeast AK Room				

Information To Build On ASBESTOS BULK SAMPLE LOG Engineering • Consulting • Testing						
Homogeneous Area Sample Number	Material Description	Sample Location	Approximate Quantity	% Asbestos Type	NESHAP Category	Comments
38 64			and the second s			
4" Stink Rock Pipe.	Insulation	South Hallway				
of White Mastic	,,,	AK Room				
39 65	<u>(Marine Marine) (Marine) (Mar</u>	Sallas JAA	506/2°ne	e/		Control of the Contro
39 65 4" Yellow Fiberalis	s Ape Insulati	200 Room				
& White Mastic	· ·					уудын сорын үүрөө үнд үнд амига тамага тамага тамага байган амын үнөө бай үүрөө амын амын амын амага тамага
39 66						
AND CONTRACTOR OF THE CONTRACT		SouthHallway AIC Room				
40 67		<u>aka ketin kan minister makera kemining akan untuk pangan panda pangan keting di Add Perla</u>	16'59			
Block AK Da	m per	Middle East Gurt Room				•
40 68		egenperatura en en estado en	30'sg			
White AK Do	rmper	South west Hallway AK R	ŕ			
(4) 69			950 Ln	r <i>col</i>		<u>wake kalapata Mari Unan Maria anda anda anda anda anda Maria Mari</u>
Black Pipe 1	Pastic	Steel Cast AIC Lines-North Side Italiway		America (all chickes a sound conserve communication)	odenova oce i stre zavenove e e promo a na d	
(41) 1 70 VI	COLUMN TO COMMON	<u> </u>				
		Steel Cast AK Lines-South Side				•
V	,	Hallway				
		<i></i>				
	ere e					
South Side	s Next				***************************************	
					MARIE CHIMINAL CHILDREN CONTROL	



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202026 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166 Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/19/12 10:15 AM

Analysis Date: 4/19/2012 Collected: 4/18/2012

Project: Manatee Courthouse - 3rd Floor - Phase II - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos <u>Asbestos</u> Sample Description **Appearance Fibrous** % Non-Fibrous % Type **None Detected** Concrete Floor 100% Non-fibrous (other) 71 Gray Deck Non-Fibrous 171202026-0001 Homogeneous 72 Concrete Floor **None Detected** 100% Non-fibrous (other) Grav Deck Non-Fibrous 171202026-0002 Homogeneous 73 Concrete Ceiling Gray 100% Non-fibrous (other) **None Detected** Deck Non-Fibrous 171202026-0003 Homogeneous Concrete Ceiling 100% Non-fibrous (other) None Detected Gray Deck Non-Fibrous 171202026-0004 Homogeneous 75 A/C Duct Mastic Black 91% Non-fibrous (other) 9% Chrysotile Non-Fibrous 171202026-0005 Homogeneous 76 A/C Duct Mastic Stop Positive (Not Analyzed) 171202026-0006 A/C Duct Mastic Tan 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202026-0007 Homogeneous 78 A/C Duct Mastic Tan 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202026-0008 Homogeneous

Analyst(s)	
Natasha Montova (39)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Limberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202026 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn PotharstPSI (Miami)7950 NW 64th St.Miami, FL 33166

Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/19/12 10:15 AM

Analysis Date: 4/19/2012 Collected: 4/18/2012

Project: Manatee Courthouse - 3rd Floor - Phase II - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Description **Appearance** Sample **Fibrous** % Non-Fibrous % Type Baseboard **None Detected** 100% Non-fibrous (other) 79 Black Non-Fibrous 171202026-0009 Homogeneous Mastic 2% Chrysotile 79A 98% Non-fibrous (other) Brown Non-Fibrous 171202026-0009A Homogeneous 80 Baseboard Red/Purple 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202026-0010 Homogeneous Mastic 100% Non-fibrous (other) None Detected 80A Beige Non-Fibrous 171202026-0010A Homogeneous Plaster Gray/Tan 20% Cellulose 80% Non-fibrous (other) **None Detected** Fibrous 171202026-0011 Heterogeneous 81A Coat <1% Glass 100% Non-fibrous (other) **None Detected** Gray Non-Fibrous 171202026-0011A Homogeneous None Detected 82 Plaster Cellulose 80% Non-fibrous (other) Gray/Tan 20% Fibrous <1% Glass 171202026-0012 Heterogeneous 82A Coat Gray 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202026-0012A Homogeneous

Analyst(s)	
Natasha Montoya (39)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Limberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202026 CustomerID: PSI59

CustomerPO: ProjectID:

Attn: Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166 Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/19/12 10:15 AM

Analysis Date: 4/19/2012 Collected: 4/18/2012

Project: Manatee Courthouse - 3rd Floor - Phase II - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

	Non-Asbestos			<u>oestos</u>	<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
83 171202026-0013	Plaster	Gray/Tan Fibrous Heterogeneous	20% Cellulose <1% Glass	80% Non-fibrous (other)	None Detected
83A 171202026-0013A	Coat	Gray Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
84 171202026-0014	Block	White Non-Fibrous Homogeneous	<1% Cellulose	100% Non-fibrous (other)	None Detected
85 171202026-0015	Block	White Non-Fibrous Homogeneous	<1% Cellulose	100% Non-fibrous (other)	None Detected
86 171202026-0016	Carpet Mastic	Yellow Non-Fibrous Homogeneous	<1% Synthetic	100% Non-fibrous (other)	None Detected
87 171202026-0017	Carpet Mastic	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
88 171202026-0018	Sheet Vinyl Flooring	Gray/Beige Fibrous Heterogeneous	5% Cellulose 20% Synthetic 5% Glass	70% Non-fibrous (other)	None Detected
89 171202026-0019	Wallpaper	Tan/White Fibrous Heterogeneous	95% Cellulose	5% Non-fibrous (other)	None Detected

Analyst(s)	
Natasha Montoya (39)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Emberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202026 CustomerID: PSI59

Achaetae

CustomerPO: ProjectID:

Glenn PotharstPSI (Miami)7950 NW 64th St.Miami, FL 33166

Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/19/12 10:15 AM

Analysis Date: 4/19/2012 Collected: 4/18/2012

Non-Asbestos

Project: Manatee Courthouse - 3rd Floor - Phase II - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

	NOII-ASDESIOS		<u>bestos</u>	ASDESTOS	
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
90 171202026-0020	Drywall	Gray/Tan Fibrous Heterogeneous	10% Cellulose	90% Non-fibrous (other)	None Detected
90A 171202026-0020A	Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
91 171202026-0021	Drywall	Gray/Tan Fibrous Heterogeneous	10% Cellulose <1% Glass	90% Non-fibrous (other)	None Detected
91A 171202026-0021A	Joint Compound	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
92 171202026-0022	Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
93	Fire Caulk	Red Non-Fibrous Homogeneous	<1% Glass	100% Non-fibrous (other)	None Detected
94	Liquid Nail	Yellow Non-Fibrous Homogeneous	<1% Cellulose	100% Non-fibrous (other)	None Detected
95 171202026-0025	Sink Undercoat	Black Non-Fibrous Homogeneous		98% Non-fibrous (other)	2% Chrysotile

Analyst(s)

Natasha Montoya (39)

Kimberly Wallace, Laboratory Manager or other approved signatory

Emberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202026 CustomerID: PSI59

CustomerPO: ProjectID:

th: Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166 Phone: (305) 471-7721 Fax: (305) 593-1915 Received: 04/19/12 10:15 AM

Analysis Date: 4/19/2012 Collected: 4/18/2012

Project: Manatee Courthouse - 3rd Floor - Phase II - 0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Description **Appearance** Sample **Fibrous** % Non-Fibrous % Type **None Detected** Vapor Barrier <1% Cellulose 100% Non-fibrous (other) 96 Black Non-Fibrous 171202026-0026 Homogeneous Floor Tile **None Detected** 97 Beige 100% Non-fibrous (other) Non-Fibrous 171202026-0027 Homogeneous 97A Mastic Yellow 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202026-0027A Homogeneous 98 Floor Tile Pink 100% Non-fibrous (other) None Detected Non-Fibrous 171202026-0028 Homogeneous 98A Mastic Yellow 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202026-0028A Homogeneous 99 Floor Tile 3% Chrysotile Green 97% Non-fibrous (other) Non-Fibrous 171202026-0029 Homogeneous 99A 93% Non-fibrous (other) 7% Chrysotile Mastic Black Non-Fibrous 171202026-0029A Homogeneous 100 Insulation Tan 100% Cellulose 0% Non-fibrous (other) **None Detected** Fibrous 171202026-0030 Homogeneous

Analyst(s)	
Natasha Montoya (39)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Lomberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



Asbestos Chain of Custody EMSL Order Number (Lab Use Only):

171202026

EMSL AVALYTICAL INC 19501 NE 10 TAVE BAY A NORTH MIAM BEACH FL 33179

> PHONE. (305) 650-0577 FAX: (305) 650-0576

Company: PSI, Miami			if Bill to is	-Bill to: Same I Different note instructions in	Comments**
Street: 7950 N	1	street	Third Party Billing Zip/Postal Code:	requires written authoriza	
City: Miami Report To (Name): Gle				Col	intry:
			Fax #:		
Telephone #: 786-2	36-9102	A	Email Address:	,	
Please Provide Results: Fax VEmail Purchase Orde					2903
riease Frovide Results.		urchase Orde	r: U Options* – Please Che	.S. State Samples Tai	Cen:
☐3 Hour ☐ 6 Hour		48 Hour		96 Hour 1 1 Wee	k
*For TEM Air 3 hr through 6 hr, p.	lease cell ahead to schedule.	*There is a premi	um charge for 3 Hour TEM A	HERA OF EPA Level II TAT.	You will be asked to sign
PCM - Air			e with EMSL's Terms and Co 5hr TAT (AHERA only)	TEM- Dust	ytical Price Guide.
☐ NIOSH 7400		AHERA 40 CF		Microvac - ASTN	D 5755
MOSHA 8hr. TWA	100	NIOSH 7402	14, 101, 100	☐ Wipe - ASTM D6	
PLM - Bulk (reporting limit)		EPA Level II			n (EPA 600/J-93/167)
PLM EPA 600/R-93/116 (The state of the s	ISO 10312		Soll/Rock/Vermicu	
☐ PLM EPA NOB (<1%)		1 - Bulk	VI =		A (0.25% sensitivity)
Point Count	1	EM EPA NOB		PLM CARB 435	
□ 400 (<0.25%) □ 1000 (<	- 1 TT 1		(non-friable-NY)	TEM CARB 435	
Point Count w/Gravimetric	, 0	Chatfield SOP		☐ TEM CARB 435	C (0.01% sensitivity)
□ 400 (<0.25%) □ 1000 (<	0.1%)	EM Mass Ana	ysis-EPA 600 sec. 2.5	☐ EPA Protocol (Se	mi-Quantitative)
NYS 198.1 (friable in NY)	TEN	I - Water: EP/	. 100.2		rantitative)
NYS 198.6 NOB (non-fria	ble-NY) Fibe	irs >10µm 🔲	Waste Drinking		
☐ NIOSH 9002 (<1%)			Waste Drinking	0	
	Check For Positiv	re Stop – Cle	arly identify Homog	enous Group	
Samplers Name: Man	uelboras		Samplers Signature:	7	
Sample #		le Description	.+	Volume/Area (Air) HA # (Bulk)	Date/Time Sampled
71-100 3	willing the	Grisk		3	4/18/12
	Managara Managara and Angara and A				
		-1			
		x	7		
/ h1/		$I \subseteq I$	11		
A_{λ}	salyze what	ts only	in the		
				•	
06	hestos choo	+"			
as	bestos shee	f."		· · ·	
as	bestos shee	f."			
Client Sample # (s):	bestos shee	f."		Total # of Samples:	
	bestos shee	f " Date:		Total # of Samples:	
Client Sample # (s): Relinquished (Client):		Date:	- distro	Time	1016 100
Client Sample # (s):	SL-FEDEN	Date:	- distro	Time Time	1016 100

Manate Controsse - 3rd Floor - Phase 15 /18/12

Inform To Build	ation 4 On P	ASBESTOS BULK S)G	eri	<u> </u>
Engineering • Consulting • 1 Homogeneous Area Sample Number	esung Material Description	Sample Location	Approximate Quantity	% Asbestos Type	NESHAP Category	Comments
42 71			8.000'sa			
Bane Corcrete F	bor Deck	Sootheast Room	<i>_</i>			·
42 72			Annual Control of the			
		South middle Cortroom	A CONTRACTOR AND A CONT		, .	•
43 73			3000'sa			
Bare Concrete (Teiling Deck	Southeas Room				
43 74						
		South Mobile Courtroom				·
Black A/C Dic	t Mustic	Southeast Room	10059		aarkent Administrativa nõlandi vaurun õverent All-Addel	
(F) 76		South Middle Room	A CONTRACTOR OF THE PROPERTY O			
45 77			105°S4			
Tom ALC Duct 1	Mostic	South Center Gurtroom				
45 78 		South Hallway			manuschin der Schreibung der Schreib	
G6)79	1 . 21 10	4 a 1 . 1 . 5	90' Linear	C	1	s e s
Black Baseboan	I yI PASHE	South east Halleay	Non asbes Phase	tos sus pe 1 – Gna	d-Same Imalian	e as the other Sample

Information
To Build On ASBESTOS BULK SAMPLE LOG % Asbestos Type Material Description Sample Location Comments Sample Number Category Northeast Burgardy Baseboard y Mastic Office Non asbestos suspectmaterial-same as the Phose I-Confirmation Sample 9000'sa Wall Plaster over Gray Chat South Room SoutheastHallway Southwest Wall 5/50000 Probar Block South Room South Center Hallway 700050 Yellow Conget Mosfic SoutheastRoom Southwat Office 120'59 Southwest Restroom & Some as the other North Side Confirmation Sample Sheet Viny/ Floring

Hamolog Carlage Std Yber - Prose OI

Information To Build On Engineering • Consulting • Testing	ASBESTOS BULK S	AMPLE LOG	
Homogeneous Area Sample Number Material Descri	otion Sample Location	1 % Ashestos Tynet	SHAP Comments
52 89 Wall Paper	Southwest Restro	120sq Some as the ath Somple	er side-Canflomatio
53 90 Drywall Mid + Tope	Soldwest Chiefron	13,000 sq	
<u> </u>	South Hallway	The second secon	
54 92 White Window Golk	South wast Court your	500 Lineal Somme material as Compre material S	the other side ample
55 93 Red Fire Caulk	Southeast Rom	600 Line 1	
56 94 Liquid Nail	th/hway	6.000 sq Non asbestas Suspect The other Side - Gon	makrial-Same as firmation Sample
Black Sink Undercoat	South east Room	4'sq	
58 96 Black Vapor Barrier	South Wall	1,800 = 9	
59 97 12'k 12''Beige Ft. + Yellow Mastic Upper l	1-lallway	Confirmation Sum other those-(Sid	ple-Same as the

Ť.

Hardre Calloge 3d Har- Hore II

Information ASBESTOS BULK SAMPLE LOG Engineering • Consulting • Testing				
Homogeneous Area Sample Number Material Description	Sample Location	Approximate % Asbestos Type NESHAP Comments Quantity Category		
60 98 12"X12" Rink Fit + Yellow Mastic (Upperlayer)	Hallway	150'sg Confirmation Sample -Same as the other Side - (Phase-or-North Side)		
61) 99 12"X12" Lite Green Ft & Black Mastic - (Lower Layer)	South Center Cortinom	9.000'so Confirmation Sample-Same as the other side-(North Side)		
62 100 Wall Interior Insulation	South Hallway	13.00039 Confirmation Sample - Sameas the other side (North Side)		
63 101 Gray AK Duct Mastic	Southwest Courtroom	60'39		
64 102 Black Stink Rock & White Mastic	Sulhwest AK Room	Some type as the other side. (North Side)		
Blank & Jellow AIC Duct Interior Insulation	South Center Cortrogn	<u>4,500 sg'</u>		
Tom Coulk	South Hallway	100 39		
67 105 Block Mastic	Steel Cast Pipe-Hallway	300 Lineal Confirmation Sample-Some as the other Side (North Side)		



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

miamilab@emsl.com http://www.emsl.com

EMSL Order: 171202068 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166

Phone: (305) 471-7721 Fax: (305) 593-1915 04/23/12 8:00 AM Received: Analysis Date: 4/23/2012

Collected:

Project: Manatee Courthouse - Mezzanine PR#0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

			Non-As	sbestos	<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
1	Ceiling Tile	Gray/White	55% Cellulose	40% Non-fibrous (other)	None Detected
171202068-0001		Fibrous Heterogeneous	5% Glass		
2	Ceiling Tile	Gray/W hite	55% Cellulose	40% Non-fibrous (other)	None Detected
171202068-0002		Fibrous Heterogeneous	5% Glass		
3	Ceiling Tile	Gray/W hite	55% Cellulose	40% Non-fibrous (other)	None Detected
171202068-0003		Fibrous Heterogeneous	5% Glass		
4	Drywall	Gray/Tan	20% Cellulose	80% Non-fibrous (other)	None Detected
171202068-0004		Fibrous Heterogeneous	<1% Glass		
4A	Joint Compound	White		100% Non-fibrous (other)	None Detected
171202068-0004A		Non-Fibrous Homogeneous			
5	Drywall	Gray/Tan	15% Cellulose	85% Non-fibrous (other)	None Detected
171202068-0005		Fibrous Heterogeneous	<1% Glass		
5A	Joint Compound	White		100% Non-fibrous (other)	None Detected
171202068-0005A		Non-Fibrous Homogeneous			
6	Drywall	Gray/Tan	15% Cellulose	85% Non-fibrous (other)	None Detected
171202068-0006		Fibrous Heterogeneous	<1% Glass		

Analyst(s) Natasha Montoya (46)

Kimberly Wallace, Laboratory Manager or other approved signatory

Emberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

miamilab@emsl.com http://www.emsl.com

EMSL Order: 171202068 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst **PSI (Miami)** 7950 NW 64th St. Miami, FL 33166

(305) 471-7721 Phone: (305) 593-1915 Fax: Received: 04/23/12 8:00 AM Analysis Date: 4/23/2012

Collected:

Project: Manatee Courthouse - Mezzanine PR#0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Description **Appearance** Sample **Fibrous** % Non-Fibrous % Type **None Detected** Joint Compound 100% Non-fibrous (other) 6A White Non-Fibrous 171202068-0006A Homogeneous **None Detected** 7 Vinyl Flooring Gray/Beige 15% Cellulose 78% Non-fibrous (other) Fibrous Glass 171202068-0007 Heterogeneous Wollastonite Carpet Mastic Black/Yellow 2% Cellulose 93% Non-fibrous (other) 5% Chrysotile Non-Fibrous 171202068-0008 Heterogeneous Carpet Mastic Stop Positive (Not Analyzed) 171202068-0009 Plaster White <1% Cellulose 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202068-0010 Homogeneous 10A Plaster 100% Non-fibrous (other) **None Detected** Gray Non-Fibrous 171202068-0010A Homogeneous **None Detected** Plaster White 100% Non-fibrous (other) Non-Fibrous 171202068-0011 Homogeneous 11A Plaster 100% Non-fibrous (other) **None Detected** Grav Non-Fibrous 171202068-0011A Homogeneous Emberly a Wallace

Analyst(s)

Natasha Montoya (46)

Kimberly Wallace, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

miamilab@emsl.com http://www.emsl.com

EMSL Order: 171202068 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166

Phone: (305) 471-7721 Fax: (305) 593-1915 04/23/12 8:00 AM Received: Analysis Date: 4/23/2012

Collected:

Project: Manatee Courthouse - Mezzanine PR#0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

			Non-As	<u>sbestos</u>	<u>Asbestos</u>
Sample	Description	Appearance	% Fibrous	% Non-Fibrous	% Type
12 171202068-0012	Caulk	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
13 171202068-0013	Baseboard	Black Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
13A 171202068-0013A	Mastic	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
14 171202068-0014	Baseboard	Red/Purple Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
14A 171202068-0014A	Mastic	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
15 171202068-0015	Carpet Glue	Yellow/Green Non-Fibrous Heterogeneous		100% Non-fibrous (other)	None Detected
15A 171202068-0015A	Leveling Compound	Gray Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
15B 171202068-0015B	Mastic	Black Non-Fibrous Homogeneous		94% Non-fibrous (other)	6% Chrysotile

Analyst(s) Natasha Montoya (46)

Kimberly Wallace, Laboratory Manager or other approved signatory

Lomberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202068 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn PotharstPSI (Miami)7950 NW 64th St.Miami, FL 33166

Phone: (305) 471-7721
Fax: (305) 593-1915
Received: 04/23/12 8:00 AM
Analysis Date: 4/23/2012

Collected:

Project: Manatee Courthouse - Mezzanine PR#0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Description **Appearance** Sample **Fibrous** % Non-Fibrous % Type **None Detected** Carpet Glue <1% Synthetic 100% Non-fibrous (other) Yellow/Green 16 Non-Fibrous 171202068-0016 Heterogeneous **None Detected** 16A Leveling 100% Non-fibrous (other) Gray Compound Non-Fibrous 171202068-0016A Homogeneous 16B Mastic Stop Positive (Not Analyzed) 171202068-0016B Pyrobar Block White 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202068-0017 Homogeneous 18 Pipe Mastic White/Yellow 45% Glass 53% Non-fibrous (other) **None Detected** Insulation Fibrous <1% Synthetic 171202068-0018 Heterogeneous 2% Cellulose Insulation 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202068-0019 Homogeneous 15% Chrysotile 19A Mastic Black 85% Non-fibrous (other) Non-Fibrous 171202068-0019A Homogeneous 20 Insulation 100% Non-fibrous (other) **None Detected** Black Non-Fibrous 171202068-0020 Homogeneous

Analyst(s)

Natasha Montoya (46)

Kimberly Wallace, Laboratory Manager or other approved signatory

Emberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202068 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst PSI (Miami) 7950 NW 64th St. Miami, FL 33166 Phone: (305) 471-7721
Fax: (305) 593-1915
Received: 04/23/12 8:00 AM
Analysis Date: 4/23/2012

Collected:

Project: Manatee Courthouse - Mezzanine PR#0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Description **Appearance** Sample **Fibrous** % Non-Fibrous % Type **None Detected** Foil White/Silver 50% Non-fibrous (other) 20A 50% Cellulose Fibrous 171202068-0020A Heterogeneous Stop Positive (Not Analyzed) 20B Mastic 171202068-0020B Insulation White 95% Cellulose 5% Non-fibrous (other) **None Detected** Fibrous 171202068-0021 Homogeneous 21A Mastic White 5% Synthetic 95% Non-fibrous (other) **None Detected** Non-Fibrous 171202068-0021A Homogeneous 22 A/C Dampener 30% Glass 70% Non-fibrous (other) **None Detected** Black Non-Fibrous 171202068-0022 Homogeneous 23 A/C Mastic Gray 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202068-0023 Homogeneous 23A A/C Mastic White <1% Synthetic 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202068-0023A Homogeneous 24 A/C Mastic 100% Non-fibrous (other) **None Detected** Grav Non-Fibrous 171202068-0024 Homogeneous

Analyst(s)

Natasha Montoya (46)

Kimberly Wallace, Laboratory Manager or other approved signatory

Limberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1%

Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202068 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn Potharst
PSI (Miami)
7950 NW 64th St.
Miami, FL 33166

Phone: (305) 471-7721
Fax: (305) 593-1915
Received: 04/23/12 8:00 AM
Analysis Date: 4/23/2012

Collected:

Project: Manatee Courthouse - Mezzanine PR#0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Sample Description **Appearance Fibrous** % Non-Fibrous % Type **None Detected** Insulation 33% Non-fibrous (other) 25 Yellow 65% Glass Fibrous 2% Cellulose 171202068-0025 Heterogeneous Plaster **None Detected** 26 White 100% Non-fibrous (other) Non-Fibrous 171202068-0026 Homogeneous 27 Vapor Barrier Black 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202068-0027 Homogeneous 28 Plaster Peach 100% Non-fibrous (other) None Detected Non-Fibrous 171202068-0028 Homogeneous Plaster Peach 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202068-0029 Homogeneous 30 Floor Tile 3% Chrysotile Green 97% Non-fibrous (other) Non-Fibrous 171202068-0030 Homogeneous None Detected 30A 100% Non-fibrous (other) Carpet Mastic Yellow <1% Synthetic Non-Fibrous 171202068-0030A Homogeneous 30B Mastic Black 95% Non-fibrous (other) 5% Chrysotile Non-Fibrous 171202068-0030B Homogeneous

Analyst(s)	
Natasha Montoya (46)	

Kimberly Wallace, Laboratory Manager or other approved signatory

Emberly a Wallace

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



19501 NE 10th Ave. Bay A, N. Miami Beach, FL 33179

Phone/Fax: (305) 650-0577 / (305) 650-0578

http://www.emsl.com miamilab@emsl.com

EMSL Order: 171202068 CustomerID: PSI59

CustomerPO: ProjectID:

Glenn PotharstPSI (Miami)7950 NW 64th St.Miami, FL 33166

Phone: (305) 471-7721
Fax: (305) 593-1915
Received: 04/23/12 8:00 AM
Analysis Date: 4/23/2012

Collected:

Project: Manatee Courthouse - Mezzanine PR#0552903

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 and/or EPA 600/M4-82-020 Method(s) using Polarized Light Microscopy

Non-Asbestos **Asbestos** Sample Description **Appearance Fibrous** % Non-Fibrous % Type Floor Tile Stop Positive (Not Analyzed) 31 171202068-0031 31A Carpet Mastic Yellow <1% Synthetic 100% Non-fibrous (other) **None Detected** Non-Fibrous 171202068-0031A Homogeneous Mastic Stop Positive (Not Analyzed) 171202068-0031B

Analyst(s)

Natasha Montoya (46)

Emberly a Wallace

Kimberly Wallace, Laboratory Manager or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. None Detected = <1% Samples analyzed by EMSL Analytical, Inc. N. Miami Beach, FL NVLAP Lab Code 200204-0



Asbestos Chain of Custody EMSL Order Number (Lab Use Only):

171202068

EMSL AWALYTICA INC. 19601 NE 10^T AVE BAY A NORTH MIAM BEACH FL 33179

PHONE: (305) 650-0577 FAX: (305) 650-0578

Street: 7950 City: Miami	NW 641		Third Party Billi	SL-Bill to: Same [is Different note instructions ing requires written author	s in Comments**
Report To (Name):	2/ 57	elProvince: Fla	Zip/Postal Code:		Country:
Tolorband 70/	Henn Potho	ivst	Fax#:		- Julies y
Telephone #: 786 -			Email Address:		
Project Name/Number: Please Provide Results		Courthouse	MOZZA	100 DDH	455 2005
	The state of the s	all Purchase Or	der	II C Chain Committee	Jakon:
☐3 Hour ☐ 6 Ho	eur 24 Hou	maround Time (TA	T) Options* ~ Piease C	heck	
*For TEM Air 3 hr through 6 h an authorization form PCM - Air	r manage sall at a contra	And the second s	72 Hour	96 Hour 1 1 W	eek 2 Wee
PCM - Air	for this service. Analysi	s completed in accorda	mium charge for 3 Hour TEM noe with EMSL's Terms and (Conditions located in the A	T. You will be asked to
☐ NIOSH 7400		and the second s	MANUAL INT. INTERNA DUILA	TEM-Dust	The Golde.
WOSHA Shr. TWA		AHERA 40 C	FR, Part 763	☐ Microvac - AST	TM D 5755
PLM - Bulk (reporting fire	nit)	☐ NIOSH 7402		☐ Wipe - ASTM [06480
☐ PLM EPA 600/R-93/116 (<1%)		☐ EPA Level II	i c	☐ Carpet Sonication (EPA 600/J-93/1	
☐ PLM EPA NOB (<1%)	- (- 1 / 0)	☐ ISO 10312		Soll/Rock/Vermic	ulite
Point Count		TEM - Bulk		☐ PLM CARB 435	- A (0.25% sensitiv
□ 400 (<0.25%) □ 1000	(<0.1%)	TEM EPA NOI		LI PLM CARB 435	- B (0.1% sensitivity
Point Count w/Gravimetric		☐ Chatfield SOP	.4 (non-friable-NY)	LI TEM CARB 435	- B (0.1% sensitivity
☐ 400 (<0.25%) ☐ 1000 ((<0.1%)		lysis-EPA 600 sec. 2.5	LI IEM CARB 435	- C (0.01% sensitiv
J NYS 198.1 (friable in N	Y)	TEM - Water: EP	A 100 2	LI EPA Protocol (S	emi-Quantitative)
NYS 198.6 NOB (non-fr	riable-NY)		Waste Drinking	☐ EPA Protocol (C	luantitative)
NIOSH 9002 (<1%)		All Fiber Sizes	Waste Drinking	Other:	
	The state of the s				
	Check For Po	ositive Ston - Cl	ark identify Use	100	Part of the second seco
ampiere Name: M	Mal	ositive Stop - Cir	party Identify Homog	enous Group	P. Spilly, W. Starter, Co.
	wellowood	ositive Stop - Cla	Samplers Signature:	enous Group	1000160
Sample #	mel Borro	ositive Stop - Cla	sarty identify Homog Samplers Signature:	Volume/Area (Air)	Date/Time Sampled
1	mel Borro	ositive Stop – Cla	sarty identify Homog Samplers Signature:	Volume/Area (Air)	Sampled
1	mel Borro	ositive Stop – Cla	sarty identify Homog Samplers Signature:	Volume/Area (Air)	
1	mel Borro	ositive Stop – Cla	sarty identify Homog Samplers Signature:	Volume/Area (Air)	Sampled
1	mel Borro	ositive Stop – Cla	sarty identify Homog Samplers Signature:	Volume/Area (Air)	Sampled
Sample # Bu	uef Borro	ample Description	Samplers Signature:	Volume/Area (Air)	Sampled
Sample # Bu	uef Borro	ample Description	Samplers Signature:	Volume/Area (Air)	Sampled
Sample # 1	salyze w	sample Description	Samplers Signature:	Volume/Area (Air) HA # (Bulk)	Sampled
Sample # 1	uef Borro	sample Description	Samplers Signature:	Volume/Area (Air)	Sampled
Sample # 1	salyze w	sample Description	Samplers Signature:	Volume/Area (Air) HA # (Bulk)	Sampled
Sample # 1-3/ Bu AAA ORSA int Sample # (s):	salyze w	hat's only	Samplers Signature:	Volume/Area (Air) HA # (Bulk)	Sampled
Sample # 1-3/ Bu A A A A A A A A A A A A A	salyze w	sample Description	Samplers Signature:	Volume/Area (Air) HA # (Bulk)	Sampled
Sample # 1-3/ Be A OS Int Sample # (s): Inquished (Client):	salyze whose shows	hat's only	Samplers Signature:	Volume/Area (Air) HA # (Bulk) Sotal # of Samples: Time:	Sampled
Sample # /-3/ Bu A OS Int Sample # (s): Inquished (Client): Inived (Lab): Iments/Special Instruction	salyze whose shows	pate: Date:	Samplers Signature:	Volume/Area (Air) HA # (Bulk) Potal # of Samples: Time:	Sampled

Page 1 of ____ pages

Controlled Document - Asbestox GOC - R2 - 1/12/2010

FF DOIN EZÉ

Mezzanine

Information To Build On Engineering • Consulting • Testing	ASBESTOS BULK			and the second s
Homogeneous Area Sample Number Material Description	Sample Location	Approximate Quantity % Asbestos Type	NESHAP Category	Comments
2'x2' White Celling Tile	Lobby Area	[200'sq.]		
MIM2	Room 301			onstoren engles pagangan mananan an anaman an anaman an anaman an a
M 1 M 3	Room 303			
M2 M4 Wall Textured Drywall/Joint Compound	Lobby	3000 ⁵ 29		
M2 M5 Nall	Room 303			
M2 M6 Ceiling	Reshoom	36 39.		
M3 M7 Shoot Viny Hooring	Pestroom	36'sq		
Yellow Carpet Mastic over Black Floor Mastic	Room 304	700'sq.		
(M4) M9.33	Room 303			

Information To Build On Engineering • Consulting • Testing	ASBESTOS BULK S	SAMPLE LOG	mikrizali UCN sirrificio 99 45 salaha maysaa aygga cirifiddi umansaa laya saa
Homogeneous Area Sample Number Material Description	Sample Location	Approximate	Comments
M5 MID White over Gray Plaster	Room 301	3000 '50	
M 5 MII	Room 303		
Mbite Window Caulk	Jobby	200'lin	
M7 M13 Black baseboard w/ White Mastic	Lobby	50 ln.	
M8 M14 Burgardy baseboard W/ White Mastic	Down 352	200'lin	
6 reen Carpet 6 lue / Yellow Carpet 6 lue / Leveling Compound / Black Floor Mastra	Labby	230 ¹ sq.	NA Genetus vakus vakski öökiskussus ja vaska vaksik kussus ja vaska vaksik sunnin kaksik
	Lobby enfrance		
M10 M17 White Pyrobar Block	Room 302	200'sq.	
M11 MIB White Pipe Martie Insulation	Room 302	15°1 in	

Information To Build On Engineering • Consulting • Testing	ASBESTOS BULK	SAMPLE LO)G		TTTCCCTTTCCAUTTCCTTCCTTCCTTCCTTCCTTCCTTC
Homogeneous Area Sample Number Material Description	Sample Location	Approximate Quantity	% Asbestos Type	NESHAP Calegory	Comments
M(2) M29		50 lin,			
4" Block Wasp Stinkrock Insulation w/ Black Mastic	Room 301				
M13 M20		50' lin,			
4" Black Stinkrock Insulation w/ Foil and Black Mastic	Room 301				
M 14 M21		10 / //n.			CHARTON CHARTON CONTRACTOR CHARTON CHA
2" White Cloth Insulation w/ White Mastic	Room 302	·			
M 15 M22		16 lin			
Black A/C Dampener	Room 301				
M 16 M23		50 'sq.			
Light Gray A/C Mostic over White A/e Mostic	Lobby Area				
M17 M24 129		50'54			CONTRACTOR
Dark Gray A/C Mostice	Room 301				
M18 M25 130		300′ sq.			The second secon
Interior A/C Duct Insulation	Room Sol				
M19/ M26 131		60′52.			
White Crown Molding Plaster	Room 301				-
M20 M27 132		200° sq.			
TO THE PARTY OF TH			·····		•

200m 301

Black Vapor Barrier

omogeneous Area Sample Number Material Description	Sample Location	Approximate Quantity	% Asbestos Type	NESHAP Category	Comments
121 MZ 8 133		205° 59,			
Peach Wall Plaster	Room 30)	national-physical agrammawath			
121 M29 134	anni dan samun samun samun samun bidagada basa darmasa kalenda samun sayang mahalif Arpendeka			And the state of t	
	Room 301				-
M22) M30 135		400°sg.			
2"x12" Green Floor Tile w/	Hallway to Room 301				
lellow Carpet Glue + Black Mastic	Koom 201				
M(22) M(31) 136					
	Room 301				
			deg Vivelino kolonomo do deministra de destruito de destruito de describir de de describir de de		-
ANNA SERVICIO DE MANA DE LA PRINCIPIO DE LA PR		***************************************			
	The state of the s		:		
		TO A STATE OF THE PARTY OF THE			
				101	
			<u> </u>		
		Marie and the second se			
PERIODEN MATERIAL MATERIAL REPORT AND				MO-stormerson and accordance and ANOCH	
		700 0000 AAD ON WALLAND MANAGEMENT WATER OF THE PARTY OF	<u> </u>		

STAFF CERTIFICATIONS



STATE OF FLORIDA



DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION

ASBESTOS LICENSING UNIT 1940 NORTH MONROE STREET TALLAHASSEE FL 32399-0783

(850) 487-1395

ROTHENBURG, MICHAEL W 1512 S. TRASK ST. TAMPA FL 33629

Congratulations! With this license you become one of the nearly one million Floridians licensed by the Department of Business and Professional Regulation. Our professionals and businesses range from architects to yacht brokers, from boxers to barbeque restaurants, and they keep Florida's economy strong.

Every day we work to improve the way we do business in order to serve you better. For information about our services, please log onto www.myfloridalicense.com. There you can find more information about our divisions and the regulations that impact you, subscribe to department newsletters and learn more about the Department's initiatives.

Our mission at the Department is: License Efficiently, Regulate Fairly. We constantly strive to serve you better so that you can serve your customers. Thank you for doing business in Florida, and congratulations on your new license!



STATE OF FLORIDA

AC# 5346177

DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION

EA0000041

11/17/10 108123520

ASBESTOS CONSULTANT - ENGINEER ROTHENBURG, MICHAEL W

IS LICENSED under the provisions of Ch. 469 FS.
Expiration date: NOV 30, 2012 L10111702405

DETACH HERE

AC# 5346177

STATE OF FLORIDA

DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION ASBESTOS LICENSING UNIT

SEQ# L10111702405

DATE BATCH NUMBER LICENSE NBR
11/17/2010 108123520 EA0000041

The ASBESTOS CONSULTANT - ENGINEER Named below IS LICENSED Under the provisions of Chapter 469 FS Expiration date: NOV 30, 2012

> ROTHENBURG, MICHAEL W 1512 S TRASK ST TAMPA FL 33629

CHARLIE CRIST GOVERNOR CHARLIE LIEM SECRETARY

DISPLAY AS REQUIRED BY LAW



National Voluntary Laboratory Accreditation Program



SCOPE OF ACCREDITATION TO ISO/IEC 17025:2005

EMSL Analytical, Inc.

Skylake Executive Industrial Park 19501 N.E. 10th Ave., Bay A N. Miami Beach, FL 33179 Ms. Kimberly A. Wallace

Phone: 305-650-0577 Fax: 305-650-0578

E-Mail: kwallace@emsl.com URL: http://www.emsl.com

BULK ASBESTOS FIBER ANALYSIS (PLM)

NVLAP LAB CODE 200204-0

NVLAP Code Designation / Description

18/A01 EPA-600/M4-82-020: Interim Method for the Determination of Asbestos in Bulk Insulation

Samples

2012-04-01 through 2013-03-31

Effective dates

Page 1 of 1

Pavid I. alderman

For the National Institute of Standards and Technology

United States Department of Commerce National Institute of Standards and Technology



Certificate of Accreditation to ISO/IEC 17025:2005

NVLAP LAB CODE: 200204-0

EMSL Analytical, Inc.

N. Miami Beach, FL

is accredited by the National Voluntary Laboratory Accreditation Program for specific services, listed on the Scope of Accreditation, for:

BULK ASBESTOS FIBER ANALYSIS

This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2005.

This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality management system (refer to joint ISO-ILAC-IAF Communique dated January 2009).

2012-04-01 through 2013-03-31

Effective dates



Pavid T. Wolerman

For the National Institute of Standards and Technology

Asbestos Consulting & Training Systems

39430.5369CERT/BIR

900 N.W. 5TH Avenue, Fort Lauderdale, Florida 33311

This is to Certify that Manuel Porras



7950 NW 64th Street, Miami.FL

Processed By:



To Authenticate Certificate www.seagulltraining.com -800-966-9933

has successfully completed an English

Asbestos Building Inspection Refresher

10-Jun-11

10-Jun-11

Individual above has completed the requsite training for accreditation under TSCA Title II

Meets state requirements of 326 IAC (IDEM) and FL49-0001020/CN-0006273.

NDAAC Provider #451

Trainer(s): James F. Stump

Training Address: 900 Northwest Fifth Ave., Fort Lauderdale, Fl. 33311

Successful course completion based on exam score on: 06/10/11

James F. Stump, Course Sponsor

NDER CIVIL AND CRIMINAL PENALTIES OF LAW FOR MAKING OR SUBMISSION OF FALSE OF PRAUDULENT STATEMENTS OR

Certificate Number...... 1 5 Ø 8 7

9-Jun-12

This Certificate Expires:

Course Number

SE1123



Certificate # 7ME12051101AI00008

This is to certify that

Kevin Callahan

has on 12/7/11, in Orlando, FL completed the requirements for asbestos accreditation under Section 206 of TSCA Title II, 15 U.S.C. 2646

AHERA Asbestos Inspector Training

as approved by the State of Florida and the U.S.E.PA. under 40 C.F.R. 763 (AHERA) on 12/5/11 - 12/7/11 and passed the associated examination on 12/7/11 with a score of 70% or better CM = 3.0

Provider #: FL49-0001221

Course # : FL49-0002839

Soc. Sec #: XXX-XX-0172

Accreditation Expires: 12/7/12


Bill Young


Thomas Bradford Mayhew


META - P.O. Box 786 - Lawrence KS 66044 - 800-444-6382

FIELD DRAWINGS WITH SAMPLE LOCATIONS













FIELD DRAWINGS OF ASBESTOS CONTAINING MATERIALS LOCATIONS













PRE-RENOVATION ASBESTOS INSPECTION REPORT

FOR

MANATEE COUNTY HISTORICAL COURTHOUSE SECOND FLOOR - FLOORING AND WALL RENOVATIONS 1115 MANATEE AVENUE WEST BRADENTON, FLORIDA 34205

Prepared for

CROSS ENVIRONMENTAL SERVICES PO BOX 229 CRYSTAL SPRINGS, FLORIDA 33524

ATTENTION: MR. ROSS WORLEY

Prepared by

EE&G

EE&G Environmental Services, LLC 5005 West Laurel Street, Suite 110 Tampa, Florida 33607 (813) 287-1005

April 7, 2011 EE&G Project No. 2011-4210

CONTENTS

<u>Section</u>		<u>Page</u>
1.0 - INTRODI	JCTION	1-1
2.0 - BUILDIN	G DESCRIPTION	2-1
3.0 - METHOD	OS AND LIMITATIONS	3-1
3.1 3.2 3.3	ASBESTOS SURVEY METHODSLABORATORY ANALYSIS METHODSLIMITATIONS	3-1
4.0 - SURVEY	RESULTS	4-1
4.1 4.2	ASBESTOS ANALYSIS RESULTSADDITIONAL OBSERVATIONS	
5.0 - RECOM	MENDATIONS	5-1
5.1 5.2 5.3 5.4 5.5	RECOMMENDATIONS FOR REGULATED (FRIABLE) ACM	5-1 5-1 5-1
6.0 - SIGNATU	JRE PAGE	6-1
TABLES		
TABLE 1	Survey Results	4-2
APPENDICES		
APPENDIX A	General Terms: Types of Asbestos-Containing Materials Types of Asbestos-Containing Roofing Materials NESHAP Categories	
APPENDIX B APPENDIX C	Laboratory Report Certificates	

SECTION 1.0

INTRODUCTION

An asbestos inspection was conducted at the Manatee County Historical Courthouse located at 1115 Manatee Avenue West in Bradenton, Florida. The inspection was conducted on March 30, 2011 by AHERA-certified inspector Michael H. Reid of EE&G Environmental Services, LLC (EE&G).

The purpose of this asbestos inspection was to identify the presence, extent, and condition of asbestos-containing materials (ACM) in the surveyed areas of this facility. The areas surveyed during this inspection included flooring and walls located on the second floor of the building, which were indicated by County representatives to be impacted during upcoming renovation activities. All observed suspect materials were either sampled to determine asbestos content or assumed to contain asbestos.

Terms used in this report are defined in the General Terms section located in Appendix A. Additional information on the classification of ACM for National Emissions Standards for Hazardous Air Pollutants (NESHAP) is also located in Appendix A. These NESHAP categories are helpful in determining the need for asbestos abatement and must be used in the NESHAP notification of intent to renovate or demolish.

SECTION 2.0

BUILDING DESCRIPTION

The structure was observed to be a four-story building constructed of masonry-on-slab. Interior walls were finished with drywall, wood paneling, vinyl wall covering, and stucco/plaster. Interior floors were finished with multiple layers of combinations of vinyl floor tile (VFT), vinyl floor covering (VFC), and carpet; judges desks located in the courtrooms were placed on raised wooden platforms, inspection beneath these platforms was not performed, as the use of destructive assessment methods would have been necessary; ceramic tile flooring was observed in bathrooms, however EE&G was informed that these materials would not be impacted during the renovations and were not sampled. Interior ceilings were not observed, but the remains of a drop-in ceiling tile grid were present. Other locations at the facility, as well as heating, ventilation, and air conditioning, plumbing, and roofing systems were not included in this survey.

SECTION 3.0

METHODS AND LIMITATIONS

3.1 ASBESTOS SURVEY METHODS

The renovation areas were inspected for suspect ACM, unless otherwise noted. Each observed suspect material was assigned a homogenous area number, described, and measured. Each observed suspect material was either sampled or assumed to be asbestos-containing. Samples of suspect ACM were collected using procedures established by the United States (US) Environmental Protection Agency (EPA) Code of Federal Regulations (CFR) Title 40 Part 763 Subpart E, Asbestos-Containing Materials in Schools.

3.2 LABORATORY ANALYSIS METHODS

Samples were delivered to American Asbestos Laboratories, Inc. in Tampa, Florida for analysis. Upon arrival at the laboratory, the samples were logged-in and stored for analysis. Analyses were performed using the polarized light microscopy (PLM) method of asbestos detection using guidelines and procedures established in the Method for the Determination of Asbestos in Bulk Building Materials (EPA-600/R-93-116 July, 1993).

3.3 LIMITATIONS

This asbestos inspection report has been prepared by EE&G in a manner consistent with that level of care and skill ordinarily exercised by members of the profession currently practicing under similar conditions. No other warranty, expressed or implied is made. The intent of this survey report is to assist the owner or client in locating ACM. Under no circumstances is this survey to be utilized as a proposal or a project specification document without the expressed written consent of EE&G.

The survey was conducted to identify suspect ACM in accessible areas of the structure. The inspection was limited to flooring and wall materials located on the second floor of the building (not including bathrooms), which were reported to be impacted by upcoming renovation activities. Judges desks located in the courtrooms were placed on raised wooden platforms, inspection beneath these platforms was not performed, as the use of destructive assessment methods would have been necessary. If other areas at this location are to be impacted during planned or future renovations, a separate asbestos survey of these areas will be required. Some ACM may not have been discovered due to inaccessibility or missing/incomplete plans. Any suspect materials discovered subsequent to the issue of this survey report should be sampled and analyzed to determine asbestos content and to initiate appropriate responses.

Analyses were carried out by PLM. While the most commonly accepted analytical method for detecting asbestos in bulk materials, PLM is known to have limited resolution and may not detect extremely small asbestos fibers. Certain materials, notably vinyl floor tiles, may contain extremely fine asbestos fibers that are beyond the resolution of PLM.

EE&G's interpretations and recommendations are based upon the results of sample collection and analyses in compliance with environmental regulations, quality control and assurance standards, and the scope of work as indicated in EE&G's proposal, dated March 23, 2011. The results, conclusions, and recommendations contained in this report pertain to conditions observed at the time of the survey. Other conditions elsewhere in the subject building(s) may differ from those in the inspected/surveyed locations and, such conditions are unknown, may change over time, and have not been considered.

This report was prepared solely for the use of EE&G's client, and is not intended for use by third party beneficiaries. The client shall indemnify and hold EE&G harmless against any liability for any loss arising out of or relating to reliance by any third party on any work performed thereunder, or the contents of this report. EE&G will not be held responsible for the interpretation or use by others of data developed pursuant to the compilation of this report, or for use of segregated portions of this report.

SECTION 4.0

SURVEY RESULTS

4.1 ASBESTOS ANALYSIS RESULTS

The results of the PLM analyses and assessment of suspect ACM are summarized in Table 1. The original laboratory report is attached as Appendix B.

4.1.1 Asbestos-containing materials

Asbestos was identified in amounts greater than 1 percent in the following materials:

- Black floor mastic.
- 12"x12" Grey vinyl floor tile (VFT) and black mastic.
- White/tan VFT and black mastic.
- 12"x12" Grey with blue streaks VFT and black mastic.
- 12"x12" Grey with green specks VFT and black mastic.

Refer to Table 1 for the location, quantity, and condition of these materials.

4.1.2 Nonasbestos-containing materials

Asbestos was not detected or was found in amounts less than or equal to 1 percent in the following materials:

- Black baseboard mastic.
- White lightweight concrete.
- White stucco-finished wall.
- Tan 12"x12" VFT and yellow glue.
- Red vinyl cove base (VCB) and brown glue.
- Grey VCB and brown glue.
- White drywall system.
- Pink 12"x12" VFT and yellow glue.
- Brown carpet glue.
- Black VCB and brown glue.
- Black sink undercoating.
- Green/white drywall/stucco system.
- White block wall.
- Tan pebble patterned vinyl floor covering (VFC) and white glue.

Refer to Table 1 for the location of these materials.

4.2 ADDITIONAL OBSERVATIONS

In addition to the results presented in Section 4.1, EE&G observed the following:

• Other potential asbestos-containing materials were observed within the building. These materials were reported to be outside the renovation scope of work.

TABLE 1. SURVEY RESULTS FOR SECOND FLOOR FLOORING AND WALL RENOVATION PROJECT AT THE MANATEE COUNTY HISTORICAL COURTHOUSE

tion Category	<u>–</u>	AN N	AN	AN	AN	_ _	AN N	
Condition	Good	A A	Υ Υ	¥ Z	Z Z	Good	N A	
Friability	Nonfriable	ΑN	ΑN	ΑN	Ϋ́	Nonfriable	NA	,
Asbestos Content	2-5% C	NAD	NAD	NAD	NAD	2-5% C in VFT; 2-5% C in mastic	NAD	
Approx. Quantity	8,220 SF	NA	AN	NA	NA	270 SF	NA	
HA Location	Court rooms B (beneath red and blue carpet), D E and G, bailiff's offices (3), court room E – jury room.	Interior walls	Interior walls	Interior walls	Hall outside court room G (top layer)	Hall outside court room G (beneath tan 12" VFT)	Interior walls	
Sample ID	001-003	004-006	600-200	010-012	013-015	013A-015A	016-018	
Material Description	Black floor mastic	Black baseboard mastic	White lightweight concrete	White stucco-finished walls	Tan 12"x12" VFT and yellow glue	Grey 12"x12" VFT and black mastic	Red VCB and brown glue	
НА	01	02	03	04	90	90	20	

NA = Not Applicable HA = Homogenous Area

NAD = No Asbestos Detected TSI = Thermal System Insulation

VFT = Vinyl Floor Tile VCB = Vinyl Cove Base

SF = Square Feet LF = Linear Feet

CT = Ceiling Tile

All quantities are approximate. All asbestos detected is chrysotile unless otherwise noted.

EE&G: Pre-Renovation Asbestos Survey

НА	Material Description	Sample ID	HA Location	Approx. Quantity	Asbestos Content	Friability	Condition	NESHAP Category
60	White drywall system	022-024	Interior walls	N	NAD	۲ ۲	N A	ΑΝ
10	12"x12" Pink VFT and yellow glue	025-027	Hallways (top layer) and landing by elevator (top layer)	NA	QVN	NA	NA	NA
11	12"x12" White/tan VFT and black mastic	025A-027A	Hallways (top layer) and landing by elevator (top layer)	650 SF	2-5% C in VFT; 5-10% C in mastic	Nonfriable	Good	_
12	Brown carpet glue	028-030	Beneath blue and red carpet	N	NAD	₹ Z	N	_
13	12"x12" Grey with blue streaks VFT and black mastic	031-033	Landing by elevator (bottom layer), court rooms a (beneath carpet), c (beneath carpet) and f, mechanical room at south end of hallway, southeast offices (2 – beneath red carpet), librarians office (beneath red carpet), bailiff's office (1), and restrooms (2 – beneath vertical carpet), bailiff's office (1),	5,266 SF	2-5% C in VFT; 5-10% C in mastic	Nonfriable	Good	_

NA = Not Applicable NAD = No Asbestos Detected
HA = Homogenous Area TSI = Thermal System Insulation

VFT = Vinyl Floor Tile VCB = Vinyl Cove Base

SF = Square Feet LF = Linear Feet

CT = Ceiling Tile

All quantities are approximate. All asbestos detected is chrysotile unless otherwise noted.

EE&G: Pre-Renovation Asbestos Survey

НА	Material Description	Sample ID	HA Location	Approx. Quantity	Asbestos Content	Friability	Condition	NESHAP Category
14	12"x12" Grey with green specks VFT and black mastic	034-036	Hallways (bottom layer) and in front of bailiff's offices (beneath carpet)	1,666 SF	2-5% C in VFT; 5-10% in mastic	Nonfriable	Good	_
15	Black cove base and brown glue	037-039	Interior walls	NA	NAD	NA	NA	NA
16	Black sink undercoating	040	Records room	N	<1% C	Ϋ́	ΑΝ	ΑΝ
17	Green/white drywall/stucco system	041-043	Interior walls	NA	NAD	NA	NA	NA
18	White block wall	044-046	Interior walls	N	NAD	Ϋ́	ΑΝ	ΑN
19	Tan pebble pattern VFC and white glue	047-049	Bathrooms (top layer)	NA	QVN	NA	VΝ	ΑN

NA = Not Applicable NAD = No Asbestos Detected
HA = Homogenous Area TSI = Thermal System Insulation

All quantities are approximate. All asbestos detected is chrysotile unless otherwise noted.

VFT = Vinyl Floor Tile VCB = Vinyl Cove Base

SF = Square Feet LF = Linear Feet

CT = Ceiling Tile

SECTION 5.0

RECOMMENDATIONS

5.1 RECOMMENDATIONS FOR REGULATED ACM (RACM)

No materials were identified as RACM.

5.2 RECOMMENDATIONS FOR CATEGORY I NONFRIABLE ACM

The following materials were identified as Category I Nonfriable ACM:

- Black floor mastic.
- 12"x12" Grey VFT and black mastic.
- White VFT and black mastic.
- 12"x12" Grey streak VFT and black mastic.
- 12"x12" Grey speckled VFT and black mastic.

These materials must be removed prior to any activities that would release asbestos fibers. Specifically, any renovation activity that will crush, abrade, or dissolve the matrix of these materials must be performed by a Florida-licensed Asbestos Contractor. If they will not be impacted during renovation, then no other special handling is required.

5.3 RECOMMENDATIONS FOR CATEGORY II NONFRIABLE ACM

No materials were identified as Category II Nonfriable ACM.

5.4 GENERAL RECOMMENDATIONS

- If other areas at this location are to be impacted during renovation, an asbestos survey of these areas will be required.
- Suspect materials discovered after this inspection should be sampled and analyzed to determine asbestos content and to initiate appropriate responses.
- An operations and maintenance (O&M) program should be implemented to manage ACM that will remain in the building. An O&M program will prevent asbestos fiber release, resuspension of previously released fibers, and ensure proper control of asbestos fibers if a release occurs.
- Damaged ACM should be repaired or removed at the start of the O&M program.
 The O&M program should be continued until renovation or demolition activities result in the removal of the ACM or until the condition of the ACM requires removal.

- Any repair and maintenance activities where the ACM is likely to release asbestos fibers must be conducted by personnel who have attended a 16-hour OSHA Class III operations training course.
- Any maintenance and custodial activities where the ACM is contacted but asbestos fibers are unlikely to be released must be conducted by personnel who have attended a 2-hour OSHA Class IV operations training course.

5.5 SPECIFIC RECOMMENDATIONS

Based on the results of this renovation survey, EE&G has the following specific recommendations:

- Removal and disposal of ACM for the purposes of renovation must be performed by a Florida-licensed asbestos contractor.
- If damaged ACM was identified during this survey, it should be repaired or removed regardless of the scope of the renovation.
- A licensed asbestos consulting firm should perform daily air monitoring of the renovation areas during asbestos removal to document the air quality, perform daily inspections, and provide final visual inspections and final air clearance testing.
- Prior to renovation activities, the renovation areas should be inspected for
 potentially hazardous materials, such as Freon, mercury, lead, solvents, caustic
 materials, and flammable materials. The identified materials should be removed
 from the area, and properly disposed of in accordance with federal, state, and
 local regulations.
- EE&G recommends a hazards communications program be implemented to protect workers in other trades from inadvertent exposure to asbestos fibers during the renovation.
- Since the flooring materials are Category I Nonfriable ACM, The Florida Department of Environmental Protection Southwest District does not require 10-day notification prior to removal, however a courtesy notification may be requested before project commencement. Additionally, if structural or load bearing walls are to be demolished as part of the renovation activities, the Department may require 10-day notification prior to commencement of the work. The general contractor should also keep a copy of this survey at the construction site during the entire construction project as proof of compliance with 40 CFR 61 (NESHAP).

SECTION 6.0

SIGNATURE PAGE

Submitted by,

D. Kirk Smith

Senior Project Professional, EE&G

Reviewed by

Daniel J. Cottrell, Ph.D., P.G. Senior Technical Advisor, EE&G

Asbestos Consultant #DD0000010

APPENDIX A

GENERAL TERMS:

TYPES OF ASBESTOS-CONTAINING MATERIALS TYPES OF ASBESTOS-CONTAINING ROOFING MATERIALS **NESHAP CATEGORIES FOR ACM**

TYPES OF ASBESTOS-CONTAINING MATERIALS

<u>Asbestos-Containing Material (ACM)</u>

Asbestos-containing materials, as defined by National Emission Standards for Hazardous Air Pollutants (NESHAP), are materials that have an asbestos content of greater than 1 percent.

Friable Material

Material that can be crumbled or reduced to a powder using normal hand pressure. Nonfriable material is too hard to be crumbled or reduced to a powder without the use of tools. Nonfriable materials may become friable if abraded or broken.

Suspect Materials

There are three broad classes that define suspect, asbestos-containing materials. These are: 1) surfacing material, 2) thermal system insulation, and 3) miscellaneous material. All materials that fit the description of these materials (as described below) are suspected to contain asbestos, until sampled and analyzed.

- Surfacing Material Materials applied by spray or trowel are classified as surfacing materials. Asbestos was used in a variety of surfacing materials for fireproofing, acoustic dampening, condensation control, and decorative purposes. Surfacing materials that contain asbestos usually occur as fireproofing on steelframe members, textured ceilings, or acoustic plaster ceilings.
- Thermal System Insulation (TSI) Material Chill water, hot water, and steam-generating mechanical systems are frequently insulated with materials that contain asbestos. Pipes may be insulated with a nonasbestos-containing material, but have mastic or plastered joints that contain asbestos. Insulation materials that contain asbestos are generally found in boiler rooms and chiller rooms, in pipe chases in walls, in pipe runs above suspended ceilings, or in crawl spaces under buildings. Insulation covered with an undamaged jacket or wrap is classified as nonfriable. Adhesives used to hold insulation in place or provide an airtight seal are also nonfriable materials. Most other types of thermal insulation are friable.
- Miscellaneous Material Miscellaneous building materials are materials that are used for finishing of interior spaces, or adhesive materials applied to building materials and roofs. These materials have been manufactured with asbestos for strength enhancement, fire retardation, condensation control, acoustical dampening, or corrosion resistance. The most common type of friable miscellaneous material is ceiling tile. Most other miscellaneous materials are nonfriable materials such as vinyl floor tile, adhesives, and cementitious panels (Transite™).

TYPES OF ASBESTOS-CONTAINING ROOFING MATERIALS (ACRM)

Field Membrane

This area is usually the predominant part of any roof deck and is comprised of all nonflashed areas and is applied directly to the roof substrate over an intermediate insulating layer. It usually consists of alternating layers of rolled-out felts and hot tar, topped with more hot tar to waterseal, and gravel. The asbestos, if found, is in one or more of the layers of tar or may be in the felts themselves.

Edge Flashing

This component consists of a cold bull/pitch applied to the substrate around the perimeter of a flat roof deck. An additional 8" - 12" of felt is applied to the bull/pitch to seal the edge of the roof substrate before a 4" - 6" piece of metal drip guard is placed over these materials to counterflash and protect against wind and rain. The field membrane felts are then blended in with the inner edge to conform with the rest of the roof. The asbestos, if found, is in the layers of bull/pitch, tar, or may be in the flashing felts themselves.

Wall Base/Parapet Flashing

This component consists of a cold bull/pitch applied to the roof substrate, adjoining wall base, fan/vent, scupper trough, hatch, chimney, or raised parapet wall. An additional 12" - 48" of felt (often painted silver) is applied to the bull/pitch to seal the edges of the roof substrate, wall(s), or the side or top of the concrete parapet wall. The field membrane felts are then blended in with the inner edge to conform with the rest of the roof. The asbestos, if found, is in the layers of bull/pitch, tar, or may be in the flashing felts themselves.

Roof Fixture Flashing

This component consists of a cold bull/pitch applied to the roof substrate around any of the following fixtures: roof drain, vent-thru-roof stack (VTR), pitch pan, gooseneck vents, mechanical equipment supports, or any other roof penetration. An additional sheet of metal counterflashing (extending 4" - 24" from the center) is applied to the bull/pitch to seal the edges to the roof substrate. The field membrane felts are placed over up to the fixture sides to conform with the rest of the roof. The asbestos, if found, is in the layers of bull/pitch, tar, or may be in the flashing felts themselves.

NESHAP CATEGORIES FOR ACM

Regulated ACM (RACM)

All ACM that is friable or likely to become friable during renovation or demolition activities is considered to be RACM. These materials must be removed from buildings prior to renovation or demolition activities that will disturb them.

Category I Nonfriable ACM

Resilient flooring, such as vinyl floor tile and rolled vinyl sheeting, valve packings and gaskets, and asphalt (bituminous) roofing materials are all classified as Category I Nonfriable materials. If these materials are in good condition, they are not likely to become friable during demolition, and therefore, may remain in place for demolition. However, these materials must be removed prior to renovations if the renovation involves alteration that would render them friable.

Category II Nonfriable ACM

Category II materials are all other nonfriable materials that are not classified as Category I. Asbestos cement products and plaster are the most common types of Category II materials. Most Category II materials are likely to become friable during demolition, and therefore, must be removed prior to demolition. These materials must be removed prior to renovations if the renovation involves alteration that would render them friable.

APPENDIX B

LABORATORY ANALYSIS REPORT **PLM RESULTS**

REPORT

CROSS ENVIRONMENTAL SERVICES SENT

P.O. BOX 1229 TO:

CRYSTAL SPRINGS, FL 33524

ROSS WORLEY

813-783-1688/FAX:813-788-9114

Thank you for your business.

PREPARED AAL

Asbestos Department

5005 WEST LAUREL STREET

SUITE 110

TAMPA, FL 33607 NVLAP Code 101775

(813) 287-1005

Polarized Light Microscopy (PLM) with dispersion staining techniques according to the Analysis:

United States (US) Environmental Protection Agency (EPA) "Method for the Determination of Asbestos in Bulk Building Materials," EPA/600/R-93-116, July, 1993.

Date in : March 31, 2011 : BULK Sample Type

#Of Samples Date out : April 7, 2011 : 52

> Collected by : M.R. : M.R. Delivery by

Received by : KIA : M104124 Work Order#

: 2011 4210 EE&G Project#

: MANATEE CTY HISTORICAL CRTHSE Project

Analyzed By:

Authorized Signature Khandaker I. Anam

Due to the small size of asbestos fibers associated with vinyl floor tiles, TEM analysis is recommended for all floor ti containing < 1% or no detectable asbestos by visual estimation.

This report may not be reproduced except in full, without the written approval of AAL. AAL will not be held responsible for the use of its reports issued in part to third parties or authorized agents of the client.

This report shall not be used by the client to claim product endorsement by NVLAP nor any agency of the United States Government. All NVLAP reports displaying NVLAP logo must have at least one signature to be valid.

The following analytical results presented in this report pertain only to the samples analyzed. American Asbestos Laboratories assumes no responsibility for whether the samples accurately represent the material in question.

Page 1

LABORATORY BULK SAMPLE ANALYSIS REPORT

CLIENT : CROSS ENVIRONMENTAL SERVICES PROJECT : MANATEE CTY HISTORICAL CRTHSE

Samples were analyzed in accordance with the Interim Method as described in 40 CFR, Part 763, Vol. 52, No. 210

					PERCEN	PERCENT ASBESTOS FIBERS	EKS		%NON-ASB
ID# ANA	DESCRIPTION	LOCATION	SAMPLE NUMBER	CHRY	AMOS	CROC TREM	M ANTH	OTHER	FIBERS
)1A KIA	BLACK FLOOR MASTIC	MAIN CTRM-N.SIDE	001	2-5					1-2
JIB KIA	BLACK FLOOR MASTIC	MAIN CTRM-E.SIDE	002	2-5					1-2
OIC KIA	BLACK FLOOR MASTIC	MAIN CTRM-W.SIDE	003	5-10					1-2
02A KIA	BLACK BASEBOARD MASTIC	MAIN CT RM-LEFT	004		NO ASBES'	NO ASBESTOS DETECTED			1-2
02B KIA	BLACK BASEBOARD MASTIC	MAIN CTRM-MIDDLE	005		NO ASBES	NO ASBESTOS DETECTED			1-2
02C KIA	BLACK BASEBOARD MASTIC	MAIN CT RM-RIGHT	900		NO ASBES	NO ASBESTOS DETECTED			1-2
03A KIA	WHITE LGT WEIGHT CONCRETE	MAIN CT-N.WINDOW	007		NO ASBES	NO ASBESTOS DETECTED			1-2
03B KIA	WHITE LGT WEIGHT CONCRETE	MAIN CT-E.WINDOW	800		NO ASBES	NO ASBESTOS DETECTED			1-2
03C KIA	WHITE LGT WEIGHT CONCRETE	MAIN CT-S.WINDOW	600		NO ASBES	NO ASBESTOS DETECTED			1-2
04A KIA	, WHITE STUCCO WALL	NORTH SIDE WALL	010		NO ASBES	NO ASBESTOS DETECTED			1-2
04B KIA	WHITE STUCCO WALL	EAST SIDE WALL	011		NO ASBES	NO ASBESTOS DETECTED			1-2
04C KIA	WHITE STUCCO WALL	SOUTH SIDE WALL	012		NO ASBES	NO ASBESTOS DETECTED			1-2
05A KIA * Comments:	A TAN 12"X12" VFT	HALL OUTS. CTRM	013	NO ASBEST	NO ASBES OS DETECTED	NO ASBESTOS DETECTED NO ASBESTOS DETECTED	JUE		1-2

LABORATORY BULK SAMPLE ANALYSIS REPORT CONTINUED

April 7, 2011 10:05

: CROSS ENVIRONMENTAL SERVICES : MANATEE CTY HISTORICAL CRTHSE CLIENT PROJECT

m# ANA	A DESCRIPTION	LOCATION	SAMPLE NIMBER	CHRY	PERCENT ASBESTOS FIBERS AMOS CROC TREM	ANTH	OTHER	%NON-ASB
05B KIA * Comments:	TAN 12"X12" VFT S:	HALL OUTS. CTRM	014	NO ASBESTOS D	SBESTOS DETEC			1-2
05C KIA * Comments:	TAN 12"X12" VFT s:	HALL OUTS. CTRM	015	NO ASBESTOS E	NO ASBESTOS DETECTED NO ASBESTOS DETECTED IN YELLOW GLUE			1-2
06A KIA * Comments:	GREY 12" VFT & BLK MASTIC s:	HALL OUTS. CTRM	013A	2-5 5-10% CHRYSOT	2-5 5-10% CHRYSOTILE DETECTED IN BLACK MASTIC	STIC		1-2
06B KIA * Comments:	GREY 12" VFT & BLK MASTIC s:	HALL OUTS. CTRM	014A	2-5 5-10% CHRYSOT	2-5 5-10% CHRYSOTILE DETECTED IN BLACK MASTIC	ASTIC		1-2
06C KIA * Comments:	GREY 12" VFT & BLK MASTIC	HALL OUTS. CTRM	015A	2-5 5-10% CHRYSOT	2-5 5-10% CHRYSOTILE DETECTED IN BLACK MASTIC	ASTIC		1-2
07A KIA * Comments:	RED COVE BASE	тнкоибноит вм	016	NO ASBESTOS D	NO ASBESTOS DETECTED NO ASBESTOS DETECTED IN BROWN/BEIGE GLUE	3LUE		1-2
07B KIA * Comments:	RED COVE BASE	THROUGHOUT BM	017	NO ASBESTOS I	NO ASBESTOS DETECTED NO ASBESTOS DETECTED IN BROWN/BEIGE GLUE	3LUE		1-2
07C KIA * Comments:	RED COVE BASE	THROUGHOUT BM	018	NO ASBESTOS I	NO ASBESTOS DETECTED NO ASBESTOS DETECTED IN BROWN/BEIGE GLUE	3LUE		1-2
08A KIA * Comments:	GREY COVE BASE	THROUGHOUT BM	019	NO ASBESTOS I	NO ASBESTOS DETECTED NO ASBESTOS DETECTED IN BROWN/BEIGE GLUE	SLUE		1-2
08B KIA * Comments:	GREY COVE BASE	THROUGHOUT BM	020	NO ASBESTOS I	NO ASBESTOS DETECTED NO ASBESTOS DETECTED IN BROWN/BEIGE GLUE	3LUE		1-2

 α Page LABORATORY BULK SAMPLE ANALYSIS REPORT CONTINUED

April 7, 2011 10:05

: CROSS ENVIRONMENTAL SERVICES : MANATEE CTY HISTORICAL CRTHSE

CLIENT PROJECT

RS ANTH OTHER FIBERS	1-2	10-15	10-15	10-15	1-2	1-2	1-2	1-2	1-2
PERCENT ASBESTOS FIBERS CHRY AMOS CROC TREM	NO ASBESTOS DETECTED NO ASBESTOS DETECTED IN BROWN/BEIGE GLUE	NO ASBESTOS DETECTED	NO ASBESTOS DETECTED	NO ASBESTOS DETECTED	NO ASBESTOS DETECTED NO ASBESTOS DETECTED IN YELLOW GLUE	NO ASBESTOS DETECTED IN YELLOW GLUE	NO ASBESTOS DETECTED IN YELLOW GLUE	2-5 5-10% CHRYSOTILE DETECTED IN BLACK MASTIC	2-5
SAMPLE NUMBER	021	022	023	024	025	026	027	025A	026A
LOCATION	ТНКОИСНОИТ ВМ	ALL SYSTEM O ASBESTOS DETECTED IN WHITE DRYWALL NO ASBESTOS DETECTED IN WHITE JOINT COMPOUND	ALL SYSTEM NO ASBESTOS DETECTED IN WHITE DRYWALL NO ASBESTOS DETECTED IN WHITE JOINT COMPOUND	ALL SYSTEM NO ASBESTOS DETECTED IN WHITE DRYWALL NO ASBESTOS DETECTED IN WHITE JOINT COMPOUND	THROUGHOUT HLWY	THROUGHOUT HLWY	THROUGHOUT HLWY	THROUGHOUT HLWY	THROUGHOUT HLWY
DESCRIPTION	GREY COVE BASE	WHITE DRYWALL SYSTEM Layer 1: NO ASBESTOS DETECTE Layer 2: NO ASBESTOS DETECTE	WHITE DRYWALL SYSTEM Layer 1: NO ASBESTOS DETECTE Layer 2: NO ASBESTOS DETECTE	WHITE DRYWALL SYSTEM Layer 1: NO ASBESTOS DETECTE Layer 2: NO ASBESTOS DETECTE	PINK 12"X12" VFT	PINK 12"X12" VFT	PINK 12"X12" VFT	WHITE VFT & BLACK MASTIC	WHITE VFT & BLACK MASTIC
ANA	Comments:	KIA	KIA	KIA	A KIA Comments:	3 KIA Comments:	Comments:	A KIA Comments:	KIA
#OI	08C * Cor	09A	09B	D60	10A * Coj	10B * Co	10C * Co	11A * Co	1118

CLIENT : CROSS ENVIRONMENTAL SERVICES PROJECT : MANATEE CTY HISTORICAL CRTHSE

LABORATORY BULK SAMPLE ANALYSIS REPORT CONTINUED

ID# ANA	DESCRIPTION	LOCATION	SAMPLE NUMBER	PERC CHRY AMOS	PERCENT ASBESTOS FIBERS IOS CROC TREM	ANTH OTHER	%NON-ASB FIBERS
11C KIA * Comments:	WHITE VFT & BLACK MASTIC	THROUGHOUT HLWY	027A	2-5 5-10% CHRYSOTILE DI	2-5 5-10% CHRYSOTILE DETECTED IN BLACK MASTIC	O.	1-2
12A KIA * Comments:	BLUE CARPET & GLUE	COURT ROOM C	028	NO ASBESTOS DETECTED NO ASBESTOS DETECTED	NO ASBESTOS DETECTED DETECTED IN BROWN GLUE		20-25
12B KIA * Comments:	BLUE CARPET & GLUE	COURT ROOM C	029	NO ASBESTOS DETECTED NO ASBESTOS DETECTED	NO ASBESTOS DETECTED PETECTED IN BROWN GLUE		1-2
12C KIA * Comments:	BLUE CARPET & GLUE	COURT ROOM C	030	NO ASBESTOS DETECTED NO ASBESTOS DETECTED	NO ASBESTOS DETECTED BETECTED IN BROWN GLUE		1-2
13A KIA * Comments:	GREY 12"X12" VFT & MASTIC	CT RM F THROUGH.	031	2-5 5-10% CHRYSOTILE D	2-5 5-10% CHRYSOTILE DETECTED IN BLACK MASTIC	, C	1-2
13B KIA * Comments:	GREY 12"X12" VFT & MASTIC	CT RM F THROUGH.	032	2-5 5-10% CHRYSOTILE D	2-5 5-10% CHRYSOTILE DETECTED IN BLACK MASTIC	IC	1-2
13C KIA * Comments:	GREY 12"X12" VFT & MASTIC	CT RM F THROUGH.	033	2-5 5-10% CHRYSOTILE D	2-5 5-10% CHRYSOTILE DETECTED IN BLACK MASTIC	IC	1-2
14A KIA * Comments:	GREY 12"X12" VFT	ADJ.RMS TO RECRM	034	2-5 5-10% CHRYSOTILE D	2-5 5-10% CHRYSOTILE DETECTED IN BLACK MASTIC	וכ	1-2
14B KIA ** Comments:	GREY 12"X12" VFT	ADJ.RMS TO RECRM	035	2-5 5-10% CHRYSOTILE D	2-5 5-10% CHRYSOTILE DETECTED IN BLACK MASTIC	IC	1-2
14C KIA * Comments:	GREY 12"X12" VFT	ADJ.RMS TO RECRM	036	2-5 5-10% CHRYSOTILE D	2-5 5-10% CHRYSOTILE DETECTED IN BLACK MASTIC	IC	1-2

Page 5

LABORATORY BULK SAMPLE ANALYSIS REPORT CONTINUED

April 7, 2011 10:05

: CROSS ENVIRONMENTAL SERVICES : MANATEE CTY HISTORICAL CRTHSE **PROJECT** CLIENT

WORK ORDER NUMBER: M104124

W. #UI	\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \	NORTH	NOTATION	CANADI E NITAGEE	Van V	PERCENT ASBESTOS FIBERS		ANTALI	dallac	%NON-ASB
	#71 T#7	DESCRIPTION	COUNTY	SAIM LE MOMBEN				ALVIII.	OINEN	FIDENS
15A KIA * Comments:	KIA ments:	BLACK COVE BASE	REC RM THROUGH.	037	NO ASBESTOS DE	NO ASBESTOS DETECTED NO ASBESTOS DETECTED NO	TED			1-2
15B KIA * Comments:	KIA ments:	BLACK COVE BASE	REC RM THROUGH.	038	NO ASBESTOS DE	NO ASBESTOS DETECTED NO ASBESTOS DETECTED	TED			1-2
15C KIA * Comments:	KIA ments:	BLACK COVE BASE	REC RM THROUGH.	039	NO ASBESTOS DE	NO ASBESTOS DETECTED NO ASBESTOS DETECTED	TED			1-2
16A K	KIA	BLACK SINK UNDERCOATING	REC RM	40	<1					1-2
17A K	KIA	GREEN/WH DRYWALL & STUCCO REC RM THROUGH. Layer 1: NO ASBESTOS DETECTED IN WHITE/GREY DRYWALL Layer 2: NO ASBESTOS DETECTED IN GREEN STUCCO	REC RM THROUGH. N WHITE/GREY DRYWALL GREEN STUCCO	41	Z	NO ASBESTOS DETECTED	TED			12-20
17B K	KIA	GREEN/WH DRYWALL & STUCCO REC RM THROUGH. Layer 1: NO ASBESTOS DETECTED IN WHITE/GREY DRYWALL Layer 2: NO ASBESTOS DETECTED IN GREEN STUCCO	REC RM THROUGH. N WHITE/GREY DRYWALL N GREEN STUCCO	42	Z.	NO ASBESTOS DETECTED	TED			12-20
17C K	KIA	GREEN/WH DRYWALL & STUCCO REC RM THROUGH. Layer 1: NO ASBESTOS DETECTED IN WHITE/GREY DRYWALL Layer 2: NO ASBESTOS DETECTED IN GREEN STUCCO	REC RM THROUGH. N WHITE/GREY DRYWALL N GREEN STUCCO	43	, Z,	NO ASBESTOS DETECTED	TED			12-20
18A K	KIA	WHITE BLOCK WALL	MAIN COURT ROOM	44	2	NO ASBESTOS DETECTED	твр			2-5
18B K	KIA	WHITE BLOCK WALL	REC RM	45	2	NO ASBESTOS DETECTED	TED C. C.	A Company of the Comp	A CONTRACTOR OF THE PARTY OF TH	25
18C F	KIA	WHITE BLOCK WALL	AT ROOM C	46	2	NO ASBESTOS DETECTED	red	arter and property or comments from the	Politica Martina Constitution of the Constitut	1-2
							The second of the second		Games Section of the Control of the	
						A.		All Control of the Co	A 100 CO	

Analytical results pertain only to the sample(s) analyzed.

SIL = Silver, SR = Sheet rock; SUB = Substance; S = Synthetic; TEXT = Textured; TR = Trace; TRAN = Transite; TREM = Tremolite; VERM = Vermiculite; VYL = Vinyl; W = Wollastonite; WH = White; YEL = Yellow. ABBREVIATIONS: ANA = Analyst; ASB = Asbestos; CHRY = Chrysotile; AMOS = Amosite; CROC = Crocidolite; TERM = Term/Act; ANTH = Anthophylite; ACT = Actinolite; AL = Aluminum; ANTH = Anthophylite; BLK=Black; BACK=Backing; BL=Blue; BRN=Brown; C=Cellulose; CALC=Calcareous; CPT=Carpet; CTL=Ceiling tile; CEM=Cement; COV=Cover; DEB=Debris; FG=Fiberglass; FIB=Fibrous, fibers; MAS=Mastic; MAT=Material; MIC=Micaceous; MW=Mineral wool; ORG=Orange; PAI=Paint; PAP=Paper; PL=Plastic; PVDR=Powder; RCF=Refractory ceramic fiber; RUB=Rubber;

Quality Control Officer



EE&G Environmental Services, LLC 5005 West Laurel Street, Suite 110 Tampa, Florida 33607



BULK TRANSMITTAL FORM CHAIN OF CUSTODY

CLIENT: Les		PROJEC	ECT: MAINTER Courty HIST COURTHOUSE
CLIENT CONTACT:_	Ross Worley	PROJE	ECT NUMBER: <u>2011-42 го</u>
DATE COLLECTED:_	3 30.11	PHASE	E/TASK: 360124
DATE SENT:	3 - 30 . 11	DATE V	VERBAL NEEDED: 4-5-//
STOP AT FIRST POS	ITIVE: Y (N)	(circle one) DATE V	WRITTEN NEEDED: 4-5-11
SAMPLE PREFIX		H.	
SAMPLE NUMBER	COLOR	SAMPLE DESCRIPTION	
1661	BINOIL	Man of Ran floor ma	ASTR of row MAIN
2. 002	The state of the s		e side of room
3		J .	w side of row.
4. 004	Black	BASE BOAR MOUS	
5. <u>605</u>			milds
6	<u>- 4</u>		right
7007	white	Lyt weall contract on	n N winder
8. <u>005</u>		Window SIN lelge	fort e vintou
9	<u> </u>	<u> </u>	5 Window
10. <u>Ulo</u>	white	Stores wall	N side and
110i/		<u> </u>	e sile un!
12. <u>6i2</u>			S site was
13	IAN	JAN Specked 12' over	gray HAH outsil of ctm & to must
14		1) tile a Mister	Rn +Hacktock
15. <u>0)5</u>		<u> </u>	
16	Red	Red and Both	- Hrough + BM
17. <u>6) 7</u>			
18	<u></u>	<u></u>	
19014	910/	Cove BASI	Hrow of BM
20. <u>()</u> 0	<u> </u>	1	<u> </u>
CHAIN OF CUSTODY	: PRINT NAME/S	IGNATURE	PURPOSE
	A	On A D	
<u>3-30 /1</u>	DIKE EM	VEIN A	C T A C T A
	111 //1	= Collection T = Transportation A	A= Analysis LLO2 I E BAM
	0 /		

EE&G

CONTINUATION OF BULK TRANSMITTAL FORM CHAIN OF CUSTODY

	Page 2 of 7
PROJECT NUMBER:	2011-4010

PHASE/TASK: TSU-U

MPLE NUMBER	COLOR boy	SAMPLE DESCRIPTION	SAMPLE LOCATION HAVINGOUT RIM
022	White	Diyunol System	Ct in 6
023	Î	1	cr rn f
024	F		ct me
025	WHIT I/PIK	12 Pink Julik UFt over	Ittroughet HANCAN
026	1	yellow probble steet. Walt	711:39:31
027	_	& Black Master	
ს 28	Blux	Blue CARRY E Glun	et en c
N			1
U30	b		1
03/	Grey	Gory Strenk 12 VFT &	CF RM F
032		MASKIL	+Hroghout 1
033	4	4	7. 4
034	Sek/Grex	12' VF+	ADJ Bums to
635			records RM
036		<i>V</i>	
037	BIAUL	Cove BAG	In rec RM Herough
038			1
039	<u>b</u>	<u></u>	J
046	BIACK	Sink onlewing	Pei lm
041	Greenfullite	DOWNAIL & STUCCO	REC RM 1 Hrougho
042			
043			
044	- Colfits	Blook and Bedfor Street & Drym	man at lon
045			Pec Row
046			Cf Rn &
	-		
····			
· · · · · · · · · · · · · · · · · · ·			

	•		
AIN OF CUSTODY:	PRINT NAME/SIG	SNATURE	EIVED
-30 -17	mile led	mol 2 DI MAR	3 1 2011 - 11 11 66

C= Collection T= Transportation A= Analysis

American Asbestos Laboratories

REPORT

SENT

CROSS ENVIRONMENTAL SERVICES

TO:

P.O. BOX 1229

CRYSTAL SPRINGS, FL 33524

ROSS WORLEY

813-783-1688/FAX:813-788-9114

Thank you for your business.

PREPARED AAL

BY:

Asbestos Department

April 15, 2011 13:17

5005 WEST LAUREL STREET

SUITE 110

TAMPA, FL 33607 NVLAP Code 101775

(813) 287-1005

Analysis:

Polarized Light Microscopy (PLM) with dispersion staining techniques according to the

United States (US) Environmental Protection Agency (EPA) "Method for the Determination of Asbestos in Bulk Building Materials," EPA/600/R-93-116, July, 1993.

Sample Type

: BULK

Date in

: April 15, 2011

#Of Samples

: 3

Date out

: April 15, 2011

Collected by

: M.R.

Delivery by

: M.R.

Work Order#

: M104161

Received by

: KIA

EE&G Project#

: 2011 4210

Project

: MANATEE CTY HISTORICAL CRTHSE

Analyzed By:

Khandaker I. Anam

Authorized Signature

Due to the small size of asbestos fibers associated with vinyl floor tiles, TEM analysis is recommended for all floor ti containing <1% or no detectable asbestos by visual estimation.

This report may not be reproduced except in full, without the written approval of AAL. AAL will not be held responsible for the use of its reports issued in part to third parties or authorized agents of the client.

This report shall not be used by the client to claim product endorsement by NVLAP nor any agency of the United States Government. All NVLAP reports displaying NVLAP logo must have at least one signature to be valid.

The following analytical results presented in this report pertain only to the samples analyzed. American Asbestos Laboratories assumes no responsibility for whether the samples accurately represent the material in question.

LABORATORY BULK SAMPLE ANALYSIS REPORT

CLIENT : CROSS ENVIRONMENTAL SERVICES PROJECT : MANATEE CTY HISTORICAL CRTHSE

Samples were analyzed in accordance with the Interim Method as described in 40 CFR, Part 763, Vol. 52, No. 210

WORK ORDER NUMBER: M104161

						PERCEN	PERCENT ASBESTOS FIBERS	S FIBERS			%NON-ASB
1D#	ANA	ANA DESCRIPTION	LOCATION	SAMPLE NUMBER	CHRY	AMOS	CROC TREM	TREM	ANTH	OTHER	FIBERS
01A KIA		TAN PEBBLE VINYL SHEET	#1 ON MAP	047		NO ASBES	NO ASBESTOS DETECTED	TED			15-25
* Comments:	nents:				NO ASBESTO	NO ASBESTOS DETECTED IN WHITE GLUE	IN WHITE	GLUE			
01B KIA	KIA	TAN PEBBLE VINYL SHEET	#2 ON MAP	048		NO ASBES	NO ASBESTOS DETECTED	TED			15-25
* Comments:	nents:				NO ASBESTO	NO ASBESTOS DETECTED IN WHITE GLUE	IN WHITE	GLUE			
01C KIA		TAN PEBBLE VINYL SHEET	#3 ON MAP	049		NO ASBES	NO ASBESTOS DETECTED	TED			15-25
* Comments:	nents:				NO ASBEST	NO ASBESTOS DETECTED IN WHITE GLUE	IN WHITE	GLUE			




Quality Control Officer

Analytical results pertain only to the sample(s) analyzed.

ABBREVIATIONS: ANA=Analyst; ASB=Asbestos; CHRY=Chrysotile; AMOS=Amosite; CROC=Crocidolite; TERM=Term/Act; ANTH=Anthophylite; ACT=Actinolite; AL=Aluminum; ANTH=Anthophylite; SIL=Silver; SR=Sheet rock; SUB=Substance; S=Synthetic; TEXT=Textured; TR=Trace; TRAN=Transite; TREM=Tremolite; VERM=Vermiculite; VYL=Vinyl; W=Wollastonite; WH=White; YEL=Yellow. BLK=Black; BACK=Backing; BL=Blue; BRN=Brown; C=Cellulose; CALC=Calcareous; CPT=Carpet; CTL=Ceiling tile; CEM=Cement; COV=Cover; DEB=Debris; FG=Fiberglass; FIB=Fibrous, fibers; MAS=Mastic; MAT=Material; MIC=Micaceous; MW=Mineral wool; ORG=Orange; PAI=Paint; PAP=Paper; PL=Plaster; PLAS=Plastic; PWDR=Powder; RCF=Refractory ceramic fiber; RUB=Rubber;



5005 W. Laurel Street, Suite 110 Tampa, Florida 33607 (813) 287-1005 Phone (813) 287-8545 Fax



BULK TRANSMITTAL FORM CHAIN OF CUSTODY

CLIENT: Ces	R	· ·	After county Hist contiflue
CLIENT CONTACT:_	11 .11 /		ER: 2011-4210
DATE COLLECTED:		DATE VERBAL N	IEEDED: 4 · /5 · //
DATE SENT: $\frac{4}{}$	/\$: //	DATE WRITTEN	NEEDED: 4 · 18·11
STOP AT FIRST POS	SITIVE: Y (N) (circle one)	
SAMPLE PREFIX	001		
SAMPLE NUMBER	COLOR	SAMPLE DESCRIPTION	SAMPLE LOCATION
1. 047	+AM	PebBic SHED Uynle	#1 ON MP
2. <u>043</u>			#JON MAD
3 . <u>649</u>	<u> </u>	<u>b</u>	#3 ON Max
4.			
5			
6			
7			
8			
9		•	
10			
11.			The state of the s
12.			
13.			
14.			
15			
16			
17			
18	***************************************		
19			
20.			
4.0.	***		
CHAIN OF CUSTODY DATE/TIME	: PRINT NAME/SIC	SNATURE	PURPOSE
		m.a.l.	PORPOSE
<u>4.14.//</u>	Mike Reid	Collection T= Transportation A= Analysis	APR 1 5 2011
			2,0

APPENDIX C

CERTIFICATES



Mayhew Environmental Training Associates

Certificate # 7ME05131001AIR0017

This is to certify that

Michael H. Reid

completed the requirements for asbestos accreditation under Section 206 of TSCA Title II, 15 U.S.C. 2646 has on 5/13/10, in Tampa, FL

AHERA Asbestos Building Inspector Refresher Course

as approved by the State of Florida and the U.S.E.P.A. under 40 C.F.R. 763 (AHERA) on 5/13/10 - 5/13/10 and passed the associated examination on 5/13/10

with a score of 70% or better CM = 0.5

Provider #: FL49-0001221 Course #: FL49-0004718

MAYHEW

ANSAC

Soc. Sec #: XXX-XX-4273 Accreditation Expires: 5/13/11

Dean Althage Instructor

Thomas Bradford Mayhew -BUMM President


P.O. Box 786

800-444-6382

Lawrence KS 66044

META

N GON OF TOTAL TRANSPORT



Certificate of Accreditation to ISO/IEC 17025:2005

NVLAP LAB CODE: 101775-0

American Asbestos Laboratories, Inc.

Tampa, FL

is accredited by the National Voluntary Laboratory Accreditation Program for specific services, isted on the Scope of Accreditation, for:

BULK ASBESTOS FIBER ANALYSIS

This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality management system (refer to joint ISO-ILAC-IAF Communique dated January 2009). This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2005.

2010-04-01 through 2011-03-31

Effective dates



For the National Institute of Standards and Technology

NVLAP-01C (REV. 2009-01-28)

AC# 4590097

STATE OF FLORIDA

DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION ASBESTOS LICENSING UNIT

SEQ# L09091503701

BATCH NUMBER LECENSE NBR

09/15/2009 090140625 ZA344

The ASBESTOS BUSINESS ORGANIZATION Named below IS LICENSED Under the provisions of Chapter 469 FS. Expiration date: NOV 30, 2011

EE & G ENVIRONMENTAL SERVICES LLC JAY W SALL 14505 COMMERCE WAY SUITE 400 MIAMI LAKES FL 33014

CHARLIE CRIST GOVERNOR

DISPLAY AS REQUIRED BY LAW

CHARLES W. DRAGO SECRETARY

STATE OF FLORIDA

DEPARTMENT OF BUSINESS AND PROFESSIONAL REGULATION ASBESTOS DICENSING UNIT

SEQ#510092501299

BATCH NUMBER PERSONNERS

09/25/2010 100120327 DD0000010/

The ASBESTOS CONSULTANT

Named below IS LICENSED
Under the provisions of Chapter 469 FS.
Expiration date: NOV 30, 2012

COTTRELL, DANIEL JOSEPH 6367 SW 44 ST MIAMI FL

FL 33155 5142 WET

CHARLIE CRIST GOVERNOR

DISPLAY AS REQUIRED BY LAW

CHARLIE LIEM SECRETARY