



1112 Manatee Avenue West
Bradenton, FL 34205
purchasing@mymanatee.org

Solicitation Addendum

Addendum No.: 2
Solicitation No.: 21-TA003505AJ
Project No.: 6022385
Solicitation Title: Southeast Master Lift Station 677E Rehabilitation
Addendum Date: November 16, 2020
Procurement Contact: Abby Jenkins

IFBC No. 21-TA003505AJ is amended as set forth herein. Responses to questions posed by prospective bidders are provided below. This addendum is hereby incorporated in and made a part of IFBC No. 21-TA003505AJ.

QUESTIONS AND RESPONSES:

Q1. On C-3 it states 122 GPM with peak season @ 378 GPM, on sheet M-3 it states the existing pumps are rated at 2100 GPM @ 90 TDH (No Pumps on) and 1300 GPM @ 143 TDH (All Pumps on). What are the parameters we are to use to size the bypass pump equipment?

R1. The bypass pump should be designed to meet 1600 GPM @ 185 TDH. This will ensure that the highest head condition within the system can be met while also handling peak flows that may occur during the wet season.

NOTE:

Items that are ~~struck through~~ are deleted. Items that are underlined have been added or changed. All other terms and conditions remain as stated in the IFBC

INSTRUCTIONS:

Receipt of this addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the response being deemed non-responsive.

END OF ADDENDUM

AUTHORIZED FOR RELEASE