

**IFB #14-2404-OV, 44<sup>th</sup> Avenue East (From 30<sup>th</sup> Street East to 45<sup>th</sup> Street East)**

**Addendum #4,**

**November 19, 2014**

**Page 1 of 1**

**Measurement and Payment:**

**Bid Items ETS-1 and ETS-2 – Effluent Treatment System**

The quantity for Effluent Treatment Systems to be paid for under this section shall be for the setup and removal of the Effluent Treatment System (ETS-1) and for equipment and labor required to operate the treatment system for one (1) week (ETS-2). Effluent treatment shall follow EPA Test Method 6010 for Total Arsenic and Total Lead.

Effluent treatment must yield less than 10 ppb total dissolved arsenic as tested by EPA Test Method 6010. The CONTRACTOR shall contact the COUNTY to obtain effluent samples from the discharge in this area for Total Arsenic and Total Lead by EPA Test Method 6010. The dewatering system shall remain off until test results are available (typically 3-5 work days, please plan ahead).

If the test results are below the FDEP groundwater cleanup target levels (GCTLs), dewatering can commence without treatment. If the results are above the applicable GCTLs, CONTRACTOR shall implement treatment system measures to remove the contaminants from the effluent prior to continuing discharge. All dewatering cost shall be included in base bid as part of typical construction activities.