



1112 Manatee Avenue West
Bradenton, FL 34205
purchasing@mymanatee.org

Solicitation Addendum

Addendum No.: 2
Solicitation No.: 22-TA004390LP
Project No.: 6108460
Solicitation Title: 75th ST W Rebase from Cortez RD to Bridge #134094
Addendum Date: December 02, 2022
Procurement Contact: Leslie Peer

IFBC No. 22-TA004390LP is amended as set forth herein. Responses to questions posed by prospective bidders are provided below. This Addendum is hereby incorporated in and made a part of IFBC No. 22-TA004390LP.

The deadline to submit all inquiries concerning interpretation, clarification or additional information pertaining to this IFBC was November 21, 2022.

CHANGE TO:

ADVERTISEMENT, DATE, TIME AND PLACE DUE:

Change to Date, Time and Place Due:

The Due Date and Time for submission of Bids in response to this Invitation for Bid Construction (IFBC) is ~~December 05, 2022~~ **December 12, 2022 at 2:00 PM ET.** Bids must be delivered to the following location:

CHANGE TO:

SECTION A, INFORMATION FOR BIDDERS, A.01 BID DUE DATE:

Change to Information for Bidders, A.01 Bid Due Date:

The Due Date and Time for submission of Bids in response to this Invitation for Bid Construction (IFBC) is ~~December 05, 2022~~ **December 12, 2022 at 2:00 PM ET.** Bids must be delivered the following location: Manatee County Administration Building, 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205 and time stamped by a Procurement representative prior to the Due Date and Time.

CHANGE TO:

SECTION A, INFORMATION FOR BIDDERS, A.51 SOLICITATION SCHEDULE:

Scheduled Item	Scheduled Date
Question and Clarification Deadline	November 21, 2022
Final Addendum Posted	November 30, 2022
Bid Response Due Date and Time	December 05, 2022 , <u>December 12, 2022</u> 2:00 PM, ET
Projected Award	December 2022 <u>January 2023</u>

REPLACE:

SECTION B, BID FORMS, APPENDIX K, BID PRICING FORM

Replace Appendix K Bid Pricing Form, with Appendix K Bid Pricing Form Revised 2 issued with this Addendum 2 and available for download as a separate attachment.

QUESTIONS AND RESPONSES:

- Q1. There is only about 435 SY and not 4000. Can the milling quantity be adjusted? there is a slight adjustment of the milling per plan measurement. Please see attached. The bridge still receives mill & resurface, even though the CIP base is not required in this area.**
- R1. There is a slight adjustment of the milling per plan measurement. The bridge still receives mill & resurface, even though the CIP base is not required in this area. See Appendix K Bid Pricing Form Revised 2 attached to this Addendum 2 and available for download as a separate attachment.
- Q2. With that small window of lane restrictions, can the work be performed at night.**
- R2. Lane closures and work can occur between 7AM - 5PM.
- Q3. AC Adjustment has been discussed with Manatee County and we are under the impression that the Paving manager for Manatee County has approved AC Adjustments on current projects. Can you get clarification on this?**
- R3. Manatee County would not make adjustments to the asphalt cost on this contract due to its shorter construction timeframe.

Q4. The answer to question number 3 in Addendum 1 that was dated and received yesterday says that “Due to high traffic volumes, lane closures are ONLY permitted from 0 AM – 2 PM.” This statement, taken at face value, means that night work is not permitted. Is this correct? If so, please know that this requirement is extremely restrictive and will result in unnecessarily high costs. Please clarify this as soon as possible and/or extend the bid date.

R4. See R2. and Change to Due Date.

NOTE:

Deleted items will be ~~struck through~~, added or modified items will be underlined. All other terms and conditions remain as stated in the IFBC.

INSTRUCTIONS:

Receipt of this Addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the response being deemed non-responsive.

END OF ADDENDUM

AUTHORIZED FOR RELEASE

APPENDIX K, BID PRICING FORM (REVISED 2)
75TH ST WEST - REBASE
COUNTY PROJECT NO. 6108460

Bidders must provide prices for each available line item on each tab for their bid to be considered responsive.

LINE NUMBER	FDOT ITEM NO.	DESCRIPTION	ESTIMATED QUANTITY	U/M	UNIT PRICE BID A 150 CALENDAR DAYS	EXTENDED PRICE BID A	UNIT PRICE BID B 240 CALENDAR DAYS	EXTENDED PRICE BID B
MOBILIZATION & MAINTENANCE OF TRAFFIC								
1.	101-1	MOBILIZATION	1.00	LS				
2.	102-1	MAINTENANCE OF TRAFFIC	1.00	LS				
SUBTOTAL MOBILIZATION & MAINTENANCE OF TRAFFIC								
ROAD WORK								
3.	104-18	INLET PROTECTION SYSTEM	41.00	EA				
4.	MC-1	COLD-IN-PLACE RECYCLE 8" DEPTH	50,466.00	SY				
5.	327-70-6	MILLING EXIST ASPH PAVT, 1" TO 2" AVG DEPTH	50,903.00	SY				
6.	334-MC	TYPE S-I ASPHALT CONCRETE W/TACK COAT, 2"	5,599.00	TN				
7.	334-MC	TYPE S-III ASPHALT CONCRETE W/TACK COAT, 1"	2,800.00	TN				
8.	520-1-10	CONCRETE CURB & GUTTER, TYPE F (INCLUDING CONCRETE FLUMES)	40.00	LF				
9.	522-1	CONCRETE SIDEWALK, 4" THICK (INCLUDING HANDICAP RAMPS)	342.00	SY				
10.	522-2	CONCRETE DRIVEWAYS, 6" THICK	149.00	SY				
11.	527-2	DETECTABLE WARNINGS	360.00	SY				
SUBTOTAL ROAD WORK								
SIGNING AND PAVEMENT MARKINGS								
12.	0523-3	PATTERNED PAVEMENT	585.00	SY				
13.	700-1-11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	38.00	AS				
14.	700-1-60	SINGLE POST SIGN, REMOVE	11.00	AS				
15.	704-1-2	TUBULAR MARKER, DURABLE, 36" YELLOW POST	8.00	EA				
16.	0710-11290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	144.00	SF				
17.	711-11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	522.00	LF				
18.	711-11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	14.00	LF				
19.	711-11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE & CROSSWALK	560.00	LF				
20.	711-11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	0.50	GM				
21.	711-11-160	THERMOPLASTIC, STANDARD, WHIT, MESSAGE OR SYMBOL	23.00	EA				
22.	711-11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	74.00	EA				
23.	711-11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	252.00	LF				
24.	711-11-241	THERMOPLASTIC, STANDARD, YELLOW, 2X4' SKIP GUIDELINE	0.23	GM				
25.	711-11-15101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	2.69	GM				
26.	0711-15102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	0.02	GM				
27.	0711-15131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6" 10-30 SKIP OR 3-9 LANE DROP	2.45	GM				
28.	0711-15201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	2.63	GM				
29.	0711-15231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	0.99	GM				
SUBTOTAL SIGNING AND PAVING								
UTILITY IMPROVEMENTS								
30.	U1	MANHOLE FRAME & COVER (INCLUDING RAINWATER INSERT)	5.00	EA				
31.	U2	POLYMER CONCRETE ADJUSTMENT RING(S) (PER MANHOLE)	5.00	EA				
SUBTOTAL UTILITY IMPROVEMENTS								
LIGHTING								
32.	0630 2 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH (2" HDPE)	40.00	LF				
33.	0630 2 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE (2" HDPE)	370.00	LF				
34.	0633 8 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	1,720.00	LF				
35.	0635 2 11	POLYMER CONCRETE ADJUSTMENT RING(S) (PER MANHOLE) PULL & SPLICE BOX, F&I 13"X24" COVER SIZE	4.00	EA				
36.	0660 3 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	1.00	EA				
37.	0660 3 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	7.00	EA				
38.	0660 3 60	VEHICLE DETECTION SYSTEM - MICROWAVE, REMOVE, COMPLETE SYSTEM	1.00	EA				
39.	0670 5111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	1.00	AS				
40.	0670 5400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	1.00	AS				
41.	0682 1113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	1.00	EA				
42.	0684 1 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	1.00	EA				
43.	0685 1 12	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION	1.00	EA				
44.	0685 2 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	1.00	EA				
SUBTOTAL MOBILIZATION & MAINTENANCE OF TRAFFIC, ROAD WORK, SIGNING & PAVEMENT MARKINGS, SIGNALIZATION, AND UTILITY IMPROVEMENTS								
CONSTRUCTION CONTINGENCY COUNTY AUTHORIZED USE ONLY (10% OF SUBTOTAL PRICE)								
GRAND TOTAL								
ALTERNATE BID A								
45.	520-5-46-MC	TRAFFIC SEPARATOR CONCRETE - TYPE IV, 8.5' WIDE (Include signs and striping as necessary)	120.00	LF				

UPDATED

Bidder: _____

Signature: _____

*To be considered responsive, it is the sole responsibility of the bidder to correctly calculate and manually enter all sub-total, contingency and total bid price fields.