



Financial Management Department  
Procurement Division  
1112 Manatee Ave W Suite 803  
Bradenton, FL 34205-7804  
Phone: (941) 745-3730  
[www.mymanatee.org](http://www.mymanatee.org)

August 18, 2017

TO: All Interested Bidders

SUBJECT: **IFB 17-1514CB** – SLS N1H Rehabilitation & Emergency Backup Pump

**ADDENDUM #3**

**Bidders are hereby notified that this Addendum shall be acknowledged on Bid Form Page 1 and made a part of the above-named bidding and contract documents. Bids submitted without acknowledgment of the Addendum will be considered incomplete.**

The following items are issued to add to, modify, and clarify the bid and contract documents. These items shall have the same force and effect as the original bid and contract documents. Cost involved shall be included in the bid prices. Bids to be submitted by the specified bid opening time date due and shall conform to the additions and revisions listed herein.

**DELETE** Bid Form pages 3 through 6 and **INSERT** revised Bid Form pages 3 through 6 that are attached. Changes from Addendum #2 are highlighted in yellow.

END OF ADDENDUM 3

Bids will be received at Manatee County Procurement, 1112 Manatee Avenue West, Bradenton, Florida 34205 until **Wednesday, August 23, 2017 at 2:00 PM.**

Sincerely,

Chris Daley, CPPO CPPB  
Buyer Manager

#

PRISCILLA TRACE \* CHARLES B. SMITH \* STEPHEN JONSSON \* ROBIN DISABATINO \* VANESSA BAUGH \* CAROL WHITMORE \* BETSY BENAC

District 1

District 2

District 3

District 4

District 5

District 6

District 7#

#

**BID FORM**

(Submit in Duplicate)

**SLS N1H Rehabilitation & Emergency backup Pump**  
**Bid "A" Based on Completion Time of 150 Calendar Days**

ITEM NO.	DESCRIPTION	U/M	EST. QTY.	UNIT PRICE	EXTENDED PRICE
<b>REHABILITATION</b>					
1	Wetwell Cleaning	SF	1,350	\$	\$
2	Wetwell Discharge Piping, HDPE DR-11, 8"	LF	114	\$	\$
3	Pump Base Ells, BPIU.14	EA	3	\$	\$
4	Pump Base Elbow Mounting Plate	EA	3	\$	\$
5	S.S. Pipe Bracing, 12 ft dia., triplex	EA	4	\$	\$
6	PVC Stilling Well, 6"	LF	28	\$	\$
7	Replace Ex. Wetwell Top Slab	EA	1	\$	\$
8	Vent, PVC Sch 80, 6" (to odor control system)	LF	5	\$	\$
9	Aluminum Hatch Cover, (Wetwell)	EA	1	\$	\$
10	2" S.S.Pump Guide Rail System	LF	90	\$	\$
11	Repair Existing Liner, as needed	SF	675	\$	\$
12	Grout Fill Ex. Drain, Abandon	EA	1	\$	\$
13	PVC Drain Line for Odor Control, 2" PVC	LF	5	\$	\$
14	Gate Valve, Flanged, 8"	EA	5	\$	\$
15	Swing Check Valve, Flanged, 8"	EA	3	\$	\$
16	Gate Valve, MJ, 12"	EA	1	\$	\$
17	Gate Valve, MJ, 2"	EA	1	\$	\$
18	PVC Pipe (C900), 12"	LF	10	\$	\$
19	Ductile Iron Pipe				
19.1	8" DI Pipe, FLG	LF	25	\$	\$
19.2	12" DI Pipe, FLG	LF	20	\$	\$
20	Ductile Iron Fittings				
20.1	4"x8" Ecc. Reducer, DI, FLG	EA	3	\$	\$
20.2	8" Tee, DI, FLG	EA	2	\$	\$
20.3	8" Cross, DI, FLG	EA	1	\$	\$
20.4	8"x12" Red. 90 Bend, DI, FLG	EA	1	\$	\$
20.5	12" 90 Bend, DI, MJ	EA	1	\$	\$
20.6	12" 45 Bend, DI, MJ	EA	1	\$	\$
21	Coupling Adapters, D.I., FLG, 12"	EA	4	\$	\$
22	Quick Coupler Adapter, male, alum., 6"	EA	1	\$	\$
23	Quick Coupler Adapter, male, alum., 2"; w/ PVC filled conc. support	EA	1	\$	\$
24	S.S. Adjustable Valve Supports, flange attachment	EA	7	\$	\$
25	Remove Existing Structure, Valve Vault	EA	1	\$	\$
26	Remove Existing Structure, Meter Vault	EA	1	\$	\$
27	Concrete Slab	SY	50	\$	\$
28	Influent Line Plug, 18"	EA	2	\$	\$
29	By-Pass Pumping	LS	1	\$	\$
30	Water Line, PE, 3/4"	LF	50	\$	\$
31	Water Line, PE, 2"	LF	138	\$	\$
32	PVC Casing, 3"	LF	40	\$	\$
33	Relocated Ex. Meter, Backflow, & Hose Bibb Assembly	LS	1	\$	\$
34	Remove & Replace Electric Meter Can	EA	1	\$	\$
35	Remove & Replace Fused Safety Switch (disconnect)	EA	1	\$	\$
36	Remove & Replace Control Panel	EA	1	\$	\$
37	TCU & Fiberglass Enclosure, DFS	EA	1	\$	\$

Bidder Name: \_\_\_\_\_

Authorized Signature: \_\_\_\_\_

REVISED BID FORM- 3

**BID FORM**

(Submit in Duplicate)

**SLS N1H Rehabilitation & Emergency backup Pump  
Bid "A" Based on Completion Time of 150 Calendar Days**

ITEM NO.	DESCRIPTION	U/M	EST. QTY.	UNIT PRICE	EXTENDED PRICE
38	Junction Box, 304 SS	EA	1	\$	\$
39	Remove & Replace Sch 80 PVC Conduit, 2"	LF	125	\$	\$
40	Replace Electrical Service	LF	10	\$	\$
41	Remove & Replace Electrical Mounting Structure	EA	1	\$	\$
42	Washed Shell with Weed Barrier	SY	340	\$	\$
43	Driveway, 6" thick reinf. concrete	SY	210	\$	\$
44	Concrete Repair, 2" thick	SF	338	\$	\$
45	Removable 4" Dia. Steel Bollards w/ Yellow PVC Covers	EA	4	\$	\$
46	Storm Pipe, PVC, 10"	LF	38	\$	\$
47	Concrete Storm Mitered End Section	EA	1	\$	\$
48	Emergency Shower & Eyewash, Speakman S.S. SE-1255	EA	1	\$	\$
49	Flow Meter, 8" Ultra Mag (UM06)	EA	1	\$	\$
50	Generator Receptacle (JR5B2044FR) & Support	EA	1	\$	\$
51	Level Transducer, GSX3-PP100-A49-B49-XX-C01-D49	EA	1	\$	\$
52	New concrete wetwell fillet (3,000 psi, Type II, no reinf.)	CY	2	\$	\$
53	New concrete wetwell bottom (4,000 psi, Type II, with reinf.)	CY	4	\$	\$
	Rehabilitation SubTotal				\$
EMERGENCY BACK UP PUMP					
54	Reinforced Concrete Slab (poured in place)	SY	15	\$	\$
55	Emergency Backup Pump & Fuel Tank	LS	1	\$	\$
56	PVC Pipe (C900, DR-18), 6" (Pump Discharge Line)	LF	26	\$	\$
57	HDPE DR-11, 8" (Pump Suction Line)	LF	32	\$	\$
58	Ductile Iron Fittings				
58.1	4"x6" Red., DI, FLG	EA	2	\$	\$
58.2	4"x8" Red., DI, FLG	EA	1	\$	\$
58.3	6" 45 deg., DI, FLG	EA	2	\$	\$
58.4	6" 90 deg., DI, FLG	EA	1	\$	\$
58.5	8" 45 deg., DI, FLG	EA	1	\$	\$
58.6	8" 90 deg., DI, FLG	EA	1	\$	\$
58.7	8" 90 deg., DI, MJ	EA	1	\$	\$
59	Sch 80 PVC Conduit, 2"	LF	15	\$	\$
60	Level Transducer, GSX3-PP100-A49-B49-XX-C01-D49	EA	1	\$	\$
61	PVC Stilling Well, 6"	LF	28	\$	\$
62	Permits	LS	1	\$	\$
	Emergency Back-up Pump Subtotal				\$
63	Mobilization	LS	1	\$	\$
64	Miscellaneous Work & Clean Up	LS	1	\$	\$
65	Record Drawings	LS	1	\$	\$
	TOTAL BASE BID "A" - Based on Completion Time of 150 Calendar Days				\$
66	CONTRACT CONTINGENCY WORK (USED ONLY WITH COUNTY APPROVAL)		10% OF TOTAL BASE BID		\$
	TOTAL OFFER FOR BID "A" with Contract Contingency - Based on Completion Time of 150 Calendar Days				\$

Bidder Name: \_\_\_\_\_

Authorized Signature: \_\_\_\_\_

REVISED BID FORM- 4

**BID FORM**

(Submit in Duplicate)

**SLS N1H Rehabilitation & Emergency backup Pump**  
**Bid "B" Based on Completion Time of 210 Calendar Days**

ITEM NO.	DESCRIPTION	U/M	EST. QTY.	UNIT PRICE	EXTENDED PRICE
<b>REHABILITATION</b>					
1	Wetwell Cleaning	SF	1,350	\$	\$
2	Wetwell Discharge Piping, HDPE DR-11, 8"	LF	114	\$	\$
3	Pump Base Ells, BPIU.14	EA	3	\$	\$
4	Pump Base Elbow Mounting Plate	EA	3	\$	\$
5	S.S. Pipe Bracing, 12 ft dia., triplex	EA	4	\$	\$
6	PVC Stilling Well, 6"	LF	28	\$	\$
7	Replace Ex. Wetwell Top Slab	EA	1	\$	\$
8	Vent, PVC Sch 80, 6" (to odor control system)	LF	5	\$	\$
9	Aluminum Hatch Cover, (Wetwell)	EA	1	\$	\$
10	2" S.S.Pump Guide Rail System	LF	90	\$	\$
11	Repair Existing Liner, as needed	SF	675	\$	\$
12	Grout Fill Ex. Drain, Abandon	EA	1	\$	\$
13	PVC Drain Line for Odor Control, 2" PVC	LF	5	\$	\$
14	Gate Valve, Flanged, 8"	EA	5	\$	\$
15	Swing Check Valve, Flanged, 8"	EA	3	\$	\$
16	Gate Valve, MJ, 12"	EA	1	\$	\$
17	Gate Valve, MJ, 2"	EA	1	\$	\$
18	PVC Pipe (C900), 12"	LF	10	\$	\$
19	Ductile Iron Pipe				
19.1	8" DI Pipe, FLG	LF	25	\$	\$
19.2	12" DI Pipe, FLG	LF	20	\$	\$
20	Ductile Iron Fittings				
20.1	4"x8" Ecc. Reducer, DI, FLG	EA	3	\$	\$
20.2	8" Tee, DI, FLG	EA	2	\$	\$
20.3	8" Cross, DI, FLG	EA	1	\$	\$
20.4	8"x12" Red. 90 Bend, DI, FLG	EA	1	\$	\$
20.5	12" 90 Bend, DI, MJ	EA	1	\$	\$
20.6	12" 45 Bend, DI, MJ	EA	1	\$	\$
21	Coupling Adapters, D.I., FLG, 12"	EA	4	\$	\$
22	Quick Coupler Adapter, male, alum., 6"	EA	1	\$	\$
23	Quick Coupler Adapter, male, alum., 2"; w/ PVC filled conc. support	EA	1	\$	\$
24	S.S. Adjustable Valve Supports, flange attachment	EA	7	\$	\$
25	Remove Existing Structure, Valve Vault	EA	1	\$	\$
26	Remove Existing Structure, Meter Vault	EA	1	\$	\$
27	Concrete Slab	SY	50	\$	\$
28	Influent Line Plug, 18"	EA	2	\$	\$
29	By-Pass Pumping	LS	1	\$	\$
30	Water Line, PE, 3/4"	LF	50	\$	\$
31	Water Line, PE, 2"	LF	138	\$	\$
32	PVC Casing, 3"	LF	40	\$	\$
33	Relocated Ex. Meter, Backflow, & Hose Bibb Assembly	LS	1	\$	\$
34	Remove & Replace Electric Meter Can	EA	1	\$	\$
35	Remove & Replace Fused Safety Switch (disconnect)	EA	1	\$	\$
36	Remove & Replace Control Panel	EA	1	\$	\$
37	TCU & Fiberglass Enclosure, DFS	EA	1	\$	\$

Bidder Name: \_\_\_\_\_

Authorized Signature: \_\_\_\_\_

REVISED BID FORM- 5



**BID FORM**

(Submit in Duplicate)

**SLS N1H Rehabilitation & Emergency backup Pump  
Bid "B" Based on Completion Time of 210 Calendar Days**

ITEM NO.	DESCRIPTION	U/M	EST. QTY.	UNIT PRICE	EXTENDED PRICE
38	Junction Box, 304 SS	EA	1	\$	\$
39	Remove & Replace Sch 80 PVC Conduit, 2"	LF	125	\$	\$
40	Replace Electrical Service	LF	10	\$	\$
41	Remove & Replace Electrical Mounting Structure	EA	1	\$	\$
42	Washed Shell with Weed Barrier	SY	340	\$	\$
43	Driveway, 6" thick reinf. concrete	SY	210	\$	\$
44	Concrete Repair, 2" thick	SF	338	\$	\$
45	Removable 4" Dia. Steel Bollards w/ Yellow PVC Covers	EA	4	\$	\$
46	Storm Pipe, PVC, 10"	LF	38	\$	\$
47	Concrete Storm Mitered End Section	EA	1	\$	\$
48	Emergency Shower & Eyewash, Speakman S.S. SE-1255	EA	1	\$	\$
49	Flow Meter, 8" Ultra Mag (UM06)	EA	1	\$	\$
50	Generator Receptacle (JRSB2044FR) & Support	EA	1	\$	\$
51	Level Transducer, GSX3-PP100-A49-B49-XX-C01-D49	EA	1	\$	\$
52	New concrete wetwell fillet (3,000 psi, Type II, no reinf.)	CY	2	\$	\$
53	New concrete wetwell bottom (4,000 psi, Type II, with reinf.)	CY	4	\$	\$
<b>Rehabilitation SubTotal</b>					\$
<b>EMERGENCY BACK UP PUMP</b>					
54	Reinforced Concrete Slab (poured in place)	SY	15	\$	\$
55	Emergency Backup Pump & Fuel Tank	LS	1	\$	\$
56	PVC Pipe (C900, DR-18), 6" (Pump Discharge Line)	LF	26	\$	\$
57	HDPE DR-11, 8" (Pump Suction Line)	LF	32	\$	\$
58	Ductile Iron Fittings				
58.1	4"x6" Red., DI, FLG	EA	2	\$	\$
58.2	4"x8" Red., DI, FLG	EA	1	\$	\$
58.3	6" 45 deg., DI, FLG	EA	2	\$	\$
58.4	6" 90 deg., DI, FLG	EA	1	\$	\$
58.5	8" 45 deg., DI, FLG	EA	1	\$	\$
58.6	8" 90 deg., DI, FLG	EA	1	\$	\$
58.7	8" 90 deg., DI, MJ	EA	1	\$	\$
59	Sch 80 PVC Conduit, 2"	LF	15	\$	\$
60	Level Transducer, GSX3-PP100-A49-B49-XX-C01-D49	EA	1	\$	\$
61	PVC Stilling Well, 6"	LF	28	\$	\$
62	Permits	LS	1	\$	\$
<b>Emergency Back-up Pump Subtotal</b>					\$
63	Mobilization	LS	1	\$	\$
64	Miscellaneous Work & Clean Up	LS	1	\$	\$
65	Record Drawings	LS	1	\$	\$
<b>TOTAL BASE BID "B" - Based on Completion Time of 210 Calendar Days</b>					\$
66	<b>CONTRACT CONTINGENCY WORK (USED ONLY WITH COUNTY APPROVAL)</b>		<b>10% OF TOTAL BASE BID</b>		\$
<b>TOTAL OFFER FOR BID "B" with Contract Contingency - Based on Completion Time of 210 Calendar Days</b>					\$

Bidder Name: \_\_\_\_\_

Authorized Signature: \_\_\_\_\_