

REVISED - APPENDIX K, BID PRICING FORM						
IFBC NO. 20-TA003437AJ						
SATELLITE LIFT (LS) STATION R&R 2020 Group 1						
BID BASED ON A COMPLETION TIME OF 270 CALENDAR DAYS						
ITEM NO.	DESCRIPTION	U/M	QTY.	UNIT	PRICE	EXTENDED PRICE (\$)
LS Manatee Palms 312						
1	Wetwell Cleaning	SF	290			
2	Wetwell Discharge Piping, HDPE DR-11, 4"	LF	42			
3	Pump Base Ells, BPIU-14	EA	2			
4	Pump Base Ell Mounting Plate	EA	2			
5	S.S. Pipe Bracing, 6 ft dia.	EA	2			
6	Modify Existing Rim Elevation					
6.1	Wet Well	VF	0.25			
7	Replace Existing Top Slab					
7.1	Intentionally Left Blank					
7.2	Valve Vault	EA	1			
8	PVC Vent, Sch 80, 4"	EA	1			
9	Aluminum Hatch Cover, 36"x48", single door (Wetwell)	EA	1			
10	Aluminum Hatch Cover, 48" x 48", double door (Valve Vault) <u>H-20 rating required.</u>	EA	1			
11	2" S.S.Pump Guide Rail System	LF	25			
12	Resilient (Link) Seals w/ Carrier Pipe & Liner Repair	EA	5			
13	Wetwell Liner, spray-on	SF	290			
14	Intentionally Left Blank					
15	Remove & Replace Ex. PVC Drain P-trap (regROUT)	EA	1			
16	Intentionally Left Blank					
17	Gate Valve, FLG, 4"	EA	3			
18	Swing Check Valve, FLG, 4"	EA	2			
19	Gate Valve, MJ, 4"	EA	1			
20	Intentionally Left Blank					
21	Pipe, PVC (DR-18), 4"	LF	10			
22	Ductile Iron Fittings					
22.1	Intentionally Left Blank					
22.2	Cross, FLG, 4"	EA	1			
22.3	90, FLG, 4"	EA	2			
22.4	90, MJ, 4"	EA	1			
22.5	Intentionally Left Blank					
23	Coupling Adapters, D.I., FLG, 4"	EA	1			
24	Quick Coupler Adapter, aluminum, male w/ Alum. Dust Cap, 4"	EA	1			
25	Intentionally Left Blank					
26	Intentionally Left Blank					
27	Complete Removal of Existing Structure	EA	1			
28	Construct New Valve Vault	EA	1			
29	Intentionally Left Blank					
30	Influent Line Plug, 8"	EA	1			
31	By-Pass Pumping	LS	1			
32	Water Service Connection and Line					
32.1	2" saddle and PE tubing	LF	50			
33	Upgrade / Relocate Ex. Meter, Backflow, & Hose Bibb Assembly	EA	1			
34	Replace Ex. Tapping Saddle; Install Brass Plug	EA	1			

Bidder Name: _____

Authorized Signature: _____

Electronic signatures are accepted.

APPENDIX K, BID PRICING FORM
IFBC NO. 20-TA003437AJ
SATELLITE LIFT (LS) STATION R&R 2020 Group 1
BID BASED ON A COMPLETION TIME OF 270 CALENDAR DAYS

ITEM NO.	DESCRIPTION	U/M	QTY.	UNIT	PRICE	EXTENDED PRICE (\$)
35	Remove & Replace Electric Meter Can	EA	1			
36	Remove & Replace Fused Safety Switch (disconnect)	EA	1			
37	Remove & Replace Control Panel	EA	1			
37.1	Includes TCU Bubbler Unit (TBU-360) by DFS	EA	1			
38	TCU & Fiberglass Enclosure, DFS	EA	1			
39	Junction Box, 304 SS	EA	0			
40	Remove & Replace Sch 80 PVC Conduit	LF	0			
41	Remove & Replace Electrical Service	LF	20			
42	Remove & Replace Electrical Mounting Structure	EA	1			
43	Elect. System Study & Elect. Study Analysis, (NFPA 70E), complete	LS	1			
44	Ex. Antenna Concrete Base, remove & disposal	LS	1			
45	Intentionally Left Blank					
46	Brick & Mortar Valve Supports, 3 Total, Max. 8" High (if required)	VF	3			
47	Intentionally Left Blank					
48	Intentionally Left Blank					
49	Intentionally Left Blank					
50	Concrete Repair, 2" thick (if required)	SF	145			
51	Intentionally Left Blank					
52	Sodding	SY	66			
53	Existing Manhole Rim, modification	EA	1			
54-63	Intentionally Left Blank					
Subtotal Construction Cost						
64	Mobilization*	LS	1			
65	Record Drawings*	LS	1			
Total Base Bid Based on Completion Time of 270 Calendar Days for Manatee Palms 312						
66	Contract Contingency (10% of Subtotal Construction Cost)		10%			
Total Bid with Contract Contingency Based on Completion Time of 270 Calendar Days for Manatee Palms 312						

ITEM NO.	DESCRIPTION	U/M	QTY.	UNIT	PRICE	EXTENDED PRICE (\$)
LS Rye Rd School 355						
1	Wetwell Cleaning	SF	354			
2	Wetwell Discharge Piping, HDPE DR-11, 4"	LF	56			
3	Pump Base Ells, BPIU-14	EA	2			
4	Pump Base Ell Mounting Plate	EA	2			
5	S.S. Pipe Bracing, 6 ft dia.	EA	2			
6	Modify Existing Rim Elevation					
6.1	Wet Well	VF	0.5			
7	Replace Existing Top Slab					
7.1	Wet Well	EA	1			
7.2	Intentionally Left Blank					
8	PVC Vent, Sch 80, 6"	EA	1			
9	Aluminum Hatch Cover, 36" x 60", single door (Wetwell)	EA	1			
10	Intentionally Left Blank					

Bidder Name: _____

Authorized Signature: _____

Electronic signatures are accepted.

APPENDIX K, BID PRICING FORM						
IFBC NO. 20-TA003437AJ						
SATELLITE LIFT (LS) STATION R&R 2020 Group 1						
BID BASED ON A COMPLETION TIME OF 270 CALENDAR DAYS						
ITEM NO.	DESCRIPTION	U/M	QTY.	UNIT	PRICE	EXTENDED PRICE (\$)
11	2" S.S.Pump Guide Rail System	LF	32			
12	Intentionally Left Blank					
13	Wetwell Liner, spray-on	SF	354			
14	Remove Ex. Liner	SF	354			
15	Intentionally Left Blank					
16	Grout Fill Ex. Drain, abandon	EA	1			
17	Gate Valve, FLG, 4"	EA	3			
18	Swing Check Valve, FLG, 4"	EA	2			
19	Gate Valve, MJ, 6"	EA	1			
20	Pipe, D.I., FLG, 4"	LF	5			
21	Pipe, PVC (DR-18), 4"	LF	10			
22	Ductile Iron Fittings					
22.1	Tee, FLG, 4"	EA	2			
22.2	Intentionally Left Blank					
22.3	90, FLG, 4"	EA	1			
22.4	90, MJ, 4"	EA	1			
22.5	Reducer, MJ, 4"x6"	EA	1			
23	Intentionally Left Blank					
24	Quick Coupler Adapter, aluminum, male w/ Alum. Dust Cap, 4"	EA	1			
25	S.S. Adjustable Valve Supports, FLG attachment	EA	2			
26	Abandon Existing Structure	EA	1			
27	Intentionally Left Blank					
28	Intentionally Left Blank					
29	Concrete Slab, Valve Assembly	EA	1			
30	Influent Line Plug, 10"	EA	1			
31	By-Pass Pumping	LS	1			
32	Water Service Connection and Line					
32.1	2" saddle and PE tubing	LF	23			
33	Upgrade / Relocate Ex. Meter, Backflow, & Hose Bibb Assembly	EA	1			
34	Replace Ex. Tapping Saddle; Install Brass Plug	EA	1			
35	Remove & Replace Electric Meter Can	EA	1			
36	Remove & Replace Fused Safety Switch (disconnect)	EA	1			
37	Remove & Replace Control Panel	EA	1			
37.1	Includes TCU Bubbler Unit (TBU-360) by DFS	EA	1			
38	TCU & Fiberglass Enclosure, DFS	EA	1			
39	Junction Box, 304 SS	EA	1			
40	Remove & Replace Sch 80 PVC Conduit	LF	30			
41	Remove & Replace Electrical Service	LF	30			
42	Remove & Replace Electrical Mounting Structure	EA	1			
43	Elect. System Study & Elect. Study Analysis, (NFPA 70E), complete	LS	1			
44	Ex. Antenna Concrete Base, remove & disposal	LS	1			
45	Washed Shell with Weed Barrier	SY	150			
46	Intentionally Left Blank					
47	6' High Black Vinyl Coated Galvanized Fence	LF	16			

Bidder Name: _____

Authorized Signature: _____

Electronic signatures are accepted.

APPENDIX K, BID PRICING FORM
IFBC NO. 20-TA003437AJ
SATELLITE LIFT (LS) STATION R&R 2020 Group 1
BID BASED ON A COMPLETION TIME OF 270 CALENDAR DAYS

ITEM NO.	DESCRIPTION	U/M	QTY.	UNIT	PRICE	EXTENDED PRICE (\$)
48	6' High Black Vinyl Coated Galvanized Fence Gate	EA	1			
49	6' High Black Vinyl Coated Galvanized Corner/Gate Post	EA	6			
50	Concrete Repair, 2" thick (if required)	SF	177			
51	Install New Lift Station Driveway, 6" thick concrete	SY	65			
52	Intentionally Left Blank					
53	Intentionally Left Blank					

Subtotal Construction Cost

EMERGENCY GENERATOR REMOVAL-EMERGENCY BACKUP PUMP INSTALLATION

54	Site Demolition	LS	1			
55	Reinforced Concrete Slab (poured in place)	SY	15			
56	Emergency Backup Pump & Fuel Tank	LS	1			
57	PVC Pipe (C900, DR-18), 6" (Pump Discharge Line)	LF	26			
58	HDPE DR-11, 8" (Pump Suction Line)	LF	32			
59	Ductile Iron Fittings					
59.1	4"x6" Red., DI, FLG	EA	2			
59.2	4"x8" Red., DI, FLG	EA	1			
59.3	6" 45 deg., DI, FLG	EA	2			
59.4	6" 90 deg., DI, FLG	EA	1			
59.5	8" 45 deg., DI, FLG	EA	1			
59.6	8" 90 deg., DI, FLG	EA	1			
59.7	8" 90 deg., DI, MJ	EA	1			
60	Sch 80 PVC Conduit, 2"	LF	15			
61	Level Transducer, GX53-PP300-A49-B49-50-C01-D49	EA	1			
62	PVC Stilling Well, 6"	LF	28			
63	Permits	LS	1			

Generator Subtotal Construction Cost

Subtotal Overall Cost

64	Mobilization	LF	1			
65	Record Drawings	LS	1			

Total Base Bid Based on Completion Time of 270 Calendar Days

64	Contract Contingency (10% of Subtotal Construction Cost)		10%			
----	--	--	-----	--	--	--

Total Bid with Contract Contingency Based on Completion Time of 270 Calendar Days for LS Rye Rd School 355

ITEM NO.	DESCRIPTION	U/M	QTY.	UNIT	PRICE	EXTENDED PRICE (\$)
LS River Wilderness 3 531						
1	Wetwell Cleaning	SF	502			
2	Wetwell Discharge Piping, HDPE DR-11, 4"	LF	63			
3	Pump Base Ells, BPIU-14	EA	2			
4	Pump Base Ell Mounting Plate	EA	2			
5	S.S. Pipe Bracing, 7 ft dia.	EA	2			
6	Intentionally Left Blank					
6.1	Intentionally Left Blank					
7	Replace Existing Top Slab					

Bidder Name: _____

Authorized Signature: _____

Electronic signatures are accepted.

APPENDIX K, BID PRICING FORM						
IFBC NO. 20-TA003437AJ						
SATELLITE LIFT (LS) STATION R&R 2020 Group 1						
BID BASED ON A COMPLETION TIME OF 270 CALENDAR DAYS						
ITEM NO.	DESCRIPTION	U/M	QTY.	UNIT	PRICE	EXTENDED PRICE (\$)
7.1	Wet Well	EA	1			
7.2	Intentionally Left Blank					
8	PVC Vent, Sch 80, 4"	EA	1			
9	Aluminum Hatch Cover, 36" x 60", single door (Wetwell)	EA	1			
10	Intentionally Left Blank					
11	2" S.S.Pump Guide Rail System	LF	39			
12	Intentionally Left Blank					
13	Wetwell Liner, spray-on	SF	502			
14	Intentionally Left Blank					
15	Intentionally Left Blank					
16	Grout Fill Ex. Drain, abandon	EA	1			
17	Gate Valve, FLG, 4"	EA	3			
18	Swing Check Valve, FLG, 4"	EA	2			
19	Gate Valve, MJ, 4"	EA	1			
20	Pipe, D.I., FLG, 4"	LF	5			
21	Pipe, PVC (DR-18), 4"	LF	18			
22	Ductile Iron Fittings					
22.1	Tee, FLG, 4"	EA	2			
22.2	Intentionally Left Blank					
22.3	90, FLG, 4"	EA	1			
22.4	90, MJ, 4"	EA	1			
22.5	Intentionally Left Blank					
23	Coupling Adapters, D.I., FLG, 4"	EA	1			
24	Quick Coupler Adapter, aluminum, male w/ Alum. Dust Cap, 4"	EA	1			
25	S.S. Adjustable Valve Supports, FLG attachment	EA	2			
26	Abandon Existing Structure	EA	1			
27	Intentionally Left Blank					
28	Intentionally Left Blank					
29	Concrete Slab, Valve Assembly	EA	1			
30	Influent Line Plug, 8"	EA	1			
31	By-Pass Pumping	LS	1			
32	Water Service Connection and Line					
32.1	2" saddle and PE tubing	LF	55			
33	Upgrade / Relocate Ex. Meter, Backflow, & Hose Bibb Assembly	EA	1			
34	Replace Ex. Tapping Saddle; Install Brass Plug	EA	1			
35	Remove & Replace Electric Meter Can	EA	1			
36	Remove & Replace Fused Safety Switch (disconnect)	EA	1			
37	Remove & Replace Control Panel	EA	1			
37.1	Includes TCU Bubbler Unit (TBU-360) by DFS	EA	1			
38	TCU & Fiberglass Enclosure, DFS	EA	1			
39	Junction Box, 304 SS	EA	1			
40	Remove & Replace Sch 80 PVC Conduit	LF	30			
41	Intentionally Left Blank					
42	Remove & Replace Electrical Mounting Structure	EA	1			

Bidder Name: _____

Authorized Signature: _____

Electronic signatures are accepted.

APPENDIX K, BID PRICING FORM						
IFBC NO. 20-TA003437AJ						
SATELLITE LIFT (LS) STATION R&R 2020 Group 1						
BID BASED ON A COMPLETION TIME OF 270 CALENDAR DAYS						
ITEM NO.	DESCRIPTION	U/M	QTY.	UNIT	PRICE	EXTENDED PRICE (\$)
43	Elect. System Study & Elect. Study Analysis, (NFPA 70E), complete	LS	1			
44	Ex. Antenna Concrete Base, remove & disposal	LS	1			
45	Intentionally Left Blank					
46	Intentionally Left Blank					
47	Intentionally Left Blank					
48	Intentionally Left Blank					
49	Intentionally Left Blank					
50	Concrete Repair, 2" thick (if required)	SF	251			
51	Install New Lift Station Driveway, 6" thick concrete	SY	24			
52	Sodding	SY	50			
53	Existing Manhole Rim, modification	EA	1			
54-63						
Subtotal Construction Cost						
64	Mobilization*	LS	1			
65	Record Drawings*	LS	1			
Total Base Bid Based on Completion Time of 270 Calendar Days						
66	Contract Contingency (10% of Subtotal Construction Cost)		10%			
Total Bid with Contract Contingency Based on Completion Time of 270 Calendar Days for River Wilderness 3 531						
Grand Total Bid with Contract Contingency Based on Completion Time of 270 Calendar Days (Manatee Palm 312 + Rye Rd School 355 + River Wilderness 3 531)						\$ -

Bidder Name: _____

Authorized Signature: _____

Electronic signatures are accepted.