

**PART 2 PRODUCTS**

**2.01 GENERAL**

All enclosures shall comply with the standard detail for shape and size and shall include a 24"W x 24"H access door with a hasp for a padlock. The enclosure shall be securely attached to a concrete base with anchor brackets installed on the interior of the enclosure, through the flange base of the enclosure itself or through a stainless steel anchor hinge.

**2.02 ALUMINUM ENCLOSURE**

- A. The roof, walls and access panels shall be constructed of mill finish aluminum, ASTM B209, solid sheet construction, with a wall thickness of one eighth inch.
- B. All structural members shall be aluminum. No wood or "particle board" shall be allowed in assembly.
- C. Multi-sectional enclosures shall fit together with overlapping "tongue and groove" joints and be secured internally with mechanical fasteners.
- D. All assembly fasteners shall be stainless steel or aluminum.

**2.03 STAINLESS STEEL ENCLOSURE**

- A. The roof, walls and access panels shall be constructed stainless steel, type 316, solid sheet construction, with a wall thickness of one eighth inch.
- B. All structural members shall be stainless steel. No wood or "particle board" shall be allowed in assembly.
- C. Multi-sectional enclosures shall fit together with overlapping "tongue and groove" joints and be secured internally with mechanical fasteners.
- C. All assembly fasteners shall be stainless steel.

**FIBERGLASS ENCLOSURE**

- A. Enclosure shall be a 1 piece molded fiberglass enclosure with a base flange for mounting to the concrete slab and a full recessed door opening with a lip. Enclosure shall be by Allied Molded Products, or approved equal. Color shall be as directed by the Engineer.
- B. Full length piano style hinge, door latch, padlock hasp and all bolts and other hardware shall be of stainless steel.

**PART 3 EXECUTION**

**3.01 INSTALLATION**

- A. Enclosure shall be assembled and mounted on the concrete pad according to the manufacturer's instructions and the contract drawings.
- B. Enclosure shall be installed plumb, level and square.


**END OF SECTION**

# APPENDICES



**REPORT OF THE  
GEOTECHNICAL INVESTIGATION**

**SUBURBAN PIPELINE PROJECT - PHASE I  
WATER DISTRIBUTION SYSTEM  
MANATEE COUNTY, FLORIDA**



July 8, 2009

Manatee County Government  
1022 - 26<sup>th</sup> Avenue East  
Bradenton, Florida 34208

Attention: Mr. Paul Schamell  
Project Manager

**RE: Report of the Geotechnical Investigation  
Suburban Pipeline Project - Phase I  
Water Distribution System  
Manatee County, Florida  
Our File: DES 096393  
Work Assignment #9  
IFAS # WO900254**

Dear Paul:

Pursuant to your request and authorization, **DRIGGERS ENGINEERING SERVICES, INC.** has completed the requested geotechnical investigation for Phase I of the subject project. Presented herein are the results of our field and laboratory studies together with a general discussion of subsurface soil and groundwater conditions along the pipeline alignments. Results of our studies for Phase II will be presented in a separate report.

**GEOTECHNICAL INVESTIGATION PROGRAM**

A combined field and laboratory investigation program was undertaken to characterize the general nature of the subsurface soils and potential impacts with respect to the planned potable water distribution system.

**FIELD INVESTIGATION** - Plates I-A through I-R of the report attachments identify the respective positioning of thirty-three (33) shallow classification borings that were typically advanced to the requested depth of 8 feet below existing grade, where feasible. In accordance with your request, the classification borings were generally spaced a nominal 500 feet apart. The locations of the classification borings were identified in the field by our personnel with the assistance of the pipeline alignment plans provided by CH<sub>2</sub>M Hill. The locations depicted are considered approximate since they were not surveyed. Ground surface elevation information was not available.

The classification borings were conducted utilizing hand auger equipment wherein the soils were classified virtually continuously below existing grades to the termination depth. Where difficulties were encountered in advancing the borings, a small power auger was utilized in an attempt to advance the borings. Logs of the classification borings are presented in the report attachments reflecting visual together with estimated Unified Soil Classification. Groundwater depths measured during the course of our field investigation are noted on each respective boring log.

**LABORATORY CLASSIFICATION TESTS** - A limited laboratory classification testing program was undertaken to aid in characterizing the engineering properties of the subsurface soils. Our laboratory tests included grainsize analyses, Atterberg liquid and plastic limits and organic content. Selected samples were also tested for corrosivity potential. Atterberg limits, corrosivity and organic content results are presented on the Summary of Laboratory Test Results in the appendix. Results of the grainsize analyses are included in the report attachments reflecting the percent finer (by weight) versus the equivalent grain diameter or U.S. Standard Sieve size.

### **GENERALIZED SUBSURFACE CONDITIONS**

The results of our classification borings indicate that the subsurface soils typically consist of fine sands comprising the SP to SP-SM Unified Soil Classifications. Also penetrated were silty to clayey sands (SM to SC soils) interbedded with the relatively cleaner sands. Based upon our laboratory testing program, the fine sands typically contain minimal silt and clay fines, less than 10% by weight. However, some of the silty to clayey sand seams exhibited fines contents of up to about 18 percent, with the clayey sands exhibiting moderate plasticity characteristics. Some of the sands also contained traces to various concentrations of shell. Note that a thin seam of organic peat was encountered at a depth of about 3.0 to 3.4 feet at boring location HA-29.

Exceptions to the general trend occurred at nine (9) of the boring locations where a variably weathered limestone caprock was encountered. This generally thin rock unit was first encountered at depths ranging from about 0.8 to 5 feet beneath present grades. Where it was possible to penetrate below the limestone with a hand auger or small power auger, the unit was about generally about 6 inches to 2 feet in thickness. Note that at boring locations HA-1, HA-25 and HA-27 it was not possible to penetrate through the rock and boulders. Review of the Manatee County Soil Survey indicates the presence of Broward, Hallandale and Wabasso Variant soils in the project vicinity. The typical profile of each of these soil types includes shallow depth limestone, limestone boulders or gravel.

Groundwater was typically measured within a depth range of 5.8 to 7.6 feet below existing grade at the time of our geotechnical studies. At several locations, groundwater was not evident within the boring completion depth. It should be noted that these classification borings were conducted in middle to late June in the early part of the normal wet season. While there had been periods of heavy rainfall preceding our field investigation, there is the potential for groundwater to occur at shallower depths in response to intense or prolonged rainfall. Water may also occur in a temporarily perched state above the low permeability silty to clayey sand zones or discontinuous limestone caprock.

The Soil Survey information indicates that, under natural conditions, seasonal high groundwater levels for Broward, Hallandale and Wabasso Variant soils may occur within a foot of the ground surface. EauGallie-Myakka soils, which the Soil Survey map indicates in the southwester portion of the project area, have an indicated seasonal high groundwater level between 0.5 and 1.5 feet below grade. It should be noted that the Soil Survey estimates do not consider the effects of development and drainage improvements, all of which can affect groundwater levels. Inconsideration of the above, we would anticipate no more than a nominal 2 foot rise in groundwater above current water levels during the normal wet season. Confirmation of potential seasonal fluctuations would necessitate installing shallow piezometers and monitoring groundwater levels during the remainder of the wet season.

## **GEOTECHNICAL EVALUATION AND RECOMMENDATIONS**

**PLANNED FACILITIES** - We understand that the subject project consists of the construction of potable water mains of varying diameters and probably of HDPE construction. Based upon plans provided and discussions with Mr. Bob Cannarella, P.E. with CH<sub>2</sub>M Hill, the water mains will generally be constructed outside of existing pavements utilizing either directional drilling or standard cut and cover construction, with a burial depth of no more than about 5 feet.

**PIPELINE SUBGRADE CONDITIONS** - Our geotechnical studies suggest that the subgrade soils typically consist of fine sands containing minimal silt fines. These soil types should generally be suitable for pipe support provided that the subgrade is prepared in accordance with project specifications. In general, this will necessitate appropriate compaction at the bottom of excavation and throughout backfill soils required to re-establish existing grades in accordance with Manatee County specifications.

**SUITABILITY OF EXCAVATED SOILS FOR USE AS BACKFILL** - Fine sands indicated in our geotechnical studies will certainly represent suitable materials for replacement and compaction as backfill following pipeline installation. These fine sands comprising the SP to SP-SM Unified Soil Classification should respond effectively to conventional vibratory compaction. Results of corrosivity testing suggest that the soils along the pipeline routes fall within the “Slightly Aggressive” FDOT corrosivity classification.

Where silty to clayey sands were evidenced, these soils typically occurred in relatively thin layers. Accordingly, the soils with increased fines and some plasticity can probably be mixed with the cleaner sands during the excavation and backfilling process to improve the workability of these soils. Similarly, the thin organic zone evidenced in boring HA-29 can probably be mixed with the overlying and underlying sands and incorporated in the backfill. Where highly organic soils or plastic soils may exist near the bottom of the excavation or in greater thickness than suggested by the program of borings, it may be necessary to undercut the highly organic or plastic soils at least 2 feet and replace these materials with properly compacted granular backfill or gravel so as to produce a firm and unyielding subgrade for subsequent pipeline construction and backfilling operations.

The exploratory borings and Soil Survey information indicate that the pipeline construction will encounter shallow depth limestone, limestone boulders and limestone gravel in some areas. Gravel sized material may be incorporated within the sandy backfill soils. Rocks larger than about 3 inches should be excluded. Of course, rocks and oversize materials should be excluded from the pipe zone to minimize the potential for damage to the pipe.

It is important to recognize that the soils may exist in a very low natural moisture content depending upon the rainfall occurring at the time of construction or at high moisture contents when excavated below the water table. Accordingly, these soil types may require some adjustment in moisture content to achieve efficient and effective compaction. In general, it is beneficial to adjust moisture contents to within  $\pm 2\%$  of the optimum moisture as established by the Standard Proctor moisture-density relationship as set forth in AASHTO T-99.

**CONSTRUCTION CONSIDERATIONS** - Portions of the pipeline may be constructed utilizing open-cutting and rapid backfilling following pipeline installation. Depending on the depth of the cut, it may be necessary to adjust the slope ratios to no steeper than about 1.5 horizontal to 1.0 vertical in order to minimize sloughing or caving during the backfilling operations. Utilization of this slope ratio will necessitate proper dewatering and protection of the slope with respect to erosion and sloughing. Alternatively, trench-box construction would be considered in lieu of a sloped excavation. Naturally, the contractor must comply with applicable OSHA requirements with respect to trench safety.

In anticipation of cut depths typically 4 to 5 feet or less, we would not anticipate the need for a significant amount of construction dewatering throughout the project. Of course, abnormal rainfall could produce higher than expected groundwater levels and necessitate some local management of groundwater during pipeline construction. In that event, we would envision that the dewatering could be effectively accomplished by the application of a nominal 12 inch gravel drainage blanket of durable, washed limerock, granite or crushed concrete having a grading of no coarser than an FDOT No. 89. The gravel drainage blanket could then be used in conjunction with interior sumping in order to control groundwater levels below the invert of the pipeline and allow appropriate placement and compaction of the subgrade and backfill.

We understand that portions of the pipeline may be installed utilizing directional drilling. Care, of course, must be exercised during the directional drilling process in order to appropriately stabilize the horizontal borehole with drilling slurry so as to avoid potential caving of overlying soils that could cause unacceptable settlements to overlying or adjacent utilities or structures. Conversely, one must avoid overpressuring the drilling slurry that could result in unacceptable discharge of drilling slurry to the ground surface. The apparently discontinuous limestone caprock will also impact the utilization of directional drilling. Excavations may be needed where rock may exist at drilling entry and exit points. Where the rock layer is relatively shallow, the pipeline could be installed at a greater depth. However, this may force the pipe deeper than the intended maximum depth of 5 feet in some locations. The caprock will also present difficulties with excavations for service line connections.

Where rock was encountered and could not be penetrated during our authorized investigation, deeper borings are recommended to check the thickness of the rock which would affect both directional drilling and pipe direct burial depths. Additional more closely spaced borings would also be informative to help delineate the extent, thickness and nature of the limestone unit.

**CONSTRUCTION INSPECTION AND TESTING** - The authorized geotechnical investigation consisted of a series of relatively widely spaced, hand advanced classification borings intended to define generalized subsurface conditions that may be expected throughout the project limits. Clearly, the potential exists that localized variations or unexpected conditions may occur that would warrant modifications in construction procedures. Accordingly, it will be important to implement an appropriate program of geotechnical inspection of any open cuts during the construction stage to assist in identifying any such anomalous conditions and to provide economical recommendations for any necessary remediation. Inspection should be performed by a qualified geotechnical inspector familiar with the detailed contents of this report.

Compaction testing will also be required during the subgrade preparation and backfilling operations to check that the soils are being compacted in accordance with Manatee County compaction requirements. The compaction tests should be conducted in such a manner so as to check that all of the backfill soils are being uniformly densified to project specification requirements.

**LIMITATIONS** - The geotechnical investigation program was undertaken to provide general information to assist in the design and construction of the planned facilities. Our investigation may not have included all information that the prospective contractor may require in the preparation of his bid proposal. The contractor is certainly encouraged to conduct such additional studies as he may deem necessary to qualify his proposal.

Our geotechnical investigation was limited to an examination of subsurface soil and groundwater conditions so as to address geotechnical design and construction issues. Studies relative to environmental issues or impacts was not within the authorized scope of services.

**DRIGGERS ENGINEERING SERVICE, INC.** appreciates the opportunity to serve you during this phase of the design stage of the water distribution system. Should you have any questions concerning our report, please do not hesitate to contact the undersigned at your convenience.

Respectfully submitted,


**DRIGGERS ENGINEERING SERVICES, INC.**

*Nicholas T. Korecki 7-9-09*

Nicholas T. Korecki, P.E.

Senior Geotechnical Engineer

FL Registration No. 45529



F. Jaime Driggers, P.E.

President

FL Registration No. 16989

NTK

NTK-REP\096393-I

Copies submitted: (3) Manatee County Government.; Attn: Paul Schamell  
(2) CH<sub>2</sub>M Hill.; Attn: Mr. Bob Cannarella, P.E.



**APPENDIX**

**PLATES I-A THROUGH 1-R - TEST BORING LOCATION PLANS**



**HAND AUGER BORING LOGS**

**SUMMARY OF LABORATORY TEST RESULTS**

**GRAINSIZE ANALYSES**



**PLATES I-A THROUGH I-R - TEST BORING LOCATION PLANS**

W:\Manatee County Waterline Drawings\T\cover.dwg Plotted 2/18/2009 0:13 pm By: bklieni Model Plot Scale: 1=10 Xref Dwg's



DSGN	BJK				VERIFY SCALE	<b>CH2MHILL</b> 4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT No. 60747.70	SHEET	C1
DR	BJK			BAR IS ONE INCH ON ORIGINAL DRAWING.	25th ST W FROM 53rd AVE W TO 5423 25TH ST W			DWG	C1.DWG
CHK	RAC			0 = NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.				DATE	JUNE 2009
APVD	RAC	NO.	DATE	REVISION	BY			APVD	PROJ
ROBERT A. CANNARELLA, P.E. Fla. P.P.No. 17367									

Manatee County Waterline Drawings\Tcover.dwg Plotted 2/18/2009 0:13 Pm By: bkienl Model Plot Scale: 1=10 Xref Dwg's



DSGN	BJK			
DR	BJK			
CHK	RAC			
APVD	RAC			
NO.	DATE	REVISION	BY	APVD

5528				
5521				
5525				
5531				
5536				
5608				
5610				
5612				
5619				
5611				
5619				
5631				

VERIFY SCALE  
 BAR IS ONE INCH ON ORIGINAL DRAWING.  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

**CH2MHILL**  
 4350 WEST CYPRESS STREET SUITE 600  
 TAMPA, FLORIDA 33607-4155  
 LB 0002934 AA C000656


MANATEE COUNTY  
 SUBURBAN SYSTEM  
 WATER LINE REPLACEMENT PROJECT  
 PHASE 1  
 MANATEE COUNTY, FLORIDA  
 PROJECT No. 60747.70

PLAN SHEET NEW WATER MAIN  
 25th ST W FROM 5427 TO 5619

SHEET	C2
DWG	C2.DWG
DATE	JUNE 2009
PROJ	386879.WM


PLATE I-B

V:\Manatee County Waterline\Drawings\Tlcover.dwg Plotted: 2/18/2009 0:13 pm By: bklenl Model Plot Scale: 1=10 Xref Dwg's



▲ HAND AUGER BORING LOCATION

SCALE: 1" = 40'



DSGN	BJK				
DR	BJK				
CHK	RAC				
APVD	RAC	NO.	DATE	REVISION	BY
					APVD

ROBERT A. CANNARELLA, P.E.  
Fla. P.P. No. 17367

VERIFY SCALE  
BAR IS ONE INCH ON ORIGINAL DRAWING.  
IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

**CH2MHILL**  
4350 WEST CYPRESS STREET SUITE 600  
TAMPA, FLORIDA 33607-4155  
LB 0002934 AA C000656

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70

PLAN SHEET NEW WATER MAIN  
25th ST W FROM 5623 TO 57th AVE W

SHEET	C3
DWG	C3.DWG
DATE	JUNE 2009
PROJ	386879.WM

V:\Manatee County Waterline Drawings\Ticover.dwg Plotted 2/18/2009 0:13 pm By: bklein Model Plot Scale: 1=10 Xref Dwg: 5







PLATE 1-D


DSGN BJK DR BJK CHK RAC APVD RAC NO. DATE REVISION BY APVD	<b>VERIFY SCALE</b> BAR IS ONE INCH ON ORIGINAL DRAWING. 0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.	<b>CH2MHILL</b> 4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT No. 60747.70	PLAN SHEET NEW WATER MAIN 24th ST W FROM 53rd AVE W TO 5411 24th ST W	SHEET C4 DWG C4.DWG DATE JUNE 2009 PROJ 386879.WM
--	--	---	---	--	--

V:\Manatee County Waterline\Drawings\T1cover.dwg Plotted 2/18/2009 0:13 pm By: bklein Model Plot Scale: 1=10 Xref Dwg's



DSGN	BJK							VERIFY SCALE	<b>CH2MHILL</b> 4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT No. 60747.70	SHEET	C5
DR	BJK						BAR IS ONE INCH ON ORIGINAL DRAWING.	DWG			C5.DWG	
CHK	RAC						0 = 1"	DATE			JUNE 2009	
APVD	RAC						IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.	PROJ			386879.WM	
ROBERT A. CANNARELLA, P.E. Fla. P.P. No. 17367		NO.	DATE	REVISION	BY	APVD				PLAN SHEET NEW WATER MAIN 24th ST W FROM 5417 TO 5615 24th ST W		

V:\Manatee County Waterline\Drawings\Ticover.dwg Plotted: 2/18/2009 013 pm By: bklehl Model Plot Scale: 1=10 Xref: DWG5



**LEGEND:**  
 ▲ HAND AUGER BORING LOCATION

PLATE I-F

ROBERT A. CANNARELLA, P.E.  
 Fla. P.P. No. 17367

DSGN	BJK						
DR	BJK						
CHK	RAC						
APVD	RAC	NO.	DATE	REVISION	BY	APVD	

**VERIFY SCALE**  
 BAR IS ONE INCH ON ORIGINAL DRAWING.  
 0 1"  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

**CH2MHILL**  
 4350 WEST CYPRESS STREET SUITE 600  
 TAMPA, FLORIDA 33607-4155  
 LB 0002934 AA C000656



MANATEE COUNTY  
 SUBURBAN SYSTEM  
 WATER LINE REPLACEMENT PROJECT  
 PHASE 1  
 MANATEE COUNTY, FLORIDA  
 PROJECT No. 60747.70

PLAN SHEET NEW WATER MAIN  
 24th ST W FROM 5719 24th ST W TO 57th AVE W

SHEET	C6
DWG	C6.DWG
DATE	JUNE 2009
PROJ	386879.WM



W:\Manatee County Waterline Drawings\Tlcover.dwg Plotted 2/18/2009 0:13 pm By: bkienl Model Plot Scale: 1"=10' Xref Dwg's




SCALE: 1" = 40'

**LEGEND:**  
 ▲ HAND AUGER BORING LOCATION

PLATE I-G

DSGN BJK DR BJK CHK RAC APVD RAC ROBERT A. CANNARELLA, P.E. Fla. P.P. No. 17367	NO.	DATE	REVISION	BY	APVD	VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.	<b>CH2MHILL</b> 4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT No. 60747.70	PLAN SHEET NEW WATER MAIN 23rd ST CT W FROM 54th AVE DR W TO 55th AVE W	SHEET	C7
			DWG	C7.DWG							
			DATE	JUNE 2009							
			PROJ	386879.WM							

V:\Manatee County Waterline\Drawings\Ticover.dwg Plotted 2/18/2009 0:13 pm By: bkienl Model Plot Scale: 1=10 Xref Dwg's



**LEGEND:**



▲ HAND AUGER BORING LOCATION

SCALE: 1" = 40'

**PLATE I-H**

DSGN	BJK								VERIFY SCALE	<b>CH2MHILL</b> 4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT No. 60747.70	SHEET	C8
DR	BJK							BAR IS ONE INCH ON ORIGINAL DRAWING.	DWG			C8.DWG	
CHK	RAC							0 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.	DATE			JUNE 2009	
APVD	RAC	NO.	DATE	REVISION	BY	APVD				PLAN SHEET NEW WATER MAIN	PROJ	386879.WM	
ROBERT A. CANNARELLA, P.E. Fla. P.P. No. 17367													

V:\Manatee County Waterline\Drawings\Ticover.dwg Plotted: 2/18/2009 01:13 pm By: bklehr Model Plot Scale: 1"=10' Xref: Dwg's



**LEGEND:**  
 ▲ HAND AUGER BORING LOCATION

PLATE 1-1

DSGN	BJK				
DR	BJK				
CHK	RAC				
APVD	RAC	NO.	DATE	REVISION	BY

VERIFY SCALE  
 BAR IS ONE INCH ON ORIGINAL DRAWING.  
 0 1"  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.


**CH2MHILL**  
 4350 WEST CYPRESS STREET SUITE 600  
 TAMPA, FLORIDA 33607-4155  
 LB 0002934 AA C000656

MANATEE COUNTY  
 SUBURBAN SYSTEM  
 WATER LINE REPLACEMENT PROJECT  
 PHASE 1  
 MANATEE COUNTY, FLORIDA  
 PROJECT No. 60747.70

PLAN SHEET NEW WATER MAIN  
 21st ST W FROM 5325 TO 55th AVE W

SHEET	C9
DWG	C9.DWG
DATE	JUNE 2009
PROJ	386879.WM


V:\Manatee County Waterline Drawings\Ticover.dwg Plotted: 2/18/2009 0:13 pm By: bkiehl Model Plot Scale: 1=10 Xref: Dwg's



**LEGEND:**

▲ HAND AUGER BORING LOCATION

SCALE: 1" = 40'



**LEGEND:**

▲ HAND AUGER BORING LOCATION

SCALE: 1" = 40'

**PLATE I-J**

DSGN	BJK			
DR	BJK			
CHK	RAC			
APVD	RAC	NO.	DATE	REVISION

ROBERT A. CANNARELLA, P.E.  
Fla. P.P. No. 17367

VERIFY SCALE  
BAR IS ONE INCH ON ORIGINAL DRAWING.  
0 1"  
IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.



**CH2MHILL**  
4350 WEST CYPRESS STREET SUITE 500  
TAMPA, FLORIDA 33607-4155  
LB 0002934 AA C000656

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70

PLAN SHEET WATER LINE  
22nd ST W FROM 53rd AVE W TO 5327 22nd ST W



SHEET	C10
DWG	C10.DWG
DATE	JUNE 2009
PROJ	386879.WM

U:\Manatee County Waterline\Drawings\T\cover.dwg Plotted: 2/19/2009 0:13 pm By: bk1eh1 Model Plot Scale: 1=10 Xref: Dwg's



DSGN	BJK			VERIFY SCALE	<p><b>CH2MHILL</b> 4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656</p>	<p>MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT No. 60747.70</p>	SHEET	C11
DR	BJK			BAR IS ONE INCH ON ORIGINAL DRAWING.			DWG	C11.DWG
CHK	RAC			0 = 1"			DATE	JUNE 2009
APVD	RAC	NO.	DATE	IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.			PROJ	386879.WM

V:\Manatee County Waterline\Drawings\Ticover.dwg Plotted: 2/18/2009 0:13 pm By: bk1e1n1 Model Plot Scale: 1=10 Xref Dwg's



DSGN	BJK				
DR	BJK				
CHK	RAC				
APVD	RAC	NO.	DATE	REVISION	BY


VERIFY SCALE  
 BAR IS ONE INCH ON ORIGINAL DRAWING.  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

**CH2MHILL**  
 4350 WEST CYPRESS STREET SUITE 600  
 TAMPA, FLORIDA 33607-4155  
 LB 0002934 AA C000656

MANATEE COUNTY  
 SUBURBAN SYSTEM  
 WATER LINE REPLACEMENT PROJECT  
 PHASE 1  
 MANATEE COUNTY, FLORIDA  
 PROJECT No. 60747.70


PLAN SHEET NEW WATER MAIN  
 23rd ST W FROM 55th AVE W TO 5628

SHEET	C12
DWG	C12.DWG
DATE	JUNE 2009
PROJ	386879.WM



SCALE: 1" = 40'

**LEGEND:**  
 ▲ HAND AUGER BORING LOCATION



SCALE: 1" = 40'

**LEGEND:**  
 ▲ HAND AUGER BORING LOCATION


PLATE I-M

DSGN BJK DR BJK CHK RAC APVD RAC	NO.	DATE	REVISION	BY	APVD	<b>VERIFY SCALE</b> BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.	<b>CH2MHILL</b> 4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT No. 60747.70	SHEET C14 DWG C14.DWG DATE JUNE 2009 PROJ 386879.WM
	ROBERT A. CANNARELLA, P.E. Fla. P.P. No. 17367								

V:\Manatee County Waterline\Drawings\Ticover.dwg Plotted: 2/18/2009 013 pm By: bklehr Model Plot Scale: 1=10 Xref: Dwg's



W:\Manatee County Waterline Drawings\Ticover.dwg Plotted 2/18/2009 0:13 pm By: bklein Model Plot Scale: 1"=10' Xref Dwg's



**LEGEND:**  
 ▲ HAND AUGER BORING LOCATION

SCALE: 1" = 40'

PLATE I-N


DSGN BJK DR BJK CHK RAC APVD RAC		NO.    DATE _____	REVISION _____	BY    APVD _____	VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING. 0    1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.	<b>CH2MHILL</b> 4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT No. 60747.70	PLAN SHEET NEW WATER MAIN 21st ST CT W FROM 5624 TO 57th AVE W	SHEET C15 DWG C15.DWG DATE JUNE 2009 PROJ 386879.WM
---	--	----------------------	-------------------	---------------------	--	---	--	---	--

ROBERT A. CANNARELLA, P.E.  
 Fla. P.P. No. 17367






\\Manatee County\Waterline\Drawings\Ticover.dwg Plotted: 2/18/2009 0:13 pm By: bk1e1 Model Plot Scale: 1"=10' Xref: Dwg: 51



**LEGEND:**  
 ▲ HAND AUGER BORING LOCATION



**LEGEND:**  
 ▲ HAND AUGER BORING LOCATION

PLATE I-P

DSGN	BJK				
DR	BJK				
CHK	RAC				
APVD	RAC	NO.	DATE	REVISION	BY

ROBERT A. CANNARELLA, P.E.  
 Fla. P.P. No. 17367


**VERIFY SCALE**  
 BAR IS ONE INCH ON ORIGINAL DRAWING.  
 0 1"  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

**CH2MHILL**  
 4350 WEST CYPRESS STREET SUITE 600  
 TAMPA, FLORIDA 33607-4155  
 LB 0002934 AA C000656


MANATEE COUNTY  
 SUBURBAN SYSTEM  
 WATER LINE REPLACEMENT PROJECT  
 PHASE 1  
 MANATEE COUNTY, FLORIDA  
 PROJECT No. 60747.70

PLAN SHEET NEW WATER MAIN  
 16th ST W FROM 5506 TO 57th AVE W

SHEET	C17
DWG	C17.DWG
DATE	JUNE 2009
PROJ	386879.WM



SCALE: 1" = 40'



SCALE: 1" = 40'

**LEGEND:**

▲ HAND AUGER BORING LOCATION

DSGN	BJK
DR	BJK
CHK	RAC
APVD	RAC

NO.	DATE	REVISION	BY	APVD

VERIFY SCALE  
 BAR IS ONE INCH ON ORIGINAL DRAWING.  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

**CH2MHILL**  
 4350 WEST CYPRESS STREET SUITE 600  
 TAMPA, FLORIDA 33607-4155  
 LB 0002934 AA C000656

MANATEE COUNTY  
 SUBURBAN SYSTEM  
 WATER LINE REPLACEMENT PROJECT  
 PHASE 1  
 MANATEE COUNTY, FLORIDA  
 PROJECT No. 60747.70

PLAN SHEET NEW WATER MAIN  
 55th AVE W FROM CENTERLINE OF 23rd ST W TO 1807

SHEET	C19
DWG	C19.DWG
DATE	JUNE 2009
PROJ	386879.WM

Xref Dwg's Model Plot Scale: 1=10  
 Plotted: 2/18/2009 01:3 pm By: bkierl  
 \\Manatee County\Waterline\Drawings\T1cover.dwg

V:\Manatee County Waterline\Drawings\Ticover.dwg Plotted 2/18/2009 0:13 pm By: bkleinl Model Plot Scale: 1=10 Xref Dwg's





PLATE I-R

DSGN BJK DR BJK CHK RAC APVD RAC	NO.	DATE	REVISION	BY	APVD	VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING. 0" 1" IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.	<b>CH2MHILL</b> 4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT No. 60747.70	PLAN SHEET NEW WATER MAIN 55th AVE W FROM 1805 TO 18th ST W	SHEET	C20	
										DWG	C20.DWG	
										DATE	JUNE 2009	
										PROJ	386879.WM	


ROBERT A. CANNARELLA, P.E.  
 Fla. P.P. No. 17367

## **HAND AUGER BORING LOGS**




**DRIGGERS ENGINEERING SERVICES INCORPORATED**

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
		<b>WATER TABLE:</b> See "Note"		<b>DATE:</b> 6/23/09
<b>TECHNICIAN:</b> S.F.		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 6.0' *	
<b>LOCATION:</b> See Plate I-A		<b>TEST NUMBER:</b> HA-1		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with roots and rock fragments (SP)	0		* Could not penetrate below depth 6.0' due to LIMESTONE.  Note: Water Table not encountered within depth of 6.0'.
	Light brown Fine SAND with rock fragments (SP)			
	Grayish-brown Fine SAND with trace of shell fragments (SP)	2		
	Light brownish-gray Fine SAND (SP)			
	Light brown Fine SAND (SP)			
	Brown and light brown clayey Fine SAND (SC)	4		
	Grayish-brown Fine SAND with large pieces of cream colored LIMESTONE (SP)			
		6		
		8		
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**


HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
		<b>WATER TABLE:</b> 6.5'	<b>DATE:</b> 6/23/09	
<b>TECHNICIAN:</b> S.F.		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 7.5' *	
<b>LOCATION:</b> See Plate I-A		<b>TEST NUMBER:</b> HA-2		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with shell fragments and trace of roots (SP)	0	▽	* Could not penetrate below depth 7.5' due to abundant shell fragments.
	Tan Fine SAND (SP)		▽	
	Tan and light orange Fine SAND with pockets of clayey Fine SAND (SP/SC)	2	▽	
	Tan Fine SAND with shell fragments (SP)		▽	
	Light grayish-brown Fine SAND with abundant shell fragments (SP)	4	▽	
			▽	
		6	▽	
			▽	
		8	▽	
			▽	
		10	▽	
			▽	
		12	▽	
			▽	
		14	▽	



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
		<b>WATER TABLE:</b> 6.8'	<b>DATE:</b> 6/23/09	
<b>TECHNICIAN:</b> S.F.		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 8.0'	
<b>LOCATION:</b> See Plate I-A		<b>TEST NUMBER:</b> HA-3		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with roots and rock fragments (SP)	0		
	Light grayish-brown Fine SAND (SP)			
	Light brown and light orange clayey Fine SAND (SC)	2		
	Tan Fine SAND (SP)			
	Light gray, light brown and orange clayey Fine SAND (SC)			
	Light brown Fine SAND (SP)	4		
	Brown slightly silty Fine SAND (SP-SM)			
	Light brown Fine SAND with shell fragments (SP)	6		
		8		
		10		
		12		
		14		













**DRIGGERS ENGINEERING SERVICES INCORPORATED**

**HAND AUGER BORING LOG**

<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County	
<b>TECHNICIAN:</b> S.F.		<b>WATER TABLE:</b> 6.9'	<b>DATE:</b> 6/23/09
<b>LOCATION:</b> See Plate I-B		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 8.0'
		<b>TEST NUMBER:</b> HA-4	

ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with surficial roots and trace of rock fragments (SP)	0	[Symbol: Dotted pattern with small circles and dashes]	
	Gray Fine SAND with trace of roots (SP)			
	Light grayish-brown Fine SAND (SP)	2		
	Light brown Fine SAND with trace of Limestone Gravel (SP)			
	Tan Fine SAND (SP)	4		
	Light grayish-tan Fine SAND (SP)			
		6		
	Grayish-brown Fine SAND with shell fragments (SP)	8		
		10		
		12		
		14		

<b>HAND AUGER BORING LOG</b>				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
		<b>WATER TABLE:</b> 6.9'	<b>DATE:</b> 6/23/09	
<b>TECHNICIAN:</b> S.F.		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 8.0'	
<b>LOCATION:</b> See Plate I-B		<b>TEST NUMBER:</b> HA-5		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with roots, shell and rock fragments (SP)	0		
	Light grayish-brown Fine SAND (SP)			
		2		
	Tan Fine SAND with some cemented sand (SP)			
	Brownish-gray clayey Fine SAND with trace of shell fragments (SC)			
		4		
	Light brown Fine SAND (SP)			
	Light grayish-brown Fine SAND with shell fragments (SP)			
		6		
	Light brown Fine SAND with shell fragments (SP)			
		8		
		10		
		12		
		14		




**DRIGGERS ENGINEERING SERVICES INCORPORATED**

**HAND AUGER BORING LOG**

<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County	
<b>TECHNICIAN:</b> S.F.		<b>WATER TABLE:</b> 7.1'	<b>DATE:</b> 6/23/09
<b>LOCATION:</b> See Plate I-C		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 8.0'
		<b>TEST NUMBER:</b> HA-6	

ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with trace of roots and trace of rock fragments (SP)	0		
	Light brown Fine SAND (SP)	2		
	Tan Fine SAND (SP)			
	Brown silty Fine SAND (SM)	4		
	Brown Fine SAND (SP)	6		
	Light brown Fine SAND (SP)	8		
		10		
		12		
		14		

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
<b>TECHNICIAN:</b> M.H.		<b>WATER TABLE:</b> 7.4'	<b>DATE:</b> 6/23/09	
<b>LOCATION:</b> See Plate I-D		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 8.0'	
		<b>TEST NUMBER:</b> HA-7		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with shell fragments (SP)	0		
	Grayish-brown Fine SAND with trace of cream colored calcareous, clayey Fine SAND (SP)			
	Grayish-brown Fine SAND with small shell fragments and trace of clayey Fine SAND pockets (SP)	2		
	Tan Fine SAND with shell fragments (SP)	4		
	Light orange and tan Fine SAND with shell fragments (SP)			
	Very light gray Fine SAND with some shell fragments (SP)	6		
	Light grayish-brown Fine SAND with shell fragments (SP)	8		
		10		
		12		
		14		

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
		<b>WATER TABLE:</b> 7.2'	<b>DATE:</b> 6/23/09	
<b>TECHNICIAN:</b> M.H.		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 8.0'	
<b>LOCATION:</b> See Plate I-D		<b>TEST NUMBER:</b> HA-8		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with surficial roots (SP)	0	[Symbol: Dotted with small 'x' marks]	
	Tan Fine SAND (SP)	2	[Symbol: Dotted]	
	Light brown clayey Fine SAND with light orange veins and trace of shell fragments (SC)	4	[Symbol: Diagonal lines with small triangles]	
	Tan Fine SAND (SP)		[Symbol: Dotted]	
	Tan Fine SAND with shell fragments (SP)	6	[Symbol: Dotted with larger triangles]	
	Light grayish-brown Fine SAND with shell fragments (SP)	8	[Symbol: Dotted with larger triangles]	
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

**HAND AUGER BORING LOG**

<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County	
<b>TECHNICIAN:</b> M.H.		<b>WATER TABLE:</b> 6.2'	<b>DATE:</b> 6/23/09
<b>LOCATION:</b> See Plate I-D		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 8.0'
		<b>TEST NUMBER:</b> HA-9	

ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with shell fragments and trace of roots (SP)	0		
	Brown Fine SAND (SP)	2		
	Grayish-brown slightly silty Fine SAND (SP-SM)	4		
	Tan Fine SAND with trace of shell fragments (SP)	6		
	Tan Fine SAND with shell fragments (SP)	8		
		10		
		12		
		14		

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
		<b>WATER TABLE:</b> 7.6'	<b>DATE:</b> 6/23/09	
<b>TECHNICIAN:</b> M.H.		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 8.0'	
<b>LOCATION:</b> See Plate I-E		<b>TEST NUMBER:</b> HA-10		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with surficial roots and some shell fragments (SP)	0	▽▽▽▽	
	Light brown Fine SAND with trace of shell fragments (SP)		▽▽▽▽	
		2	▽▽▽▽	
			▽▽▽▽	
		4	▽▽▽▽	
	Tan Fine SAND (SP)		▽▽▽▽	
	Light brown slightly clayey Fine SAND (SP-SM)		▽▽▽▽	
		6	▽▽▽▽	
	Light brown Fine SAND (SP)		▽▽▽▽	
	Light grayish-brown Fine SAND with shell fragments (SP)		▽▽▽▽	
		8	▽▽▽▽	
			▽▽▽▽	
		10	▽▽▽▽	
			▽▽▽▽	
		12	▽▽▽▽	
			▽▽▽▽	
		14	▽▽▽▽	



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
		<b>WATER TABLE:</b> 6.9'	<b>DATE:</b> 6/23/09	
<b>TECHNICIAN:</b> M.H.		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 8.0'	
<b>LOCATION:</b> See Plate I-E		<b>TEST NUMBER:</b> HA-11		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with surficial roots (SP)	0	▽	
	Grayish-brown Fine SAND with trace of shell fragments (SP)		▽	
	Brownish-gray Fine SAND with trace of shell fragments (SP)	2	▽	
	Light grayish-brown Fine SAND with some shell fragments (SP)		▽	
		4	▽	
			▽	
	Tan Fine SAND with shell fragments (SP)	6	▽	
	Grayish-brown Fine SAND with shell fragments (SP)		▽	
		8	▽	
			▽	
		10	▽	
			▽	
		12	▽	
			▽	
		14	▽	






**DRIGGERS ENGINEERING SERVICES INCORPORATED**

<b>HAND AUGER BORING LOG</b>				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
<b>TECHNICIAN:</b> M.H.		<b>WATER TABLE:</b> 7.2'	<b>DATE:</b> 6/23/09	
<b>LOCATION:</b> See Plate I-F		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 8.0'	
		<b>TEST NUMBER:</b> HA-12		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Dark brownish-gray Fine SAND with surficial roots (SP)	0		
	Tannish-brown Fine SAND (SP)			
	Light brown Fine SAND with pockets of clayey Fine SAND (SP/SC)	2		
	Brown clayey Fine SAND with light orange veins (SC)			
	Brown and light brown Fine SAND (SP)	4		
	Light grayish-brown Fine SAND with shell fragments (SP)	6		
		8		
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
		<b>WATER TABLE:</b> See "Note"		<b>DATE:</b> 6/23/09
<b>TECHNICIAN:</b> M.B.		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 8.0'	
<b>LOCATION:</b> See Plate I-G		<b>TEST NUMBER:</b> HA-13		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with some roots and some shell fragments (SP)	0		Note: Water Table not encountered within depth of 8.0'.
	Light grayish-brown Fine SAND with shell fragments (SP)			
		2		
	Cream colored LIMESTONE			
	Light brownish-gray clayey Fine SAND (SC)	4		
	Tan Fine SAND with shell fragments (SP)			
		6		
	Light grayish-brown Fine SAND with shell fragments (SP)			
		8		
		10		
		12		
		14		




**DRIGGERS ENGINEERING SERVICES INCORPORATED**

**HAND AUGER BORING LOG**

<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County	
<b>TECHNICIAN:</b> M.H.		<b>WATER TABLE:</b> See "Note"	<b>DATE:</b> 6/22/09
<b>LOCATION:</b> See Plate I-H		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 8.0'
		<b>TEST NUMBER:</b> HA-14	

ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Gray Fine SAND with roots (SP)	0		
	Grayish-brown Fine SAND with shell fragments (SP)	2		
	Light brown Fine SAND with trace of clayey Fine SAND pockets (SP)			
	Light grayish-brown Fine SAND with shell fragments (SP)	4		
	Brown clayey Fine SAND (SC)			
	Brown Fine SAND with trace of shell fragments (SP)	6		
		8		Note: Borehole caved in to depth of 7.1'.
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

**HAND AUGER BORING LOG**

<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County	
<b>TECHNICIAN:</b> M.H.		<b>WATER TABLE:</b> See "Note"	<b>DATE:</b> 6/22/09
<b>LOCATION:</b> See Plate I-I		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 8.0'
		<b>TEST NUMBER:</b> HA-15	

ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with shell and rock fragments (SP)	0		<p>Note: Borehole caved in to depth of 7.7'.</p> <p>Soils wet at approximate depth of 6.7' - Water Table measured at depth of 7.6'.</p>
	Brown Fine SAND (SP)			
		2		
		4		
	Brown Fine SAND with Limestone Gravel (SP)			
	Grayish-brown Fine SAND with Limestone Gravel (SP)	6		
	Light brown Fine SAND with some shell fragments (SP)			
	Tan Fine SAND with trace of shell fragments (SP)			
		8		
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
		<b>WATER TABLE:</b> 7.2'	<b>DATE:</b> 6/22/09	
<b>TECHNICIAN:</b> M.H.		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 8.0'	
<b>LOCATION:</b> See Plate I-J		<b>TEST NUMBER:</b> HA-16		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with roots (SP)	0	[Symbol: Dotted]	
	Tan Fine SAND (SP)		[Symbol: Dotted]	
		2	[Symbol: Dotted]	
	Brown clayey Fine SAND (SC)		[Symbol: Diagonal Lines]	
	Light brown slightly clayey Fine SAND with pockets of clayey Fine SAND (SP-SM/SC)		[Symbol: Diagonal Lines]	
		4	[Symbol: Diagonal Lines]	
	Light brownish-tan Fine SAND (SP)		[Symbol: Dotted]	
	Brown Fine SAND (SP)		[Symbol: Dotted]	
		6	[Symbol: Dotted]	
	Grayish-brown Fine SAND (SP)		[Symbol: Dotted]	
		8	[Symbol: Dotted]	
			[Symbol: Dotted]	
		10	[Symbol: Dotted]	
			[Symbol: Dotted]	
		12	[Symbol: Dotted]	
			[Symbol: Dotted]	
		14	[Symbol: Dotted]	



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

**HAND AUGER BORING LOG**

<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County	
<b>TECHNICIAN:</b> M.H.		<b>WATER TABLE:</b> See "Note"	<b>DATE:</b> 6/22/09
<b>LOCATION:</b> See Plate I-J		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 8.0'
		<b>TEST NUMBER:</b> HA-17	

ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with roots and rock fragments (SP)	0		<p>Note: Water Table not encountered within depth of 8.0'.</p> <p>Soils wet at approximate depth of 7.0'.</p>
	Light brown Fine SAND (SP)	2		
	Tan Fine SAND (SP)	4		
	Light brown Fine SAND with trace of cream colored calcareous, clayey Fine SAND (SP)			
	Brownish-gray slightly clayey Fine SAND with some shell fragments (SP-SM)	6		
	Light grayish-brown Fine SAND with shell fragments (SP)	8		
		10		
		12		
		14		




**DRIGGERS ENGINEERING SERVICES INCORPORATED**

**HAND AUGER BORING LOG**

<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County	
<b>TECHNICIAN:</b> M.H.		<b>WATER TABLE:</b> See "Note"	<b>DATE:</b> 6/22/09
<b>LOCATION:</b> See Plate I-K		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 5.0' *
		<b>TEST NUMBER:</b> HA-18	

ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with some shell fragments and trace of roots (SP)	0	[Symbol: Pattern of small triangles and dots]	* Could not penetrate below depth 5.0' due to LIMESTONE.  Note: Water Table not encountered within depth of 5.0'.
	Brownish-gray Fine SAND with shell fragments and trace of dark brown cemented sand (SP)	2		
	Tan Fine SAND (SP)			
	Light orangish-brown Fine SAND (SP)	4		
	Light brown and brown Fine SAND (SP)			
		6		
		8		
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

**HAND AUGER BORING LOG**


<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County	
		<b>WATER TABLE:</b> See "Note"	<b>DATE:</b> 6/22/09
<b>TECHNICIAN:</b> M.H.		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 3.0' *
<b>LOCATION:</b> See Plate I-R		<b>TEST NUMBER:</b> HA-18A	

ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with roots and shell fragments (SP)	0	[Symbol: Pattern of small triangles]	<p>*Could not penetrate below depth 3.0' due to LIMESTONE.</p> <p>Note: Water Table not encountered within depth of 3.0'.</p>
	Light grayish-brown Fine SAND (SP)			
	Light grayish-brown Fine SAND with shell fragments (SP)	2	[Symbol: Pattern of small triangles]	
		4		
		6		
		8		
		10		
		12		
		14		



**HAND AUGER BORING LOG**

<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393	<b>CLIENT:</b> Manatee County <b>WATER TABLE:</b> 7.2' <b>DATE:</b> 6/22/09
<b>TECHNICIAN:</b> M.H.	<b>DATE:</b> 6/22/09 <b>COMPLETION DEPTH:</b> 8.0'
<b>LOCATION:</b> See Plate I-K	<b>TEST NUMBER:</b> HA-19

ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Gray Fine SAND with trace of roots (SP)	0		
	Gray and light gray Fine SAND (SP)	2		
	Light tannish-brown Fine SAND (SP)	4		
	Brown very clayey Fine SAND (SC)	6		
	Dark brown slightly silty Fine SAND (SP-SM)	8		
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
<b>TECHNICIAN:</b> M.H.		<b>WATER TABLE:</b> 5.8'	<b>DATE:</b> 6/22/09	
<b>LOCATION:</b> See Plate I-K		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 8.0'	
		<b>TEST NUMBER:</b> HA-20		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with roots (SP)	0		
	Grayish-brown Fine SAND with trace of shell fragments (SP)			
	Gray Fine SAND with shell fragments (SP)			
	Dark brown slightly silty Fine SAND with trace of roots (SP-SM)	2		
	Gray and light gray Fine SAND with trace of shell fragments (SP)			
	Dark brown Fine SAND (SP)	4		
	Brown Fine SAND (SP)	6		
		8		
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
<b>TECHNICIAN:</b> M.H.		<b>WATER TABLE:</b> 7.5'	<b>DATE:</b> 6/23/09	
<b>LOCATION:</b> See Plate I-L		<b>DATE:</b> 6/23/09	<b>COMPLETION DEPTH:</b> 8.0'	
		<b>TEST NUMBER:</b> HA-21		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with shell and rock fragments (SP)	0		
		2		
	Light brownish-tan Fine SAND (SP)			
	Light brownish-gray clayey Fine SAND with light orange veins and shell fragments (SC)	4		
	Light tannish-gray slightly silty Fine SAND (SP-SM)			
		6		
	Tan Fine SAND with trace of shell fragments (SP)			
	Light grayish-brown Fine SAND with abundant shell fragments (SP)			
		8		
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
<b>TECHNICIAN:</b> M.B.		<b>WATER TABLE:</b> See "Note"	<b>DATE:</b> 6/22/09	
<b>LOCATION:</b> See Plate I-L		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 8.0'	
		<b>TEST NUMBER:</b> HA-22		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Grayish-brown Fine SAND with roots (SP)	0		Note: Borehole caved in to depth of 6.5'.
	Light gray Fine SAND with trace of rock fragments (SP)			
	Light tannish-brown Fine SAND with trace of cream colored calcareous, weakly cemented sand (SP)	2		
	Light grayish-brown clayey Fine SAND with light orange veins (SC)	4		
	Light grayish-brown Fine SAND (SP)			
	Tan Fine SAND with abundant shell fragments (SP)	6		
	Light tannish-gray Fine SAND with some shell fragments (SP)			
		8		
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

**HAND AUGER BORING LOG**

<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County	
<b>TECHNICIAN:</b> M.B.		<b>WATER TABLE:</b> See "Note"	<b>DATE:</b> 6/22/09
<b>LOCATION:</b> See Plate I-L		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 8.0'
		<b>TEST NUMBER:</b> HA-23	

ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Light brown Fine SAND with trace of roots and trace of shell fragments (SP)	0		Note: Borehole caved in to depth of 6.8'. Water Table measured at depth of 6.7'.
	Brownish-gray Fine SAND with trace of roots (SP)			
	Tan Fine SAND (SP)	2		
	Brown and light brown clayey Fine SAND (SC)			
	Brown Fine SAND (SP)	4		
	Light brown Fine SAND (SP)	6		
		8		
		10		
		12		
		14		

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
		<b>WATER TABLE:</b> See "Note"	<b>DATE:</b> 6/22/09	
<b>TECHNICIAN:</b> M.B.		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 8.0'	
<b>LOCATION:</b> See Plate I-M		<b>TEST NUMBER:</b> HA-24		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with shell fragments (SP)	0	▽▽▽▽	Note: Borehole caved in to depth of 7.4'.
	Light gray Fine SAND with trace of orangish-brown clayey Fine SAND (SP)	2	▽▽▽▽	
	Brown Fine SAND with trace of slightly clayey Fine SAND pockets and trace of Limestone Gravel (SP)	4	▽▽▽▽	
	Tan Fine SAND with limestone fragments (SP)		▽▽▽▽	
	Light tannish-brown Fine SAND (SP)		▽▽▽▽	
	Light brown Fine SAND with shell fragments (SP)	6	▽▽▽▽	
	Light tan Fine SAND with trace of shell fragments (SP)		▽▽▽▽	
		8	▽▽▽▽	
			▽▽▽▽	
		10	▽▽▽▽	
			▽▽▽▽	
		12	▽▽▽▽	
			▽▽▽▽	
		14	▽▽▽▽	



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

**HAND AUGER BORING LOG**

<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County	
<b>TECHNICIAN:</b> M.B.		<b>WATER TABLE:</b> See "Note"	<b>DATE:</b> 6/22/09
<b>LOCATION:</b> See Plate I-M		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 2.5' *
		<b>TEST NUMBER:</b> HA-25	


ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Gray Fine SAND (SP)	0		<p>* Could not penetrate below depth 2.5' due to LIMESTONE.</p> <p>Note: Water Table not encountered within depth of 2.5'.</p>
	Light grayish-brown Fine SAND with large pieces of cream colored LIMESTONE (SP)	2		
		4		
		6		
		8		
		10		
		12		
		14		



# DRIGGERS ENGINEERING SERVICES INCORPORATED

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
<b>TECHNICIAN:</b> M.B.		<b>WATER TABLE:</b> See "Note"		<b>DATE:</b> 6/22/09
<b>LOCATION:</b> See Plate I-N		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 8.0'	
		<b>TEST NUMBER:</b> HA-26		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brown Fine SAND with surficial roots (SP)	0		Note: Borehole caved in to depth of 7.3'.
	Tan Fine SAND (SP)	2		
		4		
	Tannish-brown Fine SAND with shell fragments (SP)	6		
	Light brown Fine SAND with shell fragments (SP)	8		
		10		
		12		
		14		






# DRIGGERS ENGINEERING SERVICES INCORPORATED

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
<b>TECHNICIAN:</b> M.B.		<b>WATER TABLE:</b> See "Note"	<b>DATE:</b> 6/22/09	
<b>LOCATION:</b> See Plate I-O		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 2.0' *	
		<b>TEST NUMBER:</b> HA-27		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with surficial roots (SP)	0		* Could not penetrate below depth 2.0' due to LIMESTONE.  Note: Water Table not encountered within depth of 2.0'.
	Light brown Fine SAND (SP)			
	Cream colored LIMESTONE			
		2		
		4		
		6		
		8		
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

<b>HAND AUGER BORING LOG</b>				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
		<b>WATER TABLE:</b> See "Note"	<b>DATE:</b> 6/22/09	
<b>TECHNICIAN:</b> M.B.		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 8.0'	
<b>LOCATION:</b> See Plate I-O		<b>TEST NUMBER:</b> HA-28		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with trace of roots and trace of rock fragments (SP)	0		Note: Borehole caved in to depth of 7.5'.
	Large Pieces of Cream Colored LIMESTONE			
		2		
	Gray Fine SAND with trace of roots (SP)			
	Light grayish-brown Fine SAND with trace of roots (SP)	4		
	Light tan Fine SAND with shell fragments (SP)			
		6		
	Light grayish-brown Fine SAND with seams of dark brown Fine SAND (SP)			
	Light grayish-brown Fine SAND with shell fragments (SP)	8		
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
		<b>WATER TABLE:</b> 5.8'	<b>DATE:</b> 6/22/09	
<b>TECHNICIAN:</b> M.B.		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 8.0'	
<b>LOCATION:</b> See Plate I-P		<b>TEST NUMBER:</b> HA-29		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Gray Fine SAND with trace of surficial roots (SP)	0		
	Light gray Fine SAND (SP)			
		2		
	Dark brown organic Fine SAND (SP-SM/Pt)			
	Brown Fine SAND (SP)			
	Light brown and brown Fine SAND (SP)	4		
	Dark brown Fine SAND (SP)	6		
		8		
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

**HAND AUGER BORING LOG**

<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County	
<b>TECHNICIAN:</b> M.B.		<b>WATER TABLE:</b> 5.8'	<b>DATE:</b> 6/22/09
<b>LOCATION:</b> See Plate I-P		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 8.0'
		<b>TEST NUMBER:</b> HA-30	

ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Gray Fine SAND with some surficial roots (SP)	0		
	Light brown Fine SAND with shell fragments (SP)			
	Light gray Fine SAND with trace of roots (SP)	2		
	Brown Fine SAND (SP)			
	Light orangish-brown clayey Fine SAND (SC)			
	Tan and light orange Fine SAND with abundant shell fragments (SP)	4		
	Light grayish-tan Fine SAND with shell fragments (SP)	6		
	Light brown Fine SAND with abundant shell fragments (SP)	8		
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

<b>HAND AUGER BORING LOG</b>				
<b>PROJECT:</b>		<b>CLIENT:</b>		
Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		Manatee County		<b>DATE:</b>
<b>TECHNICIAN:</b>		<b>WATER TABLE:</b>	6.4'	
M.B.		<b>DATE:</b>	6/22/09	
<b>LOCATION:</b>		<b>COMPLETION DEPTH:</b>		
See Plate I-P		8.0'		
<b>TEST NUMBER:</b>		HA-31		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with shell and rock fragments (SP)	0	▽	Note: Borehole caved in to depth of 6.5'.
	Light gray Fine SAND (SP)		▽	
	Dark brown slightly organic Fine SAND (SP)	2	▽	
	Light gray, gray and dark brown Fine SAND (SP)		▽	
	Brown Fine SAND (SP)	4	▽	
			▽	
	Light brown Fine SAND (SP)	6	▽	
			▽	
		8	▽	
			▽	
		10	▽	
			▽	
		12	▽	
			▽	
		14	▽	



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

**HAND AUGER BORING LOG**

<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County	
<b>TECHNICIAN:</b> M.B.		<b>WATER TABLE:</b> See "Note"	<b>DATE:</b> 6/22/09
<b>LOCATION:</b> See Plate I-Q		<b>DATE:</b> 6/22/09	<b>COMPLETION DEPTH:</b> 8.0'
		<b>TEST NUMBER:</b> HA-32	

ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brownish-gray Fine SAND with shell fragments and trace of roots (SP)	0		<p>Note: Water Table not encountered within depth of 8.0'.</p> <p>Soils damp at depth of 7.8'.</p>
	Grayish-brown Fine SAND with trace of shell fragments (SP)	2		
	Brown Fine SAND with shell fragments (SP)	4		
	Light tan Fine SAND (SP)	6		
		8		
		10		
		12		
		14		



**DRIGGERS ENGINEERING SERVICES INCORPORATED**

HAND AUGER BORING LOG				
<b>PROJECT:</b> Suburban Pipeline Project - Phase I Manatee County, Florida Project No.: DES 096393		<b>CLIENT:</b> Manatee County		
<b>TECHNICIAN:</b> M.B.		<b>WATER TABLE:</b> See "Note"	<b>DATE:</b> 6/22/09	
<b>LOCATION:</b> See Plate I-R		<b>COMPLETION DEPTH:</b> 8.0'		
		<b>TEST NUMBER:</b> HA-33		
ELEV. (FT)	DESCRIPTION	DEPTH (FT)	SYMBOL	REMARKS
	Brown Fine SAND with cemented sand and some roots (SP)	0		Note: Water Table not encountered within depth of 8.0'.  Soils moist at depth of 6.9'.
	Dark brown Fine SAND (SP)			
		2		
		4		
	Dark brown slightly silty Fine SAND with shell fragments (SP-SM)	6		
		8		
		10		
		12		
		14		

## **SUMMARY OF LABORATORY TEST RESULTS**



## SUMMARY OF LABORATORY TEST RESULTS

BORING NO.	DEPTH (ft)	DESCRIPTION	W %	Y <sub>d</sub> (pcf)	G <sub>s</sub>	ATTERBERG LIMITS			P.P. (tsf)	U.C.	CON.	G.S.	ORG. (%)	pH	Cl. (ppm)	SO <sub>4</sub> (ppm)	RES. (Ohm-cm)
						LL	PL	SL									
HA-1	2.5-3.3	Light brownish-gray Fine SAND										*					
HA-3	5.1-5.8	Brown slightly silty Fine SAND										*					
HA-3	5.8-8.0	Light brown Fine SAND with shell fragments										*		6.9	65	54	8,200
HA-5	5.3-7.3	Light grayish-brown Fine SAND with shell fragments										*					
HA-6	3.9-5.0	Brown silty Fine SAND	15.7				NP	NP				**	12.8				
HA-7	7.7-8.0	Light grayish-brown Fine SAND with shell fragments										*					
HA-8	5.0-7.3	Tan Fine SAND with shell fragments										*					
HA-9	0.5-2.5	Brown Fine SAND										*					
HA-11	2.5-5.5	Light grayish-brown Fine SAND with some shell fragments										*					
HA-12	6.0-8.0	Light grayish-brown Fine SAND with shell fragments										*					
HA-13	0.5-3.0	Light grayish-brown Fine SAND with shell fragments										*					
HA-14	4.3-6.0	Brown clayey Fine SAND	19.8				34	17				**	16.8				
HA-15	0.5-5.0	Brown Fine SAND										*		7.1	35	60	19,000
HA-17	1.1-4.0	Light brown Fine SAND										*					
HA-19	5.0-8.0	Dark brown slightly silty Fine SAND										*					
HA-20	1.3-2.5	Dark brown slightly silty Fine SAND with trace of roots										*					
HA-21	4.3-6.4	Light tannish-gray slightly silty Fine SAND										*					
HA-22	6.1-7.2	Tan Fine SAND with abundant shell fragments										*					

W % = Water Content  
 Y<sub>d</sub> (pcf) = Dry Density  
 G<sub>s</sub> = Specific Gravity  
 LL = Liquid Limit  
 PL = Plastic Limit  
 SL = Shrinkage Limit  
 P.P. (tsf) = Pocket Penetrometer  
 U.C. = Unconfined Compression  
 Con. = Consolidation Test  
 G.S. (+1) = Grainsize Analysis (Hydrometer)  
 ORG. (%) = Organic Content  
 Cl. (ppm) = Total Chloride  
 SO<sub>4</sub> (ppm) = Total Sulfate  
 RES. (ohm-cm) = Lab Resistivity  
 \* = See Test Curves  
 \*\* = Percent Passing No. 200 Sieve

**CLIENT:** Manatee County  
**PROJECT:** Suburban Pipeline Project - Phase I,  
 Manatee County, Florida  
**FILE:** DES 096393

# SUMMARY OF LABORATORY TEST RESULTS


BORING NO.	DEPTH (ft)	DESCRIPTION	W %	Y <sub>d</sub> (pcf)	G <sub>s</sub>	ATTERBERG LIMITS				U.C.	CON.	G.S.	ORG. (%)	pH	Cl. (ppm)	SO <sub>4</sub> (ppm)	RES. (Ohm-cm)
						LL	PL	SL	SL								
HA-23	2.8-3.5	Brown and light brown clayey Fine SAND	18.4			31	18					** 18.6					
HA-24	5.5-8.0	Light tan Fine SAND with trace of shell fragments									*						
HA-26	1.4-4.9	Tan Fine SAND									*						
HA-28	4.2-6.7	Light tan Fine SAND with shell fragments									*						
HA-29	2.7-3.2	Dark brown organic Fine SAND										5.5					
HA-29	5.6-8.0	Dark brown Fine SAND									*						
HA-30	2.9-3.5	Light orangish-brown clayey Fine SAND	16.7			31	18				** 17.8						
HA-30	3.5-4.6	Tan and light orange Fine SAND with abundant shell fragments									*						
HA-31	1.7-2.8	Dark brown slightly organic Fine SAND										3.1					
HA-31	5.9-8.0	Light brown Fine SAND									*						
HA-32	0.5-4.1	Grayish-brown Fine SAND with trace of shell fragments									*						
HA-33	0.5-6.0	Dark brown Fine SAND									*						

W % = Water Content  
 Y<sub>d</sub> (pcf) = Dry Density  
 G<sub>s</sub> = Specific Gravity  
 LL = Liquid Limit  
 PL = Plastic Limit  
 SL = Shrinkage Limit  
 P.P. (tsf) = Pocket Penetrometer  
 U.C. = Unconfined Compression  
 = Consolidation Test  
 = Grainsize Analysis (Hydrometer)  
 = Organic Content  
 = Total Chloride  
 = Total Sulfate  
 = Lab Resistivity  
 = See Test Curves  
 = Percent Passing No. 200 Sieve

**CLIENT:** Manatee County  
**PROJECT:** Suburban Pipeline Project - Phase I,  
 Manatee County, Florida  
**FILE:** DES 096393

## **GRAINSIZE ANALYSES**

DRIGGERS ENGINEERING SERVICES, INC.




Number	Depth	Natural Moisture	L.L.	P.L.	P. I.	Classification
HA-1	2.5' - 3.3'					Light brownish-gray Fine SAND

CLIENT:	Manatee County
PROJECT:	Suburban Pipeline Project - Phase I, Manatee County, Florida
FILE:	DES 096393

**DRIGGERS ENGINEERING SERVICES, INC.**



Number	Depth	Natural Moisture	L.L.	P.L.	P.I.	Classification
HA-3	5.1' - 5.8'					Brown slightly silty Fine SAND


  

GRAVEL	Coarse	Medium	Fine	SILT or CLAY
--------	--------	--------	------	--------------

CLIENT:	Manatee County
PROJECT:	Suburban Pipeline Project - Phase I, Manatee County, Florida
FILE:	DES 096393

DRIGGERS ENGINEERING SERVICES, INC.




Number	HA-3	Depth	5.8' - 8.0'	Natural Moisture		L.L.		P.L.		P.I.		Classification	Light brown Fine SAND with shell fragments

CLIENT: Manatee County  
 PROJECT: Suburban Pipeline Project - Phase I, Manatee County, Florida  
 FILE: DES 096393



DRIGGERS ENGINEERING SERVICES, INC.




Number	Depth	Natural Moisture	L.L.	P.L.	P.I.	Classification
HA-7	7.7' - 8.0'					Light grayish-brown Fine SAND with shell fragments

CLIENT: Manatee County  
 PROJECT: Suburban Pipeline Project - Phase I, Manatee County, Florida  
 FILE: DES 096393



**DRIGGERS ENGINEERING SERVICES, INC.**




Number	Depth	Natural Moisture	L. L.	P. L.	P. I.	Classification
HA-8	5.0' - 7.3'					Tan Fine SAND with shell fragments


  

CLIENT:	Manatee County
PROJECT:	Suburban Pipeline Project - Phase I, Manatee County, Florida
FILE:	DES 096393

**DRIGGERS ENGINEERING SERVICES, INC.**




DRIGGERS ENGINEERING SERVICES, INC.



Number	Depth	Natural Moisture	L.L.	P.L.	P.I.	Classification
HA-11	2.5' - 5.5'					Light grayish-brown Fine SAND with some shell fragments


CLIENT: Manatee County  
 PROJECT: Suburban Pipeline Project - Phase I, Manatee County, Florida  
 FILE: DES 096393

**DRIGGERS ENGINEERING SERVICES, INC.**



GRAVEL		SAND		SILT or CLAY	
		Coarse	Medium	Fine	
Number	Depth	Natural Moisture	L.L.	P.L.	P. I.
HA-12	6.0' - 8.0'				
CLIENT: Manatee County PROJECT: Suburban Pipeline Project - Phase I, Manatee County, Florida FILE: DES 096393					
Classification: Light grayish-brown Fine SAND with shell fragments					


DRIGGERS ENGINEERING SERVICES, INC.



Number	Depth	Natural Moisture	L.L.	P.L.	P.I.	Classification
HA-13	0.5' - 3.0'					Light grayish-brown Fine SAND with shell fragments

CLIENT: Manatee County  
 PROJECT: Suburban Pipeline Project - Phase I, Manatee County, Florida  
 FILE: DES 096393

DRIGGERS ENGINEERING SERVICES, INC.




Number	Depth	Natural Moisture	L.L.	P.L.	P.I.	Classification
HA-15	0.5' - 5.0'					Brown Fine SAND

CLIENT:	Manatee County
PROJECT:	Suburban Pipeline Project - Phase I, Manatee County, Florida
FILE:	DES 096393

DRIGGERS ENGINEERING SERVICES, INC.



Number	Depth	Natural Moisture	L.L.	P.L.	P.I.	Classification
HA-17	1.1' - 4.0'					Light brown Fine SAND


  

GRAVEL		SAND		SILT or CLAY	
	Coarse	Medium	Fine		

CLIENT:	Manatee County
PROJECT:	Suburban Pipeline Project - Phase I, Manatee County, Florida
FILE:	DES 096393


DRIGGERS ENGINEERING SERVICES, INC.



GRAVEL		SAND		SILT or CLAY	
Coarse		Medium		Fine	
Number	Depth	Natural Moisture	L.L.	P.L.	P.I.
HA-19	5.0' - 8.0'				
CLIENT: Manatee County		PROJECT: Suburban Pipeline Project - Phase I, Manatee County, Florida			
FILE: DES 096393					
Classification		Dark brown slightly silty Fine SAND			




**DRIGGERS ENGINEERING SERVICES, INC.**



GRAVEL		SAND		SILT or CLAY		
		Coarse	Medium	Fine		
Number	Depth	Natural Moisture	L. L.	P. L.	P. I.	Classification
HA-20	1.3' - 2.5'					DARK BROWN SLIGHTLY SILTY FINE SAND with trace of roots

CLIENT: Manatee County  
 PROJECT: Suburban Pipeline Project - Phase I, Manatee County, Florida  
 FILE: DES 096393

DRIGGERS ENGINEERING SERVICES, INC.



Number	Depth	Natural Moisture	L.L.	P.L.	P.I.	Classification
HA-21	4.3' - 6.4'					Light tan/ash-gray slightly silty Fine SAND


  

GRAVEL	Coarse	Medium	Fine
SAND			
SILT or CLAY			

CLIENT:	Manatee County
PROJECT:	Suburban Pipeline Project - Phase I, Manatee County, Florida
FILE:	DES 096393

DRIGGERS ENGINEERING SERVICES, INC.




Number	Depth	Natural Moisture	L.L.	P.L.	P. I.	Classification
HA-22	6.1' - 7.2'					Tan Fine SAND with abundant shell fragments

CLIENT: Manatee County  
 PROJECT: Suburban Pipeline Project - Phase I, Manatee County, Florida  
 FILE: DES 096393



**DRIGGERS ENGINEERING SERVICES, INC.**




Number	Depth	Natural Moisture	L.L.	P.L.	P.I.	Classification
HA-26	1.4' - 4.9'					Tan Fine SAND

CLIENT:	Manatee County
PROJECT:	Suburban Pipeline Project - Phase I, Manatee County, Florida
FILE:	DES 096393



**DRIGGERS ENGINEERING SERVICES, INC.**




Number	Depth	Natural Moisture	L.L.	P.L.	P.I.	Classification
HA-29	5.6' - 8.0'					Dark brown Fine SAND

CLIENT:	Manatee County
PROJECT:	Suburban Pipeline Project - Phase I, Manatee County, Florida
FILE:	DES 096393

**DRIGGERS ENGINEERING SERVICES, INC.**




Number	Depth	Natural Moisture	L. L.	P. L.	P. I.	Classification
HA-30	3.5' - 4.6'					Tan and light orange Fine SAND with abundant shell fragments

CLIENT: Manatee County  
 PROJECT: Suburban Pipeline Project - Phase I, Manatee County, Florida  
 FILE: DES 096393

GRAVEL: \_\_\_\_\_ SAND: Medium Fine SILT or CLAY: \_\_\_\_\_




**DRIGGERS ENGINEERING SERVICES, INC.**



GRAVEL: \_\_\_\_\_ SAND: Medium \_\_\_\_\_ Fine \_\_\_\_\_ SILT or CLAY: \_\_\_\_\_

Number	Depth	Natural Moisture	L.L.	P.L.	P.I.	Classification	CLIENT:
HA-31	5.9' - 8.0'					Light brown Fine SAND	Manatee County
							Suburban Pipeline Project - Phase I, Manatee County, Florida
							FILE: DES 096393


**DRIGGERS ENGINEERING SERVICES, INC.**



GRAVEL		SAND		SILT or CLAY		
Coarse		Medium		Fine		
Number	Depth	Natural Moisture	L.L.	P.L.	P.I.	Classification
HA-32	0.5' - 4.1'					grayish-brown Fine SAND with trace of shell fragments

CLIENT: Manatee County  
 PROJECT: Suburban Pipeline Project - Phase I, Manatee County, Florida  
 FILE: DES 096393

**DRIGGERS ENGINEERING SERVICES, INC.**



Number	Depth	Natural Moisture	L.L.	P.L.	P.I.	Classification
HA-33	0.5' - 6.0'					Dark brown Fine SAND

CLIENT:	Manatee County
PROJECT:	Suburban Pipeline Project - Phase I, Manatee County, Florida
FILE:	DES 096393

**Network Setup(cont.)**

**HTTP:** Enabled  
 Port Number: 80  
 Max Connections: 32  
 Secure HTTP (SSL): Disabled  
 Secure HTTP Port Number: 443  
**WINS:** Enabled  
 WINS Server Addresses:

**SMTP**

SMTP Server Address:

**LDAP**

Primary LDAP Address:  
 Alternate LDAP Address:  
 Maximum LDAP Search Results: 25

**POP3**

POP3 Server Address:  
 Login Name:  
 Receipt of E-mail via POP3: Enabled  
 Send Confirm on Request: Enabled  
 Incoming E-mail cover sheet: Enabled

**FTP:**

**Web Services**

Scan Template Mgmt: Disabled  
 SMart eSolutions: Not Enrolled  
 Validation Client: Disabled

**Network Scanning Setup**

Network Scanning Enabled: Enabled  
 Confirmation Sheet Enabled: Disabled

**Network Scanning (Default Repository)**

Protocol: FTP  
 Server Name:  
 Path:  
 Login Name:  
 Volume:  
 NDS Context:  
 NDS Tree:

**Network Scanning (Template Pool)**

Protocol: FTP  
 Server Name:  
 Path:  
 Login Name:  
 Volume:  
 NDS Context:  
 NDS Tree:

**Network Scanning (Alternate Repository 1)**

Protocol: FTP  
 Server Name:  
 Path:  
 Login Name:  
 Volume:  
 NDS Context:  
 NDS Tree:

**Network Scanning (Alternate Repository 2)**

Protocol: FTP  
 Server Name:  
 Path:  
 Login Name:  
 Volume:  
 NDS Context:  
 NDS Tree:

**Network Scanning (Alternate Repository 3)**

Protocol: FTP  
 Server Name:  
 Path:  
 Login Name:  
 Volume:  
 NDS Context:  
 NDS Tree:

**Network Scanning (Alternate Repository 4)**

Protocol: FTP  
 Server Name:  
 Path:  
 Login Name:  
 Volume:  
 NDS Context:  
 NDS Tree:

**Port Setup**

**Ethernet Profile**

Ethernet Card: pci card  
 MAC Address: 00:00:aa:cf:69:d9  
 Speed: auto  
 802.1x: Disabled

**USB Printer Port Settings**

USB Port Enabled: Enabled  
 USB Timeout: 5 seconds

**Server Fax Setup**

Server Fax Enabled: Disabled  
 Protocol: FTP  
 Server Name: 0.0.0.0  
 Path:  
 Volume:  
 NDS Context:  
 NDS Tree:

**Media Trays**

Media Name: standard, white and x=432mm, y=279mm  
 Media Type: standard  
 Media Color: white  
 Media Size: x=432mm, y=279mm  
 Media Name: standard, white and x=356mm, y=216mm  
 Media Type: standard  
 Media Color: white  
 Media Size: x=356mm, y=216mm  
 Media Name: standard, white and x=216mm, y=279mm  
 Media Type: standard  
 Media Color: white  
 Media Size: x=216mm, y=279mm  
 Media Name: standard, white and x=216mm, y=279mm  
 Media Type: standard  
 Media Color: white  
 Media Size: x=216mm, y=279mm  
 Media Name: standard, white and x=216mm, y=279mm  
 Media Type: standard  
 Media Color: white  
 Media Size: x=216mm, y=279mm  
 Media Name: not present  
 Media Type:  
 Media Color:  
 Media Size:  
 Media Name: not present  
 Media Type:  
 Media Color:  
 Media Size:

**Network Authentication Setup**

**Kerberos**

Primary Realm:  
 Primary KDC Address:  
 Backup KDC Address:  
 Alternate1 Realm:  
 Alternate1 KDC Address:  
 Backup1 KDC Address:  
 Alternate2 Realm:  
 Alternate2 KDC Address:  
 Backup2 KDC Address:

**Server Message Block (SMB)**

NT Domain:  
 Alternate1 NT Domain:  
 Alternate2 NT Domain:

**Novell Directory Services (NDS)**

Default Tree:  
 Default Context:  
 Alternate1 Tree:  
 Alternate1 Context:  
 Alternate2 Tree:  
 Alternate2 Context:

**Accounting Setup**

Accounting Mode: None  
 Authentication Mode: n/a

**Report Profile**

Profile Date: Sep 23, 2009 at 07:03 AM  
Profile Time: 07:03 AM

**Device Profile**

Device Name: XRX0000AACF69D9  
Device Serial Number: WTD074514E  
Service Phone Number:  
Fax Line1: 0000000  
Fax Line2: -----  
Geographic Region: unknown  
Xerox Asset Tag:  
Customer Asset Tag:

**Installed Options**

Internet Fax (S/W): installed/enabled  
Network Server Fax (S/W): installed/disabled  
Scan to File (S/W): installed/enabled  
Scan to E-mail (S/W): installed/enabled  
Save Job for Reprint (S/W): Disabled and Deleted  
Searchable File Formats: installed/enabled  
Custom Services(S/W): installed/disabled  
Network Accounting (S/W): not installed  
OnDemand Img. Overwrite (S/W): installed/disabled  
Immed. Img. Overwrite (S/W): installed/disabled  
User Data Encryption: installed/enabled  
Embedded Fax (S/W): installed/enabled  
Fax Card: present  
Extended Fax Card: not present  
Fax Memory Size: 507 MB  
USB Printer Port: present  
Image Processing Card: not present  
Foreign Interface Board: not present  
Net Controller RAM Size: 640 MB  
Net Controller Disk Size: used=812MB/total=80026MB  
EPC Memory Size: 384 MB  
Image Disk: not present  
Finisher Type: Office Finisher (LCSS) with Hole Punch  
Finisher Punch: Present  
Finisher Folder: not present

**Printer Setup**

System Software Version: 025.054.039.00000  
Net Controller Software Version: 060.069.10508  
UI Software Version: 025.060.047  
IOT Software Version: 092.008.000  
SIP Software Version: 025.054.054  
DADH Software Version: 025.018.000  
Paper Feeder Software Version: 000.040.000  
High Cap. Trays Software Version: 000.010.009  
PFP Software Version: -----  
Finisher Software Version: 003.051.000  
Fax Software Version: 003.008.002  
Scanner Software Version: 017.005.000  
Network Controller OS: 060.069.15311  
Tray Priority: 4,3,1,2,5  
Low Power Mode Timer: 8 minutes  
Sleep Mode Timer: 45 minutes  
Startup Config Report Enabled: Enabled  
Paper Substitution Enabled: Enabled  
Error Sheets Enabled: Enabled  
Banner Sheet Enabled: Enabled

**Document Defaults:**

Size: x= 216mm, y= 279mm  
Type: System-Default  
Color: unspecified  
Copies: 1  
2 Sided Printing: 1 Sided  
Collated Sets: Enabled  
Output Tray: Top Tray

**Interpreter Profiles**

Language Description: PCL  
Language Level: 6  
Language Version: 6  
Default Orientation: portrait  
Default X-Resolution: 600  
Default Y-Resolution: 600  
Current X-Resolution: 600  
Current Y-Resolution: 600

**Interpreter Profile(cont.)**

Interpreter Memory: 16106240  
Language Description: PostScript  
Language Level: 3  
Language Version: 3016  
Default Orientation: portrait  
Default X-Resolution: 600  
Default Y-Resolution: 600  
Current X-Resolution: 600  
Current Y-Resolution: 600  
Interpreter Memory: 16106240

**Network Setup**

**NetWare:**

Print Server Name: Disabled  
NDS Tree: XRX\_0000AACF69D9  
NDS Context: Xerox\_DS\_Tree  
Primary NDS Server: Xerox\_DS\_Context  
Novell Filing Transport: 0.0.0.0  
IPX Frame Type: IP  
Poll Interval: ethernet\_auto  
SAP Rate: 5  
Primary Bindery File Server 1: 60  
Primary Bindery File Server 2:  
Primary Bindery File Server 3:  
Primary Bindery File Server 4:  
IPX Network Number:

**TCP/IPv4:**

Host Name: Enabled  
IP Address: XRX0000AACF69D9  
Broadcast Address: 127.0.0.1  
Subnet Mask: 255.255.0.0  
Default Gateway: 0.0.0.0  
Automatic Addressing: DHCP  
LPD Enabled: Enabled  
LPD Port Number: 515  
Raw TCP/IP Printing Enabled: Enabled  
Raw TCP/IP Port Number: 9100  
TCP/IP Self AssignAddr Enabled: Enabled  
TCP/IP Self Assigned Address: 169.254.200.160  
Multicast DNS Enabled: Enabled  
Domain Name:  
Primary DNS Server:  
Alternate DNS Server 1:  
Dynamic DNS Enabled:

**TCP/IPv6:**

Host Name: Enabled  
Link Local Address: XRX0000AACF69D9  
Use Router Supplied Prefix: Enabled  
Stateless Global Address 1: ::  
Stateless Global Address 2: 0Vq0  
Manual Address: ::  
DHCP Addressing: Use DHCP as directed by a router  
DHCP Address:  
Default Gateway:  
Prefer IPv6 DNS over IPv4: Enabled  
IPv6 Domain Name:  
Primary DNS Server: ::  
Alternate DNS Server 1: ::  
Alternate DNS Server 2: ::

**SLP:**

Version: Disabled  
Port Number: 1  
Character Set: 427  
Directory Agent: ASCII  
Scope 1: DEFAULT  
Scope 2:  
Scope 3:  
Message Type: 1  
Multicast Radius: 255  
MTU: 1400

**AppleTalk:**

Name: Disabled  
Zone: XRX\_0000AACF69D9  
Printer Type: \*

**Microsoft Networking:**



SMB Host Name: Disabled  
Printer (Share) Name: XRX0000AACF69D9  
Workgroup: PRINTER  
Number of Connections: WORKGROUP  
Connection Timeout: 30  
Transport: 600  
IP/Ethernet







CIP  
CHLORINE INJECTION  
POINT



**BID DOCUMENTS**

ROBERT A. CANNARELLA, P.E.  
Fla. P.E. No. 17367

DESIGN	BJK
DR	BJK
CHK	RAC
APVD	RAC

NO.	DATE

VERIFY SCALE  
BARS ONE INCH ON ORIGINAL DRAWING.  
0 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.


**CH2MHILL**  
4350 WEST CYPRESS STREET SUITE 600  
TAMPA, FLORIDA 33607-4155  
LB 0002934 AA C000656

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT NO. 607/41/70



KEY PLAN


SHEET	G3
DWG	G3.DWG
DATE	JULY 2009
PROJ	386879.WM






ROBERT A. CANNARELLA P.E. Fla. P.E. No. 17367		APVD		NO.		DATE		BY		APVD		REVISION	
OSGN	BLK	DR	BLK	CHK	RAC	NO.	DATE	BY	APVD	VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.			
<b>BID DOCUMENTS</b>													
<b>CH2M HILL</b>													
4350 WEST CYPRUS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656													
MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT NO. 60747.70													
PLAN SHEET WATER LINE 25th ST W FROM 53rd AVE W TO 5423													
SHEET	C1	DWG	C1.DWG	DATE	JULY 2009	PROJ	366879.WM						





FOR CONTINUATION SEE SHEET C18

FOR CONTINUATION SEE SHEET C18



**BID DOCUMENTS**

ROBERT A. CANNARELLA, P.E. Fla. P.E. No. 17367	APVD	RAC	NO.	DATE	BY	APVD	REVISION
OSGN	BLK	BLK					
DR	BLK	BLK					
CHK	BLK	BLK					
	RAC	RAC					

VERIFY SCALE	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT NO. 60747.70
BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.	PLAN SHEET NEW WATER MAIN 25th ST W FROM 5427 TO 5619

SHEET	C2
DWG	C2.DWG
DATE	JULY 2009
PROJ	366879.WM



INSTALL F.H. ASSY & 1-6\"/>

INSTALL 6\"/>


INSTALL 598 LF OF 6\"/>

INSTALL 598 LF OF 6\"/>






**A**  
C3  
**DETAIL**



DESIGN		BJK		
DR		BJK		
CHK		RAC		
APVD		RAC		
NO.		NO.	DATE	
BY		APVD	REVISION	
VERIFY SCALE		BARS IS ONE INCH ON ORIGINAL DRAWING. 0 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.		
<b>CH2M HILL</b>		MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000666 PROJECT No. 60747.70		
<b>BID DOCUMENTS</b>		MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 25th ST W FROM 5623 TO 57th AVE W PROJECT No. 60747.70		
ROBERT A. CANNARELLA P.E. Fla. P.E. No. 17367	APVD	RAC	NO.	DATE
SHEET	C3	DATE	JULY 2009	PROJ
DWG	C3.DWG			



ROBERT A. CANNARELLA, P.E.  
Fla. P.E. No. 17367

DESIGN	BLJK
CHECK	BLJK
APPROVED	RAC
NO.	DATE

# BID DOCUMENTS


BY	APVD
REVISION	


VERIFY SCALE  
 BAR IS ONE INCH ON ORIGINAL DRAWING.  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

**CH2MHILL**  
 4350 WEST CYPRUS STREET SUITE 600  
 TAMPA, FLORIDA 33607-4155  
 LB 0002934 AA C000656


MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1  
 MANATEE COUNTY, FLORIDA  
 PROJECT No. 60747.70

SHEET	C4
DWG	C4.DWG
DATE	JULY 2009
PROJ	386879.WM





FOR CONTINUATION SEE SHEET C18





**BID DOCUMENTS**

ROBERT A. CANNARELLA, P.E. Fla. P.E. No. 17367	OSGN	BLJK	NO.	DATE	BY	APVD	REVISION
	DR	BLJK					
	CHK	RAC					
		RAC					


  

VERIFY SCALE	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT NO. 60747.70
BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.	<b>CH2MHILL</b> 4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656
PLAN SHEET NEW WATER MAIN 24th ST W FROM 5417 TO 5615	SHEET DWG DATE PROJ
	C5 C5.DWG JULY 2009 336879.WM






DESIGN		BLJK		VERIFY SCALE		<b>CH2M HILL</b> 4350 WEST CYPRUS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT No. 60747.70	PLAN SHEET NEW WATER MAIN 24th ST W FROM 57th AVE W	SHEET	C6
DR	BLJK		0	1"	DWG				C6.DWG	
CHK	RAC		0	1"	DATE	JULY 2009				
APVD	RAC			REVISION	PROJ	366879.WM				
ROBERT A. CANNARELLA, P.E.										
Fla. P.E. No. 17367										



NOTES: RIGHT-OF-ENTRY METER CONNECTIONS FOR 5404 23RD ST. COURT W THROUGH 5414 23RD ST. COURT W. RELOCATE METERS FROM BACK OF PROPERTIES IN QUESTION TO THE LOCATION SHOWN ON THE DRAWINGS FOR THE NEW METER. RIGHT-OF-ENTRY REQUIRED FOR THIS WORK. CONSTRUCT NEW 1 INCH SERVICE LINE ON PRIVATE PROPERTY FROM EXISTING HOUSE SERVICE CONNECTION TO PLANNED LOCATION OF NEW METER WITHIN ROW. COMPLETE INCLUDING ALL RESTORATION. ALL WORK TO BE COMPLETED BY A MANATEE COUNTY LICENSED PLUMBER. ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH THE SPECIFICATIONS AND PAYMENT FOR CUSTOMER SIDE RIGHT-OF-ENTRY SERVICE LINE SHALL BE IN ACCORDANCE WITH THE APPROPRIATE BID ITEM.


CONTINUATION SEE SHEET C8



CONTINUATION SEE SHEET C18

CONTINUATION SEE SHEET C18


ROBERT A. CANNARELLA P.E. Fla. P.E. No. 17367		BJK BJK RAC		NO. DATE		BY APVD		VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.		<b>CH2M HILL</b> 4350 WEST CYPRUS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656		MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT No. 60747.70		PLAN SHEET NEW WATER MAIN 23rd ST CT W FROM 54th AVE DR W TO 55th AVE W		SHEET C7 DWG C7.DWG DATE JULY 2009 PROJ 386879.WM	
<h1>BID DOCUMENTS</h1>																	



CONTINUATION SEE SHEET C7

CONTINUATION SEE SHEET C9




CONTINUATION SEE SHEET C9



DESIGN		BJK	CHECK		BJK	DATE		REVISION		BY		APVD		VERIFY SCALE		<p><b>CH2M HILL</b> 4350 WEST CYPRUS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656</p>		<p>MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT NO. 60747.70</p>		<p>PLAN SHEET NEW WATER MAIN 55th AVE DR W FROM 23rd ST CT W &amp; 21st ST W</p>		SHEET		C8	
DR		BJK	CHK		BJK	NO.		NO.		DATE		APVD		<p>BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.</p>		<p>MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT NO. 60747.70</p>		<p>PLAN SHEET NEW WATER MAIN 55th AVE DR W FROM 23rd ST CT W &amp; 21st ST W</p>		DWG		C8.DWG			
RAC		BJK	RAC		BJK	NO.		NO.		DATE		APVD		<p>ROBERT A. CANNARELLA P.E. Fla. P.E. No. 17367</p>		<p>MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT NO. 60747.70</p>		<p>PLAN SHEET NEW WATER MAIN 55th AVE DR W FROM 23rd ST CT W &amp; 21st ST W</p>		DATE		JULY 2009			
RAC		BJK	RAC		BJK	NO.		NO.		DATE		APVD		<p>MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT NO. 60747.70</p>		<p>PLAN SHEET NEW WATER MAIN 55th AVE DR W FROM 23rd ST CT W &amp; 21st ST W</p>		PROJ		386879.WM					








ROBERT A. CANNARELLA, P.E. Fla. P.E. No. 17387		BJK BJK RAC		NO. DATE		BY APVD		REVISION	
<h1>BID DOCUMENTS</h1>									
VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.		<h2>CH2M HILL</h2> 4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000666							
MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT NO. 60747.70				PLAN SHEET WATER LINE 22nd ST W FROM 53rd AVE W TO 5327					
SHEET	C10	DWG	C10.DWG	DATE	JULY 2009	PROJ	366879.WM		








FOR CONTINUATION SEE SHEET C18

FOR CONTINUATION SEE SHEET C18



ROBERT A. CANNARELLA, P.E. Fla. P.E. No. 17387		DESIGN: BJK DRAWN: BJK CHECKED: RAC APPROVED: RAC		NO. _____ DATE _____		REVISION _____		BY: _____ APVD: _____	
<b>BID DOCUMENTS</b>									
VERIFY SCALE BARS IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.					<b>CH2M HILL</b> 4350 WEST CYPRUS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000696				
MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT NO. 60747.70					PLAN SHEET NEW WATER MAIN 23rd ST W FROM 55th AVE W TO 5628				
SHEET C12		DWG C12.DWG		DATE JULY 2009		PROJ 386879.WM			

MATCH LINE L - L

MATCH LINE M - M

MATCH LINE L - L

D

C

B

A


2

3

4

5

6



ROBERT A. CANNARELLA P.E.  
Fla. P.E. No. 17367

DSGN	BLJK
CHK	BLJK
APVD	RAC
NO.	DATE

# BID DOCUMENTS

BY	APVD
NO.	DATE

VERIFY SCALE  
 BAR IS ONE INCH ON ORIGINAL DRAWING.  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.



**CH2MHILL**  
 4350 WEST CYPRUS STREET SUITE 600  
 TAMPA, FLORIDA 33607-4155  
 LB 0002934 AA C000656

MANATEE COUNTY  
 SUBURBAN SYSTEM  
 WATER LINE REPLACEMENT PROJECT  
 PHASE 1  
 MANATEE COUNTY, FLORIDA  
 PROJECT No. 60747.70


PLAN SHEET NEW WATER MAIN  
 23rd ST W FROM 5634 TO 57th AVE W

SHEET	C13
DWG	C13.DWG
DATE	JULY 2009
PROJ	386879.WM

FOR CONTINUATION SEE SHEET C18



FOR CONTINUATION SEE SHEET C18



MATCH LINE N - N

MATCH LINE O - O

ROBERT A. CANNARELLA P.E. Fla. P.E. No. 17367		BJK BJK RAC		NO. DATE		BY APVD		VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING. 0 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.		<b>CH2M HILL</b> 4350 WEST CYPRUS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656		MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT NO. 60747.70		PLAN SHEET NEW WATER MAIN 21st ST CT W FROM 55th AVE W TO 5622		SHEET C14 DWG C14.DWG DATE JULY 2009 PROJ 366879.WM	
--	--	-------------------	--	----------	--	---------	--	--	--	---	--	---	--	---	--	--	--


BID DOCUMENTS





FOR CONTINUATION SEE SHEET C19

FOR CONTINUATION SEE SHEET C19




2

3

4


5

6



MATCH LINE P - P

MATCH LINE P - P



# 5528

# 5532

# 5536

# 5606

# 5610

# 5612

# 5527

# 5533


# 5535

# 5605

# 5607

# 5524

# 5528



**BID DOCUMENTS**

DESIGN	BLJK
CHECK	BLJK
APPROVED	RAC
NO.	DATE
BY	APPROVED

DESIGN	BLJK
CHECK	BLJK
APPROVED	RAC
NO.	DATE
BY	APPROVED

VERIFY SCALE  
 BAR IS ONE INCH ON ORIGINAL DRAWING.  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.



**CH2M HILL**  
 4350 WEST CYPRUS STREET SUITE 600  
 TAMPA, FLORIDA 33607-4155  
 LB 0002934 AA C000656

MANATEE COUNTY  
 SUBURBAN SYSTEM  
 WATER LINE REPLACEMENT PROJECT  
 PHASE 1  
 MANATEE COUNTY, FLORIDA  
 PROJECT NO. 60747.70


PLAN SHEET NEW WATER MAIN  
 20th ST W FROM 55th AVE W TO 5612

SHEET	C16
DWG	C16.DWG
DATE	JULY 2009
PROJ	366879.WM






ROBERT A. CANNARIELLA, P.E. Fla. P.E. No. 17367		OSN DR		BJK BJK		VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.		<b>CH2M HILL</b> 4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656		MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT No. 60747.70		SHEET C17	
APVD RAC		NO.		DATE		REVISION		BY APVD		PLAN SHEET NEW WATER MAIN 16th ST W FROM 5506 TO 57th AVE W		DWG C17.DWG	
NO.		DATE		REVISION		BY APVD		PROJECT No. 60747.70		DATE JULY 2009		PROJ 366879.WM	








NOTE: RIGHT-OF-ENTRY METER CONNECTIONS FOR THE NORTH AND SOUTH SIDE OF ROW ON 55TH AVE W, AT 1807, 1808, 1902, 1912, 2004, 2104, 2108 AND 2208 55TH AVE W, RELOCATE METERS FROM LOCATION ON PROPERTIES IN QUESTION TO THE LOCATION SHOWN ON THE DRAWINGS FOR THE NEW METER. RIGHT-OF-ENTRY REQUIRED FOR THIS WORK. CONSTRUCT NEW 1 INCH SERVICE LINE ON PRIVATE PROPERTY FROM EXISTING METER LOCATION TO PLANNED LOCATION OF NEW METER WITHIN ROW. COMPLETE INCLUDING ALL RESTORATION. ALL WORK TO BE COMPLETED BY A MANATEE COUNTY LICENSED PLUMBER. ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH THE SPECIFICATIONS AND PAYMENT FOR CUSTOMER SIDE RIGHT-OF-ENTRY SERVICE LINE SHALL BE IN ACCORDANCE WITH THE APPROPRIATE BID ITEM.



FOR CONTINUATION SEE SHEET C12

FOR CONTINUATION SEE SHEET C14


FOR CONTINUATION SEE SHEET C9



FOR CONTINUATION SEE SHEET C16

**BID DOCUMENTS**

ROBERT A. CANNARELLA P.E. Fla. P.E. No. 17367	APVD	NO.	DATE	REVISION	BY	APVD	VERIFY SCALE	BAR IS ONE INCH ON ORIGINAL DRAWING. IF NOT ONE INCH ON THIS SHEET, ADJUST SCALERS ACCORDINGLY.	<b>CH2M HILL</b> 4350 WEST CYPRUS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT NO. 60747.70	PLAN SHEET NEW WATER MAIN 55th AVE W FROM CENTERLINE OF 23rd ST W TO 1807	SHEET C19	DWG C19.DWG	DATE JULY 2009	PROJ 366879.WM
--	------	-----	------	----------	----	------	--------------	---	---	--	--	--------------	----------------	-------------------	-------------------



NOTES: RIGHT-OF-ENTRY METER CONNECTIONS FOR THE SOUTH SIDE OF ROW ON 55TH AVE W, AT 1802, 1804 AND 1806 55TH AVE W. RELOCATE METER FROM LOCATION ON PROPERTIES IN QUESTION TO THE LOCATION SHOWN ON THE DRAWINGS FOR THE NEW METER. RIGHT-OF-ENTRY REQUIRED FOR THIS WORK. CONSTRUCT NEW 1 INCH SERVICE LINE ON PRIVATE PROPERTY FROM EXISTING METER LOCATION TO PLANNED LOCATION OF NEW METER WITHIN ROW, COMPLETE INCLUDING ALL RESTORATION. ALL WORK TO BE COMPLETED BY A MANATEE COUNTY LICENSED PLUMBER. ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH THE SPECIFICATIONS AND PAYMENT FOR CUSTOMER SIDE RIGHT-OF-ENTRY SERVICE LINE SHALL BE IN ACCORDANCE WITH THE APPROPRIATE BID ITEM.

ROBERT A. CANNARELLA P.E.  
Fla. P.E. No. 17367

DSGN	BIJK
CHK	BIJK
APVD	RAC

# BID DOCUMENTS

NO.	DATE	BY	APVD

VERIFY SCALE  
BAR IS ONE INCH ON ORIGINAL DRAWING. 0 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.









**CH2MHILL**  
4350 WEST CYPRUS STREET SUITE 600  
TAMPA, FLORIDA 33607-4155  
LB 0002934 AA C000656

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70

PLAN SHEET NEW WATER MAIN  
55th AVE W FROM 1805 TO 18th ST W

SHEET	C20
DWG	C20.DWG
DATE	JULY 2009
PROJ	366879.WM





**BID DOCUMENTS**

**CH2M HILL**  
4350 WEST CYPRESS STREET, SUITE 600  
TAMPA, FLORIDA 33607-4155  
LB 0002934 AA C000656









**MANATEE COUNTY**  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT NO. 60747.70

DESIGN: BJK  
DRAWING: BJK  
CHECK: RAC  
APPROVED: RAC

DATE: MARCH 17, 2009

REVISION: UG-7, UG-8, UG-9, UG-10

SHEET: D1  
DWG: D1.DWG  
DATE: JULY 2009  
PROJ: 366879.WM











DESIGN	BLJK	VERIFY SCALE	BAR IS ONE INCH ON ORIGINAL DRAWING.
CHECK	BLJK	IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.	
APPROVED	RAC		
NO.	DATE	BY	APPROVED
<b>BID DOCUMENTS</b>			
<b>CH2M HILL</b>			
4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656			
MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT NO. 60747.70			
DESIGN	BLJK	SHEET	D2
CHECK	BLJK	DWG	D2.DWG
APPROVED	RAC	DATE	JULY 2009
NO.	DATE	PROJ	366879.WM



OSGN	BLK	MANATEE COUNTY	METER BOX ASSEMBLY	UW-17
DR	BLK	MANATEE COUNTY	FOR 5/8" x 3/4" & 1" METERS	
CHK	RAC	MANATEE COUNTY		
APVD	RAC	MANATEE COUNTY		

ROBERT A. CANNARELLA P.E.  
Fla. P.E. No. 17367



# BID DOCUMENTS

VERIFY SCALE  
BAR IS ONE INCH ON ORIGINAL DRAWING.  
IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

**CH2M HILL**  
4350 WEST CYPRESS STREET SUITE 600  
TAMPA, FLORIDA 33607-4155  
LB 0002934 AA C000656


MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT NO. 60747.70

SHEET D3  
DWG D3.DWG  
DATE JULY 2009  
PROJ 366879.WM





EXCAVATION - NORTH VALVE LOCATION ON 25th ST W AT SOUTH PROP LINE OF 5518 25TH ST W



EXCAVATION - NORTH VALVE LOCATION ON 25th ST W AT SOUTH PROP LINE OF 5518 25TH ST W




EXCAVATION - NORTH VALVE LOCATION ON 25th ST W AT SOUTH PROP LINE OF 5518 25TH ST W



EXCAVATION AT SOUTH PROP LINE OF 5612 25th ST W



EXCAVATION AT SOUTH PROP LINE OF 5612 25th ST W



PARTIAL PLAN - AS-BUILT DRAWINGS 25th ST W BETWEEN 55th AVE W & 57th AVE W

NOTE 1: - A 1 1/2 INCH WATER LINE RUNS ALONG THE BACK PROPERTY LINE FROM APPROXIMATELY THE NORTH PROPERTY LINE OF 5612 25TH ST W TO THE LINE PROVIDES WATER SERVICE TO CUSTOMERS ON 26TH ST W. DRAWING C-2 AND THE INFORMATION ON THIS DETAIL SHEET PROVIDE AVAILABLE INFORMATION REGARDING THE LOCATION AND CONFIGURATION OF THIS 1 1/2 INCH LINE AND ITS CONNECTION TO EXISTING WATER LINES. THE CONTRACTOR SHALL LOCATE THE EXISTING CONNECTION POINTS OF THE 1 1/2 INCH LINE AND TRANSFER CONNECTION OF THIS 1 1/2 INCH WATER LINE TO THE NEW 6 INCH WATER LINE TO BE CONSTRUCTED ON 25TH ST. W.

NOTE 2: THE CONTRACTOR SHALL PERFORM SUCH EXPLORATORY WORK AS REQUIRED TO CONFIRM THE LOCATION OF THE EXISTING NORTH AND SOUTH CONNECTION POINTS OF THE 1 1/2 INCH WATER LINE AND CONFIRM THE REQUIRED CONNECTION POINTS TO THE NEW 6 INCH WATER LINE TO BE CONSTRUCTED ON 25TH ST. W.

NOTE 3: THE SPECIFIC LOCATION AND SIZE OF CONNECTION POINTS AT THE NORTH AND SOUTH VALVE LOCATIONS SHALL BE VERIFIED PRIOR TO COMMENCING CONSTRUCTION TO INSURE THAT SERVICE LINE INTERUPTION IS MINIMIZED.

DESIGN	BJK		<b>BID DOCUMENTS</b>		REVISION				
CHK	BJK				BY	APVD	VERIFY SCALE		
APVD	RAC				SCALE	ORIGINAL DRAWING: 0	IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.		
PROJECT	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1		MANATEE COUNTY, FLORIDA	PROJECT No. 60747.70	25th ST W BACK LOT CONNECTIONS TO 26th ST W SERVICES	SHEET	D4		
DATE	JULY 2009		DWG		D4.DWG	PROJ	366879.WM		
DATE	JULY 2009		DATE		JULY 2009	PROJ	366879.WM		
DATE	JULY 2009		DATE		JULY 2009	PROJ	366879.WM		

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70





MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70

MANATEE COUNTY  
SUBURBAN SYSTEM  
WATER LINE REPLACEMENT PROJECT  
PHASE 1  
MANATEE COUNTY, FLORIDA  
PROJECT No. 60747.70





DESIGN		BLJK		VERIFY SCALE		<b>CH2M HILL</b> 4350 WEST CYPRESS STREET SUITE 600 TAMPA, FLORIDA 33607-4155 LB 0002934 AA C000656	MANATEE COUNTY SUBURBAN SYSTEM WATER LINE REPLACEMENT PROJECT PHASE 1 MANATEE COUNTY, FLORIDA PROJECT No. 607/47.70	BEST MANAGEMENT PRACTICES	SHEET	D5
DIR	BLJK		BAR IS ONE INCH ON ORIGINAL DRAWING.	0	DWG				BMP-DWG	
CHK	RAC		IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.	1"	DATE				JULY 2009	
APPROVED		RAC	NO.	DATE	REVISION	BY	APVD		PROJ	386879.WM
ROBERT A. CANNARELLA, P.E. Fla. P.E. No. 17367										
<b>BID DOCUMENTS</b>										