



1112 Manatee Ave. West
Bradenton, FL 34205
purchasing@mymanatee.org

Solicitation Addendum

Addendum No.: 1
Solicitation No.: 20-TA003346AJ
Project No.: 6079480
Solicitation Title: NRWRF Master Reuse Wet Weather Management System
Addendum Date: May 29, 2020
Procurement Contact: Abigail Jenkins

IFBC No. 20-TA003346AJ is amended as set forth herein. Responses to questions posed by prospective bidders are provided below. This addendum is hereby incorporated in and made a part of IFBC No. 20-TA003346AJ.

CHANGE TO:

SECTION A, PARAGRAPH A.01, BID DUE DATE

The Due Date and Time for submission of Bids in response to this Invitation for Bid (IFBC) is **June 5, 2020 at 3:00 P.M. E.T.** Bids must be delivered to the following location: Manatee County Administration Building, 1112 Manatee Ave. W., Suite 803, Bradenton, FL 34205 and time stamped by a Procurement representative prior to the Due Date and Time.

Due to the Manatee County Administration Building being closed in response to the current COVID-19 pandemic, Bidders who wish to hand-deliver Bids prior to the Due Date and Time shall contact the Procurement Division at 941-749-3014 upon arrival at the Manatee County Administration Building. A Procurement representative shall meet Bidder or Bidder's representative at the Manatee County Administration Building's main entrance and receive the Bid while maintaining the current social distancing guidelines. The Bid shall be time stamped by the Procurement representative prior to the Due Date and Time.

Bids received after the Due Date and Time will not be considered. It will be the sole responsibility of the Bidder to deliver its Bid to the Manatee County Procurement Division for receipt on or before the Due Date and Time. If a Bid is sent by U.S. Mail, courier or other delivery services, the Bidder will be responsible for its timely delivery to the Procurement

Division. Bids delayed in delivery will not be considered, will not be opened at the virtual public opening, and arrangements will be made for their return at the Bidder's request and expense.

SECTION A, PARAGRAPH A.03, PUBLIC OPENING OF BIDS.

Bids will be opened immediately following the Due Date and Time at the Manatee County Administration Building, Suite 803 in the presence of County officials. Bidders or their representatives may attend the Bid opening virtually by accessing the link below.

Zoom® Webinar Link:

<https://manateecounty.zoom.us/j/89722979987>

Manatee County will make public at the opening the names of the business entities which submitted a Bid and the total bid price submitted. No review or analysis of the Bids will be conducted at the Virtual Bid Opening.

QUESTIONS AND RESPONSES:

Q1. Appendix A, Minimum Qualification, Part 2 states “Bidder, or its representative(s), has made an inspection of the construction site for work specified in this IFBC on or after the date of advertisement of this IFBC and prior to the Due Date and Time.” Since this is a rebid of the same previously bid project, will it be acceptable to use our previous site visit to meet this qualification?

R1. Yes.

Q2. Can you provide the handhole schedule per sheet 60 of 61, 95-E-502 Details, 2605-444, as I'm not finding it in the electrical documents?

R2. The detail requires the handholes to be 36 inches wide by 36 inches long. Typically, the standard depth of a 36 inch by 36-inch handholes is 36 inches deep. As a minimum, the following handholes need to be at least 36 inches by 36 inches by 36 inches:

- DMW-1; HH-1
- APMW-1-2; HH-4
- DZMW-1; HH-1
- DZMW-1; HH-2
- DZMW-1; HH-3
- DZMW-1; HH-4

The following handholes may be reduced to a minimum of 24 inches by 24 inches by 24 inches:

- DMW-1; HH-2
- APMW-2; HH-2
- APMW-2; HH-3

- DZMW-1; HH-5

Q3. Is the control panel labeled as ‘SP-61’, as shown on the ‘E’ drawings, the same as the control panel labeled as ‘SP-7’, as shown on the ‘N’ drawings?

R3. Yes, the SP-7 designation on the N drawings is correct and supersedes the E drawing label.

Q4. Is the control panel labeled as ‘SP-62’, as shown on the ‘E’ drawings, the same as the control panel labeled as ‘SP-8’, as shown on the ‘N’ drawings?

R4. Yes, the SP-8 designation on the N drawings is correct and supersedes the E drawing label.

Q5. Per the specifications, the existing Scada system needs to be modified to show data of newly added PLCs SP7 & SP8. Existing Scada system make and revision is not available in specification. Please advise.

R5. Existing facility SCADA system package is Citect 2016. Contractor shall verify with Owner the specific version at the start of programming services to ensure that software has not been updated between the design and construction time periods.

Q6. The SP-63 Control panel shown on plans drawing “80-E-601” is marked as future antenna. This panel is not mentioned in Panel Schedule” 40 90 00 SUPPLEMENT 6 -1” hence not considered in the scope of supply and design. Can you confirm that this panel is outside the scope of this project?

R6. SP-63 is a starter panel for APMW-2 and is required for this project. See below additional functional requirements for starter panel SP-63:

Starter panel to include main breaker, size 1 combination starter with motor circuit protector (MCP), and control power transformer sized to power the receptacle and pole light. Starter to be controlled by manual on/off selector switch and indicator lights. Refer to spec section **40 90 00.00B Instrumentation and Control for Process Systems** for additional panel construction requirements.

NOTE: Items that are ~~struck through~~ are deleted. Items that are underlined have been added or changed. All other terms and conditions remain as stated in the IFBC.

END OF ADDENDUM

INSTRUCTIONS:

Receipt of this addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the response being deemed non-responsive.

AUTHORIZED FOR RELEASE