



1112 Manatee Avenue West  
Bradenton, FL 34205  
[purchasing@mymanatee.org](mailto:purchasing@mymanatee.org)

## Solicitation Addendum

---

Addendum No.: 6  
Solicitation No.: 23-TA004808SAM  
Project No.: 6099270, 6099271, 6099281  
Solicitation Title: US-41 Sidewalk, Lighting, Mast Arms and Water Main Improvements  
Addendum Date: September 7, 2023  
Procurement Contact: Sherri Meier

**IFBC 23-TA004808SAM is amended as set forth herein. Responses to questions posed by prospective bidders are provided below. This Addendum is hereby incorporated in and made a part of IFBC 23-TA004808SAM.**

**The deadline to submit all inquiries concerning interpretation, clarification or additional information pertaining to this IFBC was August 14, 2023.**

### **REPLACE:**

### **SECTION C, BID ATTACHMENTS, BID ATTACHMENT 9 UTILITY PLANS, PLAN SHEET G-5**

Replace Bid Attachment 9 Utility Plans, Plan Sheet G-5 with Revised Plan Sheet G-5 hereby incorporated into this IFBC and attached to this addendum.

### **QUESTIONS AND RESPONSES:**

**Q1. Is the County aware that the FDOT approved Concrete required for the curb & gutter, sidewalk and drilled shafts is not available during nighttime hours? Will exceptions be made to the lane closure restrictions when concrete is required for those types of work? These lane closures would be short in duration and length, and would be coordinated to minimize inconvenience to the travelling public (i.e. not during morning or evening rush hours, etc.). Other work such as demolition, paving, utility work, etc. would still be performed at night.**

R1. Single lane closures are permitted only between 7:30 pm and 6:00 am covering all the construction of all the improvements proposed on this project within the entire project limits.

**Q2. On the Utility Plan, plan sheet G-5, says that there is 50 LF of 10” PVC on Plan Sheet U-15, however, plan sheet U-15 is showing 8” Ductile Iron. So my question is on Plan Sheet G-5 is the total of 10” PVC 103 LF or 53 LF.**

R2. It appears we double counted the pipe on that sheet. It should be reduced from 50LF of 10” to 5 LF of 10”. Since we reduced the bridge crossing pipe diameter from 10” to 8”, it appears we included 50’ of 10” and 40’ of 8” pipe. Really it should be 5’ of 10” and 40’ of 8” pipe. We will update plan sheet G-5.

**Q3. Is the County providing the inspection & testing on this project?**

R3. The County will acquire independent CEI services upon award of this solicitation.

**NOTE:**

Deleted items will be ~~struck through~~, added or modified items will be underlined. All other terms and conditions remain as stated in the IFBC.

**INSTRUCTIONS:**

Receipt of this Addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the response being deemed non-responsive.

**END OF ADDENDUM**

AUTHORIZED FOR RELEASE

**TABULATION OF QUANTITIES**

ITEM #	ITEM	UNIT	U-1	U-2	U-3	U-4	U-5	U-6	U-7	U-8	U-9	U-10	U-11	U-12	U-13	U-14	U-15	U-16	U-17	Total
1050 31 210	Utility Pipe – Polyvinyl Chloride, F&I, Water/Sewer, 10"	LF												30		23	5			<b>58</b>
1050 31 206	Utility Pipe – Polyvinyl Chloride, F&I, Water/Sewer, 6"	LF		46	46	69		69	23											<b>253</b>
1050 51 208	Utility Pipe – Ductile Iron/Cast Iron, F&I, Water/Sewer, 8"	LF															40			<b>40</b>
1050 61 120	Utility Pipe - Steel, F&I, Casing, 20" (Split)	LF										24				24				<b>48</b>
1050 61 112	Utility Pipe - Steel, F&I, Casing, 12" (Split)	LF				12	60	12	12		36	12								<b>144</b>
1050 61 120	Utility Pipe - Steel, F&I, Casing, 20"	LF														12				<b>12</b>
1050 61 112	Utility Pipe - Steel, F&I, Casing, 12"	LF		24	24	36		36	12											<b>132</b>
1055 51 110	Utility Fitting, Ductile Iron/Cast Iron, F&I, Elbow, 10"	EA												4		4				<b>8</b>
1055 51 310	Utility Fitting, Ductile Iron/Cast Iron, F&I, Reducer, 10"	EA															2			<b>2</b>
1055 51 108	Utility Fitting, Ductile Iron/Cast Iron, F&I, Elbow, 8"	EA															4			<b>4</b>
1050 16 002	Utility Pipe - Remove and Dispose, 2.0"-4.9"	LF									12									<b>12</b>
1050 16 003	Utility Pipe - Remove and Dispose, 5"-7.9"	LF		46	46	69		69	23					20		35				<b>308</b>
1050 16 004	Utility Pipe - Remove and Dispose, 8"-19.9"	LF												30		23	49			<b>102</b>
1050 15 001	Utility Pipe - Adjust/Modify, 0"-1.9"	LF				20		10												<b>30</b>
1080 23	Utility Fixture - Tapping Saddle/Sleeve - Remove	EA				2		1												<b>3</b>
1080 23 100	Utility Fixture - Tapping Saddle/Sleeve - Furnish and Install	EA				2		1												<b>3</b>
1060 15	Utility Structure, Below Ground, Adjust/Modify	EA		1	1		1	1	1	1	2		1							<b>9</b>
1080 24 110	Utility Fixture, Valve Assembly, Furnish & Install, 10"	EA															2			<b>2</b>
1080 24 500	Utility Fixture, Valve Assembly, Adjust/Modify	EA			2	2		1	1	1	2	1	1	1	1	1	2	2		<b>18</b>
522 1	Concrete Sidewalk or Driveway, 4" Thick	SY			23		37	88	37											<b>185</b>
522 2	Concrete Sidewalk or Driveway, 6" Thick	SY							4											<b>4</b>
570 1 2	Performance Turf, Sod	SY			84	155	205	357	149		63	94		53		82				<b>1242</b>

THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE DIGITALLY SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.

DESCRIPTION		REVISIONS		MICHAEL ANTHONY SEMAGO, P.E. 87501 KIMLEY-HORN AND ASSOCIATES 100 2ND AVENUE SOUTH, SUITE 105N ST. PETERSBURG, FL 33701 REGISTRY NO. 35106	MANATEE COUNTY			TABULATION OF QUANTITIES	SHEET NO.  G-5
DATE	DESCRIPTION	DATE	DESCRIPTION		ROAD NO.	COUNTY	FINANCIAL PROJECT ID		
09/06/23	△ REVISION #1				US 41	MANATEE	433592-4-58-01		