



1112 Manatee Avenue West
Bradenton, FL 34205
purchasing@mymanatee.org

Solicitation Addendum

Addendum No.: 1
Solicitation No.: 22-R079477JH
Solicitation Title: 35th Street West Gravity Sewer Rehabilitation
Addendum Date: July 26, 2022
Procurement Contact: Jeb Hayter

ITQ No. 22-R079477JH is amended as set forth herein. Responses to questions posed by prospective bidders are provided below. This Addendum is hereby incorporated in and made a part of ITQ No. 22-R079477JH.

The deadline to submit all inquiries concerning interpretation, clarification or additional information pertaining to this ITQ was July 15, 2022.

ADD:

EXHIBIT 5, AS-BUILTS DIAGRAM

The exhibit referenced below hereby incorporated into the ITQ and available for download as a separate attachment.

Exhibit 5, as-builts diagram

REPLACE:

ATTACHMENT G, QUOTE FORM

Replace Attachment G, Quote Form with the Attachment G, Quote Form Revised issued with this Addendum 1.

QUESTIONS AND RESPONSES:

Q1. Once complete, will the County perform an underground TV inspection in order to determine satisfactory completion?

R1. Yes

Q2. Please define satisfactory completion?

Addendum No. 1
ITQ No. 22-R079477JH
35th Street West Gravity Sewer Rehabilitation

- R2. The pipe will be corrected and holding less than 1” of water under normal flow conditions.
- Q3. If the County TV’s the line and there are sags from the original contractor, is the County expecting the awarded contractor to fix those as well?**
- R3. The contractor is only responsible for 40’ each direction from the manhole.
- Q4. Is the County requiring attack coat over the base?**
- R4. Yes, per Manatee County Highway Standards.
- Q5. Site restoration bid item 4, what are the base and asphalt thickness required to be restored?**
- R5. Repair per Manatee County Highway Standards.
- Q6. Site restoration bid item 5, what are the mill and resurface thickness required to be restored?**
- R6. Repair per Manatee County Highway Standards.
- Q7. Please provide any flow data available for the sewer to be bypassed.**
- R7. No flow data available. This is not force main influenced, only local gravity.
- Q8. Please provide all pertinent elevations of the existing manhole, rims, inverts, etc., or as-builts.**
- R8. See Exhibit 5 as-builts diagram available for download as a separate attachment.

NOTE:

Deleted items will be ~~struck through~~, added or modified items will be underlined. All other terms and conditions remain as stated in the ITQ.

INSTRUCTIONS:

Receipt of this Addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the response being deemed non-responsive.

END OF ADDENDUM

AUTHORIZED FOR RELEASE

ATTACHMENT G, QUOTE FORM REVISED

ITQ NO. 22-R079477JH

GRAVITY SEWER REHABILITATION

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
1	Mobilization and Demobilization	1	LS		
2	SEWER				
3	Site Restoration				
4	Asphalt Pavement Restoration (Base & Resurface)	50	SQYD		
5	Asphalt Pavement Restoration (Mill & Resurface)	300	SQYD		
6	Miami Curb Replacement	30	LF		
7	MANHOLE				
8	Install Concrete Manhole, 4' dia	8	VF		
9	PIPE (GRAVITY SEWER)				
10	PVC, SDR 26, 8" (SEWER) 20' each direction	40	LF		
11	MISCELLANEOUS				
12	By-pass Pumping System	1	LS		
13	Temp. Structures, by-pass purposes	2	EA		
14	Erosion Control	1	LS		
15	Traffic Control	1	LS		
				BID SUBTOTAL	
CONTINGENCY - USED ONLY WITH COUNTY APPROVAL				10%	
				BID TOTAL WITH CONTINGENCY	

Bidder Name _____

Authorized Signature _____