



# MANATEE COUNTY

September 25, 2012

All Interested Bidders:

**SUBJECT:** Invitation for Bid #12-2032-OV  
Master Lift Station 27A, RTU 138, Lift Station Upgrades / Rehabilitation  
Comminutor Replacement (Project No. 404-6060782)

## **ADDENDUM #1**

**Bidders are hereby notified that this Addendum shall be acknowledged on page 00300-1 of the Bid Form and made a part of the above named bidding and contract documents. Bids submitted without acknowledgement of the Addendum will be considered incomplete.**

The following items are issued to add to, modify, and clarify the bid and contract documents. These items shall have the same force and effect as the original bidding and contract documents, and cost involved shall be included in the bid prices. Bids to be submitted on the specified bid date, shall conform to the additions and revisions listed herein.

**The stated deadline of September 21, 2012 at 5:00 pm to submit all inquiries concerning interpretation, clarification or additional information pertaining to this bid has lapsed.** This deadline has been established to maintain fair treatment for all potential bidders, while maintaining the expedited nature of the Economic Stimulus that the contracting of this work may achieve. Questions received after this date and time shall not be considered.

Attached memorandum dated September 21, 2012 provides all bidders with the Engineer's Estimate. It is important to note that Manatee County is currently receiving competitive bids which are up to 50% lower than the Engineer's Estimate. (1 total page)

## **Bidders Note:**

Engineer's Clarification and Responses to questions received from the Bidders at the Information Conference which was held on September 12, 2012 and Contractors emails through September 21, 2012.

## **Questions:**

**Question 1: What is the peak flow and what is the TDH?**

**Response:** Including the Inflow and Infiltration we see during inclement weather, contractor should anticipate a peak flow of 4,425 GPM at a TDH of 75'.

Financial Management Department – Purchasing Division  
1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205  
Phone: 941-708-7527 – Fax: 941-708-7544

**LARRY BUSTLE \* MICHAEL GALLEN \* JOHN R. CHAPPIE \* ROBIN DISABATINO \* DONNA G. HAYES \* CAROL WHITMORE \* JOE MCCLASH**  
*District 1                      District 2                      District 3                      District 4                      District 5                      District 6                      District 7*

September 25, 2012 / Addendum #1  
Invitation for Bid #12-2032-OV  
Master Lift Station 27A, RTU 138, Lift Station Upgrades / Rehabilitation  
Comminutor Replacement (Project No. 404-6060782)

**Question 2: Global Materials is requesting approval for Refratta HAC 100.**

**Response:** Bidders are required to bid the approved materials which are listed on page 74 Section 09970, Surface Protection Spray System of the Technical Specifications.

**Question 3:** For the 24" Influent Line, how long is it and where do we end the lining?

**Response:** The Pipe is to be lined from the wet well back out to the terminal manhole in 53<sup>rd</sup> Avenue, approximately 46 LF. Site location map is made a part of this Addendum No. 1.

If you have submitted a bid prior to receiving this addendum, you may request in writing that your original, sealed bid be returned to your firm. All sealed bids received will be opened on the date stated.

**END OF ADDENDUM #1**

Bids will be received at the **Manatee County Purchasing Division, 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205 until 2:00 P.M. on October 9, 2012.**

Sincerely,



Melissa M. Wendel, CPPO, Purchasing Official  
Manatee County Purchasing Division

Ov

Attachments:

1 Total Page

1 PDF Site Map referring to Question No. 3.



# MANATEE COUNTY FLORIDA

September 21, 2012

To All Bidders

Subject: Master Lift Station 27-A, RTU 138 Lift Station Upgrades,  
Proj # 402.0019706.50012004

The "construction cost estimate" for MLS 27-A Upgrades is \$305,312, three hundred five thousand, three hundred twelve dollars.

This construction cost estimate was determined as of May 19, 2012. The construction cost estimate is based on the original specifications and drawings issued with IFB #12-2032-OV. Changes to the specifications subsequent to the original documents by addenda to this bid may not be accounted in this construction cost estimate.

Sincerely,

Wayne R. Trexler, P.E.  
Engineer of Record

cc: Sherri Robinson, Project Manager  
Project File: 402.0019706.50012004

Public Works Department – Utility Engineering Division  
1022 26<sup>th</sup> Avenue East, Bradenton, FL 34208  
WEB: [www.mymanatee.org](http://www.mymanatee.org) \* PHONE: (941) 708-7450 \* FAX: (941) 708-7431

---

LARRY BUSTLE \* MICHAEL GALLEN \* JOHN R. CHAPPIE \* ROBIN DISABATINO \* DONNA HAYES \* CAROL WHITMORE \* JOE  
McCLASH

District 1  
District 7

District 2

District 3

District 4

District 5

District 6