



1112 Manatee Ave. West  
Bradenton, FL 34205  
[purchasing@mymanatee.org](mailto:purchasing@mymanatee.org)

## Solicitation Addendum

---

Addendum No.:	4
Solicitation No.:	20-TA003370CD
Project No.:	6093460
Solicitation Title:	Rubonia Water Quality Improvement Project
Addendum Date:	July 29, 2020
Procurement Contact:	Chris Daley, CPPO, CPPB - Procurement Project Manager

**IFBC No. 20-TA003370CD is amended as set forth herein. Responses to questions posed by prospective bidders are provided below. This addendum is hereby incorporated in and made a part of IFBC No. 20-TA003370CD.**

### QUESTIONS AND RESPONSES:

**Q1. The sheet pile quantity and details were revised within Addendum 2, but there appears to still be conflict. Page 20A seems to indicate approximately 18 LF long (plan view) x 10 LF length (6 LF of which is embedded). Page 37B calls out 18" long, but then provides elevations that indicate 18' long. Please confirm the intended length is 18 LF, and also revise the bid quantity (line item 64) to reflect the intended plan view length and sheet pile length.**

R1. Plan 20A that reads 18 LF long is the total length in plan view. The sheet piling detail on Sheet 37B indicates the total length of sheet pile in section. Top of cap Elev = 2.4; top of sheet pile Elev = 1.4; Bottom of sheet pile tip is at elev. = (-) 16.6'. (Therefore, 1.4 + 16.4 = 18' depth). 18' plan view x 18' depth = 324 LF. The quantity sheet (addendum # 1) indicates 360 SF of sheet piling. The Engineer used 10% additional just in case total length (in plan view) exceeds 18' length.

**Q2. On page 37, the details specifies payment for the swale crossings to be under the "Swale Crossings" pay item. Please revise the bid schedule to include this line item.**

R2. Sheet 37 (addendum # 1) regarding swale crossing, are to be paid for under Concrete Class I, Misc. Refer to Bid item # 15 on quantity sheet no 2 (Addendum # 1). Quantity = 4 CY.

**Q3. Reference Addendum Two, revised plans, plan sheet 37, SWALE CROSSING DETAIL, the 6-inch thick concrete sidewalk over the swale crossing is noted as to be paid for "under swale crossing" there is no bid item for swale crossing, please clarify.**

R3. Refer to const plan sheet # 37, swale crossing to be paid for under Concrete Class I, Misc.

**Q4. Reference Addendum Two, QUESTIONS AND RESPONSES, page 11 of 15, Q58 and R58, the question was asked in order to prevent Manatee's from swimming inside the pipe and not having a way out. There will also be 42-inch pipe discharging into open waters. Please review the response.**

R4. It is the Engineer's understanding that grates will not be installed at end of pipes that discharge into Creek. This issue can be re-opened during construction.

NOTE: Items that are ~~struck through~~ are deleted. Items that are underlined have been added or changed. All other terms and conditions remain as stated in the IFBC.

**End of Addendum**

**INSTRUCTIONS:**

Receipt of this addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the response being deemed non-responsive.

AUTHORIZED FOR RELEASE