



MANATEE COUNTY

November 23, 2010

All Interested Bidders:

SUBJECT: Invitation for Bid #10-3779-OV
Group 3 / 2010 Lift Station Emergency Generators

ADDENDUM #2

Bidders are hereby notified that this Addendum shall be acknowledged on page 00300-1 of the Bid Form and made a part of the above named bidding and contract documents. Bids submitted without acknowledgement of the Addendum will be considered incomplete.

The following items are issued to add to, modify, and clarify the bid and contract documents. These items shall have the same force and effect as the original bidding and contract documents, and cost involved shall be included in the bid prices. Bids to be submitted on the specified bid date, shall conform to the additions and revisions listed herein.

Bidders Note: The deadline for clarification requests was **November 17, 2010 at 5:00 PM**. This deadline has been established to maintain fair treatment of all potential bidders, while maintaining the expedited nature of the Economic Stimulus that the contracting of this work may achieve. Questions received after this date and time shall not be considered.


Bidders: Attached please find **Revision #1 to Addendum #1**, Response to questions received via email November 11, 2010 from Westra Construction.

If you have submitted a bid prior to receiving this addendum, you may request in writing that your original, sealed bid be returned to your firm. All sealed bids received will be opened on the date stated.

END OF ADDENDUM #2

Bids will be received at the **Manatee County Purchasing Division, 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205 until 2:00 P.M. on November 30, 2010.**

Sincerely,


R. C. "Rob" Cuthbert, C.P.M. CPPO
Purchasing Division Manager

Ov/ (2 Total pages attached) Financial Management Department – Purchasing Division
1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205
Phone: 941-708-7527 – Fax: 941-708-7544
www.mymanatee.org

LARRY BUSTLE * MICHAEL GALLEN * JOHN R. CHAPPIE * ROBIN DISABATINO * DONNA G. HAYES * CAROL WHITMORE * JOE McCLASH
District 1 District 2 District 3 District 4 District 5 District 6 District 7

MEMORANDUM



Public Works Department
1022 26th Avenue East
Bradenton, FL 34208

MANATEE COUNTY
FLORIDA

Phone: 941.708-7480
Fax: 941.708-7500
www.mymanatee.org

To: Sal Bordanaro, Project Manager
From: Wayne R. Troxler, P.E., Project Engineer Manager, X7650
Date: November 23, 2010
Subject: Response to Pre-Bid LS Egens Group 3 (Rev 1)

Response to email questions from Westra Construction:

1. *What size is the service at each lift station:* The size of the existing service breaker for each lift station is called out in the specifications, starting on page 124.
2. *What is the intent for the 300 vs 360 day period?* Normal construction time is estimated at 360 days. If the project is expedited, we expect that 300 days is possible at perhaps a higher cost.
3. This is a statement by Westra, not a question.
4. *Section 00300-9 Trench Safety Act form?* Not applicable to this project. The form must be submitted, geotechnical information is not available.
5. *How many concrete test cylinders will be required at each site by the engineer?* The specification calls for minimum 3000 psi concrete so the inspector will view the tickets, but no cylinders are required.
6. *Will the County require a silt fence?* If there are no stockpiles of fill type material on the site, silt fence is not required.
7. *How many gallons of fuel does each site require?* See paragraph 2.04.2 A 2 of the specifications.
8. *Spec page 23 Permanent power?* This addresses any power required by the contractor for his own use in order to complete the installation.
9. *Permit fees in bid?* These costs are approximate and provided for consistency between bidders. As mentioned in the pre-bid meeting, the County will reimburse any direct permitting fees over and above this amount.
10. *Is fencing applicable for this bid?* There is no fencing in this bid.
11. *How many door hangers will the County provide?* One. Project Management will generate a sample, the contractor will make as many copies as needed.

12. *Is there any limitation on any generator manufacturer that will meet the spec?* As long as the generator meets the specifications, any manufacturer will be considered.
13. *Enclosure color?* Color was not specified, but pantone green is preferred – both the enclosure and fuel tank are to be the same color.
14. *Will the County require an engineered slab including the cost for a PE stamp?* Per Hal Wolf of the Building Dept., if the slab has rebar in it (and it will), it will require a drawing or sketch of the rebar detail and an inspection prior to the concrete pour. The drawing does not have to be signed / sealed by an engineer.
15. *Please specify a fire extinguisher enclosure:* The County will review and approve or comment on the enclosure that the contractor submits. Two acceptable cabinets are the Thomas Model FEB-25 and the AmeraProducts SF-PC-105-20.
16. *KNOX box locations:* All sites with a diesel fuel tank will require a KNOX box.

Response to Info conference question:

1. *For the Utility feed change on LS 3-A, who is responsible for this work?* The relocation work and coordination with the local utility to remove the aerial feed power drop and go with underground feed is the responsibility of the contractor.

cc: Jim Marble, Lift Station Superintendent