



Financial Management Department
Purchasing Division
1112 Manatee Ave W Suite 803
Bradenton, FL 34205
Phone: (941) 749-3014
www.mymanatee.org

July 28, 2014

TO: All Interested Bidders
SUBJECT: Invitation for Bids #14-1427CD
Fence Replacement at the Manatee County Public Works Complex

ADDENDUM #1

Bidders are hereby notified that this Addendum shall be acknowledged on page Bid Form-1 of the Bid Form and made a part of the above named bidding and contract documents. Bids submitted without acknowledgment of the Addendum will be considered incomplete.

The following items are issued to add to, modify, and clarify the bid and contract documents. These items shall have the same force and effect as the original bidding and contract documents, and cost involved shall be included in the bid prices. Bids to be submitted on the specified bid date, shall conform to the additions and revisions listed herein.

1. **CHANGE** Article B.01.B.1.a, Wood Privacy Fence Panels, on page B-2 of the Bid documents to read as follows:
 - a. Panels: shall be a minimum of 5/8" thick pressure treated wood pickets, eight foot nominal height.

2. **CHANGE** Article B.01.B.1.c, Wood Privacy Fence Runners, on page B-2 of the Bid documents to read as follows:
 - c. Runners: shall be a minimum of 1" x 4" pressure treated wood.

3. **CLARIFICATION** of Article B.02.B.2, Wood Privacy Fence Installation, on page B-2 of the Bid documents:

The wood privacy fence to be installed shall be a board on board style fence.

4. **ADD** the following Article B.02.C.3.f, Installation of Fence around Gate #1 Power Source, to page B-5 of the Bid documents:

The Contractor shall furnish and install a six foot high black-vinyl coated chain link fence that is ten foot by ten foot around the power connection just north of the western edge of Gate #1. The Contractor shall furnish and install a 4 foot wide man gate with a locking mechanism on the eastern side of this fence area.

5. **CLARIFICATION** of Article B.02.C.4.b.5.a, Installation of Gate #1, on page B-6 of the Bid documents:

The frame of this gate shall aluminum.

6. **CLARIFICATION** of Article B.01.E.7, Measurement and Payment for Bid Item #3, on page B-10 of the Bid documents:

All references to PVC privacy fence shall read Wood privacy fence.

7. **CHANGE** Article B.01.E.7, Bid Item #12- Contract Contingency, on page B-12 of the Bid documents to read as Bid Item #13.

8. **ADD** the following new Article B.01.E.7, Bid Item #12, on page B-12 of the Bid documents:

BID ITEM #12- FURNISH AND INSTALL SIX FOOT HIGH BY TEN FOOT WIDE BLACK VINYL CHAIN LINK FENCE WITH 4 FOOT WIDE MAN GATE

Payment for all work included in this Bid Item shall be made at the applicable Contract lump sum price bid for furnishing and installing a six foot high by ten foot wide black vinyl chain link fence with a four foot wide man gate as listed in the Bid Form. The lump sum price bid will represent full compensation for all labor, materials, equipment and all incidentals required for the installation to complete this Bid Item.

9. **DELETE** Bid Form page Bid Form-2 and **INSERT** the REVISED Bid Form page Bid Form-2 that is attached to this Addendum #1.

10. **CHANGE** the Due Date and Time to **Monday, August 4, 2014 at 3:00 PM.**

The following questions have been presented by potential bidders:

QUESTION #1: Please clarify the frequency for the knox switches for fire (sound siren).

RESPONSE #1: All three operators are required to be equipped with a "Dual Channel - 10 DIP Switch Multi-code Receiver" No sound/Siren activation is required or needed.

QUESTION #2: For Gate #1 which is 6' x 35' cantilever gate, is the gate steel or aluminum? With a gate of this length, it is recommended that the gate be an Aluminum Sure Track Cantilever gate for strength and long term stability.

RESPONSE #2: Please see item #5 above of this Addendum #1.

QUESTION #3: As far as getting electricity to the gate operator for Gate #1, Can we pull off the existing power of the cameras that are there now?

RESPONSE #3: Power is available within 15 feet of the approximate location of the proposed Gate 1 operator. It is the selected Contractor's responsibility to tie into the power source supplied within close proximity to all three automated gates.

QUESTION #4: Regarding the Fob's for the electronic entry gates, do you need 25 fobs per gate or 25 fobs total for all 3 gates?

RESPONSE #4: Per Gate.

QUESTION #5: Can the same fobs operate all 3 gates?

RESPONSE #5: Yes, this is a requirement.

QUESTION #6: Is Convergent Technologies responsible for running its own conduit/electric for the work they are doing?

RESPONSE #6: The awarded contractor will be responsible for bringing power and conduit to their equipment.

QUESTION #7: For each fence area, are we to include the fence removal in that bid item, for instance the removal of the existing fence for Bid Item #2 will be included in the price along with the installation of the new fence for Bid Item #2?

RESPONSE #7: Yes.

END OF ADDENDUM #1

Bids will be received at Manatee County Purchasing, 1112 Manatee Avenue West, Bradenton, Florida 34205 until **Monday, August 4, 2014 at 3:00 PM.**

Sincerely,

 for

Melissa M. Wendel, CPPO
Purchasing Official

BID FORM

(Submit in Triplicate)

FENCE REPLACEMENT AT THE MANATEE COUNTY PUBLIC WORKS COMPLEXBid Based on Completion Time of 90 Calendar Days

ITEM NO.	DESCRIPTION	EST. QTY.	U/M	UNIT PRICE	EXTENDED PRICE
1	MOBILIZATION/ DEMOBILIZATION	1	LS	\$	\$
2	FURNISH AND INSTALL SIX FOOT HIGH PVC PRIVACY FENCE	310	LF	\$	\$
3	FURNISH AND INSTALL EIGHT FOOT HIGH WOOD PRIVACY FENCE	1,575	LF	\$	\$
4	FURNISH AND INSTALL SIX FOOT HIGH BLACK VINYL CHAIN LINK FENCE	545	LF	\$	\$
5	FURNISH AND INSTALL EIGHT FOOT HIGH BLACK VINYL CHAIN LINK FENCE	1,585	LF	\$	\$
6	FURNISH AND INSTALL FOUR FOOT WIDE CHAIN LINK GATE (GATE #2)	1	EA	\$	\$
7	FURNISH AND INSTALL TWELVE FOOT WIDE DOUBLE HUNG CHAIN LINK GATE (GATE #5)	1	EA	\$	\$
8	FURNISH AND INSTALL AUTOMATIC 35 FOOT WIDE CANTILEVER GATE, SIX FOOT HIGH (GATE #1)	1	EA	\$	\$
9	FURNISH AND INSTALL AUTOMATIC 25 FOOT WIDE CANTILEVER GATE, SIX FOOT HIGH (GATE #3)	1	EA	\$	\$
10	FURNISH AND INSTALL AUTOMATIC 25 FOOT WIDE CANTILEVER GATE, EIGHT FOOT HIGH (GATE #4)	1	EA	\$	\$
11	FURNISH AND INSTALL PROXIMITY CARD READERS AND ASSOCIATED EQUIPMENT (CONVRIGENT TECHNOLOGIES)				\$14,500.00
12	FURNISH AND INSTALL SIX FOOT HIGH BY TEN FOOT WIDE BLACK VINYL CHAIN LINK FENCE WITH FOUR FOOT WIDE MAN GATE	1	LS	\$	\$
	TOTAL BASE BID - Based on Completion Time of <u>90</u> Calendar Days				\$
13	CONTRACT CONTINGENCY WORK (USED ONLY WITH COUNTY APPROVAL)			10% OF TOTAL BASE BID	\$
	TOTAL OFFER with Contract Contingency- Based on Completion Time of <u>90</u> Calendar Days				\$

Bidder Name: _____

Authorized Signature: _____

REVISED Bid Form- 2