

# MANATEE COUNTY GOVERNMENT

## INTENT TO AWARD

<b>IFB NO. / TITLE</b>	IFBC No. 19-TA002946CD- Morgan Johnson Road Sidewalk from 18 Ave E to 13 Ave E- FDOT LAP Project	<b>DATE POSTED</b>	MC _____ DS _____	CC _____ BCC _____
<b>PROCUREMENT REPRESENTATIVE</b>	Chris Daley, Ext 3048	<b>PROJECTED AWARD DATE</b>	September 10, 2019	
<b>DEPARTMENT/DIVISION</b>	Public Works	<b>AUTHORIZED BY DATE</b>	Chris Daley, Procurement Manager	

### NOTICE OF INTENT TO AWARD

The Manatee County Procurement Division provides notice of its intent to award a contract with C-Squared Certified General Contractor, Inc. for the provision of Morgan Johnson Road Sidewalk from 18 Ave E to 13 Ave E- FDOT LAP Project.

### ENABLING/REGULATING AUTHORITY

Manatee County Procurement Ordinance, Sec 2-26.

### BACKGROUND/EVALUATION

The Work included in this Bid consists of construction of a sidewalk on Morgan Johnson Road from 18th Avenue East to 14th Avenue East on Bradenton, Florida. The Work also includes the construction of approximately one thousand twenty eight (1028) linear feet of twenty four inch storm drain, utility adjustments, and pavement restoration as shown on the plans. All construction on this project shall be in accordance with the latest edition of Manatee Utility and Transportation Standards, and FDOT Standard Specifications for Road and Bridge Construction.

The solicitation was advertised on June 18, 2019 on the Manatee County website and DemandStar. It was also provided to the Manatee County Chamber of Commerce and the Manasota Black Chamber of Commerce for release of its members and in the Bradenton Herald and Tempo newspapers. Responses were received from the following firms:

1. C-Squared Certified General Contractors, Inc., Palmetto, FL
2. Gator Grading & Paving, LLC, Palmetto, FL.
3. Westra Construction Corp., Palmetto, FL.

The following firms were deemed non-responsible: Westra Construction Corp.

### **EVALUATION SUMMARY:**

C-Squared Certified General Contractors, Inc. was the lowest responsible, responsive bidder. A bid tabulation of the results is attached to this Notice of Intent to Award.

### **RECOMMENDATION**

The Procurement Division and the Public Works Department recommend award to C-Squared Certified General Contractors, Inc..

ATTACHMENTS (List in order of attached)	Bid Tabulation	NAME AND NUMBER OF FUNDING SOURCE	Gas Taxes
COST	\$571,034.26	FUNDS VERIFIED	Yes

BID TABULATION  
IFB NO. 19-TA002950CD  
MORGAN JOHNSON ROAD SIDEWALK FROM 18 AVE E TO 13 AVE E- FDOT LAP PROJECT

					C-Squared Certified General Contractor, Inc.		Gator Grading & Paving, LLC	
PAY ITEM NO.	FDOT ITEM NUMBER	DESCRIPTION	UNITS	QTY.	BID PRICE PER UNIT (\$)	TOTAL BID PRICE (\$)	BID PRICE PER UNIT (\$)	TOTAL BID PRICE (\$)
1	0101-1	MOBILIZATION	LS	1	\$55,700.00	\$55,700.00	\$51,000.00	\$51,000.00
2	0102-1	MAINTENANCE OF TRAFFIC	LS	1	\$61,000.00	\$61,000.00	\$39,000.00	\$39,000.00
3	0102-60	WORK ZONE SIGN	ED	1080	\$0.30	\$324.00	\$0.42	\$453.60
4	0102-62	BARRIER MOUNTED WORK ZONE SIGN-INDEX 11871	ED	90	\$0.65	\$58.50	\$0.56	\$50.40
5	0102-74-1	CHANNELIZING DEVICE- TYPES I, II , 01. VP, DRUM, OR LCD	ED	3060	\$0.15	\$459.00	\$0.28	\$856.80
6	0102-74-7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	20	\$6.90	\$138.00	\$10.00	\$200.00
7	0104-10-3	SEDIMENT BARRIER	LF	1812	\$4.15	\$7,519.80	\$2.85	\$5,164.20
8	0104-18	INLET PROTECTION SYSTEM	EA	15	\$177.25	\$2,658.75	\$215.00	\$3,225.00
9	0107-1	LITTER REMOVAL	AC	3	\$760.00	\$2,280.00	\$675.00	\$2,025.00
10	0107-2	MOWING	AC	2	\$1,950.00	\$3,900.00	\$1,350.00	\$2,700.00
11	0110-1-1	CLEARING & GRUBBING	LS	1	\$35,000.00	\$35,000.00	\$69,800.00	\$69,800.00
12	0110-7-1	MAILBOX, F&I SINGLE	EA	5	\$228.00	\$1,140.00	\$275.00	\$1,375.00
13	0120-1	REGULAR EXCAVATION	CY	228	\$44.25	\$10,089.00	\$143.00	\$32,604.00

BID TABULATION  
IFB NO. 19-TA002950CD  
MORGAN JOHNSON ROAD SIDEWALK FROM 18 AVE E TO 13 AVE E- FDOT LAP PROJECT

					C-Squared Certified General Contractor, Inc.		Gator Grading & Paving, LLC	
PAY ITEM NO.	FDOT ITEM NUMBER	DESCRIPTION	UNITS	QTY.	BID PRICE PER UNIT (\$)	TOTAL BID PRICE (\$)	BID PRICE PER UNIT (\$)	TOTAL BID PRICE (\$)
14	0120-6	EMBANKMENT	CY	239	\$85.00	\$20,315.00	\$157.00	\$37,523.00
15	0160-4	TYPE B STABILIZATION	SY	136	\$58.00	\$7,888.00	\$45.00	\$6,120.00
16	0285701	OPTIONAL BASE, BASE GROUP 01	SY	136	\$71.15	\$9,676.40	\$47.00	\$6,392.00
17	0334-1-52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	8	\$395.00	\$3,160.00	\$498.00	\$3,984.00
18	0337-7-81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	13	\$477.00	\$6,201.00	\$428.00	\$5,564.00
19	0425-1541	INLETS, DT BOT, TYPE 0, <10'	EA	13	\$2,100.00	\$27,300.00	\$3,050.00	\$39,650.00
20	0425-2-61	MANHOLES, P-8, <10'	EA	1	\$1,850.00	\$1,850.00	\$3,100.00	\$3,100.00
21	0425-2-71	MANHOLES, J-7, <10'	EA	2	\$2,850.00	\$5,700.00	\$4,700.00	\$9,400.00
22	0430175118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	12	\$200.00	\$2,400.00	\$132.00	\$1,584.00
23	0430175218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18:S/CD	LF	529	\$103.80	\$54,910.20	\$53.00	\$28,037.00
24	0430175224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	1028	\$109.50	\$112,566.00	\$80.00	\$82,240.00

BID TABULATION  
IFB NO. 19-TA002950CD  
MORGAN JOHNSON ROAD SIDEWALK FROM 18 AVE E TO 13 AVE E- FDOT LAP PROJECT

					C-Squared Certified General Contractor, Inc.		Gator Grading & Paving, LLC	
PAY ITEM NO.	FDOT ITEM NUMBER	DESCRIPTION	UNITS	QTY.	BID PRICE PER UNIT (\$)	TOTAL BID PRICE (\$)	BID PRICE PER UNIT (\$)	TOTAL BID PRICE (\$)
25	0430830	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	10	\$260.00	\$2,600.00	\$570.00	\$5,700.00
26	0430982629	MITERED END SECTION. OPTIONAL - ELLIPTICAL / ARCH, 24" CD	EA	1	\$1,600.00	\$1,600.00	\$1,980.00	\$1,980.00
27	0522-1	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	771	\$37.35	\$28,796.85	\$45.00	\$34,695.00
28	0522-2	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	578	\$53.85	\$31,125.30	\$63.00	\$36,414.00
29	0524-1-1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	21	\$230.00	\$4,830.00	\$70.00	\$1,470.00
30	0527-2	DETECTABLE WARNINGS	SF	51	\$43.00	\$2,193.00	\$49.00	\$2,499.00
31	0570-1-2	PERFORMANCE TURF, SOD	SY	3595	\$3.05	\$10,964.75	\$3.80	\$13,661.00
32	1080-21500	UTILITY FIXTURE, VALVE/METER BOX, ADJUST	EA	12	\$271.00	\$3,252.00	\$480.00	\$5,760.00
33	0700-1-50	SINGLE POST SIGN, RELOCATE	AS	1	\$250.00	\$250.00	\$350.00	\$350.00
34	0711-11123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	111	\$11.50	\$1,276.50	\$8.00	\$888.00
<b>TOTAL BASE BID - Based on Completion Time of <u>300</u> Calendar Days</b>						\$519,122.05		\$535,465.00
35		<b>CONTRACT CONTINGENCY WORK (USED ONLY WITH COUNTY APPROVAL)</b>		<b>10% OF TOTAL BASE BID</b>		\$51,912.21		\$53,546.50

BID TABULATION  
IFB NO. 19-TA002950CD  
MORGAN JOHNSON ROAD SIDEWALK FROM 18 AVE E TO 13 AVE E- FDOT LAP PROJECT

					C-Squared Certified General Contractor, Inc.		Gator Grading & Paving, LLC	
PAY ITEM NO.	FDOT ITEM NUMBER	DESCRIPTION	UNITS	QTY.	BID PRICE PER UNIT (\$)	TOTAL BID PRICE (\$)	BID PRICE PER UNIT (\$)	TOTAL BID PRICE (\$)
TOTAL OFFER FOR BID with Contract Contingency - Based on Completion Time of <u>300</u> Calendar Days						\$571,034.26		\$589,011.50

\*\* Note- Bid response received from Westra Construction Corp. has been deemed non-responsible for not being FDOT pre-qualified in the category of sidewalks, as required by bid documents.

BID TABULATION  
IFB NO. 19-TA002950CD  
MORGAN JOHNSON ROAD SIDEWALK FROM 18 AVE E TO 13 AVE E- FDOT LAP PROJECT

			C-Squared Certified General Contractor, Inc.			Gator Grading & Paving, LLC		
PAY ITEM NO.	FDOT ITEM NUMBER	DESCRIPTION	%	MBE/ DBE	Description of Work by Subcontractor	%	MBE/ DBE	Description of Work by Subcontractor
1	0101-1	MOBILIZATION	15	DBE	Survey-As Built/Mobilization			
2	0102-1	MAINTENANCE OF TRAFFIC						
3	0102-60	WORK ZONE SIGN				100		furnish & install
4	0102-62	BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871				100		furnish & install
5	0102-74-1	CHANNELIZING DEVICE- TYPES I, II , 01. VP, DRUM, OR LCD				50		furnish
6	0102-74-7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)				50		furnish
7	0104-10-3	SEDIMENT BARRIER						
8	0104-18	INLET PROTECTION SYSTEM						
9	0107-1	LITTER REMOVAL						
10	0107-2	MOWING						
11	0110-1-1	CLEARING & GRUBBING						
12	0110-7-1	MAILBOX, F&I SINGLE						

BID TABULATION  
IFB NO. 19-TA002950CD  
MORGAN JOHNSON ROAD SIDEWALK FROM 18 AVE E TO 13 AVE E- FDOT LAP PROJECT

			C-Squared Certified General Contractor, Inc.			Gator Grading & Paving, LLC		
PAY ITEM NO.	FDOT ITEM NUMBER	DESCRIPTION	%	MBE/ DBE	Description of Work by Subcontractor	%	MBE/ DBE	Description of Work by Subcontractor
13	0120-1	REGULAR EXCAVATION						
14	0120-6	EMBANKMENT						
15	0160-4	TYPE B STABILIZATION						
16	0285701	OPTIONAL BASE, BASE GROUP 01						
17	0334-1-52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B,PG76-22						
18	0337-7-81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22						
19	0425-1541	INLETS, DT BOT, TYPE 0, <10'						
20	0425-2-61	MANHOLES, P-8, <10'						
21	0425-2-71	MANHOLES, J-7, <10'						
22	0430175118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD						
23	0430175218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18:S/CD						
24	0430175224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD						



BID TABULATION  
IFB NO. 19-TA002950CD  
MORGAN JOHNSON ROAD SIDEWALK FROM 18 AVE E TO 13 AVE E- FDOT LAP PROJECT

			C-Squared Certified General Contractor, Inc.			Gator Grading & Paving, LLC		
PAY ITEM NO.	FDOT ITEM NUMBER	DESCRIPTION	%	MBE/ DBE	Description of Work by Subcontractor	%	MBE/ DBE	Description of Work by Subcontractor
25	0430830	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE						
26	0430982629	MITERED END SECTION. OPTIONAL - ELLIPTICAL / ARCH, 24" CD						
27	0522-1	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK				100		furnish & install
28	0522-2	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK				100		furnish & install
29	0524-1-1	CONCRETE DITCH PAVT, NON REINFORCED, 3"				100		furnish & install
30	0527-2	DETECTABLE WARNINGS				100		furnish & install
31	0570-1-2	PERFORMANCE TURF, SOD	100	DBE	Sod	100		furnish & install
32	1080-21500	UTILITY FIXTURE, VALVE/METER BOX, ADJUST						
33	0700-1-50	SINGLE POST SIGN, RELOCATE						
34	0711-11123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT				100		furnish & install

This bid form is a duplication of the bid items where the Bidder shall state the percentage (%) of work of each item listed and a brief description of the work that shall be performed by the subcontractor.