



1112 Manatee Avenue West
Bradenton, FL 34205
purchasing@mymanatee.org

Solicitation Addendum

Addendum No.: 1
Solicitation No.: 22-TA004011DJ
Solicitation Title: 26th Avenue East from 27th Street E to Sugar Creek Sidewalk and
26th Street East FM Replacement
Project No.: 6098660
Addendum Date: February 16, 2022
Procurement Contact: Dave Janney
Senior Procurement Agent

IFBC 22-TA004011DJ is amended as set forth herein. Responses to questions posed by prospective bidders are provided below. This Addendum is hereby incorporated in and made a part of IFBC 22-TA004011DJ.

The deadline to submit all inquiries concerning interpretation, clarification or additional information pertaining to this IFBC was February 15, 2022.

REPLACE:

SECTION B, BID FORMS, APPENDIX K, BID PRICING FORM

Replace Appendix K Bid Pricing Form, with the Revised Appendix K Bid Pricing Form hereby incorporated into the IFBC.

QUESTIONS AND RESPONSES:

Q1. Where are the 25 CY of Class II Endwalls? We are having trouble locating it.

R1. There are two headwalls, One is per MC (Sheet No. 9) detail and the other I FDOT (Sheet No. 10).

Q2. What are sewage volumes/flows we must handle for the force main relocation work?

R2. The anticipated design flow from the mobile home park is 37 GPM.

Q3. What is the budget for this project?

R3. The construction budget is \$830,268.00

Q4. Will the oak trees at the north east corner of 26th & 27th need to be removed to construct the sidewalk?

R4. No, those are grandfather oaks, not to be removed.

Q5. The pay item for clear & grubbing is by the Acre. Shouldn't this be LS?

R5. See Addendum No. 1, Appendix K Bid Pricing Form (Revised). Changes highlighted in yellow.

Q6. The excavation and embankment pay item quantity's seem very low due to the proposed drainage being installed along with sidewalk construction. Please verify that the quantities listed are correct.

R6. See Addendum No. 1, Appendix K Bid Pricing Form (Revised). Changes highlighted in yellow.

Q7. On the bid form under MOT, it states a MOT plan. The contractor can submit from the FDOT Design Standards index 600 correct?

R7. The awarded contractor will be required to apply for a Manatee County Right of Way Permit to include MOT Plan approval. FDOT Index 600 is acceptable for shoulder and one lane closures. No road closures allowed without approval from Matt Merucci Matt.Merucci@mymanatee.org.

Q8. The plans call out in certain locations to remove the existing drainage does pay item # 38 MC.9 include the removal of existing headwall?

R8. See Addendum No. 1, Appendix K Bid Pricing Form (Revised). Changes highlighted in yellow.

Q9. There is removal of existing fence on plan sheets 12, 13, 14, I do not see a pay item for this work.

R9. Per Bid Attachment 3, Specifications_Forcemain_26th Ave E Sidewalk, Clarification of Specific Line Items;

Clearing & Grubbing shall per FDOT current specifications, and include completely removing and disposing of all buildings, timber, brush, trees, stumps, roots, rubbish, debris, fences, existing flexible pavement and base, drainage structures, culvers and pipes and other obstructions in the project area.

Q10. How was this scope of work calculated by the acre? There is a proposed ROW shown on the typical section plan sheet # 6. Is this area calculated in your acre quantity? The north side of 26th needs to be stripped of vegetation for proposed improvements. It seems that the pay item should be LS.

R10. See Addendum No. 1, Appendix K Bid Pricing Form (Revised). Changes highlighted in yellow.

Q11. Will the County take in consideration compensating the contractor with a portion of the contingency money on their projects due to material increases after the bid has been awarded. Pricing from suppliers are still increasing every few weeks and it doesn't seem to be getting any better. This goes for all material that is needed for the project. The contractor will provide proof of increases.

R11. County will consider compensating contractor with either contingency or change order for material increase assuming no delay in ordering and dated evidence of the price increase from the manufacturer.

Q12. Will the tie in's for the proposed water line need to be performed at night or will the contractor be able to connect during day time hours.

R12. There is no issue with a day-time connection.

NOTE:

Deleted items will be ~~struck through~~, added or modified items will be underlined. All other terms and conditions remain as stated in the RFQ.

INSTRUCTIONS:

Receipt of this Addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the response being deemed non-responsive.

END OF ADDENDUM

AUTHORIZED FOR RELEASE

APPENDIX K, BID PRICING FORM REVISED 22-TA004011DJ 26th AVE E FROM 27th ST E SIDEWALK, PEDESTRIAN BRIDGE, FORCE MAIN COUNTY PROJECT NO. 6098660					UNIT PRICE BID A 180 Calendar Days	EXTENDED AMOUNT BID A	UNIT PRICE BID B 270 Calendar Days	EXTENDED AMOUNT BID B
PAY ITEM NO.	MCG SPEC#	DESCRIPTION	QTY.	UNIT				
FORCE MAINS 8-INCH & UNDER								
1		Asphalt Pavement Restoration						
1.1		Base & Resurface	40	SY				
1.3		Mill & Resurface	185	SY				
2		PVC (C-900, DR-18)						
2.1		4" PVC	235	LF				
2.2		8" PVC (Casing)	18	LF				
3		Ductile Iron Fittings						
3.1		4" 45-Degree Bend	12	EA				
4		Pipe Joint Restraints (4")	20	EA				
5		Plug Valve (4")	3	EA				
6		Air Release Valve Assembly, (Above Ground)	1	EA				
7		Air Release Valve Assembly, (Waterway/Canal Crossing)	1	EA				
8		Utility Pipe - Remove & Dispose	235	LF				
9		Sewage Disposal - Pumper Trucks	1	LS				
SUBTOTAL								

SIDEWALK								
10	104-10-3	Sediment Barrier	3481	LF				
11	104-11	Floating Turbidity Barrier	27	LF				
12	104-18	Inlet Protection System	1	EA				
13	110-1-1	Clearing & Grubbing	1.00	LS				
14	120-1	Regular Excavation	33	CY				
15	120-4	Subsoil Excavation	10	CY				
16	120-6	Embankment	222	CY				
17	339-1	Miscellaneous Asphalt Pavement	6	TN				
18	400-2-2	Conc Class Class II, End Walls	25	CY				
19	430-175-115	Pipe Culvert, Optional Material, Round, 15" S/CD	230	LF				
20	430-175-118	Pipe Culvert, Optional Material, Round, 18" S/CD	233	LF				
21	430-175-236	Pipe Culvert, Opt Material, Other Shape -29"x45"	8	LF				
22	430-536-102	Straight Concrete Endwalls, 36", Single, 0 Degrees, Elliptical	2	EA				
23	430-530-100	Straight Concrete Endwalls, 30", Single, 0 Degrees, Round	2	EA				
24	430-982-123	Mitered End Section, Optional Round, 15" CD	2	EA				
25	430-982-125	Mitered End Section, Optional Round, 18" CD	3	EA				
26	515-1-2	Pipe Handrail - Guiderail, Aluminum	64	LF				
27	522-1	Concrete Sidewalk 4" Thick, including HC Ramps	1,828	SY				
28	522-2	Concrete Sidewalk and Driveways, 6" Thick	150	SY				
29	527-2	Detectable Warnings	50	SF				
30	570-1-2	Performance Turf, Sod	12,890	SY				
31	536-1-0	Guardrail - Roadway, General TL-3 w/ end treatment	171	LF				
32	700-1-11	Single Post Sign, F&I Ground Mount, Up To 12 SF	1	EA				
33	711-11-123	Thermoplastic, Standard, White, Solid, 12" For Crosswalk	520	LF				
34	711-11-125	Thermoplastic, Standard, White, Solid, 24" For Stop Line	34	LF				
35	MC4	Boardwalk	2,121	SF				
36	MC7	PVC Fence and Gates (Sugar Creek Country Club)	1	LS				
37	MC8	Drop Inlet	2	EA				
38	MC9	Remove Existing MES/Connect to Existing Pipe	5	EA				
SUBTOTAL								

PEDESTRIAN BRIDGE								
39	125-1	Excavation for Structures	35	CY				
40	125-3	Select Bedding Material	7	CY				
41	400-4-5	Conc. Class IV, Substructure	20.30	CY				
42	415-1-5	Reinf Steel-Substructure	1,432	LB				
43	455-35-5	Steel Piling, HP 14 x 73	91	LF				
44	455-120-5	Pile Point Protection, HP 14" x 73"	8	EA				
45	455-144-5	Test Piles, Steel, HP 14 x 73	25	LF				
46	460-5	Prefabricated Aluminum Pedestrian Bridge (95' x 6' Interior Width)	1	EA				
47	530-3-4	Riprap, Rub ble, F&I, Ditch Lining	20	TN				
48	530-74	Bedding Stone	12	TN				
SUBTOTAL								

SUBTOTAL ALL SECTIONS (SIDEWALK, PEDESTRIAN BRIDGE, FORCE MAINS 8-INCH & UNDER)								
10	102-1	Traffic Control Plan/Maintenanc of Traffic (MOT)						
10.1		Sidewalk & Pedestrian Bridge	1	LS				
10.2		Force Mains 8-Inch & Under	1	LS				
SUBTOTAL Traffic Control Plan/MOT								
11	101-1	Mobilization		LS				
11.1		Sidewalk & Pedestrian Bridge	1	LS				
11.2		Force Mains 8-Inch & Under	1	LS				
SUBTOTAL Mobilization								
12		Record Drawings	1	LS				
SUBTOTAL (All Sections, Traffic Control Plan/MOT, Mobilization, Record Drawings)								
13	CONTRACT CONTINGENCY WORK (COUNTY AUTH REQUIRED)		1	10%				
GRAND TOTAL (PROJECT NO. 6098660)								

BIDDER NAME _____

BIDDER SIGNATURE _____