



# MANATEE COUNTY FLORIDA

## FACSIMILE

February 6, 2009

TO: All Interested Bidders

SUBJECT: Invitation for Bid #09-0538DC  
Lift Station Rehabilitation – Braden Woods and Mill Creek #1  
ADDENDUM #1

**Bidders are hereby notified that this Addendum shall be acknowledged on the Bid Form signature pages and made a part of the above named bidding and contract documents.**

The following items are issued to add to, modify, and clarify the bid and contract documents. These items shall have the same force and effect as the original bidding and contract documents, and cost involved shall be included in the bid prices. Bids to be submitted on the specified bid date, shall conform to the additions and revisions listed herein.

1. Both of the lift stations are to be repaired to the existing PVC liner. The line is not generally damaged; it has just lost its adhesion, so this would be an epoxy based repair. In both instances, the liner needs repair at the entrance hatch and will need repair when installing new pipes and braces. Neither station will require a new liner. The square footages listed as listed on the Bid Form are estimates in relation to the square footage of area that will need repair.
2. Manatee County will remove the pumps prior to construction and replace the pumps after construction. The pumps will be provided by Manatee County. The contractor will provide the new base ells and guide rails of the size and type specified.
3. Bid Specification Section 01590 – A field office is not applicable to this project and any reference is deleted from the Invitation for Bid.
4. The contractor shall provide the electrical drawings in reference to Bid Specification Section 16231 requiring the signed and sealed site plan.

Financial Management Department - Purchasing Division  
1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205  
PHONE: 941.749.3074 \* FAX: 941.749.3034  
[www.mymanatee.org](http://www.mymanatee.org)

5. The Mill Creek generator is sitting on top of several existing bushes. It is the responsibility of Manatee County to replace (furnish and install) the bushes when construction is completed.
6. Bid Section 13300, 2.01C – Clarification: The contractor shall install the new conduit.
7. The Magnetic Flow Meter specified on the plans is the only acceptable flow meter for this project – ABB Company, ABB Model 10DX3111EED19P1A3BK54321.
8. The size of the generator is the responsibility of the contractor (an estimate is between a 25 and 30 KW). Power rating is referenced in Bid Specification Section 16231.

If you have submitted a bid prior to receiving this addendum you may request in writing that your original, sealed bid be returned to your firm. All sealed bids received will be opened on the date stated.

Bids will be received at Manatee County Purchasing, 1112 Manatee Avenue West, Suite 803, Bradenton, Florida 34205 until **February 10, 2009 at 3:00 P.M.**

Sincerely,



R.C. "Rob" Cuthbert, C.P.M.  
Purchasing Division Manager

/dcr