



MANATEE COUNTY FLORIDA

May 21, 2009

TO: All Interested Bidders

SUBJECT: **Invitation for Bid # 09-1822-DS**
**Water Main Installation- 51st Street West from Cortez to 53rd Avenue
(Cortez Road / Glen Lakes), Bradenton, FL**

ADDENDUM # 1

Bidders are hereby notified that this Addendum shall be acknowledged on pages 00300-1 of the Bid Form and made a part of the above named bidding and contract documents. Bids submitted without acknowledgement of the Addendum will be considered incomplete.

The following items are issued to add to, modify, and clarify the bid and contract documents. These items shall have the same force and effect as the original bidding and contract documents, and cost involved shall be included in the bid prices. Bids to be submitted on the specified bid date, shall conform to the additions and revisions listed herein.

Based upon instructions from the Project Manager, Mr. Mike O'Reilly, Manatee County Government, Public Works Department, Mr. Dave Schofield, Utilities Distribution Superintendent and from Mr. Jim Stockwell, Senior Project Manager.

Q1. Could you please clarify your local contractor preference? Does it only apply in cases of a "tie bid", or does it apply to bids also, where the local contractor is within a certain % of the non local bid?

A1. **Answer:** Please see E.02 (Section 2-26-6, Local preference, tie bids, Local business defined) pages 00200-2 through 00200-3.

Q2. Is there stimulus money involved on this project?

A2. **Answer:** There is no stimulus money in this project.

Finance Management Department
Mailing Address: Purchasing Division: 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205
PHONE: 941-749-3045 * FAX: 941-749-3034
www.myanatee.org

Q3. Bid Item 11 has five check valves? Can't find?

A3. Answer: Bid item 11 should be corrected to read "18"x16" Tapping Sleeve, 1 Each", there are no check valves required in this project. Please see revised Bid Forms attached. Contractors are to utilize these forms when submitting their bid package.

Q4. Are temporary jumpers needed? If so what size?

A4. Answer: Temporary jumpers are required per Manatee County Standards (2009) UW 21 and UW22. The minimum size is 2" dia. jumper, but larger may be required to obtain minimum flushing velocity required by AWWA (3.0fps min., 3.5fps preferred) for disinfection.

Q5. EPDM gaskets per new county code may not be available. If not available will need an alternate installation plan.

A5. Answer: EPDM gaskets are required. If not available they will need to be special ordered.

Q6. Pay items call for 4 tie ins. One of which is the 20 x 16 tap sleeve. Pay item should change to three.

A6. Answer: There is no need to change the quantity for pay item # 10, the 20 x 16 Sleeve, the quantity of one (1) is correct. The other three connections require an 18 x 16 Tapping Sleeve, an 8" cut in tee, and a 6" cut in tee.

Q7. Air release valves, above the pipe or are they offset to side of road?

A7. Answer: Air Release Valves are to be installed as shown on the plans. Most are above the pipe, but where the pipe is under pavement, the ARV is offset to the side of the road. No manholes will be required to house ARV's under pavement.

Q8. The specs call for the pipeline to be pigged however there are Butterfly valves in the line and they cannot allow a pig due to the disc being in the middle of the pipeline when open. Please advise what you want done to address this?

A8. Answer: The contractor can pig each section of the line between valves as he proceeds to install it, rather than wait until valves are installed, to avoid the pig hitting valves.

Finance Management Department
Mailing Address: Purchasing Division: 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205
PHONE: 941-749-3045 * FAX: 941-749-3034
www.myanatee.org

Page 3
Addendum # 1
IFB# 09-1822-DS
May 21, 2009

If you have submitted a bid prior to receiving this addendum, you may request in writing that your original, sealed bid be returned to your firm. All sealed bids received will be opened on the date stated.

THIS ADDENDUM MUST BE ACKNOWLEDGED ON THE BID FORM FOR YOUR BID TO BE CONSIDERED RESPONSIVE.

END OF ADDENDUM # 1


If you have submitted a bid prior to receiving this addendum, you may request in writing that your original, sealed bid be returned to your firm. All sealed bids received will be opened on the date stated.

THIS ADDENDUM MUST BE ACKNOWLEDGED ON THE BID FORM FOR YOUR BID TO BE CONSIDERED RESPONSIVE.

END OF ADDENDUM # 1

Bids will be received at the Manatee County Purchasing Division, 1112 Manatee Avenue West, Suite 803, Bradenton, Florida 34205 until 2:00 P.M. on June 16th 2009.

Sincerely,



R. C. "Rob" Cuthbert, CPM, CPPO
Purchasing Division Manager
Enclosure
/ds

Finance Management Department
Mailing Address: Purchasing Division: 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205
PHONE: 941-749-3045 * FAX: 941-749-3034
www.mymanatee.org

SECTION 00300

(Submit in Triplicate)

IFB# 09-1822-DS

(Page 1 of 2)

(REVISED via Addendum # 1)

(Bid "A" - Based on Completion Time of 320 Calendar Days)

PROJECT NAME: Water Main Installation – 51st Street West from Cortez to 53rd Avenue
PROJECT NUMBER : 4046042770

ITEM NO.	DESCRIPTION	UNITS	QTY.	UNIT PRICE (\$)	EXTENDED PRICE (\$)
1	16" HDPE (C-906 DR11 Class 160) (Directional Drill)	LF	1,771	\$	\$
2	16" DIP (CL-50) (Open-Cut)	LF	3,570	\$	\$
3	16" DIP (CL-53) (Inside Jacked Casing)	LF	153	\$	\$
4	8" DIP (CL 50) (Open Cut)	LF	42	\$	\$
5	6" CI (CL50) (Open-Cut)	LF	105	\$	\$
6	Ductile Iron Fittings	LB	6,200	\$	\$
7	Fire Hydrant Assembly with Gate Valve, Complete	EA	6	\$	\$
8	16" Butterfly Valve w/Box	EA	8	\$	\$
9	16" Tapping Valve w/Box	EA	2	\$	\$
10	20" x 16" Tapping Sleeve	EA	1	\$	\$
11	18"x 16" Tapping Sleeve (Addendum # 1)	EA	1	\$	\$
12	16" Pipe Joint Restraints	EA	224	\$	\$
13	8" Gate Valve w/Box	EA	1	\$	\$
14	6" Gate Valve w/Box	EA	1	\$	\$
15	Connect to Exist. Water Main	EA	4	\$	\$
16	Asphalt Road Restoration (Base & 2.0" S-1)	SY	1,105	\$	\$
17	Asphalt Road Restoration (1.0" S-III Overlay)	SY	5,200	\$	\$

BIDDER _____

**BID FORM
SECTION 00300
(Submit in Triplicate)
IFB# 09-1822-DS**

(Page 2 of 2)

(REVISED via Addendum # 1)

(Bid "A"- Based on Completion Time of 320 Calendar Days)

PROJECT NAME:	Water Main Installation – 51st Street West from Cortez to 53rd Avenue
PROJECT NUMBER :	4046042770

ITEM NO.	DESCRIPTION	UNITS	QTY.	UNIT PRICE (\$)	EXTENDED PRICE (\$)
18	Jack & Bore Steel Casing 0.406" thick 30" Dia.	LF	140	\$	\$
19	2" Air Release Valve Assembly	EA	7	\$	\$
20	Sodding	SY	3,600	\$	\$
21	Erosion Control	LS	1	\$	\$
22	Grout & plug out of service pipe	LS	1	\$	\$
23	Traffic Control, Signing & Barricades to FDOT Standards	LS	1	\$	\$
24	Concrete Sidewalk Replacement	SY	20	\$	\$
25	Concrete Curb & Gutter Replacement	LF	100	\$	\$
26	Remove & Reinstall Street Light pole	EA	1	\$	\$
27	Mobilization (Max 10% of Total Bid)	LS	1	\$	\$
28	Miscellaneous Work & Clean Up	LS	1	\$	\$
29	Discretionary	LS	1		\$140,000.00
	TOTAL BID PRICE				

BIDDER _____

BID FORM
SECTION 00300
 (Submit in Triplicate)
IFB# 09-1822-DS

(Page 1 of 2)

(REVISED via Addendum # 1)

(Bid "B" - Based on Completion Time of 260 Calendar Days)

PROJECT NAME: Water Main Installation – 51st Street West from Cortez to 53rd Avenue
PROJECT NUMBER : 4046042770

ITEM NO.	DESCRIPTION	UNITS	QTY.	UNIT PRICE (\$)	EXTENDED PRICE (\$)
1	16" HDPE (C-906 DR11 Class 160) (Directional Drill)	LF	1,771	\$	\$
2	16" DIP (CL-50) (Open-Cut)	LF	3,570	\$	\$
3	16" DIP (CL-53) (Inside Jacked Casing)	LF	153	\$	\$
4	8" DIP (CL 50) (Open Cut)	LF	42	\$	\$
5	6" CI (CL50) (Open-Cut)	LF	105	\$	\$
6	Ductile Iron Fittings	LB	6,200	\$	\$
7	Fire Hydrant Assembly with Gate Valve, Complete)	EA	6	\$	\$
8	16" Butterfly Valve w/Box	EA	8	\$	\$
9	16" Tapping Valve w/Box	EA	2	\$	\$
10	20" x 16" Tapping Sleeve	EA	1	\$	\$
11	18" x 16" Tapping Sleeve (Addendum # 1)	EA	1	\$	\$
12	16" Pipe Joint Restraints	EA	224	\$	\$
13	8" Gate Valve w/Box	EA	1	\$	\$
14	6" Gate Valve w/Box	EA	1	\$	\$
15	Connect to Exist. Water Main	EA	4	\$	\$
16	Asphalt Road Restoration (Base & 2.0" S-1)	SY	1,105	\$	\$
17	Asphalt Road Restoration (1.0" S-III Overlay)	SY	5,200	\$	\$

BIDDER _____

**BID FORM
SECTION 00300
(Submit in Triplicate)
IFB# 09-1822-DS**

(Page 2 of 2)

(REVISED via Addendum # 1)

(Bid "B" – Based on Completion Time of 260 Calendar Days)

PROJECT NAME: Water Main Installation – 51st Street West from Cortez to 53rd Avenue
PROJECT NUMBER : 4046042770

ITEM NO.	DESCRIPTION	UNITS	QTY.	UNIT PRICE (\$)	EXTENDED PRICE (\$)
18	Jack & Bore Steel Casing 0.406" thick 30" Dia.	LF	140	\$	\$
19	2" Air Release Valve Assembly	EA	7	\$	\$
20	Sodding	SY	3,600	\$	\$
21	Erosion Control	LS	1	\$	\$
22	Grout & plug out of service pipe	LS	1	\$	\$
23	Traffic Control, Signing & Barricades to FDOT Standards	LS	1	\$	\$
24	Concrete Sidewalk Replacement	SY	20	\$	\$
25	Concrete Curb & Gutter Replacement	LF	100	\$	\$
26	Remove & Reinstall Street Light pole	EA	1	\$	\$
27	Mobilization (Max 10% of Total Bid)	LS	1	\$	\$
28	Miscellaneous Work & Clean Up	LS	1	\$	\$
29	Discretionary	LS	1		\$140,000.00
	TOTAL BID PRICE				

BIDDER _____