



1112 Manatee Avenue West
Bradenton, FL 34205
purchasing@mymanatee.org

Solicitation Addendum

Addendum No.: 2
Solicitation No.: 21-TA003584DJ
Project No.: 6097980
Solicitation Title: Installation of Force Main at 41st Avenue E. and I-75
Addendum Date: January 28, 2021
Procurement Contact: Dave Janney
Senior Procurement Agent

IFBC 21-TA003584DJ is amended as set forth herein. Responses to questions posed by prospective bidders are provided below. This addendum is hereby incorporated in and made a part of IFBC 21-TA003584DJ.

ADD:

BID ATTACHMENT 4 - GEOTECHNICAL REPORT

The Bid Attachment 4- Geotechnical Report, is hereby incorporated as a separate attachment to the IFBC.

QUESTIONS AND RESPONSES:

- Q1. Regarding the tie in locations, please provide the closest valve locations on the existing force mains so we can determine the volume of sewage that must be handled during the tie in process.**
- R1. There appears to be an existing valve at Station 11+75.00 of the west of the crossing. The location of the valve on the east is unknown. It is recommended the Contactor review the Manatee County atlas maps.
- Q2. Can you email me a list of current plan holders for this job. I did not see a list on your project website.**
- R2. The solicitation was advertised through multiple sources and a list of current plan holders cannot be determined at this time.

Q3. What and how many lift stations are involved with the force main tie ins?

R3. It appears there are three lift stations involved with this project. The following lift stations are in proximity to the project area: Lift Station 666 is to the west, Lift Station 615 is to the northeast, and Lift Station 655 is to the southeast. Please review the Manatee County GIS Mobile Server for visual clarification.

Q4. Where are these stations located?

R4. Lift Station 666 is located at 7422 41st Avenue E.
Lift Station 615 is located at 3208 81st Court E.
Lift Station 655 is located at 4905 Lena Road.

Q5. Who is responsible for manning these stations and the related pumper trucks to handle the sewage?

R5. The Contractor is responsible for handling sewage. The Contractor shall coordinate with Manatee County representatives regarding lift station operations.

Q6. What are the pumping capacities of these stations?

R6. LS 615 – 295 gpm @ 83' TDH
LS 655 – 350 gpm @ 64' TDH
LS 666- No Info Available

Q7. Where can the sewage be disposed of?

R7. The tentative disposal location is the Southeast Water Reclamation Facility at 3331 Lena Road, Bradenton, FL 34211.

Disposal location of sewage will be discussed at the pre-construction meeting.

Q8. Will the line valves in the existing force main completely isolate the sewage flows?

R8. Yes, all existing line valves can isolate the existing force main.

Q9. What is the location of the line valves in both directions of the tie in points?

R9. Refer to R1.

Q10. Will any restraining of existing pipeline be required? If yes, please provide existing pipe information, details, extent, etc.

R10. Restraining of existing pipeline is not required.

- Q11. Please confirm no ARV's are required.**
- R11. There are no proposed air release valves (ARV) for this project.
- Q12. Please clarify the asphaltic concrete bid items. It appears some of the work in bid items 9 and 10 are duplicated.**
- R12. Bid Item No. 9 is Asphaltic Concrete Overlay (0.75" Minimum). Bid Item No. 10 is Asphaltic Concrete with Prime Coat (1.25" Minimum). Bid Item No. 11 is the Full Base Replacement. Please review Standard Detail UG-12: Trench with Asphalt Pavement Surface Type A-1 Pipe Bedding (Crossing) for additional clarification.
- Q13. Please confirm the intended asphalt restoration type, as the detail and bid items do not match.**
- R13. Asphalt will be restored in accordance with Standard Detail UG-12.
- Q14. In order for comparative bids, please provide the existing base and asphalt thicknesses. If unknown, please provide thicknesses for bidding purposes.**
- R14. The composition of the existing base and asphalt are unknown. Please use 1¼" for bidding purposes.
- Q15. Please provide a geotechnical report.**
- R15. See attached, Bid Attachment 4 - Geotechnical Report.
- Q16. Please confirm whether or not temporary fencing will be required around work sites.**
- R16. Temporary fencing will be required.
- Q17. Please confirm the permits expected to be acquired by the contractor, and their associated costs.**
- R17. The Contractor shall issue the final notification of operation from the FDEP, FDOT, and NPDES permit.
- Q18. If applicable, please provide a copy of the FDOT permit for crossing under I-75.**
- R18. Pending acceptance from FDEP and FDOT permits.
- Q19. Are there any soil borings available in the general vicinity of this project?**
- R19. See attached, Bid Attachment 4 - Geotechnical Report.

- Q20. Section 01150, measurement and payment, page 7 of 142 under bid item “F&I ductile iron fittings”. It calls for cement lined. Is this a mistake?**
- R20. Ductile iron fitting shall not be cement lined. All ductile iron pipe and fittings used in wastewater sewer systems shall have a green, factory applied amine cured novalac ceramic epoxy or a modified polyamine ceramic epoxy interior lining on the inside, dry film thickness shall be as defined in the Utility Approved Products List. Please review Manatee County Public Works Standards, Part I. Utilities Standards Manual, Section 1.4.2(H) for additional clarification.
- Q21. There’s no separate bid item for casing spacers. Are we to include these cost in bid item #2?**
- R21. Casing spacers are to be included in Bid Item No. 2.
- Q22. There’s no separate bid item for bell restraints. Are we to include these cost in bid item #1?**
- R22. Bell restraints are to be included in Bid Item No. 1.
- Q23. There’s no separate bid item for mechanical joint restraints. Are we to include these cost in bid items #3 through 6?**
- R23. Mechanical joints are to be included in Bid Item No. 1.
- Q24. Is the contractor responsible for obtaining any permits?**
- R24. Yes, see R17 for additional info.
- Q25. Will the engineer consider boring east and west from the median between the north and southbound lanes of I-75? 530’ is a long way to jack and bore 36” casing from one direction.**
- R25. The proposed force main shall be constructed by means of jack and bore. Alternate construction methodologies will not be considered at this time.
- Q26. Interstate 75 has been under construction in this area for over 2 years with modifications to the lanes of traffic and ditch and drainage (elevations both in the median and shoulders). Does the current set of drawings reflected those changes/new condition and as built elevations as it exist today?**
- R26. The Survey was completed in 2019, which included I-75 as well as the immediate project area.

- Q27.** The project is specified to be completed by Jack and Bore per FDOT specification 556 and standard county requirements. Although there is are no geotechnical bore holes in the documents to rely on, it is likely that the excavated soils for this project will be loose sand and silt, below the water table. Based on these conditions and the length of drive, a jack and bore operation is not acceptable for this installation. We strongly recommend the project casing installation be specified microtunneling. Microtunneling provides the necessary earth pressure and hydrostatic balance (without dewatering) including laser guided accuracy to complete this tunnel.
- R27. See attached, Bid Attachment 4 - Geotechnical Report. Alternate construction methodologies will not be considered at this time.
- Q28.** Summary of verified utilities sheet located in addendum 1, sheet no. SUE-02 has a note for Test Hole TH01 that states “No visual of utility due to saturated soil”. Can you please confirm what is meant by saturated soil? Is the utility being investigated below the ground water table?
- R28. The force main is above the groundwater table and approximately 7’-8’ below the surface.
- Q29.** Section 02325, Part 1.02, subparagraph E of the specifications require the contractor to perform all necessary soil test boring. The timing, permitting, etc. to perform this before the bid date is not possible.
- R29. The County will hire Geotech for soil density and material testing during construction.
- Q30.** Plan and Profile sheet sheets No. 4 and 5 indicate there are at least 3 soil bore holes, in addition to addendum 1, Topographic Survey, sheet 2 of 2. Please provide these soil bore holes for review.
- R30. See attached, Bid Attachment 4 - Geotechnical Report.
- Q31.** Section 02345, Part 3, subparagraph D requires the contractor to leave all sheeting in place. Is it a requirement that the shaft be constructed via driven sheet pile? If so, is it a requirement to cut the sheeting 3 feet below grade and leave the remaining in place? If the shaft can be constructed via other means, what are the requirements?
- R31. It is not a requirement that the shaft be constructed via driven sheet pile.

Q32. Overhead power lines are located at the corner of Lena Rd and 41st Ave E that will interfere with the necessary work plans. Has the Country communicated with the owner of these lines? Will they be de energized or removed?

R32. The intent is to leave the lines energized. The contractor can request FPL to hold and stabilize the pole if necessary.

NOTE:

Items that are ~~struck through~~ are deleted. Items that are underlined have been added or changed. All other terms and conditions remain as stated in the IFBC.

INSTRUCTIONS:

Receipt of this addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the response being deemed non-responsive.

END OF ADDENDUM

AUTHORIZED FOR RELEASE



REPORT OF GEOTECHNICAL EXPLORATION

I-75 & SR-70 FORCE MAIN REPLACEMENT MANATEE COUNTY, FLORIDA

AREHNA PROJECT NO. B-19-017.05 Rev1

April 1, 2019

Revised Report: March 5, 2020

Prepared For:

Ayres & Associates, Inc.

8875 Hidden River Parkway, Suite 200

Tampa, FL 33637-1038

Prepared By:

AREHNA Engineering, Inc.

5012 West Lemon Street

Tampa, Florida 33609

April 1, 2019
Revised Report: March 5, 2020

Mr. Christopher Martin, P.E.
Ayres & Associates, Inc.
8875 Hidden River Parkway, Suite 200
Tampa, FL 33637-1038

MartinC@AyresAssociates.com

Subject: **Report of Geotechnical Exploration**
I-75 & SR-70 Force Main Replacement
Manatee County, Florida
Manatee County Project No. WW01710
AREHNA Project No. B-19-017.05 Rev1

Dear Mr. Martin,

AREHNA Engineering, Inc. (AREHNA) is pleased to submit this report of our geotechnical exploration for the proposed project. Services were conducted in general accordance with AREHNA Proposal B-18-159 dated December 28, 2018 and Proposal B.Prop-19-164.Rev dated December 6, 2019. The purpose of our geotechnical study was to obtain information on the general subsurface conditions for the proposed installation of approximately 670 linear feet of 16-inch diameter force main.

This report presents our understanding of the project, outlines our exploratory procedures, and documents the field data obtained.

AREHNA appreciates the opportunity to have assisted Ayres & Associates, Inc. on this project. Should you have any questions with regards to this report, or if we can be of any further assistance, please contact this office.

Best Regards,

AREHNA ENGINEERING, INC.

FLORIDA BOARD OF PROFESSIONAL ENGINEERS CERTIFICATE OF AUTHORIZATION No. 28410

This item has been digitally signed and sealed by:

Kristina LaCava, P.E.
Geotechnical Engineer
Florida Registration 77594

on the date adjacent to the seal.
Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.





Annabella C. Hullen, E.I.
Staff Geotechnical Engineer

Distribution: 1 – Electronic Submittal
1 – File

TABLE OF CONTENTS

| | <u>Page</u> |
|---|-------------|
| 1.0 PROJECT INFORMATION AND SCOPE OF WORK | 1 |
| 1.1 Site Description and Project Characteristics..... | 1 |
| 1.2 Scope of Work..... | 1 |
| 2.0 FIELD EXPLORATION AND LABORATORY TESTING | 2 |
| 2.1 Field Exploration..... | 2 |
| 2.2 Laboratory Testing..... | 2 |
| 3.0 SUBSURFACE CONDITIONS | 3 |
| 3.1 USGS Topographic Data..... | 3 |
| 3.2 USDA Natural Resources Conservation Service Data | 3 |
| 3.3 Subsurface Conditions | 3 |
| 3.4 Groundwater Conditions..... | 4 |
| 3.5 Estimated Seasonal High Groundwater Level..... | 4 |
| 4.0 GENERAL SITE PREPARATION | 5 |
| 4.1 General | 5 |
| 4.2 On-Site Soil Suitability | 5 |
| 4.3 Horizontal Directional Drilling | 5 |
| 4.4 Excavation and Backfill..... | 6 |
| 4.5 Dewatering | 7 |
| 4.6 Pipeline Bedding | 7 |
| 4.7 General Construction Monitoring and Testing Guidelines..... | 7 |
| 5.0 BASIS FOR RECOMMENDATIONS | 8 |

LIST OF APPENDICES

APPENDIX

- Project Site Location Map – Figure 1
- Field Exploration Location Plan – Figure 2
- USGS Topographic Survey – Figure 3
- USDA Soil Survey - Figure 4
- Soil Profiles – Figure 5
- Summary of Laboratory Test Results – Table 1
- Summary of Soil Parameters – Table 2
- Field and Laboratory Procedures



1.0 PROJECT INFORMATION AND SCOPE OF WORK

1.1 SITE DESCRIPTION AND PROJECT CHARACTERISTICS

The project consists of the installation of approximately 670 linear feet of 16-inch diameter force main downstream of the Master Lift Station (MLS) 39-A (RTU 428), under I-75, where a hydraulic bottleneck exists. The project site is located at I-75 and 41st Avenue E/Lena Road in Bradenton, Florida; as indicated on the **Project Location Map, Figure 1** in the **Appendix**. The project will use horizontal directional drilling (HDD) installation methods.

1.2 SCOPE OF WORK

The purpose of our geotechnical study was to obtain information on the general subsurface conditions at the proposed project site. The subsurface materials encountered were evaluated with respect to the available project characteristics. The following services were performed:

- Requested utility location services from Sunshine811.
- Performed three Standard Penetration Test (SPT) borings to depths 30 feet. Samples were collected, and Standard Penetration Test resistances were measured at approximate intervals of two feet for the top ten feet, and five feet thereafter. The upper four feet were manually augered to avoid any possible conflicts with buried utilities.
- Visually classified and stratified the soil samples in the laboratory using the Unified Soil Classification System.
- Reported the results of the field exploration and engineering analysis. The results of the subsurface exploration are presented in this report signed and sealed by a professional engineer specializing in geotechnical engineering.



2.0 FIELD EXPLORATION AND LABORATORY TESTING

2.1 FIELD EXPLORATION

Based on email communication dated November 11, 2019 the SPT borings needed to be extended to a minimum of 30 feet. Our original scope included performing three Standard Penetration Test (SPT) borings extending to depths of approximately 15 feet.

The SPT borings were performed with the use of a Power Drill Rig using Bentonite "Mud" drilling procedures. Samples were collected and Standard Penetration Test resistances were measured at approximate intervals of two feet for the top ten feet and at approximate intervals of five feet thereafter. The soil sampling was performed in general accordance with ASTM Test Designation D-1586, entitled "Penetration Test and Split-Barrel Sampling of Soils."

Representative portions of these soil samples were sealed in glass jars, labeled and transferred to AREHNA's Tampa office for appropriate classification by a Geotechnical Engineer.

The SPT boring locations are indicated on the **Field Exploration Location Plans, Figure 2** in the **Appendix** of this report. The SPT borings were located in the field by measuring off of existing features and GPS Coordinates.

2.2 LABORATORY TESTING

The laboratory testing program consisted of natural moisture content, percent fines, and Atterberg limits performed on representative samples. The results are presented in **Table 1** in the **Appendix**.



3.0 SUBSURFACE CONDITIONS

3.1 USGS TOPOGRAPHIC DATA

The topographic survey map published by the United States Geological Survey and the existing survey information of the site was reviewed for ground surface features at the proposed project location (**Figure 3**). Based on this review, natural ground surface elevations at the project site range between approximately +25 to +30 feet.

3.2 USDA NATURAL RESOURCES CONSERVATION SERVICE DATA

The United States Department of Agriculture (USDA) Natural Resources Conservation Service (NRCS) survey for Manatee County indicates that the soils at the project site consist of the following soil units:

| Soil Unit Number | Soil Name | Depth to High Water Table (feet) |
|------------------|---|----------------------------------|
| 20 | EauGallie fine sand, 0 to 2 percent slopes | 0.5 – 1.5 |
| 26 | Floridana – Immokalee – Okeelanta association | +2 – 0 |

The soil survey also indicates that the average annual precipitation is 42 to 58 inches. The soils encountered in our SPT borings are generally consistent with the soil units listed above. The USDA Soil Survey map for the project site is attached as **Figure 4** in the **Appendix**.

3.3 SUBSURFACE CONDITIONS

The Boring Profiles on **Figure 5** in the **Appendix** should be consulted for a detailed description of the subsurface conditions encountered at each boring location. When reviewing the boring records and the subsurface profiles, it should be understood that soil conditions may vary between and away from boring locations.

The SPT borings generally encountered very loose to dense fine sands (SP, SP-SM, SM, SC) from the existing ground surface to the termination depths of 30 feet. Boring B-02 encountered stiff sandy clay (CL) from 13 feet a depth of 15 feet. Trace shell, limerock and phosphate fragments were occasionally encountered in the SPT borings. Standard Penetration Test resistances (N-Values) ranged between 1 and 34 blows per foot for the sandy soils and an N-value of 11 blows per foot was recorded for the clay soil in boring B-02.



3.4 GROUNDWATER CONDITIONS

The groundwater level was encountered in the SPT borings at depths between 3.5 to 5 feet. Fluctuation in ground water levels should be expected due to seasonal climatic changes, tidal changes, construction activity, rainfall variations, surface water runoff, and other site-specific factors. Since ground water level variations are anticipated, design drawings and specifications should accommodate such possibilities and construction planning should be based on the assumption that variations will occur.

3.5 ESTIMATED SEASONAL HIGH GROUNDWATER LEVEL

Based on the mapping performed by the USDA, soils information obtained from the site and our experience in the area, we estimate that the seasonal high groundwater level will be encountered at an approximate depth of 1.5 feet below the existing ground surface.



4.0 GENERAL SITE PREPARATION

4.1 GENERAL

Site preparation includes stripping, excavation, backfilling, and compaction.

The HDD installation operation is the responsibility of the specialty contractor (i.e. the selection of HDD equipment and operation procedures are the choices of the specialty contractor). We have provided generic guidelines for HDD operation below. Our generic installation recommendations have been based on the site conditions encountered during our geotechnical investigation. AREHNA should be notified if the site conditions are different than stated in this report, so we may modify or amend our recommendations.

Soil parameters for each soil layer encountered in each SPT boring performed are shown on **Table 2** in the **Appendix**. These soil parameters should be used in the HDD design.

4.2 ON-SITE SOIL SUITABILITY

The borings indicate that sandy soils classified as SP-SM based on the Unified Soil Classification System are present at the site to depths of up to 13 feet and are suitable for use as backfill material. The clay (CL) soils encountered at a depth of 13 to 15 feet in boring B-02 are not suitable for use as backfill.

Suitable structural fill materials should consist of fine to medium sand with less than 12 percent passing the No. 200 sieve and be free of rubble, organics, clay, debris, and other unsuitable material. Any off-site materials used as fill should be approved by AREHNA prior to acquisition.

4.3 HORIZONTAL DIRECTIONAL DRILLING

Based on the SPT borings performed, the subsurface materials generally consist of very loose to dense fine sands (SP, SP-SM, SM, SC). Stiff sandy clay (CL) was also encountered at a depth of 13 feet in boring B-02. The encountered sandy soils have a potential for caving. Soil parameters for use in the HDD design software are presented on **Table 1** in the **Appendix**.

Drilling Fluid - Drilling fluid should be used during drilling and back-reaming operations. Due to the sandy soils encountered during our investigation it is recommended that the drilling fluid be composed of clean water and bentonite. Other appropriate additives should be added at the discretion of the specialty contractor. The drilling fluid should be mixed thoroughly and be absent of any clumps or clods. Further, the drilling fluid should not be recycled and should be hauled off the site.

Heaving Potential - The soils encountered in our investigation have a low heaving potential. However, heaving may occur when attempting to back-ream too large of a hole. To minimize heaving, reaming process should be completed leaving the bored hole at full design diameter during pullback. The pullback barrel reamer should be no larger than the design bored diameter. The pullback rate should minimize



overcutting of the borehole so that excessive voids are reduced and post installation settlement may be minimized.

Monitoring – The drilling and installation operations should be monitored continuously by experienced personnel trained in all aspects of directional drilling process. These procedures include accurate monitoring and control system to track the progress and exact location of the drilling head at all times. The drilling operator should maintain record on drilling fluid pumping rates, pressures, viscosity and density, etc. throughout the entire course of drilling activities.

Horizontal and vertical adjustments should be made throughout the procedure so that the drilling profile matches the planned profile. The specific weight of the drilling fluid should be adjusted throughout the process to maintain hydrological stability. Jetting pressures should be limited to avoid drilling fluid release during drilling. However, should release of drilling fluid in the project area occur, operations should stop immediately and measures should be taken to contain release. Generic measures may include the following:

- If release is detected, the drilling crew should take immediate corrective action to contain the release and to prevent migration offsite.
- Pits and/or berms should be constructed around the borehole entry point to contain drilling fluid and return.
- Containment equipment, including earth moving equipment, portable pumps, hand tools, sandbags, hay bales, silt fencing, lumber, and vacuum trucks, should be stored and readily available at the drilling site.
- Any drilling seepage should be removed using a vacuum truck and then transported to an approved disposal site.

4.4 EXCAVATION AND BACKFILL

Excavations, whether they be utility trenches, basement excavations, or footing excavations, should be constructed in accordance with the new OSHA guidelines. The contractor is solely responsible for designing and constructing stable, temporary excavations and should shore, slope, or bench the sides of the excavations as required to maintain stability of both the excavation sides and bottom. The contractor's responsible person, as defined in 29 CFR, Part 1926, should evaluate the soil exposed in the excavations as part of the contractor's safety procedures. In no case should slope height, slope inclination, or excavation depth, including utility trench excavation depth, exceed those specified in all local, state, and federal safety-regulations.

The soils encountered are consistent with AASHTO Class C soils and will not stand vertically in an open excavation below the ground water level. Soil should not be stockpiled adjacent to excavations unless the stockpile has been included in the analyses of the excavation stability.

Excavations below the groundwater level will likely require a combination of sanded wellpoints and pumping from filtered sumps.



Any and all excavations should be backfilled with compacted fill. Fill should generally consist of dry fine sand with less than 12 percent passing the No. 200 sieve and be free of rubble, organics, clay, debris and other unsuitable material. Fill should be tested and approved prior to acquisition. Approved sand fill should be placed in loose lifts not exceeding 12 inches in thickness and should be compacted to a minimum of 95 percent of the Modified Proctor maximum dry density (ASTM D-1557). Prior to beginning compaction, soil moisture contents should be adjusted in order to facilitate proper compaction. A moisture content within 2 percentage points of the optimum indicated by the Modified Proctor Test (ASTM D-1557) is recommended prior to compaction of the fill.

4.5 DEWATERING

Construction activities should be accomplished in the “dry” with ground water levels maintained at least 1 foot below the deepest portion of any excavation. The groundwater level was encountered at depths between 3.5 and 5 feet in the SPT borings performed. Therefore, depending on the time of year construction is performed, dewatering may be required for excavations deeper than 3 feet. Dewatering can be accomplished using a sanded wellpoint system supplemented by a gravel bottom layer and pumping from a sump. Actual dewatering means and methods should be the responsibility of the contractor.

Groundwater fluctuations will likely occur due to seasonal variations, runoff, and other factors and should be considered when planning earthwork activities. The impact of runoff from adjacent properties, nearby water bodies, and other site-specific conditions which may affect groundwater recharge are beyond the scope of this exploration and should be considered when planning and designing a dewatering system.

4.6 PIPELINE BEDDING

We recommend the pipeline be supported on a bedding layer consisting of at least 6 inches of granular soils meeting the previous requirements for structural fill. Any utilities 3 feet or greater in diameter should be supported on at least 12 inches of structural fill/granular soils. The bedding layer should be compacted to at least 95 percent of the Modified Proctor maximum dry density (ASTM D-1557).

4.7 GENERAL CONSTRUCTION MONITORING AND TESTING GUIDELINES

Prior to initiating compaction operations, we recommend that representative samples of the structural fill material to be used and acceptable exposed in-place soils be collected and tested to determine their compaction and classification characteristics. The maximum dry density, optimum moisture content, gradation and plasticity characteristics should be determined. These tests are needed for compaction quality control of the structural fill and existing soils and to determine if the fill material is acceptable.

A representative number of in-place field density testes should be performed in the compacted existing soils and in each lift of structural fill or backfill to confirm that the required degree of compaction has been obtained. We recommend that at least one density test be performed for every lift of backfill and for every 100 lineal feet of trench.



5.0 BASIS FOR RECOMMENDATIONS

The analysis and recommendations submitted in this report are based upon the data obtained from the soil borings performed at the location indicated. Regardless of the thoroughness of a geotechnical exploration, there is always a possibility that conditions across site will be different from those encountered where the boring was drilled, and that conditions will not be as anticipated by the designers or contractors. In addition, the construction process itself may alter soil conditions. AREHNA is not responsible for the conclusions, opinions or recommendations made by others based on the data presented in this report.



APPENDIX


Project Site Location Map – Figure 1
Field Exploration Location Plan – Figure 2
USGS Topographic Survey – Figure 3
USDA Soil Survey - Figure 4
Soil Profiles – Figure 5
Summary of Laboratory Test Results – Table 1
Summary of Soil Parameters – Table 2
Field and Laboratory Procedures



PROJECT SITE LOCATION MAP



FIELD EXPLORATION LOCATION PLAN



LEGEND

B-X Approximate Location of SPT Boring

| REVISIONS | | | APPROVED | PREPARED BY: | NAME DATE | | | PROJECT NAME | PROJECT NO. | FIGURE NO. |
|-----------|------|--------------|----------|---|----------------|-----------|-------------|--|--------------|------------|
| NO. | DATE | DESCRIPTIONS | | | DESIGNED BY: | DRAWN BY: | CHECKED BY: | | | |
| | | | | AREHNA Engineering, Inc. 5012 West Lemon Street, Tampa, FL 33609 Phone 813.944.3464 Fax 813.944.4959 Certificate of Authorization No. 28410 | | | | MANATEE COUNTY POTABLE WATER I-75 and S.R. 70 BRADENTON, FLORIDA | B-19-017.005 | 2 |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |

USGS TOPOGRAPHIC SURVEY



USDA SOIL SURVEY




SOIL MAPPING UNITS


- 20—EauGallie fine sand, 0 to 2 percent slopes
- 26—Floridana-Immokalee-Okeelanta association

| | | | | |
|--|----------------|---|---------------------|----------------|
|  AREHNA Engineering, Inc. <small>5012 West Lemon Street, Tampa, FL 33609 Phone 813.944.3464 Fax 813.944.4959 Certificate of Authorization No. 28410</small> | DATE | PROJECT NAME | PROJECT NO. | FIG NO. |
| | 03/2019 | MANATEE COUNTY POTABLE WATER I-75 and S.R. 70 BRADENTON, FLORIDA | B-19-017.005 | 4 |


SOIL PROFILES



Latitude: 27.4636134
Longitude: -82.4600517




Latitude: 27.4636315
Longitude: -82.4593054



Latitude: 27.4637371
Longitude: -82.4585873

LEGEND



- SP UNIFIED SOIL CLASSIFICATION SYSTEM (ASTM D 2488) GROUP SYMBOL AS DETERMINED BY VISUAL REVIEW AND/OR LABORATORY TESTING
- ▽ GROUNDWATER TABLE AT THE TIME OF DRILLING
- N SPT N-VALUE IN BLOWS/FOOT FOR 12 INCHES OF PENETRATION UTILIZING AUTOMATIC HAMMER (UNLESS OTHERWISE NOTED)
- HA HAND AUGERED TO AVOID UTILITY CONFLICTS AND SAFETY REASONS
- 200 FINES PASSING THE #200 STANDARD SIEVE (%)
- NMC NATURAL MOISTURE CONTENT (%)
- LL LIQUID LIMIT (%)
- PI PLASTICITY INDEX (%)
- PL PLASTICITY LIMITS (%)
- NP NON PLASTIC

Soil Profile Notes:

1. The profiles depicted are of a generalized nature to highlight the major subsurface stratification features and material characteristics. The soil profiles include soil description, stratifications and penetration resistances. The stratifications shown on the boring profiles represent the conditions only at the actual boring location. Variations may occur and should be expected between boring locations. The stratifications represent the approximate boundary between subsurface materials and the actual transition may be gradual.
2. Groundwater levels generally fluctuate during periods of prolonged drought and extended rainfall and may be affected by man-made influences. In addition, a seasonal effect will also occur in which higher groundwater levels or temporary perched conditions are normally recorded in rainy seasons.
3. The Boring Locations Presented are Approximate and Based on Hand Held GPS with an Accuracy of +/- 10 Feet.

| | SAFETY HAMMER | AUTOMATIC HAMMER |
|--|---|---|
| GRANULAR MATERIALS- RELATIVE DENSITY | SPT N-VALUE (BLOWS/FT.) | SPT N-VALUE (BLOWS/FT.) |
| VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE | LESS THAN 4 4 to 10 10 to 30 30 to 50 GREATER THAN 50 | LESS THAN 3 3 to 8 8 to 24 24 to 40 GREATER THAN 40 |
| SILTS AND CLAYS CONSISTENCY | SPT N-VALUE (BLOWS/FT.) | SPT N-VALUE (BLOWS/FT.) |
| VERY SOFT SOFT FIRM STIFF VERY STIFF HARD | LESS THAN 2 2 to 4 4 to 8 8 to 15 16 to 30 GREATER THAN 30 | LESS THAN 1 1 to 3 3 to 6 6 to 12 12 to 24 GREATER THAN 24 |
| LIMESTONE CONSISTENCY | SPT N-VALUE (BLOWS/FT.) | SPT N-VALUE (BLOWS/FT.) |
| SOFT MEDIUM HARD VERY HARD | LESS THAN 20 20 to 50 51 to 50/3" GREATER THAN 50/3" | LESS THAN 17 17 to 41 42 to 50/6" GREATER THAN 50/6" |

| REVISIONS | | | PREPARED BY: | NAME DATE | | | BORING PROFILE | PROJECT NO. | FIGURE NO. | |
|-----------|------|--------------|--------------|--|--|--|---|--|--------------|---|
| NO. | DATE | DESCRIPTIONS | APPROVED | | | | | | | |
| | | | | AREHNA Engineering, Inc. 5012 West Lemon Street, Tampa, FL 33609 Phone 813.944.3464 Fax 813.944.4959 Certificate of Authorization No. 28410 | | | DESIGNED BY: BRH 03/2019 DRAWN BY: BRH 03/2019 CHECKED BY: AC 03/2019 SUPERVISED BY: Kristina LaCava, P.E. | MANATEE COUNTY POTABLE WATER I-75 and S.R. 70 BRADENTON, FLORIDA | B-19-017.005 | 5 |

TABLE 1
SUMMARY OF LABORATORY TEST RESULTS
 I-75 & SR-70 Force Main Replacement
 Manatee County, Florida
 AREHNA Project No. B-19-017-.005 Rev1

| Boring No. | Sample Depth (feet) | #200 | Atterberg Limits (%) | | | Natural Moisture Content (%) |
|------------|---------------------|------|----------------------|----|------------------|------------------------------|
| | | | LL | PL | Plasticity Index | |
| B-01 | 28.5 - 30.0 | 31 | NP | NP | NP | 35 |
| B-02 | 23.5 - 25.0 | 21 | 41 | 18 | 23 | 37 |

TABLE 2
SUMMARY OF SOIL SOIL PARAMETERS
I-75 & SR-7 Force Main Replacement
Manatee County, Florida
AREHNA Project B-19-017.005 Rev1

| BORING NUMBER | DEPTH (FEET) | SPT "N" AVERAGE | SOIL CLASSIFICATION | APPROXIMATE SOIL UNIT WEIGHT (PCF) | | COHESION (PSF) | SOIL ANGLE OF FRICTION (DEGREES) | EARTH PRESSURE COEFFICIENT | | SHEAR MODULUS G (ksi) |
|---------------|--------------|-----------------|---------------------|------------------------------------|--------------|----------------|----------------------------------|----------------------------|------|-----------------------|
| | | | | γ SAT | γ SUB | | | Ka | Kp | |
| B-01 | 0 - 15 | 4 | SP-SM | 100 | 37.6 | - | 29 | 0.35 | 2.86 | 0.25 |
| | 15 - 30 | 26 | SP, SP-SM | 115 | 52.6 | - | 33 | 0.29 | 3.42 | 0.92 |
| B-02 | 0 - 13 | 4 | SP-SM | 100 | 37.6 | - | 29 | 0.35 | 2.86 | 0.27 |
| | 13 - 15 | 11 | CL | 115 | 52.6 | 1375 | - | 1.00 | 1.00 | 1.78 |
| | 15 - 30 | 13 | SP, SM | 105 | 42.6 | - | 31 | 0.33 | 3.07 | 0.46 |
| B-03 | 0 - 15 | 3 | SP-SM | 100 | 37.6 | - | 28.6 | 0.35 | 2.84 | 0.19 |
| | 15 - 30 | 15 | SP, SC | 105 | 42.6 | - | 31 | 0.32 | 3.12 | 0.53 |

FIELD PROCEDURES

Standard Penetration Test (SPT) Borings

The SPT borings are performed in general accordance with ASTM D-1586, "Penetration Test and Split-Barrel Sampling of Soils." A rotary drilling process is used and bentonite drilling fluid is circulated in the boreholes to stabilize the sides and flush the cuttings. At regular intervals, the drilling tools are removed and soil samples are obtained with a standard 2-foot long, 2-inch diameter split-tube sampler. The sampler is first seated 6 inches and then driven an additional foot with blows of a 140-pound hammer falling under its own weight a distance of 30 inches. The number of hammer blows required to drive the sampler the final foot is designated the "Penetration Resistance." The penetration resistance, when properly interpreted, is an index to the soil strength and density.



LABORATORY PROCEDURES

Water Content

The water content is the ratio, expressed as a percentage, of the weight of water in a given mass of soil to the weight of the solid particles. This test is conducted in general accordance with FM 1-T265.

Percent Organics (Organic Loss on Ignition)

The amount of organic material in a sample is determined in this test. The sample is first dried and weighed, then ignited and reweighed. The amount of organic material is expressed as a percentage of the total dry weight of the sample prior to ignition. This test is conducted in general accordance with FM 1-T267.

Atterberg Limits (Plasticity)

A soil's Plasticity Index (PI) is the numerical difference between the Liquid Limit (LL) and the Plastic limit (PL). The LL is the moisture content at which the soil will flow as a heavy viscous fluid and is determined in general accordance with ASTM D-4318. The PL is the moisture content at which the soil begins to crumble when rolled into a small thread and is also determined in general accordance with FM 1-T 90.

Fines Content

In this test, the sample is dried and then washed over a No. 200 mesh sieve. The percentage of soil by weight passing the sieve is the percentage of fines or portion of the sample in the silt and clay size range. This test is conducted in general accordance with ASTM D-1140.

