KEYED NOTES

- 1 INSTALL NEW FIXTURES IN CANOPY. INSTALL NEW CONDUIT AND JUNCTION BOXES ABOVE BOTTOM OF BEAM. PROVIDE WATER—TIGHT SURFACE MOUNT OUTLET BOX TO MAINTAIN WET LOCATION LISTING FOR NEW FIXTURE.
- 2 INSTALL NEW FIXTURES. EXTEND EXISTING CIRCUITING TO NEW FIXTURES. TYPICAL.
- $\boxed{3}$ install new fixtures in hard ceiling. Extend existing circuiting to new fixtures. Typical.
- 4 EXTEND EXISTING CIRCUIT TO NEW FIXTURE LOCATION.
- 5 EXTEND NEW CIRCUIT TO LIGHTING CONTROLS CABINET IN ROOM 1048 VIA IN-GROUND JUNCTION BOX. SEE KEYED NOTES #6, 7, 8, AND 9.
- $\overline{\binom{6}{6}}$ IN-GROUND JUNCTION BOX FOR EXTERIOR LIGHTING CIRCUITS.
- 7 EXTERIOR LIGHTING WALL PENETRATION. SEE DETAIL #2, SHEET E-5.0. COORDINATE WITH ARCHITECTURAL ELEVATIONS.
- $\sqrt{8}$ (2) 1-1/4" CONDUITS TO LIGHTING CONTROLS CABINET IN ROOM 1048.
- 9 EXTERIOR GFCI RECEPACLE WITH WEATHER-PROOF WHILE IN USE COVER. FLUSH MOUNT IN PERGOLA COLUMN.
- LIGHTED KIOSK BY OTHERS. REFER TO HARDSCAPE DRAWINGS. MAKE FINAL ELECTRICAL CONNECTIONS.

LEGEND

- ETR EXISTING TO REMAIN REM REMOVE EXISTING DEVICE
- REP REPLACE EXISTING DEVICE WITH NEW DEVICE.
 MAINTAIN EXISTING CIRCUIT.
- REL REMOVE EXISTING DEVICE. INSTALL NEW FIXTURE IN NEW LOCATION.
- NEW NEW DEVICE IN EXSITING LOCATION
- (72) CONFERENCE CENTER LIGHTING CONTROL CIRCUIT NUMBER.

JE AR(

JOB NO 1019DATE Apr. 8, 201
DRAWN PJF
CHECKED PJF
REVISIONS
ISSUED FOR BID
April 19, 2011
ELECTRICAL BID SET
July 6, 2011