

# MANATEE COUNTY GOVERNMENT

## INTENT TO AWARD

<b>IFB NO. / TITLE</b>	24-TA004973SAM / SR 70 / 15 <sup>th</sup> ST. E. Water Main Relocation	<b>DATE POSTED</b>	MC _____	DS _____
<b>PROCUREMENT REPRESENTATIVE</b>	Sherri Meier	<b>PROJECTED AWARD DATE</b>	January 23, 2023	
<b>DEPARTMENT/DIVISION</b>	Public Works Department	<b>AUTHORIZED BY DATE</b>	Jacob Erickson, MBA, CPPO, NIGP-CPP <small>Digitally signed by Jacob Erickson, MBA, CPPO, NIGP-CPP Date: 2024.01.03 08:18:13 -05'00'</small> Jacob Erickson, Purchasing Official	

**NOTICE OF INTENT TO AWARD**

The Manatee County Procurement Division provides notice of its intent to award a contract with Woodruff and Sons, Inc. for the provision of SR 70 / 15<sup>th</sup> ST. E. Water Main Relocation.

**ENABLING/REGULATING AUTHORITY**

Manatee County Procurement Ordinance, Sec 2-26.

**BACKGROUND/EVALUATION**

SR 70 (15th St E) water main relocation is associated with FDOT project 447380-1 drainage and roadway improvements. The project includes construction of 230 linear feet of 24-inch class 250 DIP water main via open-cut and removal of 220 linear feet of existing 24-inch water main. Also included is connecting to the existing water main and concrete sidewalk and driveway restoration.

The solicitation was advertised on November 1, 2023 on the Manatee County website and DemandStar. It was also provided to the Manatee County Chamber of Commerce, the Manasota Black Chamber of Commerce, Gulf Coast Builders Exchange and Gulf Coast Latin Chamber of Commerce for release to their members and in the Bradenton Herald and Tempo News newspapers. Responses were received from the following firms:

1. EZ Contracting, LLC, Winter Haven, FL
2. Woodruff and Sons, Inc., Bradenton, FL

The following firms were deemed non-responsive/non-responsible: EZ Contracting, LLC.

**EVALUATION SUMMARY:**

Woodruff & Sons, Inc. was the lowest responsible, responsive bidder(s). A bid tabulation of the results is attached to this Notice of Intent to Award.

**RECOMMENDATION**

The Procurement Division and the Public Works Department recommend award to Woodruff & Sons, Inc.

<b>ATTACHMENTS</b> (List in order of attached)	Bid Tabulation	<b>COST</b>	\$578,352.98
---	----------------	-------------	--------------

<b>BID TABULATION &amp; SUMMARY</b>			<b>WOODRUFF &amp; SONS, INC.</b>
<b>IFBC NO. 24-TA004973SAM</b>			
<b>PROJECT NAME: SR 70 / 15TH ST E WATER MAIN RELOCATION</b>			
<b>ITEM</b>	<b>DESCRIPTION</b>	<b>QTY</b>	<b>AMOUNT</b>
1	Bid A Based on 160 Calendar Days Construction	1	\$578,352.98
2	Bid B Based on 130 Calendar Days Construction	1	No Bid

\* EZ Contracting, Inc. was found non-responsirve, non-responsible.

<b>BID TABULATION &amp; SUMMARY</b> <b>IFBC NO. 24-TA004973SAM</b> <b>PROJECT NAME: SR 70 / 15TH ST E WATER MAIN RELOCATION</b>				<b>WOODRUFF &amp; SONS, INC.</b>	
<b>ITEM</b>	<b>DESCRIPTION</b>	<b>QTY</b>	<b>U/M</b>	<b>UNIT PRICE</b>	<b>AMOUNT</b>
<b>I. GENERAL</b>					
1	Mobilization	1	LS	\$ 53,938.08	\$53,938.08
2	Erosion and Sediment Control	1	LS	\$ 661.57	\$661.57
3	Maintenance of Traffic	1	LS	\$ 32,085.16	\$32,085.16
4	Record Drawings	1	LS	\$ 3,817.01	\$3,817.01
5	Temporary Shut-Down Coordination (Night Work)*	1	LS	\$ 4,222.82	\$4,222.82
6	Pipeline Testing	1	LS	\$ 22,934.72	\$22,934.72
				<b>SUBTOTAL</b>	<b>\$117,659.36</b>
<b>II. PROPOSED IMPROVEMENTS</b>					
7	24" Class 250 DIP Water Main	230	LF	\$ 486.38	\$111,867.40
8	Utility Pipe, Remove & Dispose, 20-49"	220	LF	\$ 128.65	\$28,303.00
9	24" DI Fitting - 45 Deg. Bend, MJ	4	EA	\$ 4,260.33	\$17,041.32
10	Sanitary Manhole Adjustment	8	EA	\$ 6,630.84	\$53,046.72
11	Valve Box Adjustment	12	EA	\$ 3,964.86	\$47,578.32
12	Water Meter Box Adjustment	2	EA	\$ 2,604.01	\$5,208.02
13	Cut and Connect to Ex. 24" Water Main (Including	2	EA	\$ 49,910.40	\$99,820.80
14	Concrete Driveway Replacement	75	SY	\$ 241.36	\$18,102.00
15	Concrete Sidewalk Replacement	100	SY	\$ 183.06	\$18,306.00
16	Sodding	750	SY	\$ 11.79	\$8,842.50
				<b>SUBTOTAL</b>	<b>\$408,116.08</b>
				<b>SUBTOTAL WITHOUT CONTINGENCY</b>	<b>\$525,775.44</b>
17	Contract Contingency (10%) County Authorized Use Only	1	LS		\$52,577.54
				<b>SUBTOTAL</b>	<b>\$578,352.98</b>
				<b>BID A 160 CALENDAR DAYS CONSTRUCTION TOTAL</b>	<b>\$578,352.98</b>

<b>BID TABULATION &amp; SUMMARY</b> <b>IFBC NO. 24-TA004973SAM</b> <b>PROJECT NAME: SR 70 / 15TH ST E WATER MAIN RELOCATION</b>				<b>WOODRUFF &amp; SONS, INC.</b>	
<b>ITEM</b>	<b>DESCRIPTION</b>	<b>QTY</b>	<b>U/M</b>	<b>UNIT PRICE</b>	<b>AMOUNT</b>
<b>I. GENERAL</b>					
1	Mobilization	1	LS		NO BID
2	Erosion and Sediment Control	1	LS		NO BID
3	Maintenance of Traffic	1	LS		NO BID
4	Record Drawings	1	LS		NO BID
5	Temporary Shut-Down Coordination (Night Work)*	1	LS		NO BID
6	Pipeline Testing	1	LS		NO BID
<b>SUBTOTAL</b>					<b>NO BID</b>
<b>II. PROPOSED IMPROVEMENTS</b>					
7	24" Class 250 DIP Water Main	230	LF		NO BID
8	Utility Pipe, Remove & Dispose, 20-49.9"	220	LF		NO BID
9	24" DI Fitting - 45 Deg. Bend, MJ	4	EA		NO BID
10	Sanitary Manhole Adjustment	8	EA		NO BID
11	Valve Box Adjustment	12	EA		NO BID
12	Water Meter Box Adjustment	2	EA		NO BID
13	Cut and Connect to Ex. 24" Water Main (Including Restraints)	2	EA		NO BID
14	Concrete Driveway Replacement	75	SY		NO BID
15	Concrete Sidewalk Replacement	100	SY		NO BID
16	Sodding	750	SY		NO BID
<b>SUBTOTAL</b>					<b>NO BID</b>
<b>SUBTOTAL WITHOUT CONTINGENCY</b>					
17	Contract Contingency (10%) County Authorized Use Only	1	LS		NO BID
<b>BID B 130 CALENDAR DAYS CONSTRUCTION TOTAL</b>					<b>NO BID</b>