



1112 Manatee Avenue West
Bradenton, FL 34205
purchasing@mymanatee.org

Solicitation Addendum

Addendum No.:	1
Solicitation No.:	21-TA003637DJ
Project No.:	6097270
Solicitation Title:	Cortez Gardens Subdivision Water Main Replacement
Addendum Date:	March 11, 2021
Procurement Contact:	Dave Janney Senior Procurement Agent

IFBC 21-TA003637DJ is amended as set forth herein. Responses to questions posed by prospective bidders are provided below. This addendum is hereby incorporated in and made a part of IFBC 21-TA003637DJ.

REPLACE:

SECTION B, BID FORMS, APPENDIX K, BID PRICING FORM

Replace Appendix K Bid Pricing Form, with the Revised Appendix K Bid Pricing Form hereby incorporated into the IFBC.

REPLACE:

SECTION C, BID ATTACHMENTS, BID ATTACHMENT 2, ENGINEERING STANDARD SPECIFICATIONS

Replace Bid Attachment 2, Engineering Standard Specifications, with the Revised Bid Attachment 2 hereby incorporated into the IFBC.

QUESTIONS AND RESPONSES:

Q1. To be consistent with the way Manatee County had bid these water main projects we are respectfully requesting the appropriate restoration pay items be added to the bid schedule.

These would include but not limited to the following:

- **SOD / SY**
- **Concrete Removal / SY**
- **Concrete Driveway / SY**
- **Full Base Replacement / SY**

- **Asphalt Replacement / SY**
- **Asphalt Mill and Overlay / SY**
- **Concrete Valley Crossing / EA**
- **Concrete Curb Replacement / LF**

Your consideration of this request and your help are greatly appreciated.

- R1. See Appendix K (Revised) and Bid Attachment 2 (Revised) issued with this Addendum 1 and available for download as a separate attachment.
- Q2. Will a plumber be required for any of the re-establish water service/relocated meter assemblies?**
- R2. Yes, the plumber will be required to re-establish the water service from the back on the house to the front of the house where the new meter location will be.
- Q3. Will any permits be required for the water service reconnections? If so, what is the cost of each?**
- R3. No permits are required for service connections. The Contractor is required to satisfy the FDEP permitting requirements for placing a potable water system into operation.
- Q4. Key sheet 04 shows to F&I 6" water main on 60th Street West. I do not see a plan & profile sheet for this scope of work.**
- R4. The County completed the 60th Street West water main improvements; no water main is proposed along 60th Street West. As-builts of the improvements are available.
- Q5. Key sheet 04 calls out to F&I 1" corporation stop (Typical along 61st west and F&I water service line & relocate water meter. There is not a plan & profile sheet for 61 St. West. Clarify please.**
- R5. The 61st St West improvements consist solely of the addition of service connections from an existing 4-inch watermain to the relocated meter assemblies from the rear property line. Construction shall proceed in accordance with Manatee County details UW-18 and UW-21; special plan and profiles are not included for these connections.
- Q6. Key sheet 04, states that the existing water meters to be removed and returned to Manatee county public works. Is the County supplying new water meters?**
- R6. Yes, Manatee County will be providing new water meters.
- Q7. Plan sheets 05-08 shows driveway replacement, curb & gutter restoration, milling & overlay and asphalt restoration limits. I see no pay items for concrete removal, concrete driveway & curb place back, milling, asphalt resurface or striping. Typical detail sheet 21 has a road connection detail. There is no information in regard to what milling depth is required, what thickness of asphalt and also what type of asphalt is required to place back. Please clarify.**

- R7. See Appendix K (Revised) and Bid Attachment 2 (Revised) issued with this Addendum 1 and available for download as a separate attachment. Refer to Typical Detail sheet No.13 UG-12, Asphaltic concrete structure course with prime coat shall be the same depth and type as existing or a minimum of 1-1/4 inch S-I, whichever is greater.
- Q8. Does the contractor need to hire a licensed plumber to reconnect the proposed relocated meters? We cannot go on private property or hook back up the proposed on the homeowner's side. Please clarify.**
- R8. Please see R2.
- Q9. Are there any permits that need to be obtained by the contractor? There is no pay item if so.**
- R9. Please see R3.
- Q10. Are there any backflow preventers required and if so, do they need to be added to the bid form?**
- R10. Yes, back flow preventers will be required and will be provided by Manatee County.
- Q11. In the IFB on page 57 of 284 under bid items 9 & 10 F&I water service connections, can you please confirm that you are requiring the contractor as part of the testing method for this scope of work to TELIVISE or pull a MANDRAL through a 1" poly pipe? Please clarify.**
- R11. Televis and/or pulling a mandrel will not be required for services lines.

NOTE:

Items that are ~~struck through~~ are deleted. Items that are underlined have been added or changed. All other terms and conditions remain as stated in the IFBC.

INSTRUCTIONS:

Receipt of this addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the response being deemed non-responsive.

END OF ADDENDUM

AUTHORIZED FOR RELEASE

APPENDIX K, BID PRICING FORM (REVISED)
21-TA003637 DJ, CORTEZ GARDENS SUBDIVISION WATER MAIN
REPLACEMENT
COUNTY PROJECT NO. 6097270
BID A BASED ON 275 CALENDAR DAYS

ITEM NO.	DESCRIPTION	UNITS	QTY.	UNIT PRICE (\$)	EXTENDED PRICE (\$)
1	Grout Abandoned 4" Pipe	LF	1,654		
2	Grout Abandoned 6" Pipe	LF	45		
3	F&I 4" Caps	EA	4		
4	F&I 6" Caps	EA	1		
5	F&I 6" Polyvinyl Chloride (PVC) Pipe	LF	533		
6	F&I 6" Class 350 Ductile Iron (DIP) Pipe	LF	720		
7	F&I 6" Gate Valve	EA	11		
8	F&I 6" Sleeves	EA	6		
9	F&I Water Services Connection (Short 1" Polyethylene Pipe)	EA	18		
10	F&I Water Services Connection (Long 1" Polyethylene Pipe)	EA	13		
11	Remove Water Meter Box Assembly	EA	70		
12	F&I Fire Hydrant Assembly	EA	2		
13	F&I Water Meter Box Assembly	EA	32		
14	F&I 6" X 6" Tee	EA	5		
15	F&I 6" 45° Bend	EA	13		
16	F&I 6" 90° Bend	EA	3		
17	Re-Establish Residential Service Lines	EA	32		
18	Maintenance of Traffic (MOT)	LS	1		
19	Erosion And Sedimentation Control	LS	1		
20	Milling Asphalt Pavement (¾" Average Thickness)	SY	5,407		
21	F&I Asphaltic Concrete Overlay (¾" Average Thickness)	TN	49		
22	F&I Asphaltic Concrete With Prime Coat (1 ¼" Average Thickness)	TN	223		
23	F&I Full Base (8" Minimum Thickness)	SY	634		
24	Removal of Concrete	SY	555		
25	F&I Concrete Driveway	SY	481		
26	F&I Concrete Curb and Gutter	LF	227		
27	F&I Concrete Valley Crossing	LF	75		
28	F&I SOD	SY	1,537		
	SubTotal Construction Cost				
29	Mobilization	LS	1		
30	Miscellaneous Work & Clean Up	LS	1		
31	Record Drawings	LS	1		
32	Contract Contingency (10% of Subtotal Construction Cost)	%	10%		
	Total Construction Cost				

APPENDIX K, BID PRICING FORM (REVISED)
21-TA003637 DJ, CORTEZ GARDENS SUBDIVISION WATER MAIN
REPLACEMENT
COUNTY PROJECT NO. 6097270
BID B BASED ON 365 CALENDAR DAYS

ITEM NO.	DESCRIPTION	UNITS	QTY.	UNIT PRICE (\$)	EXTENDED PRICE (\$)
1	Grout Abandoned 4" Pipe	LF	1,654		
2	Grout Abandoned 6" Pipe	LF	45		
3	F&I 4" Caps	EA	4		
4	F&I 6" Caps	EA	1		
5	F&I 6" Polyvinyl Chloride (PVC) Pipe	LF	533		
6	F&I 6" Class 350 Ductile Iron (DIP) Pipe	LF	720		
7	F&I 6" Gate Valve	EA	11		
8	F&I 6" Sleeves	EA	6		
9	F&I Water Services Connection (Short 1" Polyethylene Pipe)	EA	18		
10	F&I Water Services Connection (Long 1" Polyethylene Pipe)	EA	13		
11	Remove Water Meter Box Assembly	EA	70		
12	F&I Fire Hydrant Assembly	EA	2		
13	F&I Water Meter Box Assembly	EA	32		
14	F&I 6" X 6" Tee	EA	5		
15	F&I 6" 45° Bend	EA	13		
16	F&I 6" 90° Bend	EA	3		
17	Re-Establish Residential Service Lines	EA	32		
18	Maintenance of Traffic (MOT)	LS	1		
19	Erosion And Sedimentation Control	LS	1		
20	Milling Asphalt Pavement (¾" Average Thickness)	SY	5,407		
21	F&I Asphaltic Concrete Overlay (¾" Average Thickness)	TN	49		
22	F&I Asphaltic Concrete With Prime Coat (1 ¼" Average Thickness)	TN	223		
23	F&I Full Base (8" Minimum Thickness)	SY	634		
24	Removal of Concrete	SY	555		
25	F&I Concrete Driveway	SY	481		
26	F&I Concrete Curb and Gutter	LF	227		
27	F&I Concrete Valley Crossing	LF	75		
28	F&I SOD	SY	1,537		
	SubTotal Construction Cost				
29	Mobilization	LS	1		
30	Miscellaneous Work & Clean Up	LS	1		
31	Record Drawings	LS	1		
32	Contract Contingency (10% of Subtotal Construction Cost)	%	10%		
	Total Construction Cost				

BIDDER NAME _____

BIDDER SIGNATURE _____