



1112 Manatee Avenue West
Bradenton, FL 34205
purchasing@mymanatee.org

Solicitation Addendum

Addendum No.:	1
Solicitation No.:	21-TA003719DJ
Project No.:	6100880
Solicitation Title:	Lift Station 14-A FM Replacement and Extension
Addendum Date:	July 26, 2021
Procurement Contact:	Dave Janney Senior Procurement Agent

IFBC 21-TA003719DJ is amended as set forth herein. Responses to questions posed by prospective bidders are provided below. This Addendum is hereby incorporated in and made a part of IFBC 21-TA003719DJ.

The deadline to submit all inquiries concerning interpretation, clarification or additional information pertaining to this IFBC is July 30, 2021.

REPLACE:

APPENDIX K, BID PRICING FORM

Replace Appendix K, Bid Pricing Form with Revised Appendix K issued with this Addendum 1 and available for download as a separate attachment.

REPLACE:

BID ATTACHMENT 2, CONTRACT DOCUMENTS AND TECHNICAL SPECIFICATIONS, SECTION 01150

Replace Section 01150 Measurement and Payment with the Revised Section 01150 issued with this Addendum 1 and available for download as a separate attachment.

QUESTIONS AND RESPONSES:

Q1. Regarding the joint restraint pay item, will the megalug restraints at fittings and valves be paid for in this item? Or are they to be included with the fitting price?

R1. All joint restraints shall be included in Bid Item 6: Joint Restraints

Q2. What are the sewage flow rates as it relates to the manhole to be rehabbed in 63rd Ave. E. @ 9th St. E.?

R2. Simulated flows are: 160 gpm ADF, 500 gpm peak hour

Q3. Where is the 4-1/2 CY of concrete shock pad located?

R3. See Sheet C01.

Q4. There are several asphalt drives shown to be milled and overlaid. Will these be paid for as mill & overlay in bid item #19? If not, and it is to be paid in the driveway item, please consider creating separate pay items for concrete drives and asphalt drives as has been done in previous projects.

R4. All driveway restoration within or outside of the right-of-way shall be paid as part of Bid Item 17a Asphalt Driveway Restoration or Bid Item 17b Concrete Driveway Restoration. See Revised Specification 01150 Measurement and Payment and Appendix K, Bid Pricing Form included in the Addendum 1 as separate attachments.

Q5. Are soil borings available?

R5. Refer to Bid Attachment 2, Technical Specifications, Appendix C, Report of Geotechnical Investigation.

Q6. Regarding the “guardrail replacement” can we salvage and reinstall the existing guardrail or must we replace it with new?

R6. Bid as new guard rail.

Q7. After further review of the bid schedule, please consider adding the following pay items:

- **Maintenance of Traffic**
- **Clear & Grub**
- **Inlet Protection**
- **Miscellaneous Work and Cleanup**

R7. See new Bid Item #27 Maintenance of Traffic. The remaining items shall be included in the applicable pay items of work per Section 01150, 1.07 Unit Price Item.

**Q8. Will any traffic loops be affected with the open cut pipe installation?
If so, will a pay item be added to accommodate the repairs?**

R8. It is anticipated traffic loops will be affected during pipe installation. Traffic loop restoration is provided as part of Bid Item #27 Maintenance of Traffic.

Q9. If temporary by-pass pipe is stung out east/west thru the intersection of 63rd and 9th Ave. E. while the manhole is being rehabbed, will we be able to close thru traffic on 9th?

R9. Closure of more than one lane is subject to an approved road closure from the Manatee County Transportation Department per Specification Section 01570, 1.02.

Q10. Is the county buying the concrete pumping services directly or this is part of the concrete contractor's package?

R10. The items in the Bid Documents will be the contractor's responsibility. The County will not be making a direct purchase for the concrete services.

NOTE:

Items that are ~~struck through~~ are deleted. Items that are underlined have been added or changed. All other terms and conditions remain as stated in the IFBC.

INSTRUCTIONS:

Receipt of this Addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the response being deemed non-responsive.

END OF ADDENDUM

AUTHORIZED FOR RELEASE