

# TECHNICAL MEMORANDUM FOR BRIDGE REPLACEMENT FOUR-LANE ALTERNATIVES

## Bridge Replacement at Upper Manatee River Road over Mill Creek

Contract No. 15-0909JE - Work Assignment No. 10  
County CIP No. 6030662



**PREPARED FOR:**  
MANATEE COUNTY PUBLIC WORKS  
1022 26<sup>TH</sup> AVENUE EAST  
BRADENTON, FL 34208

**PREPARED BY:**  
KISINGER CAMPO & ASSOCIATES, CORP.  
201 N. FRANKLIN STREET  
SUITE 400  
TAMPA, FL 33602

**WITH CONTRIBUTION FROM:**  
MCKIM & CREED



# Technical Memorandum for Bridge Replacement Four-Lane Alternatives

---

Upper Manatee River Road over Mill Creek  
(Existing Bridge No. 134023)

Contract No.: 15-0909JE, Work Assignment No. 10

County C.I.P. No.: 6030662

Prepared For: Manatee County



Prepared by: Kisinger Campo & Associates, Corp.



Draft Report  
November, 2021



## Table of Contents

1.0	Introduction.....	1
2.0	Existing Conditions.....	3
2.1	Existing Bridge .....	3
2.2	Existing Roadway .....	3
2.3	Existing Utilities .....	4
3.0	Design Considerations.....	7
3.1	Bridge Design Considerations.....	7
3.2	Bridge Typical Section .....	8
3.2.1	Rural Typical Section.....	8
3.2.2	Urban Typical Section .....	8
3.3	Roadway Design Considerations.....	9
3.4	Environmental Considerations .....	12
4.0	Alternatives Considered.....	13
4.1	Bridge Superstructure Alternatives .....	13
4.1.1	CIP Continuous Flat Slab Superstructure .....	13
4.1.2	12" Florida Slab Beam Superstructure.....	13
4.2	Bridge Substructure Alternatives.....	14
4.2.1	Four Span Arrangement, Piles.....	14
4.2.2	Four Span Arrangement, Drilled Shafts .....	14
4.3	Bridge Construction Phasing Alternatives .....	14
4.3.1	Phased Construction Alternative (Urban Typical Section Only) .....	15
4.3.2	Complete Detour Alternative .....	15
4.4	Roadway Phasing Alternatives .....	17
4.4.1	Complete Detour Alternative .....	17
4.4.2	Phased Construction Alternative.....	18
4.5	Potable Water Main Alternatives .....	19
4.5.1	Relocation, Subaqueous Crossing Alternative.....	19
4.5.2	Relocation, Aerial Crossing Alternative.....	19
5.0	Conclusions and Recommendations.....	21

## List of Appendices

**Appendix A:** Construction Cost Estimates

**Appendix B:** Construction Time Calculations

**Appendix C:** Exhibits

**Appendix D:** Existing Bridge Plans

**Appendix E:** Bridge Inspection Report

Note – The electronic file of this report includes direct navigation links to specific report sections, figures and appendices. Enabled links have been presented as **Bold** text in this report. Click directly on the bold text to navigate directly to the referenced report section.

## 1.0 Introduction

Upper Manatee River Road is a two-lane, undivided roadway in central Manatee County, between Parrish and Lakewood Ranch. The portion of Upper Manatee River Road considered in this Bridge Replacement Study extends from west to east, connecting Fort Hamer Road and North Rye Road. The existing Bridge No. 134023 spans over Mill Creek, located approximately 3.2 miles northeast of SR-64. Refer to **Figure 1-1** for the approximate bridge location. The existing bridge is a four-span, simply supported, prestressed concrete channel beam superstructure. Manatee County proposes this Technical Memorandum for Bridge Replacement (Memo) to evaluate factors and alternatives associated with the replacement of the existing bridge and approach roadways and replacement of an adjacent 42" diameter potable water main (PWM), located on the south side of the bridge.



**Figure 1-1: Project Location Plan View**

The proposed bridge replacement considered within this Memo includes two bridge typical section alternatives. Both alternatives are intended to allow for the future widening of Upper Manatee River Road from its current two lane configuration to a four lane configuration without need of future widening of the proposed bridge. Bridge alternatives considered commonly include 11'-0" travel lanes and 5'-0" sidewalks. Shoulder width, barrier type, and overall bridge width varies by alternative. Lateral alignment of the proposed bridge will depend on several factors including the typical section considered and construction methods utilized.

As part of the bridge improvements, the roadway vertical profile will be maintained where possible and the proposed superstructure depths will closely match that of the existing bridge. The existing bridge utilizes four prestressed concrete sheet pile wingwalls with concrete bulkhead caps. The proposed

condition will provide similar slope stability using prestressed concrete sheet pile walls along the east and west bank of Mill Creek within the project area. The approach roadway horizontal alignment and vertical profile will be adjusted as necessary for the proposed typical section improvements and will extend to a point at which the improvements can be safely transitioned back to the existing approach roadway sections.

Important factors to be considered during the design and construction of the bridge replacement include, but are not limited to, available right-of-way, environmental impacts, construction phasing or detours, removal or replacement of existing sheet pile wall, bridge replacement cost, and total time of construction.

This Memo evaluates the feasibility of two bridge superstructure alternatives. A recommended course of action is provided based on constructability concerns and cost analysis. The bridge superstructure configurations that are considered include:

- Four-Span Continuous Cast-in-Place (CIP) Concrete Slab Superstructure
- Four Spans of Simply Supported 12" Florida Slab Beam (FSB) Superstructure

Both proposed superstructure alternatives provide improved traffic capacity and bicyclist/pedestrian safety. The proposed replacement alternative will be constructed at the approximate location of the existing bridge. The proposed construction sequence and phasing alternatives are discussed further in Section **4.3**. Alternatives for the final disposition of the 42" PWM are also discussed in Section **4.5**.


A foundation of 18" square prestressed concrete piles have been estimated in the generation of bridge replacement cost estimates. Discussion of alternative bridge substructure is included in Section **4.2.2**.

A concurrent Memo is being conducted for the replacement of Bridge No. 134024, Upper Manatee River Road over Gates Creek, which is located approximately 1 mile west of Mill Creek. Additional consideration will be given to construction phasing related to concurrent bridge replacement projects for these two structures and the impacts imposed on residences with single access points located along Upper Manatee River Road between these two bridges.

## 2.0 Existing Conditions

### 2.1 Existing Bridge

Upper Manatee River Road over Mill Creek (Bridge No. 134023) is a four-span, simply supported, prestressed concrete channel beam superstructure. The substructure consists of a reinforced concrete pile bent cap founded on 12" square prestressed concrete piles. All piles at this structure have had cathodic protection integral pile jackets which were installed in August of 2010. The bridge was constructed in 1963 and carries two 11'-0" traffic lanes and two 3'-0" shoulders, with a total curb-to-curb width of 28'-0". The approach roadways are supported by prestressed concrete sheet pile backwalls and wingwalls which angle back to tie into the embankment fill. Refer to **Figure 2-1** for the existing bridge typical section.



**Figure 2-1: Existing Bridge Typical Section**

Note: The pipe offsets shown above are approximate and founded on the 1995 As-Built plans titled "South County Water Transmission Main, Phase I, 42" – Water Treatment Plant to S.R. 64", by others.

With the installation of the pile jackets in 2010, the Sufficiency Rating (SR) of the bridge showed some improvement, increasing from 45.8 in 2010, prior to the jacket installation, to 59.5 in 2011. The bridge was removed from the Structurally Deficient bridge list in 2011, but remained coded as Functionally Obsolete. The bridge SR has further decreased over time due to continued bridge deterioration and updates to the bridge's load rating analysis to the current rating of 21.8. It is anticipated that the bridge SR will continue to decrease over time with additional bridge deterioration.

The bridge was most recently inspected by the Florida Department of Transportation on March 24, 2020. A copy of this Routine Inspection Report is included as **Appendix E** to this Memo. During this most recent Routine Inspection, the bridge was found to have National Bridge Inspection (NBI) ratings of 7 Good for the Deck and Channel and 6 Satisfactory for the Superstructure and Substructure. This bridge is currently coded as Functionally Obsolete, due to lateral clearances over the deck (Deck Geometry - Intolerable). This bridge is currently posted for Load for Florida Single Unit Legal Load (SU Truck) at 19 tons, Truck Tractor Semi-Trailer Legal Load (C Truck) at 25 tons, and Single Unit Truck with One Trailer Legal Load (ST Truck) at 30 tons. The most recent Bridge Load Rating is dated January 6, 2012.

### 2.2 Existing Roadway

Upper Manatee River Road, within the project limits runs along a west to east alignment which is classified as an Urban Collector roadway. This section of Upper Manatee River Road begins at a three-way signal-controlled intersection with Fort Hamer Road, and runs east as a two-lane, two-way road for



approximately 3.9 miles before terminating at North Rye Road with a stop-controlled T-intersection. The surrounding area is primarily low-density residential. The roadway section generally consists of two 11' travel lanes with unpaved shoulders of no more than 6'. Roadside features include intermittent sidewalks and ditches, numerous residential driveway connections, and overhead utilities. County records indicate a 40' deeded right-of-way line on each side of Upper Manatee River Road. The posted speed limit on Upper Manatee River Road is 45 miles per hour (MPH), and the Annual Average Daily Traffic (AADT) is 10,500 with a current level of service grade of D. Traffic counts approximately doubled in the 20-year period from 2000 to 2020, growing from 2532 vehicles per day (VPD) to 5478 VPD, and are expected to continue increasing.

## 2.3 Existing Utilities

Constructed in 1995, the 42" PWM aerial crossings over Mill Creek is part of a water transmission main that conveys potable water from the Lake Manatee Water Treatment Plant to the intersection of S.R. 64 and Upper Manatee River Road. The aerial crossing is supported on the south side of the bridge by concrete piles with reinforced concrete caps. Lateral support is provided for the utility by connection to the bridge bent caps. The PWM extends 164' over Mill Creek, with 45 degree bends at either channel bank, which return the utility underground. Based on a review of photos taken during a site visit in October 2020 by KCA, the aerial crossings are constructed of prestressed concrete cylinder pipe (PCCP) which consists of a concrete core, a thin steel cylinder, high tensile prestressing wire and an exterior concrete mortar. Refer to **Photo 2-1** for photographic representation of the 42" PWM.



***Photo 2-1 – 42" PWM Spanning Mill Creek South of Bridge No. 134023***

PCCP is known for its resistance to corrosion, high internal pressures and external loadings, and its ability to be rapidly and economically installed. There are two types of PCCP. Lined-cylinder Pipe (LCP) was first manufactured in 1942 and Embedded-cylinder Pipe (ECP) in 1953. The main difference between the two is how they are constructed. The cross section of the LCP is layered from the inside out as follows: concrete



core, steel cylinder, prestressing wires, cement mortar. With the ECP, the steel cylinder is embedded in the concrete core and the prestressing wires wrap around the concrete core instead of the steel cylinder. Based on the photos, the aerial crossings at Mill Creek uses LCP.

The 42" PWM appears to be in good condition, approaching 30 years of service. No leaking or settling was observed. Joint repairs have been performed at some point (Refer to **Photo 2-2**) and the concrete mortar does show signs of distress from the elements, with hairline cracks in the mortar which allow rainwater to pull calcium out of the mortar to form the stalagmites (Refer to **Photo 2-3 & Photo 2-4**). There is also evidence pipe straps once secured the pipes to the concrete saddles but have since been removed.



***Photo 2-2 – Past joint repair at 42" PWM***

The existing pile and pipe support systems at both crossings consists of independent concrete piles and pile caps anchored to the ends of the existing concrete bridge substructure for lateral support. Record drawings reviewed indicated the concrete piles are 12" square prestressed concrete assemblies with CIP reinforced concrete pile caps. These pile caps were constructed with the top surface cradled to provide support of the bottom of the pipe and allow for a neoprene bearing pad between the outside face of pipe and the concrete. The record drawings reviewed indicated both the piles and the bearing pads to be installed in conformance with requirements of Florida Department of Transportation (FDOT) specifications and installed to an embedment depth in the creek bed to provide a minimum 20 ton vertical allowable load capacity. Cathodic protection pile jackets were installed on the 42" PWM support piling in conjunction with the bridge piling repairs conducted in August 2010.

Other known existing utilities in the project area include two 4" fiberglass gas line utilities attached to south barrier rail posts, Verizon buried fiber optic cable located south of the bridge, and overhead electric and telecommunication line located approximately 20' south of the bridge coping.



***Photo 2-3 – Typical mortar cracks in 42" PWM surface***



***Photo 2-4 – Calcified stalagmite growth at joints***

## 3.0 Design Considerations

The Scope of Services for this Memo does not include the development of detailed structural, roadway, or utility analysis. No survey or geotechnical data has been collected for the completion of this Memo. This Memo and the cost estimates for each alternative included are founded on Engineering Judgement, assumptions made in accordance with standard engineering practice, and observations made during field review of the project site.

### 3.1 Bridge Design Considerations

Cost estimates were developed assuming that final bridge design will be completed in accordance with the current edition of the American Association of State Highway and Transportation Officials (AASHTO) Load and Resistance Factor Design (LRFD) Bridge Design Specifications, supplemented by the January 2021 Florida Department of Transportation (FDOT) Structures Design Manual (SDM). Engineering assumptions related to proposed bridge construction were made in accordance with these manuals. Other specific design criteria to be followed during final design include the most current editions of the following:

- AASHTO LRFD Bridge Design Specifications, Customary U.S. Units, 9th Edition
- FDOT Structures Manual, January 2021 Edition, Topic No. 625-020-018, with subsequent Structures Design Bulletins
- FDOT Standard Specifications for Road and Bridge Construction, July 2021 Edition
- FDOT FY2020-21 Standard Plans for Road and Bridge Construction, Topic No. 625-010-003, with subsequent design interims.
- FDOT Design Manual, January 2021 Edition, Topic Nos. 625-000-002, with subsequent Roadway Design Bulletins.
- Manual of Uniform Minimum Standards for Design, Construction and Maintenance for Streets and Highways (2018) ("Florida Greenbook"), Topic No. 625-000-015.

Based on comments during initial scoping and subsequent project meetings, 11'-0" traffic lanes, 4'-0" bike lanes, and 5'-0" sidewalks have been included on both sides of the proposed bridge typical sections. Currently, the approach roadway does not utilize bike lanes or sidewalks, but in the future, connectivity along the length of Upper Manatee County River Road may be achieved without necessary widening of the proposed bridge.

When selecting structural alternatives for consideration, a review of the project location, existing geometric and structural conditions, and similar replacements were considered. Due to the existing low level bridge, two alternatives are implemented into the cost analysis. In consideration of the existing minimum vertical clearance, a four-span continuous CIP flat slab superstructure and a 12" Florida Slab Beam (FSB) superstructure were selected for cost estimate generation. Both superstructure alternatives include similar superstructure depths to the existing 19" thick superstructure; however, minor approach roadway infilling will be required to meet modified roadway profiles due to the differing superstructure depths and to offset modifications to the proposed bridge low member elevation resulting from increased bridge width and bridge cross slope.




Future survey and geotechnical investigations will help determine final bridge low member elevation and optimal substructure alternatives.

### 3.2 Bridge Typical Section

Two bridge superstructure alternatives have been considered which allow for the future widening of Upper Manatee River Road from its current two lane configuration to a proposed four lane configuration without the need for future widening of the replacement bridge. The proposed typical sections include a Rural and one Urban section in accordance with the FDOT Design Manual (FDM) Figures 260.1.2 and 260.1.3, respectively.

#### 3.2.1 Rural Typical Section

The proposed rural bridge typical section is based on Figure 260.1.2 of the FDM for Undivided Arterials and Collectors and includes two 11'-0" travel lanes, two 12'-8" shoulders, two interior 36" single-slope traffic barriers (1'-4" wide), two 5'-0" sidewalks, and two exterior 36" single-slope traffic barriers (1'-4" wide). Refer to **Figure 3-1** for the proposed rural typical section. The resultant curb-to-curb and out-to-out dimensions are 47'-4" and 62'-8", respectively.



**Figure 3-1 – Rural Typical Section, Florida Slab Beam (CIP Continuous Slab Similar)**


Upon completion of construction of this proposed typical section, a portion of the 12'-8" shoulder would be utilized for bicycle facilities in order to provide an equivalent level of service to the proposed urban typical section alternative.

Future widening of Upper Manatee River Road to a four lane condition could be accomplished through the removal of the interior 36" single slope traffic railing. This barrier removal would increase the bridge curb-to-curb width to 60'-0", allowing for four 11'-0" travel lanes and two 8'-0" shoulders per FDM requirements. Although no widening of the bridge would be required during a future four lane condition along Upper Manatee River Road, the construction of a separate pedestrian structure would be required to maintain pedestrian access across Mill Creek under this typical section alternative.

#### 3.2.2 Urban Typical Section

The proposed urban typical section is based on Figure 260.1.3 of the FDM for Curbed Arterials and Collectors with design speeds of 45MPH or less. Manatee County considers Upper Manatee River Road as an urban roadway. Upper Manatee River Road has a posted speed limit of 45 MPH within the project limits and it is assumed that curb and gutter will be extended beyond the bridge limits for an unknown distance to allow for this typical section. This proposed typical section allows for reduced bridge width when compared to Undivided Arterial typical sections and thus is intended to save the County in overall bridge and Right-of-Way acquisition costs under the four lane ultimate condition of the roadway.

The proposed bridge replacement includes four 11'-0" traffic lanes, two 4'-0" bike lanes, two 1'-4" shoulders, two 5'-0" raised sidewalks with 2" vertical end transitions, and two 32" vertical shape traffic railing (1'-1" wide). The resultant curb-to-curb and out-to-out dimensions are 54'-8" and 67'-2", respectively, as shown in **Figure 3-2**.



**Figure 3-2 - Urban Typical Section, Florida Slab Beam (CIP Continuous Slab Similar)**


Upon completion of construction of this proposed typical section, only two interior traffic lanes would be utilized. Future widening of Upper Manatee River road to a four lane condition could be accomplished with no modifications to the bridge, with the exception of restriping of the deck.

### 3.3 Roadway Design Considerations


Roadway typical sections were developed in conjunction with the above bridge sections and will route traffic back to the existing two-lane configuration from the proposed four-lane configuration of the bridge while laying the groundwork for future roadway expansion. The proposed urban section will consist of 11' travel lanes, 4' paved shoulders serving as bike lanes, Type F curb & gutter and a 5' sidewalk each direction on both sides of the proposed bridge. The proposed rural section will consist of 11' travel lanes and 15' paved shoulders with guardrail placed to shield the bridge approaches and 5' sidewalks. The proposed 11' travel lane width matches the existing lane widths of Upper Manatee River Road and is in accordance with Florida Greenbook, Table 3-10 minimum lane width requirements for roadways with 50 MPH or lower design speeds. The proposed design speed of 45 MPH will be considered for final roadway improvements. From 2000 to 2020, the traffic volume along Upper Manatee River Road has more than doubled and is anticipated to continue to increase over time.

To accommodate the roadway typical and maintain the existing waterline location, the proposed centerline roadway alignment will be shifted to the north. This avoids R/W and overhead utility impacts along the south side of the roadway. But the proposed improvements will require additional R/W along the north side. Also, the proposed footprint is anticipated to impact the residential parcel on the northeast corner and the adjacent side street intersection.






**Figure 3-3 – Proposed Roadway Plan**



**Figure 3-4 – Roadway Urban Typical Section**



**Figure 3-5 – Roadway Rural Typical Section**

Since the existing roadway does not feature bike lanes, the proposed 4' paved shoulder/bike lane will be sufficient for current conditions. The outside lane or wide shoulder will be tapered in to match existing conditions as well. The existing roadway also lacks sidewalks or other pedestrian facilities; proposed sidewalks will be shifted away from the roadway and will terminate at the project limits. The proposed roadway footprint at the approaches on both sides of the bridge will enable future roadway improvements along this corridor to tie in with minimal throughway cost. This is an important consideration in light of the increases in traffic volume and anticipated growth discussed in Section 2.2.

Two alternatives were evaluated for temporary traffic control during construction. Each alternative would be used for the full duration of construction work. Alternatives considered include:

- Alternative 1: Full closure of Upper Manatee River Road with a detour using County Road 64 and Rye Road.
- Alternative 2: A phased approach utilizing a portion of the existing bridge to maintain two-way traffic.

The existing overhead utilities in the southern portion of the project area are located within 30' of the centerline of the existing roadway and must be temporarily de-energized and relocated during construction. The 42" PWM on the south side of the existing bridge was considered to stay in place during construction. This utility will need to be braced to the proposed bridge. If any additional existing facilities are identified during construction, coordination with utility owners will be required to protect, relocate, or remove them as needed.

### 3.4 Environmental Considerations

Coordination with state and federal agencies will be necessary during the design phase of this project. Specific identification of environmental impacts related to the proposed bridge replacement alternatives is not included in the scope of services for this Memo. Anticipated agency coordination includes the Florida Department of Environmental Protection (FDEP), the Southwest Florida Water Management District (SWFWMD), and the United States Army Corps of Engineers (USACE). Mill Creek is a USACE Retained Waterway.

The bridge alternatives included within this Memo are intended to meet or exceed the existing hydraulic opening beneath Upper Manatee River Road. Hydraulic analysis will need to be conducted during final design to determine the downstream impacts related to the bridge and possible 42" PWM replacement and the permitting ramifications related to these impacts (if any).

Additional coordination with environmental resource agencies during the permitting process may be required. These agencies include the U.S. Fish and Wildlife Service (USFWS) and the Florida Fish and Wildlife Conservation Commission (FWC). Anticipated surface waters and vegetated wetlands and the associated costs of wetlands mitigation have been estimated as part of this Memo. Refer to **Table 5-1 – Alternatives Evaluation Matrix** and **Appendix A** for further information.

Initial permitting should be conducted early within the project design phase. Permitting often becomes the critical path in terms of design and construction timelines. Permitting efforts are not included in the construction timelines provided with this report.

During a field review conducted in October 2020, visible and audible evidence of bats residing within the beam diaphragm areas was observed. A bat exclusion project will need to be considered and executed prior to any construction activities at Bridge No. 134023.

## 4.0 Alternatives Considered

### 4.1 Bridge Superstructure Alternatives

The bridge superstructure alternatives considered include a cast-in-place continuous reinforced concrete slab and a 12" Florida Slab Beam with 6.5" CIP reinforced concrete topping. These alternatives were selected based on cost, constructability, and estimated construction schedule. The span configuration for the replacement of Bridge 134023 matches the existing bridge. However, in an effort to reduce the surface water impacts on the northwest corner of the proposed bridge, the phase constructed alternatives will include an additional 10-feet to the westernmost span. Refer to **Appendix A** for detailed construction cost estimates and **Appendix B** for detailed construction time calculations for each bridge alternative.

#### 4.1.1 CIP Continuous Flat Slab Superstructure

The use of a CIP continuous slab allows for a reduced superstructure depth when compared to a simply supported alternative. This provides benefits in cost saving due to reduced construction materials and allowing for a roadway profile and low bridge member elevation which closely match the existing bridge. Span configuration for the four-span CIP continuous superstructure will match the existing span lengths of four 30'-0" spans for all construction alternatives except the phase construction alternative, which will have a span configuration of 40'-0", 30'-0", 30'-0", and 30'-0". These span arrangements are anticipated to be optimal as it maintains or increases the existing hydraulic opening for the channel and allows for equivalent future supports of the 42" PWM to the proposed bridge substructure.

The proposed superstructure depth is assumed based on Table 2.5.2.6.3-1 of the AASHTO LRFD Bridge Design Specifications. A minimum slab depth of 20" is used in the generation of construction cost estimates for this Memo, and the superstructure depth increased to the centerline of the bridge, in accordance with the roadway cross-slope. The proposed superstructure depth for the reinforced concrete slab is 1" deeper than the existing bridge, requiring minor adjustment to the current vertical profile to maintain the existing low member elevation for all construction alternatives.

#### 4.1.2 12" Florida Slab Beam Superstructure

The 12" FSB superstructure alternative will consist of the same span configurations as the CIP continuous Flat Slab Superstructure. 12" FSB superstructure was selected over other similar FSB alternatives due to its ability to efficiently maintain the existing spans and have the capacity to support the proposed phase construction spans while remaining the most cost effective FSB depth. This superstructure depth is 1/2" shallower than the existing superstructure. This superstructure alternative will not require infilling of the approach roadways to maintain the current bridge low member elevation.

The FSB alternative will ultimately reduce the total construction time as the precast beams will be able to be set and used as bottom forms for the concrete deck. The reinforcing steel can be tied and placed on the beams with minimal formwork required to form the coping, accelerating construction of the superstructure.

## 4.2 Bridge Substructure Alternatives

A similar bridge substructure is required for both superstructure alternatives. The bridge substructure is anticipated to utilize 18" square prestressed concrete pile foundations and reinforced concrete bent caps. Additional consideration will be given to the use of 48" drilled shafts as a foundation alternative. The approach roadway fill will be maintained with concrete sheet pile walls at each abutment backwall and at all four corners of the structure.

Bridge replacement cost estimates assume 16'-0" of concrete retaining wall at all four corners of the structure, with additional backwall length in accordance with the proposed increase in bridge width.

All foundation arrangements and lengths are based on engineering judgement and ultimately will need to be revised during final design with the completion of geotechnical investigation at the project site. Additionally, other foundation alternatives may be considered with the provided geotechnical analysis.

The 3' x 3' reinforced concrete pile cap was assumed to efficiently transfer the superstructure loads to the foundation piles. The width of the cap allows enough space for the typical 4" reinforcing clear cover to the edge of the cap, and 3" reinforcing clear cover to the edge of the embedded pile tip, while using a 1" diameter #8 longitudinal reinforcing bar and a 5/8" diameter #5 transverse tie reinforcing bar.

### 4.2.1 *Four Span Arrangement, Piles*

In order to support a four span superstructure, this alternative includes a total of five 3' x 3' reinforced concrete bent caps, including two abutments and three intermediate bent caps. Due to the relatively short span length, 18" prestressed concrete piles spaced at 8'-0" are assumed at each abutment intermediate bent, each with a pile length of 70'. Concrete sheet pile wall will be installed in front of the proposed bridge piling and embedded into the proposed abutment caps.

### 4.2.2 *Four Span Arrangement, Drilled Shafts*

At the request of County staff, this additional substructure alternative has been considered, which will utilize 48" diameter drilled shaft foundations. This Memo assumes an equivalent superstructure, walls and bent caps to the single-span 18" square prestressed concrete pile foundation alternative for the generation of cost estimates. Cost estimates for this alternative should be revised prior to design to account for increased end bent sizing to accommodate the drilled shaft width. Additionally, effects on the hydraulic opening for this alternative are not considered.

This alternative has been included in order to provide an alternative to driven piles. The installation of drilled shaft foundations is anticipated to have less vibratory impacts on the adjacent 42" PWM. Drilled shaft length requirements vary widely and are heavily dependent upon soil conditions. The estimated cost of drilled shaft foundations is \$550 per linear foot of required shaft, in accordance with FDOT Structures Design Guidelines (SDG) Chapter 9. Assuming six drilled shafts per bent, drilled shaft lengths would need to exceed 21' in length prior to increasing the overall bridge construction costs estimated in **Appendix A**.

## 4.3 Bridge Construction Phasing Alternatives

Final horizontal alignment of the proposed bridge is dependent on the bridge typical section selected and the construction phasing methods utilized. This Memo considers a phased construction and a detoured alternative for the Urban Typical Section and only a detoured alternative for the Rural Typical Section.



Construction cost estimates, right-of-way acquisition estimates, and environmental impact estimates have been developed for the adjustment of the 42" PWM resulting from the proposed four lane bridge replacement alternatives. Refer to **Appendix C** for bridge typical sections, plan views, and estimated right-of-way impacts for each alternative. Bridge phasing alternatives are presented with pros and cons of each alternative below. Refer to **Appendix B** for detailed construction time calculations for each alternative considered.

#### **4.3.1 Phased Construction Alternative (Urban Typical Section Only)**

Refer to Section **4.4.2** for detailed information related to the roadway considerations for this phasing alternative. Refer to **Figure 4-1** for the phased construction alternative cross section.

##### **Pros:**

- Utilizes the existing bridge during the first phase of construction, allowing an equivalent level of service to the existing bridge during all construction operations.
- Allows for concurrent construction with Bridge No. 134024 along Upper Manatee River Road.

##### **Cons:**

- Longer overall construction duration when compared to a detour alternative. Approximate construction duration factor of 1.5.
- Higher construction cost due to additional construction phases.
- Largest Right-of-Way and Environmental Impacts

#### **4.3.2 Complete Detour Alternative**


Refer to Section **4.4.2** for detailed information related to the roadway considerations for this phasing alternative. Refer to **Figure 4-2** and **Figure 4-3** for the detoured urban and rural bridge cross sections, respectively.

##### **Pros:**


- Fastest construction duration.
- Maintains existing centerline of roadway of Upper Manatee River Road.
- Lower construction cost.

##### **Cons:**


- Cannot be completed concurrently with Bridge No. 134024 replacement.
- Decreased level of service along Upper Manatee River Road for the construction duration.
- Increased driving distance for travelers due to detour.



**Figure 4-1 – Phased Construction Alternative (Urban Typical Section Only)**



**Figure 4-2 – Detoured Construction Alternative (Urban Typical Section)**




**Figure 4-3 – Detoured Construction Alternative (Rural Typical Section)**

#### 4.4 Roadway Phasing Alternatives

##### 4.4.1 Complete Detour Alternative

A traffic detour route was considered that would eliminate any ability for the motorist to traverse East West along the Upper Manatee River Road across the bridge construction site. The detour routes were evaluated to ensure the local residential roadway won't be overwhelmed with the addition of the re-routed traffic. Considering the constraints, the shortest available detour route is depicted in **Figure 4-4**.

Detour length is the total additional travel along equivalent service roadways for a vehicle which would result from closing a bridge. The proposed work zone detour, traverses through the north-south section of Upper Manatee River Road (at the west end), SR 64, and Rye Road E (at the east end). The distance along Upper Manatee River Road from Fort Hamer Road to North Rye Road is approximately 3.9 miles. The shortest equivalent detour route includes traveling south on Upper Manatee River Road from Fort Hamer Road to SR-64, traveling east on SR-64 to Rye Road East, then traveling northeast on Rye Road East to Upper Manatee River Road. The total distance of this route is approximately 7.1 miles. The standard total detour length is therefore 3.2 miles.



**Figure 4-4 – Upper Manatee River Road Detour**


The “worst case” detour route, beginning at the nearest side street to the work area and ending at the nearest side street on the opposite side, is 10.8 miles in length. Gene Witt Elementary School and East Manatee Fire Rescue Station 3 are located on Rye Road East, which is used in the detour route. The increase in traffic volume from the detour is expected to have a negative impact on the operational effectiveness of both facilities, but not on the overall safety of the roadway. The closure itself may marginally increase response times from Fire Rescue Station 3 to locations on the opposite side of the work area. In the “worst case” scenario of an incident immediately west of the work area, the distance traveled from Fire Rescue Station 3 would increase from 4.1 miles using Rye Road East and approaching from the east to 6.9 miles using Rye Road East/SR 64 and approaching from the west. The additional 2.8 miles of travel could potentially add several minutes to response times.

#### **4.4.2 Phased Construction Alternative**

This alternative will allow for traffic to be maintained with minimal disruption, at the cost of introducing a permanent shift in the roadway alignment. Phased construction of the proposed bridge replacement would be achieved by partially constructing the proposed bridge and shifting traffic onto it in a temporary two-lane two-way condition. This condition would be maintained during removal of the existing structure and completion of the proposed bridge. A reduced work zone speed limit of 35 miles per hour is proposed and assumed for this alternative to improve safety and reduce impacts on the existing roadway and surrounding properties.



Phase 1 of construction will consist of constructing the proposed bridge to a condition as shown in **Figure 4-1** and placing Type K temporary concrete barrier per FDOT Standard Plan 102-110 to provide a temporary two-lane two-way roadway. In Phase 2, temporary pavement will be constructed to support a temporary diversion per FDOT Standard Plan 102-620 onto the partially-constructed proposed bridge, and traffic will be shifted onto the new structure until the project is completed.



**Figure 4-5 – Upper Manatee River Road Phased Alignment**

#### 4.5 Potable Water Main Alternatives

Two alternatives are considered related to the disposition of the 42" Potable Water Main located on the south side of Upper Manatee River Road at Mill Creek. These alternatives include replacement via subaqueous crossing beneath Mill Creek and replacement via aerial crossing over Mill Creek. Construction cost estimates for the Potable Water Main Alternatives were generated using recent bid tabs from similar work and consider a 30% contingency.

##### 4.5.1 Relocation, Subaqueous Crossing Alternative

Relocation of the 42" PWM utilizing a subaqueous channel crossing would require a 5' minimum depth of cover to accommodate open cut installation or use of jacking pipe, such as Meyer Polycrete (no casing required) installed by either jack and bore or microtunnel. This would require the bottom of the main to be at elevation -17' or at a depth of 25' below grade. Jack and bore installation with a casing would require an additional 2" of depth to accommodate the 60" casing, and horizontal directional drilling (HDD) would likely require an additional depth of 20' to 25'. Additionally, HDD installation would extend the installation length considerably as the required geometry to accommodate the entry and exit angles and bending radius of the pipe would drive the entry and exit points well beyond the creek. The subaqueous crossing would need 20' of separation from existing or future substructure depending upon the selected installation method. Preliminary costs associated with the subaqueous crossings are estimated to be approximately \$3,900,000 for open cut, \$4,070,000 for jack and bore, and \$4,900,000 for horizontal directional drill.

##### 4.5.2 Relocation, Aerial Crossing Alternative

For bridge alternatives requiring the replacement of the 42" PWM, the installation of a new aerial crossing supported by piles is considered. This alternative includes the installation of new supporting elements within Mill Creek for the replacement aerial crossing. It is possible long span ductile iron (DI) pipe



construction and jointing techniques may be utilized to position pipe supports closer to the creek banks and avoid potential obstructions in the center of Mill Creek. Other common pipe materials for aerial crossings include steel or PCCP.

The proposed independent pipe support system assemblies could consist of four prestressed concrete piles installed in a 2 x 2 array, with each pile embedded into the existing creek bottom. A geotechnical engineering subconsultant should be utilized during the design to determine pile embedment depths in addition to vertical, lateral, and uplift load capacities.

Piles should be topped with a CIP reinforced concrete pile cap assembly integral to each pile and provide a cradled profile in the top surface for pipe support. Neoprene bearing pads should be installed between the outside of the pipe and the concrete, and 316 stainless-steel straps and anchors to hold the pipe to the concrete pile caps.

Piles should be laterally braced in two directions with pressure treated or composite timbers anchored to the exterior faces of the piles in a cross braced and horizontal linear pattern above and below the water surface line. Anchor assemblies should include 316 stainless-steel bolts and hardware.

Connection of the new main to the existing can occur by cutting and adding a new fitting and spool between the two or via wet tap and line stop. Both options are discussed further below.

If there is the opportunity to take the existing main out of service, the connection can be made by cutting the existing main and adding a new fitting and spool. If it is decided to use DI or steel pipe for the new aerial crossing, this fitting will need to be a transition fitting. The record drawings show an isolation valve just east of Mill Creek and west of Gates Creek which could allow the complete main to be taken out of service. This would require the valves to properly isolate and their location accommodates the needed offset improvements. Further, consideration would have to be given to any water service interruption the outage may cause along with dewatering the main which is estimated to be approximately 389,000 gallons, refilling, flushing and bacteriological analysis prior to placing it back into service.

The new aerial crossing would need to be constructed to the fullest extent possible, pressure tested, chlorinated, flushed, and receive passing bacteriological results prior to being placed into service.

Preliminary cost estimates to relocate the transmission main are provided in **Appendix A**. Due to the uncertainty of taking the existing main out of service, the estimates consider the use of wet taps and line stops. Due to its readily available pricing, DI pipe was used as the material for the estimates. The total estimated construction cost for this alternative, including 30% contingency for unknowns is \$3,088,358.

## 5.0 Conclusions and Recommendations

Quantities have been prepared for the two superstructure alternatives and each associated typical section and construction phasing alternative. Detailed quantities and cost estimates were developed for the two-lane bridge replacement alternatives under a separate Technical Memorandum. Refer to the two-lane Memo for a description of how the cost estimates were developed. This four lane Memo utilizes the cost per square foot from the two lane Memo for the determination of bridge replacement costs. An Alternatives Evaluation Matrix for this project, including cost estimates, estimated Right-of-Way acquisition, estimated wetland mitigation costs, and estimated construction time is provided in **Table 5-1**. Refer to **Appendix A** for cost estimates, estimated right-of-way impacts, and wetland mitigation estimates. Refer to **Appendix B** for calculated construction time estimates.

Based on the findings of this Memo, construction of a 15" Florida Slab Beam superstructure with the proposed rural typical section, replacement of the 42" PWM with an aerial crossing and constructed under a complete detour of Upper Manatee Road is the most economically feasible alternative. However, it is recommended that this alternative be rejected in lieu of the equivalent urban typical section alternative. The reasons for this recommendation provided below:

- The use of the Urban typical section leads to an estimated 1.5 month savings in construction time, reducing the overall length of service reduction along Upper Manatee River Road.
- The rural typical section, under the future four lane ultimate condition of Upper Manatee River Road would require the future construction of a pedestrian bridge to maintain pedestrian access across Mill Creek. It is anticipated that the cost of a future pedestrian bridge would exceed the 2% cost difference estimated between these alternatives. Refer to **Table 5-1**.

In addition to having a lower estimated cost of construction, the FSB alternative will allow for faster construction compared to the Continuous Flat Slab superstructure alternative and therefore have reduced traffic interruption along Upper Manatee River Road. The FSB superstructure serves as form work for the cast-in-place topping, accelerating construction. The total estimated fee for the recommended alternative, including construction, design, construction engineering and inspection (CEI), right-of-way acquisition, and wetland mitigation is **\$9,754,949**. Approximately 39% of the overall estimate project cost is associated with the replacement of the 42" PWM.

The cost estimates generated within this Memo have been completed with minimal site specific supplemental data, such as geotechnical investigation, field survey, and subsurface utility engineering. Engineering judgement and assumptions were made in order to supplement this lack of site specific data. The cost estimates provided are subject to change based on final design.

Alternatives Evaluation Matrix																								
Bridge and Roadway																								
Evaluation Criteria	Flat Slab Bridge												Urban Typical Section											
	Rural Typical Section				Urban Typical Section								Rural Typical Section				Urban Typical Section							
	Full Detour				Full Detour				Phased Construction				Full Detour				Full Detour				Phased Construction			
Estimated Total Project Cost (in dollars)																								
Roadway Construction	\$315,491				\$299,331				\$464,949				\$315,491				\$299,331				\$464,949			
Bridge Construction	\$1,592,603				\$1,706,238				\$1,706,238				\$1,395,371				\$1,494,843				\$1,494,843			
Incidental Bridge <sup>(1)</sup>	\$923,900				\$965,983				\$965,983				\$923,900				\$965,983				\$965,983			
Phased Construction <sup>(2)</sup>	\$0				\$0				\$518,878				\$0				\$0				\$477,830			
Maintenance of Traffic (M.O.T.)	\$96,932				\$92,230				\$129,285				\$93,797				\$89,095				\$109,119			
Mobilization & Contingency <sup>(3)</sup>	\$849,598				\$891,465				\$1,096,814				\$790,429				\$828,047				\$1,021,082			
Bridge and Roadway Construction Subtotal	\$3,778,524				\$3,955,246				\$4,882,147				\$3,518,988				\$3,677,297				\$4,533,806			
Bridge and Roadway Design Estimate <sup>(4)</sup>	\$906,846				\$949,259				\$1,171,715				\$844,557				\$882,551				\$1,088,113			
42" Potable Water Main																								
Evaluation Criteria	Remain and Rehab	Replace; Aerial Crossing	Replace, HDD Subaq. Crossing	Replace, J&B Subaq. Crossing	Remain and Rehab	Replace; Aerial Crossing	Replace, HDD Subaq. Crossing	Replace, J&B Subaq. Crossing	Remain and Rehab	Replace; Aerial Crossing	Replace, HDD Subaq. Crossing	Replace, J&B Subaq. Crossing	Remain and Rehab	Replace; Aerial Crossing	Replace, HDD Subaq. Crossing	Replace, J&B Subaq. Crossing	Remain and Rehab	Replace; Aerial Crossing	Replace, HDD Subaq. Crossing	Replace, J&B Subaq. Crossing	Remain and Rehab	Replace; Aerial Crossing	Replace, HDD Subaq. Crossing	Replace, J&B Subaq. Crossing
Utility Construction Subtotal	N/A	\$3,090,000	\$4,900,000	\$4,070,000	\$257,000	\$3,090,000	\$4,900,000	\$4,070,000	\$257,000	\$3,090,000	\$4,900,000	\$4,070,000	\$257,000	\$3,090,000	\$4,900,000	\$4,070,000	\$257,000	\$3,090,000	\$4,900,000	\$4,070,000	\$257,000	\$3,090,000	\$4,900,000	\$4,070,000
Utility Design Estimate	N/A	\$154,500	\$245,000	\$203,500	\$38,550	\$154,500	\$245,000	\$203,500	\$38,550	\$154,500	\$245,000	\$203,500	\$38,550	\$154,500	\$245,000	\$203,500	\$38,550	\$154,500	\$245,000	\$203,500	\$38,550	\$154,500	\$245,000	\$203,500
Construction Subtotal	N/A	\$6,868,524	\$8,678,524	\$7,848,524	\$4,212,246	\$7,045,246	\$8,855,246	\$8,025,246	\$5,139,147	\$7,972,147	\$9,782,147	\$8,952,147	\$3,775,988	\$6,608,988	\$8,418,988	\$7,588,988	\$3,934,297	\$6,767,297	\$8,577,297	\$7,747,297	\$4,790,806	\$7,623,806	\$9,433,806	\$8,603,806
Design Subtotal	N/A	\$1,061,346	\$1,151,846	\$1,110,346	\$987,809	\$1,103,759	\$1,194,259	\$1,152,759	\$1,210,265	\$1,326,215	\$1,416,715	\$1,375,215	\$883,107	\$999,057	\$1,089,557	\$1,048,057	\$921,101	\$1,037,051	\$1,127,551	\$1,086,051	\$1,126,663	\$1,242,613	\$1,333,113	\$1,291,613
Construction Engineering & Inspection Fee <sup>(5)</sup>	N/A	\$1,098,964	\$1,214,993	\$1,098,793	\$1,010,939	\$1,127,239	\$1,239,734	\$1,123,534	\$1,233,395	\$1,275,544	\$1,369,501	\$1,253,301	\$906,237	\$1,057,438	\$1,178,658	\$1,062,458	\$944,231	\$1,082,768	\$1,200,822	\$1,084,622	\$1,149,793	\$1,219,809	\$1,320,733	\$1,204,533
Estimated Property Impacts																								
Business Impacts																								
Number of Business Relocations	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Residential Impacts																								
Number of Impacted Parcels	N/A	6	6	6	N/A	6	6	6	N/A	5	8	6	N/A	6	6	6	N/A	6	6	6	N/A	5	8	6
Total Right-of-Way Impacts																								
Acres of R/W Acquisition Required	N/A	0.443	1.181	0.582	N/A	0.409	1.152	0.549	N/A	0.798	1.125	0.808	N/A	0.443	1.181	0.582	N/A	0.409	1.152	0.549	N/A	0.798	1.125	0.808
Estimated Cost of R/W Acquisition	N/A	\$846,278	\$1,071,309	\$888,662	N/A	\$840,789	\$1,067,345	\$883,478	N/A	\$930,741	\$1,030,450	\$933,790	N/A	\$846,278	\$1,071,309	\$888,662	N/A	\$840,789	\$1,067,345	\$883,478	N/A	\$930,741	\$1,030,450	\$933,790
Estimated Environmental Impacts																								
Square Footage of Surface Water Impacts	N/A	4225	5140	4356	N/A	4792	5663	4879	N/A	5576	5837	5706	N/A	4225	5140	4356	N/A	4792	5663	4879	N/A	5576	5837	5706
Square Footage of Vegetated Wetlands Impacts	N/A	0	1568	523	N/A	87	1699	653	N/A	4966	6186	5271	N/A	0	1568	523	N/A	87	1699	653	N/A	4966	6186	5271
Estimated Cost of Environmental Impacts	N/A	\$23,280	\$39,912	\$27,864	N/A	\$27,044	\$43,758	\$31,710	N/A	\$67,428	\$77,884	\$70,402	N/A	\$23,280	\$39,912	\$27,864	N/A	\$27,044	\$43,758	\$31,710	N/A	\$67,428	\$77,884	\$70,402
Construction Duration Estimate																								
Estimated Construction Duration (Months)	22				20.5				30				21				19.5				29.5			
Preliminary Estimate of Total Project Costs	N/A	\$9,898,392	\$12,156,585	\$10,974,189	N/A	\$10,144,078	\$12,400,343	\$11,216,728	N/A	\$11,572,075	\$13,676,697	\$12,584,855	N/A	\$9,535,040	\$11,798,424	\$10,616,028	N/A	\$9,754,949	\$12,016,774	\$10,833,158	N/A	\$11,084,397	\$13,195,986	\$12,104,144
Preliminary Roadway Cost Per Square Foot	58.21				55.23				85.78				58.21				55.23				85.78			
Preliminary Bridge Cost Per Square Foot <sup>(6)</sup>	293.84				314.80				314.80				257.45				275.80				275.80			
Preliminary Total Construction Cost Multiplier	N/A	1.04	1.27	1.15	N/A	1.06	1.30	1.18	N/A	1.21	1.43	1.32	N/A	1.00	1.24	1.11	N/A	1.02	1.26	1.14	N/A	1.16	1.38	1.27

<sup>(1)</sup> Incidental Bridge includes demolition of the existing bridge & sheet pile walls and the construction of new concrete sheet pile walls.

<sup>(2)</sup> Phased Construction is 20% of the sum of Bridge Construction and Incidental Bridge.

<sup>(3)</sup> Mobilization and Contingency are each taken as a percentage of the sum of Roadway Construction, Bridge Construction, and Incidental Bridge. The percentages used are 20% and 10%, respectively.

<sup>(4)</sup> Bridge and Roadway design is estimated at 24% of the total bridge and roadway construction cost. Utility design is estimated at 15% of the total utility cost for the remain in-place alternative and 5% for all other alternatives.

<sup>(5)</sup> Construction Engineering & Inspection for the aerial crossing replacement and subaqueous replacement alternatives taken as 16%, and 14% of the total construction cost, respectively.

<sup>(6)</sup> Preliminary Bridge and Roadway Cost Per Square Foot calculated by dividing Roadway and Bridge Construction by bridge deck area seen in Appendix C.

Table 5-1 – Alternatives Evaluation Matrix

# Appendix A: Construction Cost Estimates

[THE REMAINDER OF THIS PAGE IS INTENTIONALLY LEFT BLANK]

**Bridge Alternatives Cost Summary**

Upper Manatee River Road

Mill Creek - Addendum



Designed By: BAH 09/2021

Checked By: SAB 09/2021

Detailed quantities and associated construction cost estimates were developed for the two-lane bridge replacement alternatives as part of the Technical Memorandum for Bridge Replacement at Upper Manatee River Road over Mill Creek. These detailed calculations have been used for the determination of average cost per square foot for bridge replacement (bridge elements only) and average costs per linear foot of bulkhead seawall installation. These average costs are utilized within this Addendum for the determination of bridge replacement costs for the four-lane alternatives considered.

**Table 1-1: Bridge Cost Summary**

Typical Section Alternative	Superstructure Alternative	Bridge Cost Per Square Foot <sup>(1)</sup>	Bridge Length, ft	Bridge Width, ft	Incidental Structures Cost <sup>(2)</sup>	Total Bridge Cost Estimate <sup>(3)</sup>	Cost Factor
Rural	Flat Slab	\$202.04	120.00	62.67	\$923,900	\$2,516,503	1.09
	FSB 15	\$176.57				\$2,319,271	1.00
Urban	Flat Slab	\$202.04		67.17	\$965,983	\$2,672,221	1.15
	FSB 15	\$176.57				\$2,460,826	1.06
Urban with Alignment Shift	Flat Slab	\$202.04		67.17	\$965,983	\$3,191,098	1.38
	FSB 15	\$176.57				\$2,938,656	1.27

<sup>(1)</sup> Bridge Cost Per Square Foot includes the cost of construction of superstructure, substructure, and bridge deck grooving.

<sup>(2)</sup> Incidental structures cost includes the cost of construction of concrete sheet pile walls and approach slabs, and demolition of the existing structure.

<sup>(3)</sup> Total Bridge Cost includes bridge and incidental structures costs, as well as a 3% multiplier for over water construction for all alternatives, and a 20% multiplier for phased construction for the Urban with Alignment Shift alternative.



Detour - Rural Section, No Shift					
Pay Item No.	Pay Item	Unit	Quantity	Unit Cost	Line Item Cost
Traffic Control					
102-1	Maintenance of Traffic	LS/DA	1/660	\$ 27,500.00	\$ 27,500.00
102-60	Work Zone Sign	ED	96360	\$ 0.25	\$ 24,090.00
102-99	Portable Changeable Message Sign, Temporary	ED	4002	\$ 11.00	\$ 44,022.00
102-115	Type III Barricade	ED	2640	\$ 0.50	\$ 1,320.00
				<b>TCP Total</b>	<b>\$ 96,932.00</b>
Roadway Construction					
110-1-1	Clearing and Grubbing	AC	2.46	\$ 27,000.00	\$ 66,420.00
120-1	Regular Excavation	CY	1600	\$ 8.00	\$ 12,800.00
120-6	Embankment	CY	1750	\$ 5.00	\$ 8,750.00
160-4	Type B Stabilization	SY	2654	\$ 9.00	\$ 23,888.70
285-701	Optional Base, Base Group 01	SY	288	\$ 20.00	\$ 5,766.54
285-709	Optional Base, Base Group 09	SY	2575	\$ 20.00	\$ 51,493.42
334-1-13	Superpave Asphaltic Conc, Traffic C	TN	265.43	\$ 115.00	\$ 30,524.45
337-7-83	Asphalt Concrete Friction Course, Traffic C, FC-12.5, PG 76-22	TN	199.07	\$ 140.00	\$ 27,870.15
339-1	Miscellaneous Asphalt Pavement	TN	24.7	\$ 220.00	\$ 5,434.00
522-1	Concrete Sidewalk and Driveways, 4" Thick	SY	573	\$ 50.00	\$ 28,650.00
536-1-1	Guardrail - Roadway, General TL-3	LF	661	\$ 25.00	\$ 16,525.00
536-85-24	Guardrail End Treatment - Parallel Approach Terminal	EA	4	\$ 3,000.00	\$ 12,000.00
570-1-2	Performance Turf, Sod	SY	1351	\$ 3.50	\$ 4,728.89
				<b>Rdwy Total</b>	<b>\$ 294,851.15</b>
				<b>S&amp;PM Markup (7%)</b>	<b>\$ 20,639.58</b>
				<b>Grand Total</b>	<b>\$ 412,422.73</b>

Detour - Urban Section, No Shift					
Pay Item No.	Pay Item	Unit	Quantity	Unit Cost	Line Item Cost
Traffic Control					
102-1	Maintenance of Traffic	LS/DA	1/585	\$ 27,500.00	\$ 27,500.00
102-60	Work Zone Sign	ED	85410	\$ 0.25	\$ 21,352.50
102-99	Portable Changeable Message Sign, Temporary	ED	3552	\$ 11.00	\$ 39,072.00
102-115	Type III Barricade	ED	2340	\$ 0.50	\$ 1,170.00
				<b>TCP Total</b>	<b>\$ 89,094.50</b>
Roadway Construction					
110-1-1	Clearing and Grubbing	AC	2.43	\$ 27,000.00	\$ 65,610.00
120-1	Regular Excavation	CY	1600	\$ 8.00	\$ 12,800.00
120-6	Embankment	CY	1750	\$ 5.00	\$ 8,750.00
160-4	Type B Stabilization	SY	2654	\$ 9.00	\$ 23,888.70
285-701	Optional Base, Base Group 01	SY	140	\$ 20.00	\$ 2,800.00
285-709	Optional Base, Base Group 09	SY	2575	\$ 20.00	\$ 51,493.42
334-1-13	Superpave Asphaltic Conc, Traffic C	TN	265.4	\$ 115.00	\$ 30,524.45
337-7-83	Asphalt Concrete Friction Course, Traffic C, FC-12.5, PG 76-22	TN	199.1	\$ 140.00	\$ 27,870.15
520-1-10	Concrete Curb & Gutter, Type F	LF	835	\$ 32.00	\$ 26,720.00
522-1	Concrete Sidewalk and Driveways, 4" Thick	SY	497	\$ 50.00	\$ 24,850.00
570-1-2	Performance Turf, Sod	SY	1269	\$ 3.50	\$ 4,441.50
				<b>Rdwy Total</b>	<b>\$ 279,748.22</b>
				<b>S&amp;PM Markup (7%)</b>	<b>\$ 19,582.38</b>
				<b>Grand Total</b>	<b>\$ 388,425.10</b>

Phased - Urban Section, Alignment Shift (Index 102-608)					
Pay Item No.	Pay Item	Unit	Quantity	Unit Cost	Line Item Cost
<b>Traffic Control</b>					
102-1	Maintenance of Traffic	LS/DA	1/885	\$ 27,500.00	\$ 27,500.00
0102-2200	Special Detour - Temporary Pavement	LS/SY	2976	\$ 17.50	\$ 52,080.00
0102-2300	Special Detour - Temporary	LS/CY	500	\$ 25.00	\$ 12,500.00
102-60	Work Zone Sign	ED	14160	\$ 0.25	\$ 3,540.00
102-71-15	Temporary Barrier, F&I, Anchored	LF	750	\$ 25.00	\$ 18,750.00
102-74-1	Channelizing Device - Types I, II, DI, VP, Drum, or LCD	ED	36285	\$ 0.15	\$ 5,442.75
102-89-1	Temporary Crash Cushion, Redirective Option	LO	2	\$ 1,100.00	\$ 2,200.00
102-115	Type III Barricade	ED	7080	\$ 0.50	\$ 3,540.00
102-913-21	Removable Tape, White Solid, 6"	GM	0.461	\$ 12,000.00	\$ 5,533.14
102-913-31	Removable Tape, Yellow Solid, 6"	GM	0.461	\$ 12,000.00	\$ 5,533.14
				<b>TCP Total</b>	<b>\$ 109,119.02</b>
<b>Roadway Construction</b>					
110-1-1	Clearing and Grubbing	AC	3.72	\$ 27,000.00	\$ 100,440.00
120-1	Regular Excavation	CY	1925	\$ 8.00	\$ 15,400.00
120-6	Embankment	CY	2150	\$ 5.00	\$ 10,750.00
160-4	Type B Stabilization	SY	4148	\$ 9.00	\$ 37,332.90
285-701	Optional Base, Base Group 01	SY	529	\$ 20.00	\$ 10,582.74
285-709	Optional Base, Base Group 09	SY	4024	\$ 20.00	\$ 80,473.14
334-1-13	Superpave Asphaltic Conc, Traffic C	TN	414.8	\$ 115.00	\$ 47,703.15
337-7-83	Asphalt Concrete Friction Course, Traffic C, FC-12.5, PG 76-22	TN	311.108	\$ 140.00	\$ 43,555.05
520-1-10	Concrete Curb & Gutter, Type F	LF	937	\$ 32.00	\$ 29,984.00
522-1	Concrete Sidewalk and Driveways, 4" Thick	SY	1006	\$ 50.00	\$ 50,300.00
570-1-2	Performance Turf, Sod	SY	2289	\$ 3.50	\$ 8,011.11
				<b>Rdwy Total</b>	<b>\$ 434,532.09</b>
				<b>S&amp;PM Markup (7%)</b>	<b>\$ 30,417.25</b>
				<b>Grand Total</b>	<b>\$ 574,068.36</b>

Detour - Rural Section, No Shift					
Pay Item No.	Pay Item	Unit	Quantity	Unit Cost	Line Item Cost
Traffic Control					
102-1	Maintenance of Traffic	LS/DA	1/630	\$ 27,500.00	\$ 27,500.00
102-60	Work Zone Sign	ED	91980	\$ 0.25	\$ 22,995.00
102-99	Portable Changeable Message Sign, Temporary	ED	3822	\$ 11.00	\$ 42,042.00
102-115	Type III Barricade	ED	2520	\$ 0.50	\$ 1,260.00
				<b>TCP Total</b>	<b>\$ 93,797.00</b>
Roadway Construction					
110-1-1	Clearing and Grubbing	AC	2.46	\$ 27,000.00	\$ 66,420.00
120-1	Regular Excavation	CY	1600	\$ 8.00	\$ 12,800.00
120-6	Embankment	CY	1750	\$ 5.00	\$ 8,750.00
160-4	Type B Stabilization	SY	2654	\$ 9.00	\$ 23,888.70
285-701	Optional Base, Base Group 01	SY	288	\$ 20.00	\$ 5,766.54
285-709	Optional Base, Base Group 09	SY	2575	\$ 20.00	\$ 51,493.42
334-1-13	Superpave Asphaltic Conc, Traffic C	TN	265.43	\$ 115.00	\$ 30,524.45
337-7-83	Asphalt Concrete Friction Course, Traffic C, FC-12.5, PG 76-22	TN	199.07	\$ 140.00	\$ 27,870.15
339-1	Miscellaneous Asphalt Pavement	TN	24.7	\$ 220.00	\$ 5,434.00
522-1	Concrete Sidewalk and Driveways, 4" Thick	SY	573	\$ 50.00	\$ 28,650.00
536-1-1	Guardrail - Roadway, General TL-3	LF	661	\$ 25.00	\$ 16,525.00
536-85-24	Guardrail End Treatment - Parallel Approach Terminal	EA	4	\$ 3,000.00	\$ 12,000.00
570-1-2	Performance Turf, Sod	SY	1351	\$ 3.50	\$ 4,728.89
				<b>Rdwy Total</b>	<b>\$ 294,851.15</b>
				<b>S&amp;PM Markup (7%)</b>	<b>\$ 20,639.58</b>
				<b>Grand Total</b>	<b>\$ 409,287.73</b>

Remain and Rehabilitate					
Item No.	Description	Quantity	Unit	Unit Cost	Total Cost
<b>Structural</b>					
1	Saw Cut Exist. Conc. Strut to Bridge	25	CF	\$150	\$3,750
2	Rout Exposed Rebar & Grout Patch	27	EA	\$150	\$4,050
3	Mobilization Pile Contractor	1	LS	\$15,000	\$15,000
4	Temporary Steel Piles	390	LS	\$200	\$78,000
5	Temporary Pile Bracing	1	LS	\$7,500	\$7,500
6	Remove Temporary Piles & Bracing	1	LS	\$12,500	\$12,500
6	Reattach Exist. Pipe Suppt. to New Bridge	1	LS	\$15,000	\$15,000
8	Anchor Assemblies	1	LS	\$2,000	\$2,000
<b>Mechanical</b>					
1	Epoxy Coating System	2,376	SF	\$25	\$59,400
<i>Subtotal:</i>					\$197,200
<i>30% Contingency:</i>					\$59,160
<b>Total:</b>					<b>\$256,360</b>

Replace and Relocate					
Item No.	Description	Quantity	Unit	Unit Cost	Total Cost
<b>Structural</b>					
1	Remove Exist. Conc. Pipe Suppt. / Pile Cap	250	CF	\$70	\$17,500
2	Mobilization Pile Contractor	1	LS	\$15,000	\$15,000
3	Remove Exist. Conc. Piles	3	EA	\$5,000	\$15,000
4	Precast Reinforced Concrete Piles	1040	LS	\$250	\$260,000
5	CIP Reinf. Conc. Pipe Suppt. / Pile Cap	40	CY	\$1,500	\$60,000
6	2x P.T. Pile Bracing	1	LS	\$6,000	\$6,000
7	Anchor Assemblies	1	LS	\$3,000	\$3,000
<b>Mechanical</b>					
1	Remove Exist. PCCP Pipe	200	LF	\$100	\$20,000
2	42" Class 53 FL DI Pipe	200	LF	\$1,000	\$200,000
3	DI Fittings	6	Ton	\$20,000	\$112,760
4	Wet Tap	2	EA	\$275,000	\$550,000
6	Line Stop	2	EA	\$500,000	\$1,000,000
7	Reverse Deadman	45	CY	\$1,000	\$45,000
8	Air Release/Vacuum Valve	1	EA	\$12,000	\$12,000
9	Epoxy Coating System	2,376	SF	\$25	\$59,400
<i>Subtotal:</i>					\$2,375,660
<i>30% Contingency:</i>					\$712,698
<b>Total:</b>					<b>\$3,088,358</b>



# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - FOUR LANE ALTERNATIVES

DESIGNED BY: BAH 09/2021  
CHECKED BY: SAB 09/2021

Description: Mill Creek Environmental Impact Estimates

Surface waters and vegetated wetlands have been approximated based on the U.S. Fish & Wildlife Service (FWS) National Wetlands Inventory Wetlands Mapper tool on their website (<https://www.fws.gov/wetlands/data/Mapper.html>). Environmental impacts are approximated based on developed CAD drawings for this project.

For the purposes of this analysis, bridge and roadway elements which impact surface waters and vegetated wetlands have been quantified. No additional quantity for side slopes or other adjacent modifications have been made. Estimated impacts for the utility adjustments are based on the length of pipe effecting environmental resources, multiplied by 5.5ft. (pipe diameter + 2ft.).

Mitigation costs within this analysis are founded on the published Mitigation Bank Pricing Schedule, Effective Spring/Summer 2021 from Mitigation Marketing. Unit prices used are from the Tampa Bay Mitigation Bank, which is the closest available data source. This analysis utilizes a fee of \$225,000 per credit for Vegetated Wetland Impacts and \$120,000 per credit for Surface Water Impacts. Credits are equivalent to one acre disturbed multiplied a Uniform Mitigation Assessment Method (UMAM) factor. UMAM factors for Vegetated Wetlands and Surface Waters are estimated as 0.7 and 0.5, respectively.

Impacted Resource	Base Credit Rate	UMAM Factor	Cost per Acre
Vegetated Wetland	\$225,000	0.7	\$322,000
Surface Waters	\$120,000	0.5	\$240,000

No Alignment Shift, Rural Bridge Section w/ 42" PWM Aerial Crossing				
Impacted Resource	Impact Source	Impact Area	Mitigation Rate	Impact Mitigation Cost
Veg. Wetland	North End of Bridge	0.000	\$322,000.00	\$0
Veg. Wetland	South End of Bridge	0.000	\$322,000.00	\$0
Veg. Wetland	Utility	0.000	\$322,000.00	\$0
Surface Waters	North End of Bridge	0.042	\$240,000.00	\$10,080
Surface Waters	South End of Bridge	0.038	\$240,000.00	\$9,120
Surface Waters	Utility	0.017	\$240,000.00	\$4,080
Total		0.097		\$23,280

No Alignment Shift, Rural Bridge Section w/ 42" PWM Subaqueous Crossing (J&B)				
Impacted Resource	Impact Source	Impact Area	Mitigation Rate	Impact Mitigation Cost
Veg. Wetland	North End of Bridge	0.000	\$322,000.00	\$0
Veg. Wetland	South End of Bridge	0.000	\$322,000.00	\$0
Veg. Wetland	Utility	0.012	\$322,000.00	\$3,864
Surface Waters	North End of Bridge	0.042	\$240,000.00	\$10,080
Surface Waters	South End of Bridge	0.038	\$240,000.00	\$9,120
Surface Waters	Utility	0.020	\$240,000.00	\$4,800
Total		0.112		\$27,864

No Alignment Shift, Rural Bridge Section w/ 42" PWM Subaqueous Crossing (HDD)				
Impacted Resource	Impact Source	Impact Area	Mitigation Rate	Impact Mitigation Cost
Veg. Wetland	North End of Bridge	0.000	\$322,000.00	\$0
Veg. Wetland	South End of Bridge	0.000	\$322,000.00	\$0
Veg. Wetland	Utility	0.036	\$322,000.00	\$11,592
Surface Waters	North End of Bridge	0.042	\$240,000.00	\$10,080
Surface Waters	South End of Bridge	0.038	\$240,000.00	\$9,120
Surface Waters	Utility	0.038	\$240,000.00	\$9,120
Total		0.154		\$39,912

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - FOUR LANE ALTERNATIVES

DESIGNED BY: BAH 09/2021  
CHECKED BY: SAB 09/2021

Description: Mill Creek Environmental Impact Estimates

No Alignment Shift, Urban Bridge Section w/ 42" PWM Aerial Crossing				
Impacted Resource	Impact Source	Impact Area	Mitigation Rate	Impact Mitigation Cost
Veg. Wetland	North End of Bridge	0.001	\$322,000.00	\$322
Veg. Wetland	South End of Bridge	0.001	\$322,000.00	\$322
Veg. Wetland	Utility	0.000	\$322,000.00	\$0
Surface Waters	North End of Bridge	0.048	\$240,000.00	\$11,520
Surface Waters	South End of Bridge	0.044	\$240,000.00	\$10,560
Surface Waters	Utility	0.018	\$240,000.00	\$4,320
Total		0.112		\$27,044

No Alignment Shift, Urban Bridge Section w/ 42" PWM Subaqueous Crossing (J&B)				
Impacted Resource	Impact Source	Impact Area	Mitigation Rate	Impact Mitigation Cost
Veg. Wetland	North End of Bridge	0.001	\$322,000.00	\$322
Veg. Wetland	South End of Bridge	0.001	\$322,000.00	\$322
Veg. Wetland	Utility	0.013	\$322,000.00	\$4,186
Surface Waters	North End of Bridge	0.048	\$240,000.00	\$11,520
Surface Waters	South End of Bridge	0.044	\$240,000.00	\$10,560
Surface Waters	Utility	0.020	\$240,000.00	\$4,800
Total		0.127		\$31,710

No Alignment Shift, Urban Bridge Section w/ 42" PWM Subaqueous Crossing (HDD)				
Impacted Resource	Impact Source	Impact Area	Mitigation Rate	Impact Mitigation Cost
Veg. Wetland	North End of Bridge	0.001	\$322,000.00	\$322
Veg. Wetland	South End of Bridge	0.001	\$322,000.00	\$322
Veg. Wetland	Utility	0.037	\$322,000.00	\$11,914
Surface Waters	North End of Bridge	0.048	\$240,000.00	\$11,520
Surface Waters	South End of Bridge	0.044	\$240,000.00	\$10,560
Surface Waters	Utility	0.038	\$240,000.00	\$9,120
Total		0.169		\$43,758

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - FOUR LANE ALTERNATIVES

DESIGNED BY: BAH 09/2021  
CHECKED BY: SAB 09/2021

Description: Mill Creek Environmental Impact Estimates

Alignment Shift, Urban Bridge Section w/ 42" PWM Aerial Crossing				
Impacted Resource	Impact Source	Impact Area	Mitigation Rate	Impact Mitigation Cost
Veg. Wetland	North End of Bridge and Roadway	0.114	\$322,000.00	\$36,708
Veg. Wetland	South End of Bridge	0.000	\$322,000.00	\$0
Veg. Wetland	Utility	0.000	\$322,000.00	\$0
Surface Waters	North End of Bridge	0.113	\$240,000.00	\$27,120
Surface Waters	South End of Bridge	0.000	\$240,000.00	\$0
Surface Waters	Utility	0.015	\$240,000.00	\$3,600
Total		0.242		\$67,428

Alignment Shift, Urban Bridge Section w/ 42" PWM Subaqueous Crossing (J&B)				
Impacted Resource	Impact Source	Impact Area	Mitigation Rate	Impact Mitigation Cost
Veg. Wetland	North End of Bridge and Roadway	0.114	\$322,000.00	\$36,708
Veg. Wetland	South End of Bridge	0.000	\$322,000.00	\$0
Veg. Wetland	Utility	0.007	\$322,000.00	\$2,254
Surface Waters	North End of Bridge	0.113	\$240,000.00	\$27,120
Surface Waters	South End of Bridge	0.000	\$240,000.00	\$0
Surface Waters	Utility	0.018	\$240,000.00	\$4,320
Total		0.252		\$70,402

Alignment Shift, Urban Bridge Section w/ 42" PWM Subaqueous Crossing (HDD)				
Impacted Resource	Impact Source	Impact Area	Mitigation Rate	Impact Mitigation Cost
Veg. Wetland	North End of Bridge and Roadway	0.114	\$322,000.00	\$36,708
Veg. Wetland	South End of Bridge	0.000	\$322,000.00	\$0
Veg. Wetland	Utility	0.028	\$322,000.00	\$9,016
Surface Waters	North End of Bridge	0.113	\$240,000.00	\$27,120
Surface Waters	South End of Bridge	0.000	\$240,000.00	\$0
Surface Waters	Utility	0.021	\$240,000.00	\$5,040
Total		0.276		\$77,884

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - FOUR LANE ALTERNATIVES

DESIGNED BY: SAB 09/2021  
CHECKED BY: BAH 09/2021

Description: Mill Creek R/W Estimates

Based on data obtained from Manatee County's GIS database, there are seven parcels which are effected by the proposed bridge replacement activities at Upper Manatee River Road over Mill Creek. Based on a field review, R/W impacts are not anticipated effect dwelling structures, with the exception of the northeast parcel immediately adjacent to the bridge. The parcels are listed as follows:

- Parcel 1 - E. Pons, Northwest Corner of Bridge
- Parcel 2 - M. Perez, Northeast Corner of Bridge
- Parcel 3 - M. Boston, 2nd Parcel Northeast of Bridge
- Parcel 4 - W. Sprinkle, 3rd Parcel Northeast of Bridge
- Parcel 5 - J. Jackson, 4th Parcel Northeast of Bridge
- Parcel 6 - M/I Homes of Tampa, Southwest Corner of Bridge
- Parcel 7 - Hidden Oaks of Manatee County HOA, Southeast Corner of Bridge
- Parcel 8 - Mill Creek Association, Southeast Corner of Bridge

The total amount of estimated required Right-of-Way acquisition varies according to the bridge replacement and 42" Potable Water Main replacement selected. The total quantities of estimated R/W acquisition have been taken from the CAD drawings developed for this project. Manatee County has provided an anticipated cost per square foot of R/W acquisition at \$7.00 per square foot. This value will be utilized for the determination of acquisition overall costs. For alternatives which effect dwelling structures at a parcel, it is assumed that the entire parcel must be acquired and that a 35% increase in acquisition cost is included for anticipated legal fees.

No Alignment Shift, Rural Bridge Section w/ 42" PWM Aerial Crossing				
Parcel No.	Total R/W Req. (AC)	Dwelling Effected?	Unit Cost (\$/SF)	R/W Acquisition Fee
1	0.124	No	\$7.00	\$37,810.23
2	0.158	Yes	\$110.33	\$759,375.00
3	0.079	No	\$7.00	\$24,088.77
4	0.000	No	\$7.00	\$0.00
5	0.000	No	\$7.00	\$0.00
6	0.032	No	\$7.00	\$9,757.48
7	0.016	No	\$7.00	\$4,878.74
8	0.034	No	\$7.00	\$10,367.32
Total	0.443			\$846,277.54

No Alignment Shift, Rural Bridge Section w/ 42" PWM Subaqueous Crossing (J&B)				
Parcel No.	Total R/W Req. (AC)	Dwelling Effected?	Unit Cost (\$/SF)	R/W Acquisition Fee
1	0.124	No	\$7.00	\$37,810.23
2	0.158	Yes	\$110.33	\$759,375.00
3	0.079	No	\$7.00	\$24,088.77
4	0.000	No	\$7.00	\$0.00
5	0.000	No	\$7.00	\$0.00
6	0.114	No	\$7.00	\$34,761.02
7	0.073	No	\$7.00	\$22,259.25
8	0.034	No	\$7.00	\$10,367.32
Total	0.582			\$888,661.58

No Alignment Shift, Rural Bridge Section w/ 42" PWM Subaqueous Crossing (HDD)				
Parcel No.	Total R/W Req. (AC)	Dwelling Effected?	Unit Cost (\$/SF)	R/W Acquisition Fee
1	0.124	No	\$7.00	\$37,810.23
2	0.158	Yes	\$110.33	\$759,375.00
3	0.079	No	\$7.00	\$24,088.77
4	0.000	No	\$7.00	\$0.00
5	0.000	No	\$7.00	\$0.00
6	0.216	No	\$7.00	\$65,862.98
7	0.153	No	\$7.00	\$46,652.94
8	0.451	No	\$7.00	\$137,519.46
Total	1.181			\$1,071,309.38

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - FOUR LANE ALTERNATIVES

DESIGNED BY: SAB 09/2021  
CHECKED BY: BAH 09/2021

Description: Mill Creek R/W Estimates

No Alignment Shift, Urban Bridge Section w/ 42" PWM Aerial Crossing				
Parcel No.	Total R/W Req. (AC)	Dwelling Effected?	Unit Cost (\$/SF)	R/W Acquisition Fee
1	0.151 .	No .	\$7.00 .	\$46,043.10 .
2	0.142 .	Yes .	\$122.77 .	\$759,375.00 .
3	0.010 .	No .	\$7.00 .	\$3,049.21 .
4	0.000 .	No .	\$7.00 .	\$0.00 .
5	0.000 .	No .	\$7.00 .	\$0.00 .
6	0.041 .	No .	\$7.00 .	\$12,501.77 .
7	0.023 .	No .	\$7.00 .	\$7,013.19 .
8	0.042 .	No .	\$7.00 .	\$12,806.69 .
Total	0.409			\$840,788.96 .

No Alignment Shift, Urban Bridge Section w/ 42" PWM Subaqueous Crossing (J&B)				
Parcel No.	Total R/W Req. (AC)	Dwelling Effected?	Unit Cost (\$/SF)	R/W Acquisition Fee
1	0.151 .	No .	\$7.00 .	\$46,043.10 .
2	0.142 .	Yes .	\$122.77 .	\$759,375.00 .
3	0.010 .	No .	\$7.00 .	\$3,049.21 .
4	0.000 .	No .	\$7.00 .	\$0.00 .
5	0.000 .	No .	\$7.00 .	\$0.00 .
6	0.123 .	No .	\$7.00 .	\$37,505.31 .
7	0.081 .	No .	\$7.00 .	\$24,698.62 .
8	0.042 .	No .	\$7.00 .	\$12,806.69 .
Total	0.549			\$883,477.92 .

No Alignment Shift, Urban Bridge Section w/ 42" PWM Subaqueous Crossing (HDD)				
Parcel No.	Total R/W Req. (AC)	Dwelling Effected?	Unit Cost (\$/SF)	R/W Acquisition Fee
1	0.151 .	No .	\$7.00 .	\$46,043.10 .
2	0.142 .	Yes .	\$122.77 .	\$759,375.00 .
3	0.010 .	No .	\$7.00 .	\$3,049.21 .
4	0.000 .	No .	\$7.00 .	\$0.00 .
5	0.000 .	No .	\$7.00 .	\$0.00 .
6	0.232 .	No .	\$7.00 .	\$70,741.72 .
7	0.153 .	No .	\$7.00 .	\$46,652.94 .
8	0.464 .	No .	\$7.00 .	\$141,483.43 .
Total	1.152			\$1,067,345.40 .



# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - FOUR LANE ALTERNATIVES

DESIGNED BY: SAB 09/2021  
CHECKED BY: BAH 09/2021

Description: Mill Creek R/W Estimates

Alignment Shift, Urban Bridge Section w/ 42" PWM Aerial Crossing				
Parcel No.	Total R/W Req. (AC)	Dwelling Effected?	Unit Cost (\$/SF)	R/W Acquisition Fee
1	0.421 .	No .	\$7.00 .	\$128,371.82 .
2	0.236 .	Yes .	\$73.87 .	\$759,375.00 .
3	0.100 .	No .	\$7.00 .	\$30,492.12 .
4	0.030 .	No .	\$7.00 .	\$9,147.64 .
5	0.011 .	No .	\$7.00 .	\$3,354.13 .
6	0.000 .	No .	\$7.00 .	\$0.00 .
7	0.000 .	No .	\$7.00 .	\$0.00 .
8	0.000 .	No .	\$7.00 .	\$0.00 .
Total	0.798			\$930,740.71 .

Alignment Shift, Urban Bridge Section w/ 42" PWM Subaqueous Crossing (J&B)				
Parcel No.	Total R/W Req. (AC)	Dwelling Effected?	Unit Cost (\$/SF)	R/W Acquisition Fee
1	0.421 .	No .	\$7.00 .	\$128,371.82 .
2	0.236 .	Yes .	\$73.87 .	\$759,375.00 .
3	0.100 .	No .	\$7.00 .	\$30,492.12 .
4	0.030 .	No .	\$7.00 .	\$9,147.64 .
5	0.011 .	No .	\$7.00 .	\$3,354.13 .
6	0.000 .	No .	\$7.00 .	\$0.00 .
7	0.000 .	No .	\$7.00 .	\$0.00 .
8	0.010 .	No .	\$7.00 .	\$3,049.21 .
Total	0.808			\$933,789.92 .

Alignment Shift, Urban Bridge Section w/ 42" PWM Subaqueous Crossing (HDD)				
Parcel No.	Total R/W Req. (AC)	Dwelling Effected?	Unit Cost (\$/SF)	R/W Acquisition Fee
1	0.421 .	No .	\$7.00 .	\$128,371.82 .
2	0.236 .	Yes .	\$73.87 .	\$759,375.00 .
3	0.100 .	No .	\$7.00 .	\$30,492.12 .
4	0.030 .	No .	\$7.00 .	\$9,147.64 .
5	0.011 .	No .	\$7.00 .	\$3,354.13 .
6	0.061 .	No .	\$7.00 .	\$18,600.19 .
7	0.039 .	No .	\$7.00 .	\$11,891.93 .
8	0.227 .	No .	\$7.00 .	\$69,217.11 .
Total	1.125			\$1,030,449.94 .

# Appendix B: Construction Time Calculations

[THE REMAINDER OF THIS PAGE IS INTENTIONALLY LEFT BLANK]

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Flat Slab Bridge, 4-Lane Rural Section, Detour •

Note: This construction time calculations is based on engineering judgement, assuming construction operations which are typical •  
for the bridge type and detoured construction. Field conditions which are unknown at this time are not accounted for.

Phase I - Detour and Bridge Demolition •							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Mobilization	Mobilize	-	4 •	-	1 •	20 •	Transport equipment to site. •
MOT	Maintenance of Traffic Setup	-	2 •	-	1 •	10 •	Setup detour signage. •
Clearing and Grubbing	Clear and Grub	-	1 •	-	1 •	5 •	Clear channel and approaches. •
Demolition	Demo of Existing Bridge	-	5 •	-	1 •	25 •	Complete demo. •
Total:						60 •	

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Flat Slab Bridge, 4-Lane Rural Section, Detour

Phase II - Install Replacement Bridge							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Sheet Pile Walls	Grading	2	1	-	1	7	
	Install Sheet Piling	1	3	-	2	32	
	Install Wall Cap Reinforcing	2	1	-	2	14	
	Install Wall Cap Concrete	2	1	-	2	14	Assumes substructure construction begins prior to sheet pile cap reaching full strength.
Substructure	Install Piling	3	1	-	5	40	
	Install Cap Reinforcing	-	1	-	5	25	
	Inst. Cap Concrete	1	1	-	5	28	Assumes cap fully cured before superstruction installation.
Superstructure	Inst. Bearing Pads	3	-	-	5	15	
	Install Deck Forms	3	1	-	4	32	
	Install Deck Reinforcing	-	2	-	4	40	
	Install Deck Concrete	3	1	-	4	32	
	Install Appr. Slabs	-	3	-	2	30	
	Install Barrier Reinforcing	3	1	-	4	32	Assumes installation prior to full deck cure.
	Install Barrier Concrete	3	1	-	4	32	Assumes installation prior to full deck cure.
	Deck Grooving	-	1	-	1	5	
	Install Guardrail	2	1	-	1	7	
	Stripe Deck and Approaches	2	-	-	1	2	
Site Restoration	Sodding and Site Cleaning	-	2	-	1	10	
Demobilization	Demobilize	-	1	-	1	5	
MOT	Remove MOT Setup	-	1	-	1	5	
Total:						407	

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Flat Slab Bridge, 4-Lane Rural Section, Detour

Working Day Total:	467	(Sum of Phases I & II)
Time Multiplier:	1.4	(5 Day Work Week + No Holidays)
Month Total:	22	
Use:	660 Days	22 Months x (30 Day/Month)

Note: Construction time calculations assume that approach roadway work and utility work is performed concurrently with bridge work.



# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Flat Slab Bridge, 4-Lane Urban Section, Detour •

Note: This construction time calculations is based on engineering judgement, assuming construction operations which are typical •  
for the bridge type and detoured construction. Field conditions which are unknown at this time are not accounted for.

Phase I - Detour and Bridge Demolition •							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Mobilization	Mobilize	-	4 •	-	1 •	20 •	Transport equipment to site. •
MOT	Maintenance of Traffic Setup	-	2 •	-	1 •	10 •	Setup detour signage. •
Clearing and Grubbing	Clear and Grub	-	1 •	-	1 •	5 •	Clear channel and approaches. •
Demolition	Demo of Existing Bridge	-	5 •	-	1 •	25 •	Complete demo. •
Total:						60 •	

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Flat Slab Bridge, 4-Lane Urban Section, Detour

Phase II - Install Replacement Bridge							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Sheet Pile Walls	Grading	2	1	-	1	7	
	Install Sheet Piling	1	3	-	2	32	
	Install Wall Cap Reinforcing	2	1	-	2	14	
	Install Wall Cap Concrete	2	1	-	2	14	Assumes substructure construction begins prior to sheet pile cap reaching full strength.
Substructure	Install Piling	3	1	-	5	40	
	Install Cap Reinforcing	-	1	-	5	25	
	Inst. Cap Concrete	1	1	-	5	28	Assumes cap fully cured before superstruction installation.
Superstructure	Inst. Bearing Pads	3	-	-	5	15	
	Install Deck Forms	3	1	-	4	32	
	Install Deck Reinforcing	-	2	-	4	40	
	Install Deck Concrete	3	1	-	4	32	Includes sidewalk. See Barrier notes below.
	Install Appr. Slabs	-	3	-	2	30	
	Install Barrier Reinforcing	3	1	-	2	16	Assumes installation prior to full deck cure.
	Install Barrier Concrete	3	1	-	2	16	Assumes installation prior to full deck cure.
	Deck Grooving	-	1	-	1	5	
	Install Guardrail	2	1	-	1	7	
	Stripe Deck and Approaches	2	-	-	1	2	
Site Restoration	Sodding and Site Cleaning	-	2	-	1	10	
Demobilization	Demobilize	-	1	-	1	5	
MOT	Remove MOT Setup	-	1	-	1	5	
Total:						375	

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Flat Slab Bridge, 4-Lane Urban Section, Detour •

Working Day Total:	435 •	(Sum of Phases I & II)
Time Multiplier:	1.4 •	(5 Day Work Week + No Holidays)
Month Total:	20.5 •	
Use:	<b>615 Days</b>	• 20.5 Months x (30 Day/Month)

Note: Construction time calculations assume that approach roadway work and utility work is performed concurrently with bridge work. •

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Flat Slab Bridge, 4-Lane Urban Section, Phased •

Note: This construction time calculations is based on engineering judgement, assuming construction operations which are typical for the bridge type and phased construction. Field conditions which are unknown at this time are not accounted for. •

Phase I - Project Setup •							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Mobilization	Mobilize	-	4 •	-	1 •	20 •	Transport initial equipment to site. •
MOT	Maintenance of Traffic Setup	-	2 •	-	1 •	10 •	Setup signage. •
Clearing and Grubbing	Clear and Grub	-	1 •	-	1 •	5 •	Clear channel and approaches. •
Demolition Prep	Install Temp. Sheet Pile	-	1 •	-	2 •	10 •	
Total:						45 •	

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Flat Slab Bridge, 4-Lane Urban Section, Phased

Phase II - Install Partial Replacement Bridge							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Sheet Pile Walls	Grading	-	1	-	1	5	
	Install Sheet Piling	-	2	-	2	20	Includes temp. walls.
	Install Wall Cap Reinforcing	3	-	-	2	6	
	Install Wall Cap Concrete	-	1	-	2	10	Assumes substructure construction begins prior to sheet pile cap reaching full strength.
Substructure	Install Piling	-	1	-	5	25	
	Install Cap Reinforcing	-	1	-	5	25	
	Inst. Cap Concrete	1	1	-	5	28	Assumes cap fully cured before superstruction installation.
Superstructure	Inst. Bearing Pads	2	-	-	4	8	
	Install Deck Forms	2	1	-	4	28	
	Install Deck Reinforcing	-	1	-	4	20	
	Install Deck Concrete	2	1	-	4	28	Includes sidewalk. See Barrier notes below.
	Install Appr. Slabs	-	2	-	2	20	
	Install Barrier Reinforcing	-	2	-	1	10	Assumes installation prior to full deck cure.
	Install Barrier Concrete	-	1	-	1	5	Assumes installation prior to full deck cure.
	Deck Grooving	-	1	-	1	5	
MOT	Install Temp. Barrier	-	1	-	1	5	Anchored Type K-Barrier.
	Adjust Maintenance of Traffic Setup	-	3	-	1	15	
Total:						263	



# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Flat Slab Bridge, 4-Lane Urban Section, Phased

Phase III - Demolition of Existing Bridge and Finalize Replacement Bridge							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Demolition	Demo of Existing Bridge	-	6	-	1	30	Complete demo.
Sheet Pile Walls	Grading	-	1	-	1	5	
	Install Sheet Piling	-	2	-	2	20	Tie to existing walls.
	Install Wall Cap Reinforcing	-	1	-	2	10	Additional day for coupling.
	Install Wall Cap Concrete	-	1	-	2	10	Assumes substructure construction begins prior to sheet pile cap reaching full strength.
Substructure	Install Piling	-	1	-	5	25	
	Install Cap Reinforcing	1	1	-	5	30	Additional days for coupling.
	Inst. Cap Concrete	1	1	-	5	28	Assumes cap fully cured before superstruction installation.
Superstructure	Inst. Bearing Pads	2	-	-	4	8	
	Install Deck Forms	-	1	-	4	20	
	Install Deck Reinforcing	2	1	-	4	28	Additional days for coupling.
	Install Deck Concrete	2	1	-	4	28	Includes sidewalk. See Barrier notes below.
	Install Appr. Slabs	-	2	-	2	20	
	Install Barrier Reinforcing	-	2	-	1	10	Assumes installation prior to full deck cure.
	Install Barrier Concrete	-	1	-	1	5	Assumes installation prior to full deck cure.
	Deck Grooving	-	1	-	1	5	
	Install Guardrail	2	1	-	1	7	
MOT	Remove Temp. Barrier	3	-	-	1	3	Includes sealing of dowel holes.
	Restripe Bridge Deck	2	-	-	1	2	Includes approaches
	Remove MOT Setup	-	2	-	1	10	
Site Restoration	Sodding and Site Cleaning	-	2	-	2	20	
Demobilization	Demobilize	-	1	-	1	5	
Total:						329	

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Flat Slab Bridge, 4-Lane Urban Section, Phased •

Working Day Total:	637 •	(Sum of Phases I, II, & III)
Time Multiplier:	1.4 •	(5 Day Work Week + No Holidays)
Month Total:	30 •	
Use:	900 Days	30 Months x (30 Day/Month)

Note: Construction time calculations assume that approach roadway work and utility work is performed concurrently with bridge work. •

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Florida Slab Beam Bridge, 4-Lane Rural Section, Detour •

Note: This construction time calculations is based on engineering judgement, assuming construction operations which are typical •  
for the bridge type and detoured construction. Field conditions which are unknown at this time are not accounted for.

Phase I - Detour and Bridge Demolition •							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Mobilization	Mobilize	-	4 •	-	1 •	20 •	Transport equipment to site. •
MOT	Maintenance of Traffic Setup	-	2 •	-	1 •	10 •	Setup detour signage. •
Clearing and Grubbing	Clear and Grub	-	1 •	-	1 •	5 •	Clear channel and approaches. •
Demolition	Demo of Existing Bridge	-	5 •	-	1 •	25 •	Complete demo. •
Total:						60 •	

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Florida Slab Beam Bridge, 4-Lane Rural Section, Detour

Phase II - Install Replacement Bridge							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Sheet Pile Walls	Grading	2	1	-	1	7	
	Install Sheet Piling	1	3	-	2	32	
	Install Wall Cap Reinforcing	2	1	-	2	14	
	Install Wall Cap Concrete	2	1	-	2	14	Assumes substructure construction begins prior to sheet pile cap reaching full strength.
Substructure	Install Piling	3	1	-	5	40	
	Install Cap Reinforcing	-	1	-	5	25	
	Inst. Cap Concrete	1	1	-	5	28	Assumes cap fully cured before superstruction installation.
Superstructure	Inst. Bearing Pads	3	-	-	5	15	
	Install FSBs	-	1	-	4	20	
	Install Back Rod and Deck Reinf.	2	1	-	4	28	
	Install Deck Concrete	3	1	-	4	32	Includes sidewalk. See Barrier notes below.
	Install Appr. Slabs	-	3	-	2	30	
	Install Barrier Reinforcing	3	1	-	4	32	Assumes installation prior to full deck cure.
	Install Barrier Concrete	3	1	-	4	32	Assumes installation prior to full deck cure.
	Deck Grooving	-	1	-	1	5	
	Install Guardrail	2	1	-	1	7	
	Stripe Deck and Approaches	2	-	-	1	2	
Site Restoration	Sodding and Site Cleaning	-	2	-	1	10	
Demobilization	Demobilize	-	1	-	1	5	
MOT	Remove MOT Setup	-	1	-	1	5	
Total:						383	

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Florida Slab Beam Bridge, 4-Lane Rural Section, Detour •

Working Day Total:	443 •	(Sum of Phases I & II)
Time Multiplier:	1.4 •	(5 Day Work Week + No Holidays)
Month Total:	21 •	
Use:	630 Days	21 Months x (30 Day/Month)

Note: Construction time calculations assume that approach roadway work and utility work is performed concurrently with bridge •  
work.



# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Florida Slab Beam Bridge, 4-Lane Urban Section, Detour

Note: This construction time calculations is based on engineering judgement, assuming construction operations which are typical for the bridge type and detoured construction. Field conditions which are unknown at this time are not accounted for.

Phase I - Detour and Bridge Demolition							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Mobilization	Mobilize	-	4	-	1	20	Transport equipment to site.
MOT	Maintenance of Traffic Setup	-	2	-	1	10	Setup detour signage.
Clearing and Grubbing	Clear and Grub	-	1	-	1	5	Clear channel and approaches.
Demolition	Demo of Existing Bridge	-	5	-	1	25	Complete demo.
Total:						60	

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Florida Slab Beam Bridge, 4-Lane Urban Section, Detour

Phase II - Install Replacement Bridge							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Sheet Pile Walls	Grading	2	1	-	1	7	
	Install Sheet Piling	1	3	-	2	32	
	Install Wall Cap Reinforcing	2	1	-	2	14	
	Install Wall Cap Concrete	2	1	-	2	14	Assumes substructure construction begins prior to sheet pile cap reaching full strength.
Substructure	Install Piling	3	1	-	5	40	
	Install Cap Reinforcing	-	1	-	5	25	
	Inst. Cap Concrete	1	1	-	5	28	Assumes cap fully cured before superstruction installation.
Superstructure	Inst. Bearing Pads	3	-	-	5	15	
	Install FSBs	-	1	-	4	20	
	Install Back Rod and Deck Reinf.	2	1	-	4	28	
	Install Deck Concrete	3	1	-	4	32	Includes sidewalk. See Barrier notes below.
	Install Appr. Slabs	-	3	-	2	30	
	Install Barrier Reinforcing	3	1	-	2	16	Assumes installation prior to full deck cure.
	Install Barrier Concrete	3	1	-	2	16	Assumes installation prior to full deck cure.
	Deck Grooving	-	1	-	1	5	
	Install Guardrail	2	1	-	1	7	
	Stripe Deck and Approaches	2	-	-	1	2	
Site Restoration	Sodding and Site Cleaning	-	2	-	1	10	
Demobilization	Demobilize	-	1	-	1	5	
MOT	Remove MOT Setup	-	1	-	1	5	
Total:						351	

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Florida Slab Beam Bridge, 4-Lane Urban Section, Detour •

Working Day Total:	411 •	(Sum of Phases I & II)
Time Multiplier:	1.4 •	(5 Day Work Week + No Holidays)
Month Total:	19.5 •	
Use:	585 Days •	19.5 Months x (30 Day/Month)

Note: Construction time calculations assume that approach roadway work and utility work is performed concurrently with bridge work. •

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Florida Slab Beam Bridge, 4-Lane Urban Section, Phased •

Note: This construction time calculations is based on engineering judgement, assuming construction operations which are typical •  
for the bridge type and phased construction. Field conditions which are unknown at this time are not accounted for.

Phase I - Project Setup •							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Mobilization	Mobilize	-	4 •	-	1 •	20 •	Transport initial equipment to site. •
MOT	Maintenance of Traffic Setup	-	2 •	-	1 •	10 •	Setup signage. •
Clearing and Grubbing	Clear and Grub	-	1 •	-	1 •	5 •	Clear channel and approaches. •
Demolition Prep	Install Temp. Sheet Pile	-	1 •	-	2 •	10 •	
Total:						45 •	

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Florida Slab Beam Bridge, 4-Lane Urban Section, Phased

Phase II - Install Partial Replacement Bridge							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Sheet Pile Walls	Grading	-	1	-	1	5	
	Install Sheet Piling	-	2	-	2	20	Includes temp. walls.
	Install Wall Cap Reinforcing	3	-	-	2	6	
	Install Wall Cap Concrete	-	1	-	2	10	Assumes substructure construction begins prior to sheet pile cap reaching full strength.
Substructure	Install Piling	-	1	-	5	25	
	Install Cap Reinforcing	-	1	-	5	25	
	Inst. Cap Concrete	-	1	-	5	25	Assumes cap achieves 28 day comp. strength in 25 days.
Superstructure	Inst. Bearing Pads	2	-	-	4	8	
	Install FSBs	-	1	-	4	20	
	Install Backer Rod and Deck Reinf.	2	1	-	4	28	
	Install Deck Concrete	2	1	-	4	28	Includes sidewalk. See Barrier notes below.
	Install Appr. Slabs	-	2	-	2	20	
	Install Barrier Reinforcing	-	1	-	1	5	Assumes installation prior to full deck cure.
	Install Barrier Concrete	-	1	-	1	5	Assumes installation prior to full deck cure.
	Deck Grooving	-	1	-	1	5	
MOT	Install Temp. Barrier	-	1	-	1	5	Anchored Type K-Barrier.
	Adjust Maintenance of Traffic Setup	-	3	-	1	15	
Total:						255	

# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21

Description: Construction Time Calculation - Florida Slab Beam Bridge, 4-Lane Urban Section, Phased

Phase III - Demolition of Existing Bridge and Finalize Replacement Bridge							
Activity	Item	Time			Number	Working Days	Notes
		Day(s)	Week(s)	Month(s)			
Demolition	Demo of Existing Bridge	-	6	-	1	30	Complete demo.
Sheet Pile Walls	Grading	-	1	-	1	5	
	Install Sheet Piling	-	2	-	2	20	Tie to existing walls.
	Install Wall Cap Reinforcing	-	1	-	2	10	Additional days for coupling.
	Install Wall Cap Concrete	-	1	-	2	10	Assumes substructure construction begins prior to sheet pile cap reaching full strength.
Substructure	Install Piling	-	1	-	5	25	
	Install Cap Reinforcing	2	1	-	5	35	Additional days for coupling.
	Inst. Cap Concrete	-	1	-	5	25	Assumes cap achieves 28 day comp. strength in 25 days.
Superstructure	Inst. Bearing Pads	2	-	-	4	8	
	Install FSBs	-	1	-	4	20	
	Install Backer Rod and Deck Reinf.	2	1	-	4	28	Additional days for coupling.
	Install Deck Concrete	2	1	-	4	28	Includes sidewalk. See Barrier notes below.
	Install Appr. Slabs	-	2	-	2	20	
	Install Barrier Reinforcing	-	1	-	1	5	Assumes installation prior to full deck cure.
	Install Barrier Concrete	-	1	-	1	5	Assumes installation prior to full deck cure.
	Deck Grooving	-	1	-	1	5	
	Install Guardrail	2	1	-	1	7	
MOT	Remove Temp. Barrier	3	-	-	1	3	Includes sealing of dowel holes.
	Restripe Bridge Deck	3	-	-	1	3	Includes approaches
	Remove MOT Setup	-	1	-	1	5	
Site Restoration	Sodding and Site Cleaning	-	2	-	2	20	
Demobilization	Demobilize	-	1	-	1	5	
Total:						322	



# KISINGER CAMPO & ASSOCIATES

MANATEE COUNTY  
UPPER MANATEE RIVER ROAD  
MILL CREEK - ADDENDUM

DESIGNED BY: SAB 08/2021  
CHECKED BY: JHJ 09/21


Description: Construction Time Calculation - Florida Slab Beam Bridge, 4-Lane Urban Section, Phased •

Working Day Total:	622 •	(Sum of Phases I, II, & III)
Time Multiplier:	1.4 •	(5 Day Work Week + No Holidays)
Month Total:	29.5 •	
Use:	885 Days	• 29.5 Months x (30 Day/Month)

Note: Construction time calculations assume that approach roadway work and utility work is performed concurrently with bridge work. •


# Appendix C: Exhibits

[THE REMAINDER OF THIS PAGE IS INTENTIONALLY LEFT BLANK]




REVISIONS									DRAWN BY:	MANATEE COUNTY			SHEET TITLE:		REF. DWG. NO.
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION								PLAN VIEW DETOUR - FUTURE FOUR LANE RURAL		
										ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME:		SHEET NO.
											MANATEE	N / A	UPPER MANATEE RIVER ROAD BRIDGE DEVELOPMENT REPORT		






REVISIONS								DRAWN BY:	MANATEE COUNTY			SHEET TITLE:		REF. DWG. NO.
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION							PLAN VIEW DETOUR - FUTURE FOUR LANE URBAN		
									ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME:		SHEET NO.
									CHECKED BY:		MANATEE	N / A	UPPER MANATEE RIVER ROAD BRIDGE DEVELOPMENT REPORT	




URBAN TYPICAL SECTION



CROWNED ARTERIAL (RURAL) TYPICAL SECTION


REVISIONS							DRAWN BY:	MANATEE COUNTY			SHEET TITLE:		REF. DWG. NO.	
DATE	BY	DESCRIPTION		DATE	BY		DESCRIPTION				TYPICAL SECTION FULL DETOUR			
									DESIGNED BY:	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME:  UPPER MANATEE RIVER ROAD BRIDGE DEVELOPMENT REPORT	SHEET NO.
									CHECKED BY:		MANATEE	N / A		






REVISIONS									DRAWN BY:	MANATEE COUNTY			SHEET TITLE:  PLAN VIEW PHASED - FUTURE FOUR LANE URBAN		REF. DWG. NO.
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION										
										PROJECT NAME:  UPPER MANATEE RIVER ROAD BRIDGE DEVELOPMENT REPORT	SHEET NO.				





EXISTING TYPICAL SECTION


(BRIDGE NO. 134023)




PHASE I

(BRIDGE NO. 134023)

REVISIONS							DRAWN BY:	MANATEE COUNTY			SHEET TITLE:	REF. DWG. NO.
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION		CHECKED BY:				TYPICAL SECTION PHASED CONSTRUCTION (1 OF 2)	
							DESIGNED BY:	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME:	SHEET NO.
							CHECKED BY:		MANATEE	N/A	UPPER MANATEE RIVER ROAD BRIDGE DEVELOPMENT REPORT	




PHASE II



PROPOSED TYPICAL SECTION


REVISIONS							DRAWN BY:	MANATEE COUNTY			SHEET TITLE:		REF. DWG. NO.
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION		CHECKED BY:				TYPICAL SECTION PHASED CONSTRUCTION (2 OF 2)		
							DESIGNED BY: <th>ROAD NO.</th> <th>COUNTY</th> <th>FINANCIAL PROJECT ID</th> <th>PROJECT NAME:</th> <th>SHEET NO.</th>	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME:	SHEET NO.	
							CHECKED BY:		MANATEE	N/A	UPPER MANATEE RIVER ROAD BRIDGE DEVELOPMENT REPORT		





REVISIONS								DRAWN BY:	MANATEE COUNTY			SHEET TITLE:		REF. DWG. NO.
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION			CHECKED BY:				PLAN VIEW - PROJECT LIMITS FUTURE FOUR LANE RURAL - DETOUR		
								DESIGNED BY:	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME:	SHEET NO.	
								CHECKED BY:		MANATEE	N / A	UPPER MANATEE RIVER ROAD BRIDGE DEVELOPMENT REPORT		





LEGEND:

PROPOSED R/W LINE - HDD ALTERNATIVE

PROPOSED R/W LINE - JACK & BORE ALTERNATIVE

PROPOSED R/W LINE - BRIDGE OR ROADWAY CONTROLLED

APPROXIMATE 40' DEEDED R/W LINE

GIS PARCEL LINE

EXISTING - 42" PWM

PROPOSED AERIAL CROSSING - 42" PWM

PROPOSED SUBAQUEUOUS CROSSING (HDD) - 42" PWM


PROPOSED SUBAQUEUOUS CROSSING (J&B) - 42" PWM

APPROXIMATE SURFACE WATERS LIMITS

APPROXIMATE VEGETATED WETLAND LIMITS

REVISIONS							DRAWN BY:	MANATEE COUNTY			SHEET TITLE:		REF. DWG. NO.
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION		CHECKED BY:				PLAN VIEW - PROJECT LIMITS FUTURE FOUR LANE URBAN - DETOUR		
							DESIGNED BY:	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME:	SHEET NO.	
							CHECKED BY:		MANATEE	N/A	UPPER MANATEE RIVER ROAD BRIDGE DEVELOPMENT REPORT		






REVISIONS								DRAWN BY:	MANATEE COUNTY			SHEET TITLE:  PLAN VIEW - PROJECT LIMITS FUTURE FOUR LANE URBAN - PHASED		REF. DWG. NO.
DATE	BY	DESCRIPTION	DATE	BY	DESCRIPTION			CHECKED BY:						
								DESIGNED BY:	ROAD NO.	COUNTY	FINANCIAL PROJECT ID	PROJECT NAME:	SHEET NO.	
								CHECKED BY:		MANATEE	N / A	UPPER MANATEE RIVER ROAD BRIDGE DEVELOPMENT REPORT		



# Appendix D: Existing Bridge Plans

[THE REMAINDER OF THIS PAGE IS INTENTIONALLY LEFT BLANK]






MANATEE COUNTY  
ENGINEERING DEPARTMENT  
MILL CREEK BRIDGE

PLAN - SECTIONS & DET.			
Date	Revisions	By	Designed by




BAR SCHEDULE						
N <sup>o</sup>	Size	Length	Mark	Detail	Bar Length	Unit Weight
208	#4	33'-6"			6968	
50	#4	31'-6"			1575	
50	#4	31'-0"			1550	
72	#4	15'-0"			1080	
					11173	668
12	#3	31'-0"			372	
12	#3	31'-6"			378	
					750	376
208	#3	3'-10"	310		797	376
						282
						300



MANATEE COUNTY ENGINEERING DEPARTMENT			
MILL CREEK BRIDGE			
BRN - 134023			
RE-STEEL FOR DECK TOPPING			
Date	Revisions	By	Designed by
			Drawn
			Date
			Approved by





Prestressed Bridge Deck Schedule

Mark	No	Width	Length	Design Loading	Shape
D-1	40	2'-4"	30'-6"	H-15	
D-2	8	3'-0"	31'-0"	H-15	
D-3	8	2'-4"	30'-6"	150#/ft	

4" Scupper holes in D-2 only  
See sketch above for location





Diagram of Skew Bridge (34' x 120') Showing Marking of Deck Channels  
Not to scale  
Note: All channels not marked are D-1

21-T34-19E

MANATEE COUNTY HIGHWAY DEPT  
ENGINEERING DIVISION

MILL CREEK BRIDGE (PROJ) 281

Prestressed Deck Channels

Date	Revisions	by	Designed by	Scale
12-10-62	Channel width	EC	Drawn by: AC	
			Date 12-10-62	Sheet 11
			Approved by	

63-287

63-287



# Appendix E: Bridge Inspection Report

[THE REMAINDER OF THIS PAGE IS INTENTIONALLY LEFT BLANK]



# BRIDGE INSPECTION REPORT

PREPARED FOR: FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE OWNER: MANATEE COUNTY

**DBi**

INSPECTED BY:

**KCA**

BRIDGE NO. 134023

CONTENTS OF REPORT

INSPECTION DATE: 03/24/2020

BrM Report

U/W Inspection Report

CIDR

\* Fracture Critical Data

Scour Elevation (Profile)

\* Load Rating Analysis Summary


\* Addendum (Element Notes & Photos/Sketches)

\*This section is not included in this report.



Upper Manatee River Rd. over Mill Creek

3.2 Mi. Northeast of SR-64



**FLORIDA DEPARTMENT OF TRANSPORTATION**  
**BRIDGE MANAGEMENT SYSTEM**  
**Inspection/CIDR/Bridge Profile Report**  
**Inspection**

**Structure ID: 134023****DISTRICT: D1 - Bartow****INSPECTION DATE: 3/24/2020 RDMZ**

BY: Kisinger Campo & Associates	STRUCTURE NAME: UPPER MANATEE RIVER RD OVER MILL CREEK
OWNER: 2 County Hwy Agency	YEAR BUILT: 1963
MAINTAINED BY: 2 County Hwy Agency	SECTION NO.: 13 000 007
STRUCTURE TYPE: 5 Prestressed Concrete - 22 Channel Beam	MP: 3.357
LOCATION: 3.2 MI. NE OF SR-64	ROUTE: 00000
SERV. TYPE ON: 5 Highway-pedestrian	FACILITY CARRIED: UP.MANATEE RIV RD
SERV. TYPE UNDER: 5 Waterway	FEATURE INTERSECTED: MILL CREEK

☒ FUNCTIONALLY OBSOLETE☐ STRUCTURALLY DEFICIENT

TYPE OF INSPECTION: Regular NBI

DATE FIELD INSPECTION WAS PERFORMED: ABOVE WATER: 3/24/2020 UNDERWATER: 2/20/2020

SUFFICIENCY RATING: 21.8  
HEALTH INDEX: 79.82

**FLORIDA DEPARTMENT OF TRANSPORTATION**  
**BRIDGE MANAGEMENT SYSTEM**  
**Inspection/CIDR/Bridge Profile Report**  
**Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ

BY: Kisinger Campo &amp; Associates

STRUCTURE NAME: UPPER MANATEE RIVER RD  
OVER MILL CREEK

OWNER: 2 County Hwy Agency

YEAR BUILT: 1963

MAINTAINED BY: 2 County Hwy Agency

SECTION NO.: 13 000 007

STRUCTURE TYPE: 5 Prestressed Concrete - 22 Channel Beam

MP: 3.357

LOCATION: 3.2 MI. NE OF SR-64

ROUTE: 00000

SERV. TYPE ON: 5 Highway-pedestrian

FACILITY CARRIED: UP.MANATEE RIV RD

SERV. TYPE UNDER: 5 Waterway

FEATURE INTERSECTED: MILL CREEK

- ☐ THIS BRIDGE CONTAINS FRACTURE CRITICAL COMPONENTS
- ☐ THIS BRIDGE IS SCOUR CRITICAL
- ☐ THIS REPORT IDENTIFIES DEFICIENCIES WHICH REQUIRE PROMPT CORRECTIVE ACTION
- ☒ FUNCTIONALLY OBSOLETE ☐ STRUCTURALLY DEFICIENT

TYPE OF INSPECTION: Regular NBI

DATE FIELD INSPECTION WAS PERFORMED: ABOVE WATER: 3/24/2020 UNDERWATER: 2/20/2020

**OVERALL NBI RATINGS:**

DECK: 7 Good CHANNEL: 7 Minor Damage

SUPERSTRUCTURE: 6 Satisfactory CULVERT: N/A (NBI)

SUBSTRUCTURE: 6 Satisfactory SUFF. RATING: 21.8

PERF. RATING: Good HEALTH INDEX: 79.82

**FIELD PERSONNEL / TITLE / NUMBER:****INITIALS**

Snorek, Aaron - Bridge Inspector (CBI #00573) (lead)

Aaron M Snorek

Digitally signed by Aaron M Snorek  
Date: 2020.05.01 11:45:23 -04'00'

McMinn, Brice - Bridge Inspector (CBI#00405)

Hoogland, Keith - Bridge Inspector (CBI #00341) - Lead Diver

Myers, Jared - Diver

Andrion, Luis - Tender

**REVIEWING BRIDGE INSPECTION SUPERVISOR:**

Rothman, David - Bridge Inspector (CBI #00056)

David A Rothman

Digitally signed by David A Rothman

Date: 2020.05.01 14:11:42 -04'00'

**CONFIRMING REGISTERED PROFESSIONAL ENGINEER:**

Cochran, Robert - PE #45177 Kisinger Campo & Associates  
 4524 Oak Fair Blvd.  
 Certificate of Authorization #2317  
 Tampa FL 33610

SIGNATURE: Robert P Cochran

Digitally signed by Robert P Cochran  
Date: 2020.05.04 08:20:29 -04'00'

DATE:

The official record of this package has been electronically signed and sealed using a Digital Signature as required by 61G15-23.004 F.A.C. on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be verified on any electronic copies.



This report contains information relating to the physical security of a structure and depictions of the structure. This information is confidential and exempt from public inspection pursuant to sections 119.071(3)(a) and 119.071(3)(b), Florida Statutes. Only the cover page of this report may be inspected and copied.

**FLORIDA DEPARTMENT OF TRANSPORTATION**  
**BRIDGE MANAGEMENT SYSTEM**  
**Inspection/CIDR/Bridge Profile Report**  
**Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ

## All Elements

## DECKS : Decks/Slabs

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	12 / 4	Re Concrete Deck	4177	100	0	.	0	.	0	.	4177 sq.ft
0	510 / 4	Wearing Surfaces	3381	95.37	164	4.63	0	.	0	.	3545 sq.ft
0	3220 / 4	Crack (Wearing Surface)	0	.	164	100	0	.	0	.	164 sq.ft

## Element Inspection Notes:

12/4 Note: There are two 5in. diameter fiberglass conduit utilities bolted to the right bridge rail posts. There are three 4in. diameter PVC conduits suspended with 1/2in diameter threaded rods that are spaced at 6ft. intervals below the north sidewalk. Anchorage types are unknown. The deck top is not visible due to an asphalt overlay.

## INCIDENTAL:

The traffic face of the right sidewalk has a 12in. x 5in. x 1in. spall at Abutment 1.

510/4 CS2 3220 = The asphalt overlay has transverse cracks up to full roadway width x 1/64in. wide along the skew over both abutments and intermediate bents. (164SF)

3220/4 Refer to Parent Element

## MISCELLANEOUS : Channel

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8290 / 4	Channel	0	.	1	100	0	.	0	.	1 (EA)
0	9140 / 4	Debris	0	.	1	100	0	.	0	.	1 (EA)

## Element Inspection Notes:

8290/4 The following was noted by the underwater inspectors:  
 CS2 9140 = There is debris (logs and branches) throughout the channel, not effecting the flow. (1EA)

9140/4 Refer to Parent Element

## MISCELLANEOUS : Other Elements

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8475 / 4	R/Conc Walls	0	.	0	.	167	100	0	.	167 ft
0	1080 / 4	Delamination/Spall/Patched Area	0	.	0	.	7	100	0	.	7 ft
0	1120 / 4	Efflorescence/Rust Staining	0	.	0	.	2	100	0	.	2 ft
0	1190 / 4	Abrasion(PSC/RC)	0	.	0	.	158	100	0	.	158 ft

## Element Inspection Notes:

8475/4 Note: This element represents the abutment retaining walls (backwalls) and wingwalls at all four corner of the structure. The east wall and strut had less than 3ft. of water this inspection and was not quantified in the underwater report.

CS3 1080 = The top of the northwest wingwall cap at Abutment 1 is spalled/delaminated 3ft. x 19in. x 2in. Refer to photo 1. REPAIR (3FT)

The top of the southwest wingwall cap at Abutment 1 is cracked 1/32in. wide.

The top of southwest wingwall has an 18in. long x 6in. wide delamination. Refer to photo 2. REPAIR



**FLORIDA DEPARTMENT OF TRANSPORTATION**  
**BRIDGE MANAGEMENT SYSTEM**  
**Inspection/CIDR/Bridge Profile Report**  
**Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ

The northwest wingwall has intermittent vertical cracks 5ft. long x 1/32in. wide.

CS3 1080 = The east strut has an 8in. x 7in. (full width) x 2in. spall/delamination in the bottom face between Piles 5-1 and 5-2. (1FT)

The following was noted by the underwater inspectors:

CS3 1190 = The wingwalls and struts have scale damage (loss of aggregate) up to 1/2in. deep. Refer to photo 3. (158FT)

CS3 1120 = The west and east struts along the backwalls and wingwalls have isolated corrosion bleed out. Refer to photo 4. (2FT)

The west strut have intermittent horizontal cracks up to 16in. long x 1/32in. wide along the bottom edges.

The west strut has a 4ft. 8in. long x 3in. wide (full width) delamination in the bottom face between Piles 1-5 and 1-6.

CS3 1080 = The west backwall has a 12in. x 3in. x 24in. spall at the joint between Piles 1-1 and 1-2, 6in. below the strut with backfill leakage. Refer to photo 5. (1FT)

CS3 1080 = The first joint south of the southwest wingwall transition has a 4in. x 20in. x 4in. spalled area, 24in. below the strut and extending down, that a ruler can penetrate up to 11in. due to backfill leakage. (1FT)

CS3 1080 = The first joint from the northwest wingwall transition has a 10in. x 4in. x 4in. spall at the joint with 12in. of penetration (partially buried), 31in. below the strut. (1FT)

**INCIDENTAL:**

The joints are open up to 1in. wide with backfill leakage.

At the transition joint to the southwest and northwest wingwalls, the grout in the joint stops 20in. below the strut, leaving the joints open up to 6in. wide on the outside and 1/4in. wide on the inside. A ruler can penetrate through the joint 12in. into soft backfill with leakage.

1080/4 Refer to Parent Element

1120/4 Refer to Parent Element

1190/4 Refer to Parent Element

**SUBSTRUCTURE : Substructure**

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	215 / 4	Re Conc Abutment	82	96.47	0	.	3	3.53	0	.	85 ft
0	1080 / 4	Delamination/Spall/Patched Area	0	.	0	.	3	100	0	.	3 ft

**Element Inspection Notes:**

215/4 Note: This element represents the abutment caps only. For comments relating to the retaining walls (backwalls), refer to Element 8475 R/Conc Walls.

CS1 = The abutment caps have intermittent vertical cracks 1/64in. wide.

CS3 1080 = Abutment 1 cap has a 3ft. x 2ft. x 8in. spall/delamination at the north end

**FLORIDA DEPARTMENT OF TRANSPORTATION**  
**BRIDGE MANAGEMENT SYSTEM**  
**Inspection/CIDR/Bridge Profile Report**  
**Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ

below Beam 1-1 at the utilities. Refer to photo 6. REPAIR (3FT)

1080/4 Refer to Parent Element

**SUBSTRUCTURE : Substructure**

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	226 / 4	Pre Conc Pile	3	100	0	.	0	.	0	.	3 (EA)

**Element Inspection Notes:**

226/4 Note: This element represents the three piles supporting the cap extension for the utility pipe on the south side of the structure of Bents 2 through 4 (Piles 2-7, 3-7 and 4-7). The piles have pile jackets with cathodic protection.

**SUBSTRUCTURE : Substructure**

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	227 / 4	Re Conc Pile	0	.	27	84.38	5	15.63	0	.	32 (EA)
0	1080 / 4	Delamination/Spall/Patched Area	0	.	0	.	2	100	0	.	2 (EA)
0	1090 / 4	Exposed Rebar	0	.	0	.	3	100	0	.	3 (EA)
0	1190 / 4	Abrasion(PSC/RC)	0	.	27	100	0	.	0	.	27 (EA)

**Element Inspection Notes:**

227/4 Note: This element represents the seven 12in. piles at Bents 1 and 5 and six 12in. piles at each of Bents 2 through 4. All reinforced concrete piles have pile jackets with cathodic protection.

CS2 1190 = The piles at Bent 5 have scale damage (loss of matrix) up to 1/8in. deep below the jackets. (6EA)

CS3 1080 = Pile 5-6 northwest corner has a 9in. x 5in. x 1-1/2in. spall at bottom of jacket. (1EA)

The following was noted by the underwater inspectors:

CS2 1190 = The piles have scale damage (loss of matrix) up to 1/8in. deep below the jackets. (21EA)

CS3 1090 = Pile 1-3 southeast corner has a 12in. x 9in. x 2in. spall with 3in. of exposed steel having 80% section remaining at the bottom of the jacket. REPAIR (1EA)

CS3 1090 = Pile 1-4 northeast corner has a 10in. x 5in. x 2in. spall with 2in. of exposed steel having 80% section remaining at the bottom of the jacket. REPAIR (1EA)

CS3 1090 = Pile 1-7 northeast corner has a 10in. x 6in. x 2in. spall with 4in. of exposed steel having 90% section remaining at the bottom of the jacket. Refer to photo 7. REPAIR (1EA)

CS3 1080 = Pile 3-6 northwest corner below the jacket has a 12in. x 6in. x 2-1/2in. spall - NEW. (1EA)

1080/4 Refer to Parent Element

1090/4 Refer to Parent Element

1190/4 Refer to Parent Element

**SUBSTRUCTURE : Substructure**

This report contains information relating to the physical security of a structure and depictions of the structure. This information is confidential and exempt from public inspection pursuant to sections 119.071(3)(a) and 119.071(3)(b), Florida Statutes. Only the cover page of this report may be inspected and copied.

**FLORIDA DEPARTMENT OF TRANSPORTATION**  
**BRIDGE MANAGEMENT SYSTEM**  
**Inspection/CIDR/Bridge Profile Report**  
**Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	234 / 4	Re Conc Pier Cap	154	100	0	.	0	.	0	.	154 ft

**Element Inspection Notes:**

234/4 CS1 = The caps have intermittent vertical cracks 1/64in. wide.

**SUBSTRUCTURE : Substructure**

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8298 / 4	Pile Jacket Bare	35	100	0	.	0	.	0	.	35 (EA)
0	520 / 4	Conc Re Prot Sys	1680	100	0	.	0	.	0	.	1680 sq.ft

**Element Inspection Notes:**

8298/4 Note: This element represents the structural pile jackets with cathodic protection. The jackets are square fiberglass-formed concrete filled and start approximately 12in. below the cap and extend down 6ft. 2in.

520/4 Note: The anodes at Jackets 4-1, 4-2, 4-3, 4-4 and Bent 5 are buried.

CS1 = The exposed anodes have 90% or more section remaining.

**SUPERSTRUCTURE : Superstructure**

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	109 / 4	Pre Opn Conc Girder/Beam	837	49.24	862	50.71	1	0.06	0	.	1700 ft
0	1080 / 4	Delamination/Spall/Patched Area	0	.	12	92.31	1	7.69	0	.	13 ft
0	1110 / 4	Cracking (PSC)	0	.	850	100	0	.	0	.	850 ft

**Element Inspection Notes:**

109/4 CS2 1110 = The channel beams along the fillets have intermittent longitudinal cracks up to 3ft. long x up to 0.008in. wide. Refer to photo 8.(850FT)

CS2 1080 = The channel beams have ten intermittent spalls up to 5in. x 4in. x 1/2in. at isolated locations throughout. (10FT)

CS3 1080 = Beam 3-2 has a 6in. diameter x 1/4in. deep spall with exposed steel with no measurable section loss in the bottom face of the top flange, adjacent to the eastern most scupper, at Bent 4. Refer to photo 9. REPAIR (1FT)

CS2 1080 = Beam 3-14 has a 17in. long x 5in. wide delamination in the left leg at Bent 4. (2FT)

**INCIDENTAL:**

The intermediate diaphragms have spalls/delaminations up to 6in. x 4in. x 1/4in. and intermittent diagonal cracks up to 1/16in. wide.

There are numerous bats between the beams.

1080/4 Refer to Parent Element

1110/4 Refer to Parent Element

**FLORIDA DEPARTMENT OF TRANSPORTATION**  
**BRIDGE MANAGEMENT SYSTEM**  
**Inspection/CIDR/Bridge Profile Report**  
**Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ

**SUPERSTRUCTURE : Superstructure**

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	333 / 4	Other Bridge Railing	214	88.07	29	11.93	0	.	0	.	243 ft
0	1000 / 4	Corrosion	0	.	20	100	0	.	0	.	20 ft
0	1010 / 4	Cracking	0	.	5	100	0	.	0	.	5 ft
0	1090 / 4	Exposed Rebar	0	.	4	100	0	.	0	.	4 ft
0	8518 / 4	Galvanized Steel	600	96.77	20	3.23	0	.	0	.	620 sq.ft
0	3440 / 4	Eff (Stl Protect Coat)	0	.	20	100	0	.	0	.	20 sq.ft

**Element Inspection Notes:**

333/4

Note: The bridge rails are comprised of steel guardrail panels, timber cushion blocks and concrete posts bolted to the outside edges of the deck.

CS2 1000 = The bridge rail panels and hardware have minor surface corrosion intermittently throughout. (20SF)

CS1 = The concrete bridge rail posts have intermittent vertical and horizontal cracks up to 1/32in. wide throughout.

CS2 1090 = Post 1-1 Left has exposed lack of cover steel in the top face. REPAIR (1FT)

CS2 1010 = Post 1-2 Right has full height (4ft.) vertical cracks up to 1/16in. wide and is delaminated the full height x 8in. wide. REPAIR (1FT)

CS2 1010 = Post 2-2 Right has a horizontal crack up to 1/16in. wide on the west face at the top of the sidewalk. REPAIR (1FT)

CS2 1010 = Post 2-5 Right has full height vertical cracks 1/32in. wide and is delaminated full height x 8in. wide. REPAIR (1FT)

CS2 1090 = Posts 3-4 and 3-5 Right in the top face have exposed lack of cover steel. REPAIR (2FT)

CS2 1010 = Post 3-5 Right has a vertical crack up to 1/16in. wide in the top of the east and south faces and a horizontal crack in the top face. REPAIR (1FT)

CS2 1090 = Post 4-3 Left has exposed lack of cover steel in the top face. REPAIR (1FT)

CS2 1010 = Post 4-4 Right has full height cracks x 1/16in. wide and is delaminated full height x 8in. wide with exposed lack of cover steel in the top face. Refer to photo 10. REPAIR (1FT)

1000/4

Refer to Parent Element

1010/4

Refer to Parent Element

1090/4

Refer to Parent Element

8518/4

CS2 3440 = The galvanizing is substantially effective in the corroded areas noted above. (20SF)

3440/4

Refer to Parent Element

**Total Number of Elements\*: 10**

\*excluding defects/protective systems

This report contains information relating to the physical security of a structure and depictions of the structure. This information is confidential and exempt from public inspection pursuant to sections 119.071(3)(a) and 119.071(3)(b), Florida Statutes. Only the cover page of this report may be inspected and copied.

**FLORIDA DEPARTMENT OF TRANSPORTATION**  
**BRIDGE MANAGEMENT SYSTEM**  
**Inspection/CIDR/Bridge Profile Report**  
**Inspection**

**Structure ID: 134023**

**DISTRICT: D1 - Bartow**

**INSPECTION DATE: 3/24/2020 RDMZ**

---

**Structure Notes**

BRIDGE OWNER: MANATEE COUNTY

Structure inventoried from west to east.

TRAFFIC RESTRICTION: Based on the load rating analysis dated 01/06/12, posting is required for the SU, C and ST-5 type vehicles as follows: SU = 21 tons, C = 28 tons and ST5 = 33 tons. This structure is posted at both approaches as follows: SU = 19 tons, C = 25 tons and ST5 = 30 tons. Refer to posting sign photos.

This structure is on a 12 month inspection frequency due to the NBI rating for SIA Item 70, Posting, is coded a 1.

Asphalt thickness = 3-1/2in.

**INSPECTION NOTES:**                      **RDMZ**                      **3/24/2020**

Sufficiency Rating Calculation Accepted by KNKCARX at 4/29/2020 8:37 AM

**LOAD CAPACITY EVALUATION:**

The findings of this inspection reveal no reason to warrant a new analysis; therefore, the current load rating results still govern.

The following elements were inspected underwater by the divers:

8290 Channel  
8475 R/Conc Walls  
226 Pre Conc Pile  
227 Re Conc Pile  
520 Conc Re Prot Sys

The NBI rating for SIA Item 59 Superstructure is coded a 6- Satisfactory due to cracking.

The NBI rating for SIA Item 60 Substructure is coded a 6-Satisfactory due to abrasion.

**NON-STRUCTURAL ITEMS:**

**APPROACH ROADWAYS:**

The approach roadways have map cracking up to 1/4in. wide throughout.

**APPROACH GUARDRAILS:**

The timber posts are heavily deteriorated and weathered throughout all four approach guardrails.

The guardrail end terminals at all four corners of the structure are missing reflective tape. Refer to photo 11. REPAIR

The northeast end terminal has minor impact damage.

There is minor damage to the top rail at the southwest approach guardrail.

**STRIPING:**

The roadway striping across the structure is faded.

**FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ



**Photo 1 - Element 8475 R/Conc Walls**

Spall/delamination in the northwest wingwall cap at Abutment 1

**REPAIR RECOMMENDATION:**

Repair spall-delamination in the northwest wingwall cap at Abutment 1.

FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Inspection

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ



**Photo 2 - Element 8475 R/Conc Walls**

Delamination in the southwest wingwall cap

**REPAIR RECOMMENDATION:**

Repair delamination in the southwest wingwall cap at Abutment 1.



**FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ



**Photo 3 - Element 8475 R/Conc Walls**

Typical wingwall scale damage (loss of aggregate) up to 1/2in. deep

REPAIR RECOMMENDATION:  
None



**FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ



**Photo 4 - Element 8475 R/Conc Walls**

Typical area of corrosion bleed out at the west backwall strut

REPAIR RECOMMENDATION:  
None

**FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ



**Photo 5 - Element 8475 R/Conc Walls**

Spall in the west backwall at the joint between Piles 1-1 and 1-2, 6in. below the strut with backfill leakage

REPAIR RECOMMENDATION:  
None



**FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ



**Photo 6 - Element 215 Re Conc Abutment**

Spall/delamination at the north end of Abutment 1 cap

**REPAIR RECOMMENDATION:**


Repair spall-delamination in the north end of Abutment 1 cap.

**FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ



**Photo 7 - Element 227 Re Conc Pile**

Spall with exposed steel in the northeast corner of Pile 1-7

REPAIR RECOMMENDATION:  
Repair Piles 1-3 1-4 and 1-7.

**FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ



**Photo 8 - Element 109 Pre Opn Conc Girder/Beam**

Typical longitudinal crack along channel beam fillet areas in Beam 1-5

REPAIR RECOMMENDATION:  
None



FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Inspection

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ



**Photo 9 - Element 109 Pre Opn Conc Girder/Beam**

Spall with exposed steel in Beam 3-2

**REPAIR RECOMMENDATION:**

Repair spall with exposed steel in Beam 3-2.



FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Inspection

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ



**Photo 10 - Element 333 Other Bridge Railing**

Post 4-4 right typical full height delamination

**REPAIR RECOMMENDATION:**

Repair Posts 1-1 and 4-3 left and Posts 1-2 2-2 2-5 3-4 3-5 and 4-4 right.

**FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Inspection**

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ



**Photo 11 - Inspection Notes**

Missing reflective tape on the guardrail end terminals

**REPAIR RECOMMENDATION:**

Install reflective tape on the four guardrail end terminals.

FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Inspection

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ



West Posting Sign



FLORIDA DEPARTMENT OF TRANSPORTATION  
BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Inspection

Structure ID: 134023

DISTRICT: D1 - Bartow

INSPECTION DATE: 3/24/2020 RDMZ



East Posting Sign

# FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

## Inspection/CIDR/Bridge Profile Report

Structure ID: 134023

CIDR

DATE PRINTED: 5/1/2020

## Description

### Structure Unit Identification

Bridge/Unit Key: 134023 0  
 Structure Name: UPPER MANATEE RIVER RD OVER MILL CREEK  
 Description: Spans 1 thru 4  
 Type: M - Main

### Roadway Identification

NBI Structure No (8): 134023  
 Position/Prefix (5): 1 - Route On Structure  
 Kind Hwy (Rte Prefix): 4 County Hwy  
 Design Level of Service: 1 Mainline  
 Route Number/Suffix: 00000 / 0 N/A (NBI)  
 Feature Intersect (6): MILL CREEK  
 Critical Facility: Not Defense-crit  
 Facility Carried (7): UP.MANATEE RIV RD  
 Mile Point (11): 3.357  
 Latitude (16): 027d30'49.2" Long (17): 082d24'32.8"

### Roadway Traffic and Accidents

Lanes (28): 2 Medians: 0 Speed: 45 mph  
 ADT Class: 4 ADT Class 4  
 Recent ADT (29): 7299 Year (30): 2018  
 Future ADT (114): 12664 Year (115): 2040  
 Truck % ADT (109): 6  
 Detour Length (19): 6.2 mi  
 Detour Speed: 45 mph  
 Accident Count: -1 Rate:

### Roadway Classification

Nat. Hwy Sys (104): 0 Not on NHS  
 National base Net (12): 0 - Not on Base Network  
 LRS Inventory Rte (13a): 13 000 007 Sub Rte (13b): 00  
 Functional Class (26): 17 Urban Collector  
 Federal Aid System: ON  
 Defense Hwy (100): 0 Not a STRAHNET hwy  
 Direction of Traffic (102): 2 2-way traffic  
 Emergency: ☐

### Roadway Clearances

Vertical (10): 99.99 ft Appr. Road (32): 23.6 ft  
 Horiz. (47): 32 ft Roadway (51): 29.2 ft  
 Truck Network (110): 0 Not part of natl netwo  
 Toll Facility (20): 3 On free road  
 Fed. Lands Hwy (105): 0 N/A (NBI)  
 School Bus Route: ☒  
 Transit Route: ☐

### NBI Project Data

Proposed Work (075A): Not Applicable (P)  
 Work To Be Done By (075B): Not Applicable (P)  
 Improvement Length (076): 0 ft

Improvement Cost (094): \$ 0.00  
 Roadway Improvement Cost (095): \$ 0.00  
 Total Cost (096): \$ 0.00  
 Year of Estimate (097):

### NBI Rating

Channel (61): 7 Minor Damage  
 Deck (58): 7 Good  
 Superstructure (59): 6 Satisfactory  
 Substructure (60): 6 Satisfactory

Culvert (62): N N/A (NBI)  
 Waterway (71): 9 Above Desirable  
 Unrepaired Spalls: -1 sq.ft.  
 Review Required: ☒

# FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

## Inspection/CIDR/Bridge Profile Report

Structure ID: 134023

CIDR

DATE PRINTED: 5/1/2020

**Structure Identification**

Admin Area: Sarasota/Manatee  
 District (2): D1 - Bartow  
 County (3): (13)Manatee  
 Place Code (4): No city involved  
 Location (9): 3.2 MI. NE OF SR-64  
 Border Br St/Reg (98): Not Applicable (P) Share: 0 %  
 Border Struct No (99):  
 FIPS State/Region (1): 12 Florida Region 4-Atlanta  
 NBIS Bridge Len (112): Y - Meets NBI Length  
 Parallel Structure (101): No || bridge exists  
 Temp. Structure (103): Not Applicable (P)  
 Maint. Resp. (21): 2 County Hwy Agency  
 Owner (22): 2 County Hwy Agency  
 Historic Signif. (37): 5 Not eligible for NRHP

**Geometrics**

Spans in Main Unit (45): 4  
 Approach Spans (46): 0  
 Length of Max Span (48): 31.5 ft  
 Structure Length (49): 121.4 ft  
 Total Length: 121.4 ft  
 Deck Area: 4177 sqft  
 Structure Flared (35): 0 No flare

**Age and Service**

Year Built (27): 1963  
 Year Reconstructed (106): 0  
 Type of Service On (42a): 5 Highway-pedestrian  
 Under (42b): 5 Waterway  
 Fracture Critical Details: Not Applicable

**Structure Type and Material**

Curb/Sidewalk (50): Left: 1.9 ft Right: 1.9 ft  
 Bridge Median (33): 0 No median  
 Main Span Material (43A): 5 Prestressed Concrete  
 Appr Span Material (44A): Not Applicable  
 Main Span Design (43B): 22 Channel Beam  
 Appr Span Design (44B): Not Applicable

**Deck Type and Material**

Deck Width (52): 34.4 ft  
 Skew (34): 30 deg  
 Deck Type (107): 1 Concrete-Cast-in-Place  
 Surface (108): 6 Bituminous  
 Membrane: 0 None  
 Deck Protection: None

**Appraisal****Structure Appraisal**

Open/Posted/Closed (41): P Posted for load  
 Deck Geometry (68): 2 Intolerable - Replace  
 Underclearances (69): N Not applicable (NBI)  
 Approach Alignment (72): 8-No Speed Red thru Curv  
 Bridge Railings (36a): 0 Substandard  
 Transitions (36b): 0 Substandard  
 Approach Guardrail (36c): 0 Substandard  
 Approach Guardrail Ends (36d): 0 Substandard  
 Scour Critical (113): 5 Stable w/in footing

**Navigation Data**

Navigation Control (38): Permit Not Required  
 Nav Vertical Clr (39): 0 ft  
 Nav Horizontal Clr (40): 0 ft  
 Min Vert Lift Clr (116): 0 ft  
 Pier Protection (111): Not Applicable (P)

**NBI Condition Rating**

Sufficiency Rating: 21.8  
 Health Index: 79.82  
 Structural Eval (67): 3 Intolerable - Correct  
 Deficiency: Functionally Obsolete

**Minimum Vertical Clearance**

Over Structure (53): 99.99 ft  
 Under (reference) (54a): N Feature not hwy or RR  
 Under (54b): 0 ft

**Minimum Lateral Underclearance**

Reference (55a): N Feature not hwy or RR  
 Right Side (55b): 0 ft  
 Left Side (56): 0 ft

**Schedule****Current Inspection**

Inspection Date: 03/24/2020  
 Inspector: KNKCAAS - Aaron Snorek  
 Bridge Group: E1N92  
 Alt. Bridge Group:  
 Primary Type: Regular NBI  
 Review Required: ☒

**Next Inspection Date Scheduled**

NBI: 03/24/2022  
 Element: 03/24/2021  
 Fracture Critical:  
 Underwater: 02/20/2022  
 Other/Special: 03/24/2021  
 Inventory Photo Update Due: 03/13/2022



# FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

## Inspection/CIDR/Profile Report

Structure ID: 134023

CIDR

DATE PRINTED: 5/1/2020

### Schedule Cont.

#### Inspection Types Performed

NBI ☒Element ☒Fracture Critical ☐Underwater ☒Other Special ☒

#### Inspection Intervals

##### Required (92)

##### Frequency (92)

##### Last Date (93)

##### Inspection Resources

Fracture Critical

☐

mos

Crew Hours: 4

Underwater

☒

24 mos

02/20/2020

Flagger Hours: 0

Other Special

☒

12 mos

03/24/2020

Helper Hours: 0

NBI

24 mos (91) 03/24/2020 (90)

Snooper Hours: 0

Special Crew Hours: 3

Special Equip Hours: 0

### Bridge Related

#### General Bridge Information

Parallel Bridge Seq:

Channel Depth: 7.2 ft

Radio Frequency: -1

Phone Number:

Exception Date:

Exception Type: Unknown

Accepted By Maint: 01/01/1963

Warranty Expiration: 00/00/0000

Performance Rating: Good

Bridge Rail 1: Steel guard/concret post

Bridge Rail 2: Not applicable-No rail

Electrical Devices: No electric service

Culvert Type: Not applicable

Maintenance Yard: Not FDOT Maintained

FIHS ON / OFF: No Routes on FIHS

Previous Structure:

2nd Previous Structure:

Replacement Structure:

Permitted Utilities: Power ☐Water ☐Gas ☐Fiber Optic ☒Sewage ☐Other ☒4" Dia. PVC & 5" Dia.  
FBRGLS

#### Bridge Load Rating Information

Inventory Type (065): 1 LF Load Factor

Operating Type (063): 1 LF Load Factor

Original Design Load (031): 2 M 13.5 (H 15)

Date: 01/06/2012

Initials: SLC

Load Rating Rev. Recom.: No

Load Rating Plans Status: Design or Construction

Inventory Rating (066): 7.9 tons

Operating Rating (064): 28.8 tons

FL120 Permit Rating: -1.0 tons

HS20/FL120 Max Span Rating: 28.8 tons

Dynamic Impact in Percent: 30 %

Governing Span Length: 32.8 ft

Minimum Span Length:

Distribution Method: AASHTO formula

Load Rating Notes:

#### LEGAL LOADS

SU2: 20.4 tons

SU3: 21.8 tons

SU4: 21.4 tons

C3: 31.4 tons

C4: 28.6 tons

C5: 31.2 tons

ST5: 33.2 tons

Posting (070): 1 30.0-39.9%below

Open/Posted/Closed (041): P Posted for load

#### FLOOR BEAM (FB)

FB Present: No

FB Span Length, Gov: 0.0 ft

FB Spacing, Gov: 0.0 ft

FB OPR Rating: 0.0 tons

FB SU4 OPR Rating: 0.0 tons

FB FL120 Rating: 0.0 tons

#### POSTING

Recom. SU Posting: 21 tons

Recom. C Posting: 28 tons

Recom. ST5 Posting: 33 tons

Actual SU Posting: 19 tons

Actual C Posting: 25 tons

Actual ST5 Posting: 30 tons

Actual Blanket Posting: 99 tons

Emergency Vehicle: 1 EV inapplicable

#### SEGMENTAL (SEG)

SEG Wing-Span: -1.0 ft

SEG Web-to-Web Span: -1.0 ft

SEG Transverse HL93 Operating: -1.00 RF

#### Bridge Scour and Storm Information

Pile Driving Record: No pile driving records

Foundation Type: No foundation details

Mode of Flow: Tidal

Rating Scour Eval: Low Risk - High

Highest Scour Eval: Phase III completed

Scour Evaluation Method: Standard Scour Eval

Scour Recommended I: Stop scour evaluations

Scour Recommended II: Perform add'l monitoring

Scour Recommended III: No recommendation

Scour Elevation: 999 ft

Action Elevation: 999 ft

Storm Frequency: 100

# FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

## Inspection/CIDR/Bridge Profile Report

Structure ID: 134023

CIDR

DATE PRINTED: 5/1/2020

### Elements

Inspection Date: 03/24/2020 RDMZ

### DECKS : Decks/Slabs

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	12 / 4	Re Concrete Deck	4177	100	0	.	0	.	0	.	4177 sq.ft
0	510 / 4	Wearing Surfaces	3381	95.37	164	4.63	0	.	0	.	3545 sq.ft
0	3220 / 4	Crack (Wearing Surface)	0	.	164	100	0	.	0	.	164 sq.ft

### MISCELLANEOUS : Channel

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8290 / 4	Channel	0	.	1	100	0	.	0	.	1 (EA)
0	9140 / 4	Debris	0	.	1	100	0	.	0	.	1 (EA)

### MISCELLANEOUS : Other Elements

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8475 / 4	R/Conc Walls	0	.	0	.	167	100	0	.	167 ft
0	1080 / 4	Delamination/Spall/Patched Area	0	.	0	.	7	100	0	.	7 ft
0	1120 / 4	Efflorescence/Rust Staining	0	.	0	.	2	100	0	.	2 ft
0	1190 / 4	Abrasion(PSC/RC)	0	.	0	.	158	100	0	.	158 ft

### SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	215 / 4	Re Conc Abutment	82	96.47	0	.	3	3.53	0	.	85 ft
0	1080 / 4	Delamination/Spall/Patched Area	0	.	0	.	3	100	0	.	3 ft

### SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	226 / 4	Pre Conc Pile	3	100	0	.	0	.	0	.	3 (EA)

### SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	227 / 4	Re Conc Pile	0	.	27	84.38	5	15.63	0	.	32 (EA)
0	1080 / 4	Delamination/Spall/Patched Area	0	.	0	.	2	100	0	.	2 (EA)
0	1090 / 4	Exposed Rebar	0	.	0	.	3	100	0	.	3 (EA)
0	1190 / 4	Abrasion(PSC/RC)	0	.	27	100	0	.	0	.	27 (EA)

### SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	234 / 4	Re Conc Pier Cap	154	100	0	.	0	.	0	.	154 ft

### SUBSTRUCTURE : Substructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	8298 / 4	Pile Jacket Bare	35	100	0	.	0	.	0	.	35 (EA)
0	520 / 4	Conc Re Prot Sys	1680	100	0	.	0	.	0	.	1680 sq.ft

### SUPERSTRUCTURE : Superstructure

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	109 / 4	Pre Opn Conc Girder/Beam	837	49.24	862	50.71	1	0.06	0	.	1700 ft
0	1080 / 4	Delamination/Spall/Patched Area	0	.	12	92.31	1	7.69	0	.	13 ft
0	1110 / 4	Cracking (PSC)	0	.	850	100	0	.	0	.	850 ft

This report contains information relating to the physical security of a structure and depictions of the structure. This information is confidential and exempt from public inspection pursuant to sections 119.071(3)(a) and 119.071(3)(b), Florida Statutes. Only the cover page of this report may be inspected and copied.

# FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM

REPORT ID: INSP005

## Inspection/CIDR/Bridge Profile Report

Structure ID: 134023

CIDR

DATE PRINTED: 5/1/2020

**SUPERSTRUCTURE : Superstructure**

Str Unit	Elem/Env	Description	Qty1	%1	Qty2	%2	Qty3	%3	Qty4	%4	T Qty
0	333 / 4	Other Bridge Railing	214	88.07	29	11.93	0	.	0	.	243 ft
0	1000 / 4	Corrosion	0	.	20	100	0	.	0	.	20 ft
0	1010 / 4	Cracking	0	.	5	100	0	.	0	.	5 ft
0	1090 / 4	Exposed Rebar	0	.	4	100	0	.	0	.	4 ft
0	8518 / 4	Galvanized Steel	600	96.77	20	3.23	0	.	0	.	620 sq.ft
0	3440 / 4	Eff (Stl Protect Coat)	0	.	20	100	0	.	0	.	20 sq.ft

**Total Number of Elements\*:** 10

\*excluding defects/protective systems

**Inspection Information****Inspection Date:** 03/24/2020**Type:** Regular NBI**Inspector:** KNKCAAS - Aaron Snorek**Inspection Notes:** Sufficiency Rating Calculation Accepted by KNKCARX at 4/29/2020 8:37 AM**LOAD CAPACITY EVALUATION:**

The findings of this inspection reveal no reason to warrant a new analysis; therefore, the current load rating results still govern.

The following elements were inspected underwater by the divers:

8290 Channel  
8475 R/Conc Walls  
226 Pre Conc Pile  
227 Re Conc Pile  
520 Conc Re Prot Sys

The NBI rating for SIA Item 59 Superstructure is coded a 6- Satisfactory due to cracking.

The NBI rating for SIA Item 60 Substructure is coded a 6-Satisfactory due to abrasion.

**NON-STRUCTURAL ITEMS:****APPROACH ROADWAYS:**

The approach roadways have map cracking up to 1/4in. wide throughout.

**APPROACH GUARDRAILS:**

The timber posts are heavily deteriorated and weathered throughout all four approach guardrails.

The guardrail end terminals at all four corners of the structure are missing reflective tape. Refer to photo 11. REPAIR

The northeast end terminal has minor impact damage.

There is minor damage to the top rail at the southwest approach guardrail.

**STRIPING:**

The roadway striping across the structure is faded.

**Structure Notes**

BRIDGE OWNER: MANATEE COUNTY

Structure inventoried from west to east.

TRAFFIC RESTRICTION: Based on the load rating analysis dated 01/06/12, posting is required for the SU, C and ST-5 type vehicles as follows: SU = 21 tons, C = 28 tons and ST5 = 33 tons. This structure is posted at both approaches as follows: SU = 19 tons, C = 25 tons and ST5 = 30 tons. Refer to posting sign photos.

This structure is on a 12 month inspection frequency due to the NBI rating for SIA Item 70, Posting, is coded a 1.

Asphalt thickness = 3-1/2in.


**Schedule Notes**




FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Bridge Profile

DATE PRINTED: 5/1/2020 10:41:57 AM

Left Profile by Inspection



Right Profile by Inspection



FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Bridge Profile

DATE PRINTED: 5/1/2020 10:41:57 AM

Profile Data - Numerical Summary

Inspection Date and Key:		Bent #	Left Height	Right Height	(All Heights are in Feet)
3/24/2020	RDMZ	1	15.40	16.60	
		2	17.60	16.60	
		3	13.90	14.50	
		4	10.10	12.10	
		5	9.90	10.60	

Air Temp:  
Profile Notes:  
Measurements referenced from top of curb.  
Waterline taken at Bent 2: Left and Right = 10.4ft.

Inspection Date and Key:		Bent #	Left Height	Right Height	(All Heights are in Feet)
3/28/2018	QAKV	1	15.40	16.50	
		2	17.80	16.00	
		3	13.70	14.60	
		4	10.30	12.50	
		5	10.00	10.50	

Air Temp:  
Profile Notes:  
Measurements referenced from the top of the curb.  
Waterline was taken at Bent 2: Left and Right = 11.0ft.

FLORIDA DEPARTMENT OF TRANSPORTATION BRIDGE MANAGEMENT SYSTEM  
Inspection/CIDR/Bridge Profile Report  
Bridge Profile

DATE PRINTED: 5/1/2020 10:41:57 AM

Profile Data - Numerical Summary

Inspection Date and Key: 5/1/1998		STRT	Bent #	Left Height	Right Height	(All Heights are in Feet)
(Original Inspection)			1	17.06	19.03	
			2	20.34	19.36	
			3	16.08	18.70	
			4	10.83	14.76	
			5	11.15	12.47	

Air Temp:  
Profile Notes:

The original ground line measurements, dated 5/1/98, were actually taken on and obtained from the previous routine inspection report dated 5/93.



**Routine Underwater Bridge Inspection Report**  
**BOLT UNDERWATER SERVICES, INC.**  
**for**  
**KISINGER CAMPO & ASSOCIATES, CORP.**

NBI Structure ID. (8): **134023**

Underwater Date (93): 02/20/20

---

**Structure/Roadway Identification:**

District (2): 01  
County (3): Manatee  
Feature Intersected (6): Mill Creek  
Facility Carried (7): Up Manatee River Rd.

**Underwater Inspection Details:**

Special Crew Hours: 3.0  
Max. Depth: 8ft. at Bent 1  
Type of Dive Insp.: Level II (SCUBA)  
Type of Boat Used: N/A  
Water Type/Marine Growth: Brackish – Algae/Barnacles

---

**Previous Inspection:**

Lead Diver:	C.B.I. No.:	Inspection Date:
Qualls, Dion C.	00470	02/26/18

---

**Inspection Personnel:**

Field Personnel:	Title	P.E./C.B.I. No.:	Duty:	Signature:
Hoogland, Keith S.	SUCBI	00341/Lead	Dive	Keith S Hoogland
Myers, Jared M.	SI		Dive	
Andrion, Luis A.	AUBIT		Tend	

Digitally signed by Keith S Hoogland  
DN: c=US, o=Bolt Underwater Services, ou=A01427D000001658C1628C900003298,  
cn=Keith S Hoogland  
Date: 2020.03.05 09:10:32 -05'00'

---

**8290 CHANNEL**

1 EA. = **CS-2:** 1EA.

**CS2 9140** = There is debris (logs and branches) throughout the channel, not affecting flow. (1EA)

## BOLT UNDERWATER SERVICES, INC.

Structure ID: 134023

District: 01

Inspection Date: 02/20/20

---

### 8475 R/CONC WALLS

59 FT. = CS-3: 59FT.

NOTE: This element represents the abutment retaining walls (backwalls) and wingwalls with struts at the west end of the structure.

**CS3 1190** = The wingwalls and struts have scale (loss of aggregate) up to ½in. deep. (54FT)

**CS3 1120** = The west strut along the backwalls and wingwalls have isolated areas of corrosion bleedout. (2FT)

West strut along the bottom edge has intermittent horizontal cracks, up to 16in. x 1/32in.

West strut, bottom face between Piles 1-5 and 1-6, delamination, 4ft. 8in. x 3in.

**CS3 1080** = West backwall: At the joint between Piles 1-1 and 1-2, 6in. below the strut, spall, 12in. x 3in. x 24in. into soft earth, with backfill leakage. (1FT)

**CS3 1080** = SW wingwall: 1<sup>st</sup> joint south of transition, 24in. below the strut extending down, spalled area, 4in. x 20in. x 4in. and a ruler can penetrate 11in. into the backfill material with backfill leakage. (1FT)

**CS3 1080** = NW wingwall: 1<sup>st</sup> joint from transition, 31in. below the strut, spall at the joint, 10in. x 4in. x 4in., with 12in. of penetration (partially buried). (1FT)

#### INCIDENTAL:

The joints are open up to 1in. wide with backfill leakage.

At the transition joint to the SW and NW wingwalls, the grout in the joint stops 20in. below the strut, leaving the joints open up to 6in. wide on the outside and ¼in. wide on the inside. A ruler can penetrate through the joint 12in. into soft earth backfill material, with backfill leakage.

NOTE: The east wall and strut had less than 3ft. of water this inspection and was not quantified in the underwater report.

---

### 226 PRE CONC PILE

3 EA. = CS-1: 3EA.

NOTE: This element represents the three piles supporting the cap extension for the utility pipe on the south side of the structure of Bents 2 through 4 (Piles 2-7, 3-7 and 4-7). The piles have pile jackets with cathodic protection.

# BOLT UNDERWATER SERVICES, INC.

Structure ID: 134023

District: 01

Inspection Date: 02/20/20

---

## 227 RE CONC PILE

25 EA. = CS-2: 21EA. CS-3: 4EA.

NOTE: This element represents the seven 12in. piles at Bent 1 and six 12in. piles at each of Bents 2 through 4.  
All reinforced concrete piles have pile jackets with cathodic protection.

**CS2 1190** = The piles have scale (loss of matrix) up to 1/8in. deep below the jackets. (21EA)

**CS3 1090** = Pile 1-3: SE corner below jacket, spall, 12in. x 9in. x 2in., with 3-1/2in. of exposed steel; 80% section remaining. (1EA)

**CS3 1090** = Pile 1-4: NE corner below jacket, spall, 10in. x 5in. x 2in., 2in. of exposed steel; 80% section remaining. (1EA)

**CS3 1090** = Pile 1-7: NE corner below jacket, spall, 10in. x 6in. x 2in., 4in. of exposed steel; 90% section remaining. (1EA)

**CS3 1080** = Pile 3-6: NW corner below jacket, spall, 12in. x 6in. x 2-1/2in. – NEW. (1EA)

NOTE: Bent 5 has less than 3ft. of water this inspection and was not quantified in the underwater report.

---

Cleaning Log: Piles 3-3, 3-4, 3-5 and 3-6.

---

## 8298 PILE JACKET BARE

28 EA. = CS-1: 28EA.

NOTE: This element represents the jackets with cathodic protection on Piles 1 through 7 of Bents 1 through 4.

---

## 520 CONC RE PROT SYS

1470 SF. = CS-1: 1470SF.

NOTE: The anodes at Jackets 4-1, 4-2, 4-3 and 4-4 are buried.

**CS-1** = The exposed anodes have 90% or more section remaining.

---

**INSPECTION NOTES:** Divers inspected Channel, Walls, Bents 2 through 4 each with one 12in. pre-stressed concrete pile, Bent 1 with seven 12in. reinforced concrete piles, Bents 2 through 4 each with six 12in. reinforced concrete piles and Jackets.

**STRUCTURE NOTES:** Structure inventoried west to east.

### PHOTO LOG:

- No. 1: Structure ID
- No. 2: North elevation
- No. 3: SW wingwall joint, spall
- No. 4: Pile 1-7 NE corner spall below jacket with exposed steel
- No. 5: West backwall strut, typical area of corrosion bleedout
- No. 6: West backwall strut, typical horizontal crack
- No. 7: SW wingwall, typical scale
- No. 8: West backwall between Piles 1-1 and 1-2, spall
- No. 9: Pile 3-6 NW corner, spall
- No. 10: Bent 5 backwall, less than 3ft. of water

---

*This report contains information relating to the physical security of a structure and depictions of the structure. This information is confidential and exempt from public inspection pursuant to sections 119.071(3)(a) and 119.071(3)(b), Florida Statutes.*