



Financial Management Department  
Purchasing Division  
1112 Manatee Ave W Suite 803  
Bradenton, FL 34205  
Phone: (941) 749-3074  
www.mymanatee.org

Email

June 22, 2016

TO: All Interested Bidders

SUBJECT: Invitation for Bid #16-1731DC  
Master Lift Station 1M Emergency Generator Replacement

Addendum #3

**CLARIFICATIONS**

1. On drawing E-5 general note 2. talks about programming the new generator into the existing SCADA system. Is this cost to be provided by the contractor or will the county be doing this work? Will additional I/O need to be added? **General Note 2 on Sheet E-5 states the Contractor shall terminate all new conductors on the existing controller and provide for the programming of the existing controller in order to integrate the new I/O into the County's existing SCADA system. Therefore, the cost shall be provided by the Contractor. See Sheet E-5, General Note 1, that states the Contractor shall provide for the new SCADA input/outputs (I/O) as required for the new generator installation. The new SCADA I/O shall consist of the following:**

- discrete input - generator running indication
- discrete input - generator fail indication
- discrete input - fuel tank leak detection alarm
- discrete input - fuel tank low level alarm
- discrete input - fuel tank high level alarm

**Conduit and conductor requirements for the new SCADA I/O are depicted within the contract drawings.**

2. Will the County be salvaging the existing generator or fuel tank? **The County will not be salvaging the generator and fuel tank. See Section 01010 Summary of Work, paragraph 1.01 A. and Section 01150 Measurement and Payment, Bid Item No. 2.**
3. Is bypass pumping anticipated for this project during the electrical shut down? If so what is the stations flow rate and TDH? **Bypass pumping is not anticipated, however; if required, it is the Contractor's responsibility and the County can provide the flow and TDH.**

June 22, 2016

---

4. Will the county be providing the fuel for the new generator or is that to be provided by the contractor? **No, the Contractor shall provide a full tank of fuel. See Section 01005 General Requirements, paragraph 1.01 B and Section 1150 Measurement and Payment, Bid Item No. 3.**
  
5. The temporary 400 kw generator is to be connected to the MLS using an existing generator receptacle. Where is this receptacle located? **On Sheet C-5, the top left photo calls out "existing emergency generator receptacle".**

If you have submitted a bid prior to receiving this addendum you may request in writing that your original, sealed bid be returned to your firm. All sealed bids received will be opened on the date stated.

Bids will be received at Manatee County Purchasing, 1112 Manatee Avenue West, Suite 803, Bradenton, Florida 34205 until **July 1, 2016 at 3:30 P.M.**

Sincerely,



Melissa M. Wendel, CPPO  
Purchasing Official

/dcr