

MANATEE COUNTY
FLORIDA

December 2, 2008

TO: All Interested Bidders

SUBJECT: **Invitation for Bid # 09-0043-DS**
65th Street Drainage Pipe Replacement from 12th Street to 5th Street
West (Project No. 6046000)

ADDENDUM # 1

Bidders are hereby notified that this Addendum shall be acknowledged on page 00300-1 of the Bid Form and made a part of the above named bidding and contract documents. Bids submitted without acknowledgement of the Addendum will be considered incomplete.

The following items are issued to add to, modify, and clarify the bid and contract documents. These items shall have the same force and effect as the original bidding and contract documents, and cost involved shall be included in the bid prices. Bids to be submitted on the specified bid date, shall conform to the additions and revisions listed herein.

Based upon instructions from the Project Engineer: Walter Sowa, Manatee County Government, Public Works Department.

Q1. *Is a warranty bond required?*

A1. *Answer: Yes, a three (3) year warranty bond will be required.*

Q2. *Is a Performance and Payment Bond required for this project?*

A2. *Answer: Yes. Per section C.16 Performance and Payment Bonds, a performance and payment bond is required.*

Mailing Address: Purchasing Division: 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205
PHONE: 941-749-3045 * FAX: 941-749-3034
www.mymanatee.org

December 2, 2008

Page 2

IFB# 09-0043-DS

65th Street West Drainage Pipe Replacement from 12th Street to 5th Street
Bradenton, Florida (Project No. 6046000)

ADDENDUM # 1

Q3. What are the videotaping and laser profile technology requirements for the project, as referenced by the 2007 FDOT § 430-4.48?

A3. Answer: *There is no laser profile technology required for this project at all. Please just utilize videotaping per the FDOT standards noted.*

Q4. Is there a survey or a topographical survey?

A4. Answer: *Yes there is a survey with limited elevation information. The topographical survey is available to bidders if required, from Mr. John Norrie, Public Works Department, Stormwater Coordinator at (941) 708-7450 ext. 7226.*

Q5. Will there be an inspector on site at all times or only specific times?

A5. Answer: *Full time inspections have been requested for the project; however the schedule for the inspector for the project will vary. Obviously the inspector will not be there when no work is in progress.*

Q6. Are there any permits needed for this project?

A6. Answer: *It is not anticipated that any permits will be required for this project. If a permit is required § 00700, Article 4.6 Permits addresses the rights, obligations, and responsibilities of the parties.*

Q7. What are the survey and drawing requirements?

A7. Answer: *A survey will be required for the final product. The survey needs to reference the contiguous property corners of all the affected lots. Any missing monumentation needs to be replaced as part of the scope of services for the project. The survey shall reflect the location of all new improvements, with the periodic distances from the located property corners.*

Mailing Address: Purchasing Division: 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205

PHONE: 941-749-3045 * FAX: 941-749-3034

www.mymanatee.org

December 2, 2008

Page 3

IFB# 09-0043-DS

65th Street West Drainage Pipe Replacement from 12th Street to 5th Street
Bradenton, Florida (Project No. 6046000)

ADDENDUM # 1

Q8. *Is a site visit required? Will Project Management schedule a site visit with contractors?*

A8. *Answer: A site visit is not required. Project management will not schedule a site visit with contractors prior to award.*

Q9. *Will you provide any information with regards to Florida Power (FPL)?*

A9. *Answer: FPL will provide information directly to the contractors and will be invited to the pre-construction meeting.*

Q10. *Has anyone met with or contacted the homeowners along the course of the drainage easement to make them aware that fences, sheds, fruit trees, pools, etc. are to be removed?*

A10. *Answer: Yes, homeowners have been contacted. Prior to construction, another Public Information Meeting will be scheduled, with the contractor and Public Works staff providing scheduling information to the residents, as well as other pertinent construction information. Attendance at meeting will be considered part of Mobilization.*

Q11. *Do they (the residents) have the option to do so (remove objects) themselves or is this part of Clearing and Grubbing and the Contractors obligation to move, relocate, or destroy and replace?*

A11. *Answer: The residents will be instructed to move any structures. However, the contractor should be prepared to remove or relocate any structures as needed and should plan accordingly with their bid and specifically their line item for Miscellaneous Work and Clean Up. Best efforts need to take place to remove without destruction.*

Q12. *We do not understand the purpose of the two zero quantity pay items.*

A12. *Answer: We are in need of unit pricing, just in case it is decided to use the items. Please note that unit pricing for Baled Hay or Straw should be linear foot. For the Staked Silt Fence—we are only looking for a price per foot. The Engineer will determine if it is needed during the construction.*

Mailing Address: Purchasing Division: 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205

PHONE: 941-749-3045 * FAX: 941-749-3034

www.mymanatee.org

December 2, 2008

Page 4

IFB# 09-0043-DS

65th Street West Drainage Pipe Replacement from 12th Street to 5th Street
Bradenton, Florida (Project No. 6046000)

ADDENDUM # 1

Q13. Page 12/165, 1.08 B.3 of Specifications states the tree removal permit is by Owner. Are there trees to be replaced as a compensation condition of the permit?

A13. Answer: *There are no trees to be replaced.*

Q14. Section 0750-2 states that fences "may possibly" be replaced subject to Engineer's approval. Page 12/165, 1.08D states that they all shall be replaced or repaired in kind. Is this Bid Item 19?

A14. Answer: *Fences "may possibly" need to be replaced based upon Engineer's decision and approval. The Bid Form requires an itemized price for installation of permanent fences.*


Q15. Does this mean new fences or compensation for relocating existing fences of all shapes, sizes and kind?

A14. Answer: *This would be applicable to new fences, and does not provide for direct compensation.*

END OF ADDENDUM # 1

Bids will be received at the Manatee County Purchasing Division, 1112 Manatee Avenue West, Suite 803, Bradenton, Florida 34205 until 2:00 P.M. on December 16, 2008.

Sincerely,



**R. C. "Rob" Cuthbert, CPM, CPPO
Purchasing Division Manager**

ds

Mailing Address: Purchasing Division: 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205

PHONE: 941-749-3045 * FAX: 941-749-3034

www.mymanatee.org

BID FORM

(Submit in Triplicate)

Section 00300 - ADDENDUM NO. 1 (12/2/08)

65th Avenue West Drainage Pipe Replacement from 12th Street to 5th Street West (IFB# 09-0043-DS)

BID 'A'

Based on Completion Time of 180 Calendar Days

LINE NO.	ITEM NUMBER	DESCRIPTION	EST. QTY	UNITS OF MEASURE	UNIT PRICE	COSTS
1	101-1	MOBILIZATION	1	LS	\$	\$
2	120-1	MAINTENANCE OF TRAFFIC	1	LS	\$	\$
3	104-10	BALED HAY OR STRAW (ADDENDUM 12/2/08)	0	LF	\$	\$
4	104-13	STAKED SILT FENCE	0	LF	\$	\$
5	110-1	CLEARING & GRUBBING	1	LS	\$	\$
6	110-3	REMOVAL OF EXISTING STRUCTURES (CATCH BASINS)	5	EA	\$	\$
7	120-1	REGULAR EXCAVATING	1	LS	\$	\$
8	162-2	TOP SOIL (6" THICK)	4,800	SY	\$	\$
9	425-11	DRAINAGE STRUCTURE (GRATE INLET)	5	EA	\$	\$
10	430-141-000	INSTALL 42" CLASS III	888	LF	\$	\$
11	430-141-000	INSTALL 29" X 45" RCP CLASS III	896	LF	\$	\$
12	580-332-2	TREE REMOVAL	25	EA	\$	\$
13	575-1-1	SODDING (BAHIA)	4800	SY	\$	\$
14	1600-900-26	REMOVE EXISTING PIPE (20" OR MORE)	1800	LF	\$	\$
15		PUMPING AND DEWATERING	1	LS	\$	\$
16		MISCELLANEOUS WORK AND CLEANUP	1	LS	\$	\$
17		REMOVE EXISTING FENCE	3,600	LF	\$	\$
18		INSTALL TEMPORARY CHAIN LINK FENCE AND REMOVAL OF TEMPORARY FENCE (LOCATION TO BE COORDINATED WITH EACH PROPERTY OWNER)	3,600	LF	\$	\$
19		INSTALL PERMANENT REPLACEMENT FENCE, CHAIN LINK (ADDENDUM 12/2/08)	1800	LF	\$	\$
20		INSTALL PERMANENT REPLACEMENT FENCE, WOOD FENCE (ADDENDUM 12/2/08)	1800	LF	\$	\$
21		SUB TOTAL			\$	\$
22		CONTINGENCY	1	LS		\$45,126.00
23		TOTAL PRICE- Based on Completion Time of 180 Calendar Days				\$

ADDENDUM # 1

BIDDER: _____

BID FORM - SUBCONTRACTOR PERCENTAGE
 (Submit in Triplicate)
 Section 00300 - ADDENDUM NO. 1 (12/2/08)

BID 'A'

65th Avenue West Drainage Pipe Replacement from 12th Street West to 5th Street West (IFB# 09-0043-DS)					
Based on Completion time of 180 Calendar Days					
LINE NO.	ITEM NO.	DESCRIPTION	WORK BY SUBCONTRACTOR		DESCRIPTION OF WORK
			%	MBE/WBE	BY SUBCONTRACTOR
1	101-1	MOBILIZATION			
2	120-1	MAINTENANCE OF TRAFFIC			
3	104-10	BALED HAY OR STRAW (ADDENDUM 12/2/08)			
4	104-13	STAKED SILT FENCE			
5	110-1	CLEARING & GRUBBING			
6	110-3	REMOVAL OF EXISTING STRUCTURES (CATCH BASINS)			
7	120-1	REGULAR EXCAVATING			
8	162-2	TOP SOIL (6" THICK)			
9	425-11	DRAINAGE STRUCTURE (GRATE INLET)			
10	430-141-000	INSTALL 42" RCP CLASS III			
11	430-141-000	INSTALL 29' X 45' RCP CLASS III			
12	580-332-2	TREE REMOVAL			
13	575-1-1	SODDING (BAHIA)			
14	1600-900-26	REMOVE EXISTING PIPE (20" OR MORE)			
15		PUMPING AND DEWATERING			
16		DISCRETIONARY WORK			
17		REMOVE EXISTING FENCE			
18		INSTALL TEMPORARY CHAIN LINK FENCE AND REMOVAL OF TEMPORARY FENCE (LOCATION TO BE COORDINATED WITH EACH PROPERTY OWNER)			
19		INSTALL PERMANENT REPLACEMENT FENCE, CHAIN LINK (ADDENDUM 12/2/08)			
20		INSTALL PERMANENT REPLACEMENT FENCE, WOOD LINK (ADDENDUM 12/2/08)			
21		MISCELLANEOUS WORK AND CLEAN UP			
22				TOTAL	

ADDENDUM # 1

This is a duplication of the bid items where the Bidder shall state the percentage of work (of each item listed) and a description of the work which shall be performed by a subcontractor.

BIDDER: _____

BID FORM
(Submit in Triplicate)

Section 00300 - ADDENDUM NO. 1 (12/2/08)

th Avenue West Drainage Pipe Replacement from 12th Street West to 5th Street West (IFB# 09-0043-DS)

BID "B"

Based on Completion Time of 240 Calendar Days

LINE NO.	ITEM NUMBER	DESCRIPTION	EST. QTY	UNITS OF MEASURE	UNIT PRICE	COSTS
1	101-1	MOBILIZATION	1	LS	\$	\$
2	120-1	MAINTENANCE OF TRAFFIC	1	LS	\$	\$
3	104-10	BALED HAY OR STRAW (ADDENDUM 12/2/08)	0	LF	\$	\$
4	104-13	STAKED SILT FENCE	0	LF	\$	\$
5	110-1	CLEARING & GRUBBING	1	LS	\$	\$
6	110-3	REMOVAL OF EXISTING STRUCTURES (CATCH BASINS)	5	EA	\$	\$
7	120-1	REGULAR EXCAVATING	1	LS	\$	\$
8	162-2	TOP SOIL (6" THICK)	4,800	SY	\$	\$
9	425-11	DRAINAGE STRUCTURE (GRATE INLET)	5	EA	\$	\$
10	430-141-000	INSTALL 42" CLASS III	888	LF	\$	\$
11	430-141-000	INSTALL 29" X 45" RCP CLASS III	896	LF	\$	\$
12	580-332-2	TREE REMOVAL	25	EA	\$	\$
13	575-1-1	SODDING (BAHIA)	4800	SY	\$	\$
14	1600-900-26	REMOVE EXISTING PIPE (20" OR MORE)	1800	LF	\$	\$
15		PUMPING AND DEWATERING	1	LS	\$	\$
16		MISCELLANEOUS WORK AND CLEANUP	1	LS	\$	\$
17		REMOVE EXISTING FENCE	3,600	LF	\$	\$
18		INSTALL TEMPORARY CHAIN LINK FENCE AND REMOVAL OF TEMPORARY FENCE (LOCATION TO BE COORDINATED WITH EACH PROPERTY OWNER)	3,600	LF	\$	\$
19		INSTALL PERMANENT REPLACEMENT FENCE, CHAIN LINK (ADDENDUM 12/2/08)	1800	LF	\$	\$
20		INSTALL PERMANENT REPLACEMENT FENCE, WOOD FENCE (ADDENDUM 12/2/08)	1800	LF	\$	\$
21		SUB TOTAL			\$	\$
22		CONTINGENCY	1	LS		\$45,126.00
23		TOTAL PRICE- Based on Completion Time of 240 Calendar Days				\$

ADDENDUM # 1

BID FORM - SUBCONTRACTOR PERCENTAGE
 (Submit in Triplicate)
 Section 00300 - ADDENDUM NO. 1 (12/2/08)

BID 'B'

65th Avenue West-Pipe Replacement from 12th Street West to 5th Street West (IFB# 09-0043-DS)

Based on Completion time of 240 Calendar Days

LINE NO.	ITEM NO.	DESCRIPTION	WORK BY SUBCONTRACTOR		DESCRIPTION OF WORK
			%	MBE/WBE	BY SUBCONTRACTOR
1	101-1	MOBILIZATION			
2	120-1	MAINTENANCE OF TRAFFIC			
3	104-10	BALED HAY OR STRAW (ADDENDUM 12/2/08)			
4	104-13	STAKED SILT FENCE			
5	110-1	CLEARING & GRUBBING			
6	110-3	REMOVAL OF EXISTING STRUCTURES (CATCH BASINS)			
7	120-1	REGULAR EXCAVATING			
8	162-2	TOP SOIL (6" THICK)			
9	425-11	DRAINAGE STRUCTURE (GRATE INLET)			
10	430-141-000	INSTALL 42" RCP CLASS III			
11	430-141-000	INSTALL 29' X 45' RCP CLASS III			
12	580-332-2	TREE REMOVAL			
13	575-1-1	SODDING (BAHIA)			
14	1600-900-26	REMOVE EXISTING PIPE (20" OR MORE)			
15		PUMPING AND DEWATERING			
16		DISCRETIONARY WORK			
17		REMOVE EXISTING FENCE			
18		INSTALL TEMPORARY CHAIN LINK FENCE AND REMOVAL OF TEMPORARY FENCE (LOCATION TO BE COORDINATED WITH EACH PROPERTY OWNER)			
19		INSTALL PERMANENT REPLACEMENT FENCE, CHAIN LINK (ADDENDUM 12/2/08)			
20		INSTALL PERMANENT REPLACEMENT FENCE, WOOD LINK (ADDENDUM 12/2/08)			
21		MISCELLANEOUS WORK AND CLEAN UP			
22				TOTAL	

ADDENDUM # 1

This is a duplication of the bid items where the Bidder shall state the percentage of work (of each item listed) and a description of the work which shall be performed by a subcontractor.

BIDDER: _____