



Financial Management Department
Purchasing Division
1112 Manatee Ave W Suite 803
Bradenton, FL 34205
Phone: (941) 749-3074
www.mymanatee.org

email

February 23, 2015

TO: All Interested Bidders

SUBJECT: Invitation for Bid #15-0490DC
Rookery at Perico Preserve

ADDENDUM #2

Bidders are hereby notified that this Addendum shall be acknowledged on the Bid Form and made a part of the above named bidding and contract documents.

1. Bid Opening is extended to March 3, 2015 at 3:00 P.M., same location.
2. **QUESTION:** In reviewing bridge span lengths, drawing calls for 15' span length in the middle of several bridges. Specifications call for Top Down construction. Can 15' span length be reduced to a maximum of 10' to accommodate Top Down construction?

RESPONSE: As long as changing the center span to 10' does not require any permit modifications and there are no additional pilings in the water with a 10' span, the County does not object to a reduction to a 10' center span for pedestrian bridges. Any permit modifications as a result of variance from the permitted drawings are the responsibility of the contractor.

3. Bids shall be submitted in Triplicate, one original and two copies.
4. **Question:** The Table of Contents refers to a Technical Specifications section with 14 pages. We are unable to locate. Is there a Technical Specification Section?

RESPONSE: Technical Specs and Section D are the same. Delete reference to Technical Specification on Table of Contents page.

5. **QUESTION:** Section D.1.8 states that Pensacola Bahia sod shall be used on areas to be sodded, There is no Pensacola Bahia sod available around this area. Argentine Bahia sod is readily available in this area. Can Argentine Bahia sod be used instead of the Pensacola sod?

RESPONSE: Argentine Bahia sod will be accepted for use on this project. However, note that Paragraph 2 of Section D.1.9.2 states sod containing Bermuda grass will be rejected.

6. Bid Form has been revised to include line item for "TOTAL AMOUNT OF ABOVE ITEMS." An electronic copy of the Bid Form can be downloaded for your use.

If you have submitted a bid prior to receiving this addendum you may request in writing that your original, sealed bid be returned to your firm. All sealed bids received will be opened on the date stated.

Bids will be received at Manatee County Purchasing, 1112 Manatee Avenue West, Suite 803, Bradenton, Florida 34205 until **March 3, 2015 at 3:00 P.M.**

Sincerely,


Melissa M. Wendel, CPPO
Purchasing Official

/dcr
Attachment – Bid Form

BID FORM
IFB 15--0490DC
(Submit in Triplicate)
ROOKERY AT PERICO SEAGRASS ADVANCE MITIGATION
270 Calendar Days Completion

ITEM NO.	DESCRIPTION	UNIT	QTY.	UNIT PRICE (\$)	EXTENDED PRICE (\$)
D.1.1	MOBILIZATION	LS	1	\$ -	\$ -
D.1.2	MISCELLANEOUS PERMITS AND BONDING	LS	1	\$ -	\$ -
D.1.3	CONSTRUCTION SURVEYING AND STAKEOUT (INCLUDING RECORD DRAWINGS)	LS	1	\$ -	\$ -
D.1.4	EROSION AND TURBIDITY CONTROL				
D.1.4.1.1	Staked Silt Fence	LF	8,250	\$ -	\$ -
D.1.4.1.2	Floating/Staked Turbidity Barrier	LF	2,350	\$ -	\$ -
D.1.4.1.3	Erosion and Turbidity Control Maintenance	LS	1	\$ -	\$ -
D.1.4.1.4	Turbidity Monitoring	Days	60	\$ -	\$ -
D.1.5	CLEARING AND GRUBBING				
D.1.5.1.1	Clearing and Grubbing	AC	1.60	\$ -	\$ -
D.1.5.1.2	Scalp Mowing	AC	2.96	\$ -	\$ -
D.1.6	EXCAVATION AND MOUNDING				
D.1.6.1.1	Excavation	BCY	3,606	\$ -	\$ -
D.1.6.1.2	Fill	BCY	3,606	\$ -	\$ -
D.1.6.1.3	4" Thick Large Washed Shell	SY	2,500	\$ -	\$ -
D.1.6.1.4	9" Oyster Bags	SY	507	\$ -	\$ -
D.1.7	FINISHED GRADING	AC	4.56	\$ -	\$ -
D.1.8	SODDING AND SEEDING				
D.1.8.1.1	Sodding	SY	2,533	\$ -	\$ -
D.1.8.1.2	Hydro-Seeding	SY	10,416	\$ -	\$ -
D.1.9	MITIGATION AND HABITAT PLANTING				
D.1.9.1.1	Herbicide Treatments (2)	AC	3.83	\$ -	\$ -
D.1.9.1.2	Zone A - <i>Paspalum vaginatum</i>	LN-4"	1,062	\$ -	\$ -
D.1.9.1.3	Zone A - <i>Sesuvium portulacastrum</i>	LN-4"	653	\$ -	\$ -
D.1.9.1.4	Zone A - <i>Iva imbricata</i>	LN-4"	592	\$ -	\$ -
D.1.9.1.5	Zone A - <i>Spartina patens</i>	LN-4"	575	\$ -	\$ -
D.1.9.1.6	Zone A - <i>Spartina bakeri</i>	LN-4"	1,157	\$ -	\$ -
D.1.9.1.7	Zone A - <i>Borrchia frutescens</i>	LN-4"	1,024	\$ -	\$ -
D.1.9.1.8	Zone B - <i>Paspalum notatum</i> (Sod)	SY	6,645	\$ -	\$ -
D.1.9.1.9	Zone B - <i>Capparis jamaicensis</i>	7-GAL	60	\$ -	\$ -
D.1.9.1.10	Zone B - <i>Eugenia axillaris</i>	7-GAL	90	\$ -	\$ -
D.1.9.1.11	Zone B - <i>Eugenia foetida</i>	7-GAL	60	\$ -	\$ -
D.1.9.1.12	Zone B - <i>Forestiera segregata</i>	3-GAL	90	\$ -	\$ -
D.1.9.1.13	Zone B - <i>Sophora tomentosa</i> var. <i>truncata</i>	3-GAL	30	\$ -	\$ -
D.1.9.1.14	Zone B - <i>Yucca aloifolia</i>	7-GAL	90	\$ -	\$ -
D.1.9.1.15	Zone B - <i>Dodonaea viscosa</i>	3-GAL	90	\$ -	\$ -
D.1.9.1.16	Zone B - <i>Randia aculeata</i>	3-GAL	90	\$ -	\$ -
D.1.9.1.17	Zone B - <i>Bursera simaruba</i>	15-GAL	15	\$ -	\$ -
D.1.9.1.18	Zone B - <i>Sabal palmetto</i>	10-FT CT	7	\$ -	\$ -
D.1.9.1.19	Zone B - <i>Conocarpus erectus</i>	7-GAL	30	\$ -	\$ -
D.1.9.1.20	Zone B - <i>Conocarpus erectus</i>	15-GAL	22	\$ -	\$ -

Bidder Name: _____

Authorized Signature: _____

F:\WPDOCS\IFB\2015 IFB\15-0490dc.Perico Preserve\ABF1.form.xlsx

BID FORM
IFB 15--0490DC
(Submit in Triplicate)
ROOKERY AT PERICO SEAGRASS ADVANCE MITIGATION
270 Calendar Days Completion

ITEM NO.	DESCRIPTION	UNIT	QTY.	UNIT PRICE (\$)	EXTENDED PRICE (\$)
D.1.9.1.21	Zone B - <i>Ficus aurea</i>	15-GAL	15	\$ -	\$ -
D.1.9.1.22	Zone B - <i>Capparis jamaicensis</i>	15-GAL	15	\$ -	\$ -
D.1.9.1.23	Zone B - <i>Coccoloba uvifera</i>	15-GAL	45	\$ -	\$ -
D.1.9.1.24	Mangrove Mitigation Zone - <i>Spartina alterniflora</i>	BR	2,420	\$ -	\$ -
D.1.9.1.25	Mangrove Mitigation Zone - <i>Rhizophora mangle</i>	3-GAL	110	\$ -	\$ -
D.1.9.1.26	Mangrove Mitigation Zone - <i>Rhizophora mangle</i>	PROPAGULE	439	\$ -	\$ -
D.1.9.1.27	Mangrove Mitigation Zone - <i>Avicennia germinans</i>	LN-2"	108	\$ -	\$ -
D.1.9.1.28	Rookery Island Planting - <i>Rhizophora mangle</i>	3-GAL	45	\$ -	\$ -
D.1.10	PEDESTRIAN TRAILS (COMPLETE)				
D.1.10.1.1	Trail Stake-out and Asbuilts	LS	1	\$ -	\$ -
D.1.10.1.2	Clearing and Scalp Mowing	AC	0.70	\$ -	\$ -
D.1.10.1.3	Subgrade Compaction	SY	5,102	\$ -	\$ -
D.1.10.1.4	4" Bank Run Shell	SY	5,102	\$ -	\$ -
D.1.10.1.5	Finished Grading	AC	1.05	\$ -	\$ -
D.1.11	PEDESTRIAN BRIDGES (COMPLETE)				
D.1.11.1.1	Structural Design, Inspection and Certification	LS	1	\$ -	\$ -
D.1.11.1.2	Construction Surveying and Record Drawings	LS	1	\$ -	\$ -
D.1.11.1.3	Pedestrian Bridges 1 through 5 (8' Width)	LF	602	\$ -	\$ -
D.1.11.1.4	Pedestrian Bridge 6 (24' x 18' Observation Deck)	SF	432	\$ -	\$ -
TOTAL AMOUNT					\$ -
(ABOVE ITEMS D.1.1 to D.1.11.1.4)					
Contingency Amount (10% of Total)					\$ -
TOTAL BID AMOUNT					\$ -

Bidder Name: _____

Authorized Signature: _____

F:\WP\DOCS\IFB\2015 IFB\15-0490dc-Perico Preserve\48F1.formal.docx