

MEMORANDUM



To: All Interested Bidders
Date: **January 20, 2017**
Subject: RFQ17-0361OV, Lift Station 41A, Force Main Repairs
And Manhole Rehabilitation, Whitfield Avenue and West
Country Club Lane, Bradenton, FL (Project #402-5104285)
Addendum #2

Quoters are hereby notified that this Addendum shall be acknowledged on Quote Form Page 1 of the Quote Form and made a part of the above named quoting and contract documents. Quotes submitted without Acknowledgement of the Addendum will be considered incomplete.

The following items are issued to add to, modify, and clarify the quote and contract documents. These items shall have the same force and effect as the original quoting document, and cost involved shall be included in the bid prices. Bids to be submitted on the specified quote date, shall conform to the additions and revisions listed herein.

The deadline of January 12, 2017 at 5:00 PM concerning all inquiries, interpretation, clarification or additional information pertaining to this quote has passed. No additional inquiries shall be considered. This deadline has been established to maintain fair treatment for all potential quoters, while maintaining the expedited nature of the Economic Stimulus that the contracting of this work may achieve.

Quoters Note 1: Reply date has been REVISED to read: **February 1, 2017 at 3:00 PM.**
(Was: January 27, 2017 at 3:00 PM)

Quoters Note 2: CLARIFICATION FROM ENGINEER:

Reference Contract Documents Specifications, **TABLE OF CONTENTS**, under **Division 3, CONCRETE Section 03500: Lift Station Specification** reads "ERROR! BOOKMARK NOT DEFINED." This section is not a part of this Specification package and is NOT included in this Specification.

Quoters Note 3: Excerpts of the As-Built Record plans for the existing lift station are hereby made a part of this Addendum No. 2:

Attachment "E", Improvements at MLS 41-A, Record Drawing, G-1 and C-1, dated May 2010, (2 total pdf pages).

Attachment "F", Lift Station 41-A (RTU #454) Rehab, Record Drawings, Sheet 1, through 5, dated November 2003, (5 total pdf pages).

(NOTE: THE COUNTY MAKES NO REPRESENTATION REGARDING THE ACCURACY OF THE ATTACHED PLANS)

Financial Management Department
Procurement Division
1112 Manatee Avenue West, Suite 803
Phone number: (941) 749-3014

Attachment "G". Existing wall, dated 09/20/2016, (4 total pdf pages).

Attachment "H". Photo of damaged wood and stucco of wall to be replaced dated 01/05/2017 (1 total pdf page).

Attachment "I". Photo of decorative plantings along the curved section of the wall at Carley Subdivision, Whitfield Avenue, (1 total pdf page).

Quoters Note 4: **REMOVE** current explanation of Bid Item 5, Measurement and Payment, page 33 / 257.

REPLACE WITH: "Payment for work included in this Bid item will be made at the applicable Contract lump sum price bid for removing and replacing the existing decorative wall to match the existing wall, as shown on the Drawings or where directed by the Project Representative. Measurement shall be according to the Schedule of Values. Payment shall represent full compensation for removal and disposal of the existing wall, and constructing a replacement wall, including but not limited to all labor, material and equipment, excavation backfill, compaction, concrete, reinforcement, wood framing and cladding, stucco, trim, painting, connection to the existing wall, permits, wind and building code compliance as required, protection of portions of the existing wall to remain, and all incidentals necessary for completion of this Bid Item, ready for approval and acceptance by the Engineer/Owner. The Contractor is responsible for submitting sealed plans prepared by a Florida Professional Engineer to acquire a Sign Permit for the wall replacement. The cost for a Sign Permit is \$296.00 +3%. A Certified Building Contractor or a Certified General Contractor must submit the permit application and construct the wall/sign."

Quoters Note 5: Below responses are a result of inquiries, interpretation, clarification pertaining to this project which were received at the Information Conference held on January 5, 2017 and questions received through January 12, 2017.

Q1. On the quote form, item 8 for Rehab of Manholes has a unit of measure of SF, should it be VF?

R1. No, the measure of Square Fee (SF) is correct for item 8, "Rehab and Reline Manhole".

Q2. Is dewatering to the roadside swale acceptable?

R2. Dewatering to the roadside swale is acceptable, provided it is one in accordance with FDEP requirements, and is limited to the capacity of the stormwater system.

Q3. Are all saddles to be stainless steel?

R3. Yes, all saddles and saddle hardware must be stainless steel.

Q4. Is an EZ Valve (insertion valve) acceptable instead of a line stop and tapping valve with saddle?

R4. All Quoters are required to submit their Quote in accordance with the plans and specifications which were made a part of the original Request for Quotation Document, RFQ17-03610V.

Q5. Which plants belong to the HOA, and which must be replaced after wall construction?

R5. All disturbed vegetation, with the exception of the decorative plantings along the curved section of the wall shall be replaced. The HOA will replace the decorative plantings.

Q6. Does the wall replacement item require the contractor to obtain permits and submit a design by a Florida Professional Engineer?

R6. Yes, a sign permit application must be submitted by the contractor for the wall replacement. The cost is approximately \$300.00. The application and wall construction must be completed by a Florida Certified General Contractor or a Certified Building Contractor. The contractor must prepare wall plans for the permit application to the satisfaction of the Manatee County Building Department and shall be prepared by a Florida Professional Engineer. It appears that All American Enterprises of Sarasota may have done the work on the wall in 2004.

Q7. What is the voltage and height of existing overhead power lines on Whitfield Avenue?

R7. The voltage is less than 50,000 volts and the required clearance is at least ten (10) feet radius in accordance with OSHA. The power line elevations have not been measured.


Q8. Please consider approving our epoxy liner and polymer cement materials for the manhole rehab and relining work in this project.

R8. All Quoters are required to submit their Quote in accordance with the plans and specifications which were made a part of the original Request for Quotation Document, RFQ17-03610V.

This is NOT a sealed bid solicitation. Quotes may be received via email to Olga.Valcich@mymanatee.org or faxed to 941-749-3034 or sent via U.S. Mail to Manatee County Procurement Division, Suite 803, 1112 Manatee Avenue West, Bradenton, FL 34205.

All replies are due February 1, 2017 at 3:00 PM.

Sincerely yours



For Melissa M. Wendel, CPPO, Purchasing Official
Manatee County Procurement Division

OV (13 [pdf pages attached])