

1112 Manatee Avenue West Bradenton, FL 34205 purchasing@mymanatee.org

## **Solicitation Addendum**

Addendum No.: 5

Solicitation No.: 21-TA003823CD

Project No.: 6108870

Solicitation Title: Phase II Repairs to Lake Manatee Dam

Addendum Date: October 5, 2021

Procurement Contact: Chris Daley, CPPO, CPPB - Procurement Project Manager

IFBC No. 21-TA003823CD is amended as set forth herein. Responses to questions posed by prospective bidders are provided below. This Addendum is hereby incorporated in and made a part of IFBC No. 21-TA003823CD

## **CHANGE TO:**

ADVERTISMENT PAGE, DATE, TIME, AND PLACE DUE

The Due Date and Time for submission of Bids in response to this Invitation for Bid Construction (IFBC) is October 6, 2021 October 14, 2021 at 3:00 PM ET. Bids must be delivered to the following location: Manatee County Administration Building, 1112 Manatee Ave. W., Suite 803, Bradenton, FL 34205 prior to the Due Date and Time.

## **CHANGE TO:**

## SECTION A, FIRST PARAGRAPH OF ARTICLE A.01, BID DUE DATE

The Due Date and Time for submission of Bids in response to this Invitation for Bid Construction (IFBC) is October 6, 2021 October 14, 2021 at 3:00 PM ET. Bids must be delivered to the following location: Manatee County Administration Building, 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205 and time stamped by a Procurement representative prior to the Due Date and Time.

# CHANGE TO: SECTION A, ARTICLE A.51, SOLICITATION SCHEDULE

The following schedule has been established for this Solicitation process. Refer to the County's website (<a href="www.mymanatee.org">www.mymanatee.org</a> > Business > Bids & Proposals) for meeting locations and updated information pertaining to any revisions to this schedule.

Scheduled Item	Scheduled Date
Non-Mandatory Information Conference 1112 Manatee Avenue West, Suite 863 Bradenton, FL 34205	August 20, 2021 at 10:00 AM, ET
Question and Clarification Deadline	September 14, 2021
Final Addendum Posted	September 23, 2021 October 5, 2021
Bid Response Due Date and Time	October 6, 2021 October 14, 2021, 3:00 PM, ET
Projected Award	October 2021 November 2021

## **REPLACE:**

# APPENDIX L, BID PRICING FORM, BID PRICING FORM PAGES APPENDIX L-1 THROUGH L-8

Replace Bid Pricing form pages Appendix L-1 through L-8 with the Revised bid Pricing Form pages Appendix L-1 through L-9 that are issued with this Addendum 5.

## Replace:

## **ELECTRONIC BID PRICING FORM**

Replace the Electronic Bid Pricing Form with the Revised Electronic Bid Pricing Form issued with this Addendum 5.

## **REPLACE:**

# BID ATTACHMENT 2, TECHNICAL SPECIFICATIONS, SPECIFICATION SECTION 31 23 19

Replace Specification Section 31 23 19, with the attached Specification Section 31 23 19, revised with this Addendum 5.

## **REPLACE:**

## **BID ATTACHMENT 3, PLANT SET/DRAWING, DRAWINGS SD-112**

Replace Drawing SD-112 with the Revised Drawing SD-112, issued with this Addendum 5.

## ADD:

## The following items are issued with this Addendum 5:

1. Parts lists to replace the motors, gear boxes, and ancillary equipment; shown as Motion Industries Quotes (without pricing) FL04-372057 and FL04-378658.

## **CLARIFICATON OF ENGONEER'S CHANGES:**

- 1) Per Q2- Revised Drawing Sheet SD-112
- 2) Parts lists from local vendor for motors and gears and ancillary equipment to replace the hoisting mechanisms of the Tainter Gates
- Revisions to Bid Form to provide unit pricing on Additional Item 1108 "Reconstruction of Three Fuse Plugs in Emergency Spillway"
- 4) Revisions to Bid Form to provide Additional Alternate Items unit pricing under Category 1200 not to be included in the base bid price.
- 5) Per Clarification of Q38 Addendum 4 regarding Contractor's responsibilities for handling bypass flows to maintain mandated conductivity levels in the Manatee River downstream of the dam under low flow conditions Revised Specification 31 23 19 Dewatering

## **QUESTIONS AND RESPONSES:**

- Q1. Bid item 306 and 1006 require "skim coat" for the existing concrete feature. Please provide the specification for work relating to skim coating. The specification should define the required procedures and material used for the work.
- R1. "Skim coat" referenced in the project documents refers to surface repairs required on the existing concrete components with evidence of surface erosion. Reference project specification Section 03 01 00 Rehabilitation of Concrete.
- Q2. Section D4/SD112 is shown on SD-501. There is no section D4 shown on drawing SD112, please provide clarification.
- R2. Section cuts D3/SD501 & B3/SD501 on sheet SD112 were mis-labeled. Both section cuts should read D4/SD501 on sheet SD112. Sheet SD112 revised accordingly.
- Q3. C5/SD112 shown on SD-501 notes "new reinforced concrete access steps dowel into pile cap and end sill". No rebar detail is provided for the concrete access steps. Please provide the rebar detail.
- R3. Conceptual plan shown for concrete steps. Contractor to submit a preferred reinforced concrete step design for approval.
- Q4. Regarding the below addendum



Please clarify what material you are calling for on this project. USM (Uniform Section Mat) - OR - FPM (Filter Point Mat). Additionally, please clarify what size mat you are calling for? How thick of a mattress?

R4. Uniform Section Mat is to be used. Refer to Question/Response 47 in Addendum No. 4, published September 24, 2021 for the size of the uniform section mat.

# Q5. What do we need to supply for new motors, gear boxes, and whatever else is included in the reworking of the hoisting mechanism?

R5. Parts lists are provided in this Addendum to replace the motors, gear boxes, and ancillary equipment.

## **NOTE:**

Deleted items will be struck through, added or modified items will be <u>underlined</u>. All other terms and conditions remain as stated in the IFBC.

## **INSTRUCTIONS:**

Receipt of this Addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the response being deemed non-responsive.

## **END OF ADDENDUM**

**AUTHORIZED FOR RELEASE** 

# BID FORM PHASE II REAPIRS TO LAKE MANATEE DAM BID "A" BASED ON COMPLETION TIME OF 600 CALENDAR DAYS

Task Pay Item Number	Description	Estimated Quantity	Unit	UNIT PRICE	TOTAL BID PRICE
100	Mobilization				
101	Pre-Mobilization Activities (Construction Submittals)	1	LS		
102	Utility Locates	1	LS		
103	Laydown and Setup	1	LS		
104	Office Set-Up, Maintenance and Operation	1	LS		
105	Erosion and Sediment Control Best Management Practices	1	LS		
106	Temporary Downstream Access Road	1	LS		
107	Temporary Boat/Barge Dock	1	LS		
108	General Conditions	1	LS		
109	Permits, Bonding, etc.	1	LS		
			N	MOBILIZATION SUBTOTAL=	
200	Void Filling				
201	Demonstration Project	1	LS		
202	Production – Downstream Apron	1	LS		

Bidder Name:			
			,
Authorized Sian	ature:		

Task Pay Item Number	Description	Estimated Quantity	Unit	UNIT PRICE	TOTAL BID PRICE
203	Production – Stilling Basin	1	LS		
				VOID FILLING SUBTOTAL=	
300	Downstream Channel Repai	irs			
301	Site Preparation (rip rap removal, excavation, engineered fill)	1	LS		
302	Existing Apron Slab Preparation	1	LS		
303	Reinforcement, Miscellaneous Metals, Expansion Joints, Sealant and Waterstop	1	LS		
304	Form, Pour and Cure Downstream Concrete Apron Overlay	1	LS		
305	Cast-in-Place Concrete Stairs	1	LS		
306	Concrete Stilling Basin Repairs (Skim Coat on End sill)	1	LS		
307	Training Wall Repairs	1	LS		
308	Demolition and Abandonment of Miscellaneous Metals and Drains	1	LS		
309	Ogee Repairs (Downstream and Upstream)	1	LS		
		DOWNSTRE	AM CHAN	INEL REPAIRS SUBTOTAL=	
400	Downstream Pressure Relief System				
401	Vertical Relief Wells	1	LS		
402	End Sill Relief Wells	1	LS		

Bidder Name:	
Authorized Signature:	 

Task Pay Item Number	Description	Estimated Quantity	Unit	UNIT PRICE	TOTAL BID PRICE
	DOWN	STREAM PRE	SSURE RE	ELIEF SYSTEM SUBTOTAL=	
500	Encase Spillway with Seepa	ge Barrier			
501	Construction Grading	1	LS		
502	Sheet Piling Including Concrete Cap and Handrail Installation	1	LS		
503	Deep Soil Mixing (Test Sections, Final Design Approval, F&I), Assume 10% Portland Cement and 5% Bentonite by Weight	1	LS		
504	Jet Grouting (Test Sections, Final Design Approval, F&I), Assume 10% Portland Cement and 5% Bentonite by Weight	1	LS		
505	Concrete Slab on Grade Installation	1	LS		
506	Final Grading and Restoration	1	LS		
	ENCASE SPILLWAY WITH SEE	PAGE BARRI	ER SUBTO	DTAL=	
600	Approach Channel Repairs				
601	Installation of Combi-Wall North and South Embankments	1	LS		
602	Complete Demolition and Removal of Slope Paving and Soldier Pile Wall and Lagging	1	LS		
603	Removal, Abandonment and Grouting of Monitoring Wells and Drains	1	LS		
604	Excavation of Embankments North and South of the Spillway and in Approach Channel Including Removal of Jet Grout Spoils, Organics and Other Debris	1	LS		

Bidder Name:			

	1		1	1	
Task Pay Item Number	Description	Estimated Quantity	Unit	UNIT PRICE	TOTAL BID PRICE
605	Removal of Grout Spoils from Approach Slab and Approach Wall Footings	1	LS		
606	Install Sheet Pile and Combi-Wall System with Structural Bracing for Containment Area (Cofferdam)	1	LS		
607	Install Dewatering Wells and Grout Plugs in Containment Area (Cofferdam)	1	LS		
608	Partial Dewater of Containment Area (Cofferdam). Contractor May Fully Dewater at Their Discretion.	1	LS		
609	Fully Dewater Containment Area (Cofferdam) for Minimum 30 Consecutive Days	1	LS		
610	Complete Approach Slab Repairs	1	LS		
611	Complete Approach Wall Repairs	1	LS		
612	Flood Containment Area and Cut Sheet Pile Along Approach Walls and Combi-Wall Along Approach Slab	1	LS		
613	Install Secondary Seal on Approach Wall Footings and Concrete Cap on Combi-Wall Along Approach Slab	1	LS		
614	Backfill Around Approach Walls with Engineered Fill to Achieve Final Grades	1	LS		
615	Install Continuous Reinforced Concrete Cap on Combi-Wall along North and South Embankments and Restore Grade and Slope Paving	1	LS		

Bidder Name:	
Authorized Signature:	 

Task Pay Item Number	Description	Estimated Quantity	Unit	UNIT PRICE	TOTAL BID PRICE		
616	Install Riprap to Final Grade	1	LS				
617	Placement of Watertight Slab on Grade on Embankment	1	LS				
618	Install Handrail	1	LS				
		APPROA	ACH CHAN	INEL REPAIRS SUBTOTAL=			
700	Stoplog Guide and Tainter (	Gate Rehabilit	ation				
701	Stoplog Guide Repairs	1	LS				
702	Tainter Gate Repairs	1	LS				
703	Threshold Replacement	1	LS				
704	Course Screen Chamber - Concrete Repairs	1	LS				
705	Course Screen Chamber Miscellaneous Metal Removal/Refurbishment/Coating	1	LS				
706	48" Pipe Inspection	1	LS				
	STOPLOG GUIDE AND TAINTER GATE REHABILITATION SUBTOTAL=						
800	Upstream Soil Cement Refu	rbishment					
801	Uniform Section Mat Test Section	1	LS				
802	Concrete Slope Pavement Test Section	1	LS				
803	Spot Repair Test Section	1	LS				

Bidder Name:	
Authorized Signature:	

Task Pay Item Number	Description	Estimated Quantity	Unit	UNIT PRICE	TOTAL BID PRICE
804	Full Depth Soil Cement Test Section	1	LS		
805	Spot Repair at End of Flume	1	LS		
		EAM SOIL CE	MENT REF	URBISHMENT SUBTOTAL=	
900	Mechanical Upgrade				
901	Replace Electric Motors	1	LS		
902	Replace Gear Boxes	1	LS		
903	Replace Instrumentation and Controls	1	LS		
			MECHANIC	CAL UPGRADE SUBTOTAL=	
1000	Miscellaneous Improvemen	ts			
1001	Laybys	1	LS		
1002	Concrete Deck Repairs	1	LS		
1003	New Deck Paint: Sand Blast, Remove Rust, Primer and Paint	1	LS		
1004	Add Safety Ladders	1	LS		
1005	Add/Replace Handrails	1	LS		
1006	Skim Coat Over Piers	1	LS		
1007	Boat Launch Improvements	1	LS		

Bidder Name:	
Authorized Signature:	

Task Pay Item Number	Description	Estimated Quantity	Unit	UNIT PRICE	TOTAL BID PRICE
1008	Bridge Repairs	1	LS		
		MISCELLA	NEOUS IMI	PROVEMENTS SUBTOTAL=	
1100	Demobilization				
1101	Full Depth Asphalt Milling and Asphalt Pavement	1	LS		
1102	Punchlist Inspection	1	LS		
1103	Restoration of Laydowns	1	LS		
1104	Final Cleanup	1	LS		
1105	Closeout Manuals / Submittals	1	LS		
1106	Red-Line Construction Drawings	1	LS		
1107	Borrow Area Reclamation	1	LS		
1108	Reconstruction of Three Fuze Plugs in Emergency Spillway	1	LS		
			DEN	MOBILIZATION SUBTOTAL=	
	TOTAL BASE BID "A"- Based of Time of 600 Calendar Days	on Complet	ion		
	CONTRACT CONTINGENCY WORK (USED ONLY WITH COUNTY APPROVAL)			10%	
	Contingenct- Vased on Comple Calendar Days	etion Time (			

Bidder Name:	
Authorized Signature:	 

Task Pay Item Number  Description  Esti Qu	L UNIT PRICE	TOTAL BID PRICE
--	--------------	-----------------

THE FOLLOWING PAY ITEMS ARE INTENDED TO ESTABLISH UNIT RATES FOR UNFORESEEN CIRCUMSTANCES DURING THE CONTRACT PERIOD, AND WILL NOT BE UTILIZED TO DETERMNINE CONTRACT AWARD. UNIT PRICCES SHALL INCLUDE ALL LABOR, MATERIAL, AND EQUIPENT REQUIRED.

1200					
Task Number	Description	Estimated Quantity <b>A</b>	Unit	Total Unit Price	Total Bid Price
1201	Standby Rate				
	a. Unmanned Equipment Rates	1	Hour		
	b. Earthwork Equipment Rates	1	Hour		
	c. Jet Grout Column Equipment Rates	1	Hour		
	d. Soil-Mixed Column Equipment Rates	1	Hour		
	e. Cofferdam Equipment Rates	1	Hour		
	f. Dive Team	1	Hour		
	g. Void Filling Equipment Rates	1	Hour		
1202	Emergency Demobilization				
	a. Demobilization	1	LS		
	b. Site Monitoring	5	Day		
	c. Standby rate	5	Day		
	d. Mobilization	1	LS		
1203	Inspection	1	LS		
1204	and Instrumentation and Controls	1	LS		
1205	equai)	1	LS		
1206	diameter), per length of wall	1	LF		
1207	diameter) per length of wall	1	LF		
	Extra Combi-Wall (Choose the total length of 1 pipe pile and sheet pile section)	1	LF		
1209	Extra Concrete Surface Repairs	1	SF		

Bidder Name:	
Authorized Signature:	


Task Pay Item Number	Description	Estimated Quantity	Unit	UNIT PRICE	TOTAL BID PRICE
1210	Extra Sheet Pile Wall	1	SF		
1211	Extra Deep Soil Mix Columns (3-ft diameter), per length of wall	1	LF		
1212	Placing Select Engineered Fill (in-the-dry)	1	CYD		
1213	Placing Select Engineered Fill (through the water column)	1	CYD		
1214	Expansion Joint Replacement	1	LF		
	Excavation and Disposal of Unsuitable Material	1	CYD		
1216	Reinforcing steel locating services (GPR or similar)	1	Day		

## **SECTION 31 23 19**

## **DEWATERING**

	APPROVAL STATUS							
PREPA	RED BY: GA DATE 27July2021 CHECKED DD BY:		DD	DATE	27July2021			
APPROVED BY: DB DATE 27July2021								
			REVISIO	N STATUS	6			
REV	ISSUED FOR		REVISED BY	CHECKED BY	APPROVAL	APPROVAL	DATE	
0	Bidding		GA	DD			14Sept2021	
2	Bidding		GA	ML			4Oct2021	

## Engineer's Seal



## Digital Signature

GLEN ANDERSEN P.E., STATE OF FLORIDA, PROFESSIONAL ENGINEER, LICENSE NO. 77304.

THIS ITEM HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY GLEN ANDERSEN ON 4 OCT 2021, USING AN SHA AUTHENTICATION CODE BY DIGICERT.

PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND THE DIGITAL SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

## **SECTION 31 23 19**

## **DEWATERING**

## PART 1 GENERAL

## 1.1 DESCRIPTION

Furnish, operate, and maintain dewatering measures and equipment for the control, collection, and disposal of ground and surface water entering excavations and for pressure relief wells as shown on the drawings.

## 1.2 RELATED WORK SPECIFIED ELSEWHERE

- A Specification 01 33 00 Submittal Procedures
- B. Specification 31 00 00 Earthwork

## 1.3 SUBMITTALS

- A Submit plans for dewatering the excavation areas as part of the Construction Work Plan before work starts for ENGINEER review and approval. Include means and methods for dewatering.
- B. Submit changes to dewatering means and methods to the ENGINEER for review before making those changes.

## PART 2 PRODUCTS

## 2.1 GENERAL

A. Provide, operate, and maintain a dewatering system to remove water from the cofferdam, excavations and trenches using pumps, drains, well points, piping, and other facilities necessary to keep the excavations free of water, as required by these Specifications and the Engineer. Have spare units available for immediate use in the event of equipment breakdowns or significant rainfall.

## PART 3 EXECUTION

## 3.1 PERFORMANCE

- A. General:
  - 1. Perform dewatering work as necessary at no additional cost to the Owner.
- B. Excavation Dewatering:
  - Dispose of collected construction water removed from excavations, dewatering of soil/sediment, stockpile containment areas, and decontamination water in accordance with Permit requirements.
  - 2 Treatment: Prior to discharge, collected construction water shall be

- temporarily stored in sediment traps or detention basins, whichever is more applicable to the quality of water, in accordance with FDEP requirements.
- 3. Contractor may install a groundwater dewatering system to depress water table below excavation depths as required for downstream excavations. CONTRACTOR responsible for management, sampling, and disposal of extracted groundwater. Dewatering pressure relief wells on the Contract Documents shall be installed as shown for dewatering the cofferdam. The locations are for example only and must be designed by the Contractor's Engineer and approved by the County and Engineer-of-Record.
- 4. Discharge water from groundwater dewatering system to the river channel downstream of the area being excavated. Use turbidity curtains immediately downstream of the bypass and dewatering discharge points.

## C. Service Spillway Bypass Flows:

1. The existing earthen fuse plug Emergency Spillway will function as the principal by-pass for flows down the Manatee River during construction. The sill elevation for this Spillway is 38 ft. Three of the bays will be opened by the County to handle the normal flows during construction and the remaining 5 bays with fuse plugs at elevations ranging from 44 ft to 45.5 ft will automatically open based on the water levels in the Lake.

Manatee County is mandated to maintain conductivity levels in the Manatee River downstream of the dam below a maximum target conductivity level through daily releases at a rate of either 275,000 gpd (approx. 200 gpm) or 646,300 gpd (approx. 450 gpm), depending upon the downstream conductivity levels as measured by the County at the Rye Road Bridge.

With respect to the by-pass flows, the County is responsible for:

- Managing the Emergency Spillway at the start of Construction by lowering the water levels in the Lake to below El 38 ft and removing three earthen plugs prior to the start of construction;
- Monitoring conductivity levels in the Manatee River downstream of the spillway and notifying the Contractor what level of daily release from the Lake is necessary; and,

## the Contractor is responsible for:

- Managing the downstream construction areas during high-tailwater events including but not limited to those associated with high flows through the Emergency Spillway which includes removing equipment and personnel from the area at no additional cost to the County;
- ii. Constructing and operating a bypass system (cofferdams/bladder dams, pumps, and associated piping and appurtenances) as

necessary to handle water collected from dewatering activities and the mandated daily releases to maintain downstream conductivity levels. These responsibilities are to be provided at no additional cost to the County.

iii. Replacing the three earthen plugs in the Emergency Spillway in the dry and at the end of construction per the dimensions contained on the original construction drawings for the Emergency Spillway (1983) at no additional cost to the County.

## D. Damage:

- Repair damage resulting from the dewatering and bypass flow operations or failure to maintain the Work in a suitable dry condition at no additional cost to the Owner.
  - This damage also includes returning any sediment traps or detention basins to their preconstruction condition and removing any sediment buildup in the river channel at the discharge location to return it to the preconstruction bathymetry.
- 2 Incorporate both active and passive construction controls in the Emergency Shutdown Plan for Hurricane, Tropical Storm, or Heavy Rainfall Event to:
  - i. Protect new work from being damaged; and,
  - ii. Prevent flood water from passing through the spillway in the event of a flooding of the cofferdam.
- 3. These construction controls cover every critical activity involving the safety of the dam and can include but are not limited to:
  - Scheduling and sequencing repairs to the tainter and coarse screen gates;
  - ii. Using the existing stop log to seal a bay if its tainter gate is open and cannot be lowered;
  - iii. Managing the tailwater from the Emergency Spillway in the downstream repair area, etc.
- 4. The cofferdam is designed to flood if the lake or waves from the lake reach the level indicated on the Plans.
- 5. All flood water during construction is to be released through the Emergency Spillway
- 6 Brace or otherwise protect pipelines and structures which are not stable, against floatation, when necessary.

## E. Diversion Berms:



2. Design and construct diversion berms to withstand all imposed loads to prevent injury to adjacent structures or property.

## 3.2 DEWATERING THE CONSTRUCTION SITE

- A. Dewater excavation areas and other parts of the construction site and keep free of standing water or excessively muddy conditions as needed for the Work.
- B. Provide, install, operate, and maintain drains, sumps, pumps, and other equipment needed to perform the dewatering as specified.
- C. Dewatering methods that cause a loss of fines from excavation areas are not allowed.
- D. Discharge of water pumped from excavations in accordance with Section XI, Specification 02 72 00 Construction Water Management.

## 3.3 REMOVAL OF TEMPORARY WORKS

- A. When temporary works are no longer required, remove or level and grade them to the extent required to: present a clean appearance; prevent obstruction of water flow; and prevent interference with the operation of or access to permanent works.
- B. Except as otherwise specified, remove temporary underdrain piping.
- C. Continually clean up waste, debris, and leftover materials resulting from the Cutoff Wall, Tie-Ins, or Support Columns construction process. Dispose of these materials in designated areas provided by the Owner in accordance with all Federal, State, and local regulations and codes

-- End of Section --



# Quote

MOTION INDUSTRIES

1753 SOUTH COUNTY LINE RD PLANT CITY, FL 33566 PHONE: 8635330574

FAX: 8635339386

Date: 09/30/21

Note: Due to recent volatility of raw materials, price and delivery are subject to change based on availability at time of order.

Requests for statutory and regulatory documentation (REACH, RoHS, California Prop 65, Conflict Minerals, Certificates of Conformance, Safety Data Sheets, and other applicable compliance documents) for the product(s) in this order must be communicated by the customer to the Motion Industries, Inc. sales representative at the time the order is placed. Motion Industries, Inc. cannot accept requests for these documents after completion of the sale.

To:

PENN PRO INC 2830 PARKWAY ST LAKELAND, FL

PO: QUOTE

**REL: UPDATED QUOTE** 

**Quote Number:** FL04 - 372057

Customer RFQ: QUOTE

FOB: FOB ORG, FRT PP&ADD

Quote Sent By: TERRY

**Payment Terms:** 1% 10 & 25TH NET 30

**Delivery:** STOCK UNLESS NOTED

**DIRECT SHIP** 

33811

Description	Manufacturer	Quantity	Unit	Unit Price	Amount
LINE ITEM: 001					
CHHJS-6225DA-Y-TL-7569		1	EA		
SUMITOMO CYCLO REDUCER W/ TORG	QUE LIMITER				
ITEM NO: 99999999	SUMITOMO				
		DELIVERY DATE:			

BUYER UNDERSTANDS AND AGREES THAT GOODS PRESENTED TO BUYER PURSUANT TO THIS INVOICE ARE BEING TENDERED CONTINGENT UPON BUYER'S AGREEMENT TO ALL OF MOTION'S TERMS AND CONDITIONS RELATED TO SALES, MOTION'S TERMS AND CONDITIONS ARE AVAILABLE AT THE MOTION BRANCH OR AT WWW.MOTIONINDUSTRIES.COM. BUYER'S ACCEPTANCE OF THE DELIVERY OF THE GOODS SHALL CONFIRM BUYER'S AGREEMENT TO ALL OF MOTION'S TERMS AND CONDITIONS.

PAGE 1 of 3 OCN: FL04 - 372057 PO: QUOTE REL: UPDATED QUOTE 09/30/21

Description	Manufacturer	Quantity	Unit	Unit Price	Amount
RATINGS (@1750 RPM INPUT): 134,000" LBS OUTPUT TORQUE 3 HP UNIT INCLUDES FOLLOWING SPEC 1.SPECIAL LOW SPEED SHAFT & T DIMENSIONS OF EXISTING HC1910 2.IP55 DEGREE OF ENVIRONMENT 3.INTEGRAL TORQUE LIMITER- CO ALARM SWITCH & SHUT OFF & LO NOTE: CUSTOMER SHOULD SUPP VALUES WITH ORDER ESTIMATE 3 WEEKS FOR TRANSM DELIVERY: 13-15 WEEKS AFTER R DAVID, THE PRICES ON THIS QUOTE ARE I'M SENDING THIS FOR PART NUM REGARDS TS  LINE ITEM: 002	CIAL FEATURES: FRANSITION BASE PLATE TO 60 FAL PROTECTION DIL SPRING TYPE WITH LIMI CAL TORQUE INDICATOR (O LY REQUIRED MINIMUM & N ECEIPT OF SIGNED APPRO NO LONGER VALID DUE TO IBERS AND PARTS NUMBER	T SWITCH - INCLUDING 1-100% TORQUE INDINAXIMUM (SHUT DOVINGS VAL DRAWINGS THE QUOTE BEING REFERENCES ONLY	TING  NG CATION) VN) TORQUE  EXPIRED,	Unit Price	Amount
1HP CUSTOM BRAKE MTR,1800,145TC, EXTENDED SHAFT FOR MANUAL OPER ITEM NO: 999999999 Lead Time: 14-15 WEEKS ARO		DELIVERY DATE:	EA		
1800 RPM, 145TC FRAME, 60HZ/23	30-460VZ, 10 FT-LB BRAKE	DELIVERY DATE.			
LINE ITEM: 003 1045G FLEX HUB X 4-5/8" BORE DRIVE SIDE COUPLING HUB, FINISH BO ITEM NO: 99999999	DRE FALK	1 DELIVERY DATE:	EA		
BORE DIAMETER MIN/MAX 4.62150 KEYWAY WIDTH 1.25000 INCH, DE CAN SHIP WITHIN 5 DAYS ARO					
LINE ITEM: 004 1045G FLEX HUB X 5-15/16" DRIVEN SIDE COUPLING HUB ITEM NO: 99999999	FALK	1 DELIVERY DATE:	EA		
LINE ITEM: 005 1045G SLEEVE EXP BLT COUPLING COVER ITEM NO: 01275040	FALK	2	EA		

BUYER UNDERSTANDS AND AGREES THAT GOODS PRESENTED TO BUYER PURSUANT TO THIS INVOICE ARE BEING TENDERED CONTINGENT UPON BUYER'S AGREEMENT TO ALL OF MOTION'S TERMS AND CONDITIONS RELATED TO SALES. MOTION'S TERMS AND CONDITIONS ARE AVAILABLE AT THE MOTION BRANCH OR AT WWW.MOTIONINDUSTRIES.COM. BUYER'S ACCEPTANCE OF THE DELIVERY OF THE GOODS SHALL CONFIRM BUYER'S AGREEMENT TO ALL OF MOTION'S TERMS AND CONDITIONS.

PAGE 2 of 3 OCN: FL04 - 372057 PO: QUOTE REL: UPDATED QUOTE 09/30/21

Unit **Unit Price** Description Manufacturer Quantity **Amount** DELIVERY DATE: TWO SLEEVES NEEDED FOR COMPLETE COUPLING. INCLUDES GASKET AND SEAL. HARMONIZED TARIFF CD: 8483908010 LINE ITEM: 006 1045G FSTNR SET EXP BLT 1 EΑ COUPLING FASTENER KIT ITEM NO: 01275903 **FALK DELIVERY DATE:** ONE FASTENER SET NEEDED FOR COMPLETE COUPLING HARMONIZED TARIFF CD: 7318152095 LINE ITEM: 007 1-1/4SQ X 8 KEY 1 EΑ KEY FOR DRIVE SIDE COUPLING HUB ITEM NO: 9999999 MI KEYSTOCK **DELIVERY DATE:** LINE ITEM: 008 1-3/4SQ X 12 KEY 1 EΑ KEY FOR DRIVEN SIDE COUPLING HUB ITEM NO: 99999999 MI KEYSTOCK **DELIVERY DATE:** LINE ITEM: 009 CCG5000A GUARD, CPLG 1 EΑ 2923204 ORANGE PEEL-POLYETHYLENE ITEM NO: 02314477 **FALK DELIVERY DATE:** SAFETY ORANGE POLYETHYLENE GUARD. SIZED FOR 6-3/4" MAX SHAFT SIZE (SINCE DRIVEN SIDE SHAFT IS UNKNOWN AND LARGEST ALLOWABLE SHAFT ON 1045G COUPLING IS 6-3/4" SHAFT). HARMONIZED TARIFF CD: 8483908010 SUB TOTAL: SALES TAX: TOTAL: USD Want to view inventory and place orders on-line? MotionIndustries.com can meet your needs. Register On-line at www.MotionIndustries.com.

BUYER UNDERSTANDS AND AGREES THAT GOODS PRESENTED TO BUYER PURSUANT TO THIS INVOICE ARE BEING TENDERED CONTINGENT UPON BUYER'S AGREEMENT TO ALL OF MOTION'S TERMS AND CONDITIONS RELATED TO SALES. MOTION'S TERMS AND CONDITIONS ARE AVAILABLE AT THE MOTION BRANCH OR AT WWW.MOTIONINDUSTRIES.COM. BUYER'S ACCEPTANCE OF THE DELIVERY OF THE GOODS SHALL CONFIRM BUYER'S AGREEMENT TO ALL OF MOTION'S TERMS AND CONDITIONS.

PAGE 3 of 3 OCN: FL04 - 372057 PO: QUOTE REL: UPDATED QUOTE 09/30/21



# Quote

## MOTION INDUSTRIES

1753 SOUTH COUNTY LINE RD PLANT CITY, FL 33566 PHONE : 8635330574

FAX: 8635339386

Date: 09/30/21

Note: Due to recent volatility of raw materials, price and delivery are subject to change based on availability at time of order.

Requests for statutory and regulatory documentation (REACH, RoHS, California Prop 65, Conflict Minerals, Certificates of Conformance, Safety Data Sheets, and other applicable compliance documents) for the product(s) in this order must be communicated by the customer to the Motion Industries, Inc. sales representative at the time the order is placed. Motion Industries, Inc. cannot accept requests for these documents after completion of the sale.

To:

PENN PRO INC 2830 PARKWAY ST

LAKELAND, FL 33811

PO: QUOTE

**REL: MANATEE DAM BEARINGS** 

**Quote Number:** FL04 - 378658

Customer RFQ: QUOTE

FOB: FOB ORG, FRT PP&ADD

Quote Sent By: TERRY

Payment Terms: 1% 10 & 25TH NET 30

**Delivery:** STOCK UNLESS NOTED

## DIRECT SHIP

Description	Manufacturer	Quantity	Unit	Unit Price	Amount
LINE ITEM: 001 SNW 34 X 5-15/16 ADAPTER ITEM NO: 00552723	SKF USA INC	2	EA		
ITEM NO: 00552723 Lead Time: 3-4 DAYS ARO	SKF USA INC				
		DELIVERY DATE:			
LINE ITEM: 002					
22234 CCK W33 BRG ITEM NO: 00063976	SKF USA INC	2	EA		
111EW 110. 00000070	ON GOVING	DELIVERY DATE:			
				SUB TOTAL:	
				SALES TAX:	
				TOTAL: USD	
Want to view inventory and place www.MotionIndustries.com.	orders on-line? MotionIndus	stries.com can meet	t your needs	s. Register On-line	at

BUYER UNDERSTANDS AND AGREES THAT GOODS PRESENTED TO BUYER PURSUANT TO THIS INVOICE ARE BEING TENDERED CONTINGENT UPON BUYER'S AGREEMENT TO ALL OF MOTION'S TERMS AND CONDITIONS RELATED TO SALES. MOTION'S TERMS AND CONDITIONS ARE AVAILABLE AT THE MOTION BRANCH OR AT WWW.MOTIONINDUSTRIES.COM. BUYER'S ACCEPTANCE OF THE DELIVERY OF THE GOODS SHALL CONFIRM BUYER'S AGREEMENT TO ALL OF MOTION'S TERMS AND CONDITIONS.

PAGE 1 of 1 OCN: FL04 - 378658 PO: QUOTE REL: MANATEE DAM BEARINGS 09/30/21