



MANATEE COUNTY

July 8, 2011

All Interested Bidders:

SUBJECT: Invitation for Bid #11-1867-OV
Anna Maria Water Line Improvements / Rehabilitation Project
Manatee County, FL / Project No. 404-6002870 / 6.2

ADDENDUM #1

Bidders are hereby notified that this Addendum shall be acknowledged on page 00300-1 of the Bid Form and made a part of the above named bidding and contract documents. Bids submitted without acknowledgement of the Addendum will be considered incomplete.

The following items are issued to add to, modify, and clarify the bid and contract documents. These items shall have the same force and effect as the original bidding and contract documents, and cost involved shall be included in the bid prices. Bids to be submitted on the specified bid date, shall conform to the additions and revisions listed herein.

The deadline for clarification of questions has been **extended from July 11, 2011 at 5:00 PM to July 14, 2011 at 5:00 PM.** This deadline has been established to maintain fair treatment of all potential bidders, while maintaining the expedited nature of the Economic Stimulus that the contracting of this work may achieve. Contractors note that questions received after this date and time shall not be considered

- Attached memorandum dated July 1, 2011 from Jim Stockwell, P.E., in response to questions presented at the Pre-Bid / Information Conference held on June 29, 2011. (2 total pages)
- Revised Bid Forms attached are as a result of a quantity revision. Bid Item No. 26 Blowoff Assembly, 2" has been revised from 1 EA to 2 EA. (4 total pages)

Bidders must fully complete all pages of the Bid Forms for Both Bid "A" and Bid "B". Bid Forms must be executed by an authorized signatory who has the legal authority to make the offer and bind the company.

Financial Management Department – Purchasing Division
1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205
Phone: 941-749-3055 – Fax: 941-749-3034
www.myanatee.org

LARRY BUSTLE * MICHAEL GALLEN * JOHN R. CHAPPIE * ROBIN DISABATINO * DONNA G. HAYES * CAROL WHITMORE * JOE McCLASH
District 1 District 2 District 3 District 4 District 5 District 6 District 7

July 8, 2011
Invitation for Bid #11-1867-OV
Anna Maria Water Line Improvements / Rehabilitation Project
Manatee County, FL / Project No. 404-6002870 / 6.2

- Engineer's Estimate dated April 1, 2011 is made a part of this Addendum No. 1. (1 total page)

It is important to note that Manatee County is currently receiving competitive bids which are up to 50% lower than the Engineer's Estimate.

B.03 Qualification of Bidders: The License requirement for this project is a General Contractor **OR** Underground Utility Contractor's License. A copy of the License shall be submitted along with the Contractor's Questionnaire.

ADD: Contractor shall have a minimum of two (2) years of experience.

If you have submitted a bid prior to receiving this addendum, you may request in writing that your original, sealed bid be returned to your firm. All sealed bids received will be opened on the date stated.

END OF ADDENDUM #1

Bids will be received at the **Manatee County Purchasing Division, 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205** until **2:00 P.M. on July 26, 2011.**

Sincerely,



R. C. "Rob" Cuthbert, C.P.M, CPPO
Purchasing Division Manager

Ov/ Attachment (7 Total Pages)

MEMORANDUM



PUBLIC WORKS DEPT.

Engineering Division
1022 26th Avenue East
Bradenton FL 34208,

MANATEE COUNTY
FLORIDA

Phone: 941.708.7450

Fax: 941.708.7475

www.myanatee.org

To: Vince Canna, Project Manager
From: Jim Stockwell, PE, Senior Project Engineer
Date: July 1, 2011
Subject: Anna Maria Waterline Rehab Project 404 6002870 ph 21, 22, 23 - Response to Bidders Questions

Vince:

The following questions were received at the information conference and afterwards regarding this project, and my responses are shown below:

1. Is a permit required for disposal of water from dewatering of excavations and/or wellpointing?

Answer: No, however erosion control measures may be required depending on the Contractor's methods and disposal location.

2. Will the County provide the same inspector for the project duration or will inspectors be rotated?

Answer: The County will maintain the same inspector for the duration of the project barring any unforeseen circumstances.

3. Phase 22 of the project plans, Bayview Drive, sheet 4 of 9 calls for 238LF of 4" HDPE DR 11 watermain to be installed from Station 55+25 to 57+69. No Bid Item exists for 4" HDPE. How are we to be paid for this work?

Answer: This is an error on the plans. The plans should call for 2" diameter HDPE DR11 in plan view at this location, to be consistent with the profile view. There is also an error on sheets 4 and 5 of Phase 21, from Station 13+41 to 17+72, the plans should call for 2" diameter HDPE DR 11, not DR 9. Please revise your plans accordingly.

4. Bid Item 26, Blowoff Assembly 2", calls for a quantity of one, but there is one in phase 21 and another in phase 22. Is the Bid quantity wrong?

Answer: Yes, two blowoffs will be required. The Bid Form quantity for this item will be revised accordingly.

5. Bid Item number 7, Fire Hydrant Assembly, calls for a quantity of one, but there is one in phase 21 and another in phase 23 shown as being re-used. Shouldn't there be two separate bid items, with one being a new hydrant and the other being relocated.

Answer: No. There are two new hydrants to be installed, one in phase 21 at Station 13+39 and one in phase 22 at Station 53+42. The existing hydrant in phase 23 at Station 60+51 shall be relocated and re-used as part of the waterline connection to be made at this location and shall not be paid under the new hydrant bid item. The work required for relocation of the existing hydrant shall be paid under Bid Item 16 "Connection to Existing Waterlines" because all work required to make the connections is included in this pay item. At this location, relocation of the existing hydrant is required to make the connection to the existing waterline.

Sincerely,

*Manatee County Public Works Department/Infrastructure Engineering Division * www.myanatee.org*



James Stockwell, PE
Senior Project Engineer

Cc: Olga Valcich, Construction Buyer

Attachments: None

S:\PWD_Engineering_Share\Util Eng Design\Proj\~WTR LINE Proj\AMI Water Distr Imprv\Ph-21, 28th St N\DOCS\BidderQResponse070111.doc

*Manatee County Public Works Department/Infrastructure Engineering Division * www.mymanatee.org*

LARRY BUSTLE * MICHAEL GALLEN * JOHN R CHAPPIE * ROBIN DISABATINO * DONNA HAYES * CAROL WHITMORE * JOE MCCLASH
District 1 District 2 District 3 District 4 District 5 District 6 District 7

BID FORM
(Submit in Triplicate)

Addendum #1 (7/6/2011) / Section 00300

BID "A"

IFB #11-1867-OV / Bid "A" Based on a Completion Time of 280 Calendar Days

**Anna Maria Water Line Improvements (Project No. 404-6002870 / 6.2
Ph 21 (28th St. North) / Ph 22 (Avenue B and Bayview) / Ph 23 (27th Street North
and Avenue C)**

ITEM NO.	DESCRIPTION	U/M	QTY.	UNIT PRICE	EXTENDED PRICE
1	2" HDPE Waterline (C-906) (Directional Drill)	LF	678	\$	\$
2	4" DI Waterline (CL-350) (Direct Bury)	LF	4	\$	\$
3	6" HDPE Waterline (C-906) (Directional Drill)	LF	2,369	\$	\$
4	6" DI Waterline (CL-350) (Direct Bury)	LF	107	\$	\$
5	6" Gate Valve	EA	12	\$	\$
6	Ductile Iron Fittings	LB	1,022	\$	\$
7	Fire Hydrant Assembly	EA	2	\$	\$
8	Fire Hydrant Assembly - 90 Degree	EA	1	\$	\$
9	Water Service (Long) (Single)	EA	11	\$	\$
10	Water Service (Short) (Single)	EA	29	\$	\$
11	Water Service (Long) (Double)	EA	5	\$	\$
12	Water Service (Short) (Double)	EA	5	\$	\$
13	Water Service (Triple)	EA	1	\$	\$
14	Private Water Service Relocation, Complete	EA	21	\$	\$
15	Remove Existing Gate Valve Box and Pad	EA	6	\$	\$
16	Connection to Existing Water Lines	EA	7	\$	\$

Bidder: _____

Authorized
Signature: _____

Bid "A"

00300-2/Add.#1

BID FORM
(Submit in Triplicate)

Addendum #1 (7/6/2011) / Section 00300

BID "A"

IFB #11-1867-OV / Bid "A" Based on a Completion Time of 280 Calendar Days

**Anna Maria Water Line Improvements (Project No. 404-6002870 / 6.2
Ph 21 (28th St. North) / Ph 22 (Avenue B and Bayview) / Ph 23 (27th Street North
and Avenue C)**

ITEM NO.	DESCRIPTION	U/M	QTY.	UNIT PRICE	EXTENDED PRICE
17	Driveway Restoration	SY	8	\$	\$
18	Grout Fill Abandoned Pipe	CF	47	\$	\$
19	Sodding	SY	426	\$	\$
20	Erosion Control	LS	1	\$	\$
21	Concrete Curb Replacement	LF	8	\$	\$
22	Asphalt Road Restoration (Base & Resurface)	SY	62	\$	\$
23	Asphalt Road Restoration (Mill & Resurface)	SY	298	\$	\$
24	Pipe Adapter	EA	15	\$	\$
25	Pipe Joint Restraints	EA	39	\$	\$
*26	Blowoff Assembly 2" (Addendum No. 1)	EA	2	\$	\$
27	Sidewalk Restoration	SY	2	\$	\$
28	BF Preventer with Expansion Tank & Vac Breakers	EA	63	\$	\$
29	Mobilization (Maximum 10% of Bid Total)	LS	1	\$	\$
30	Miscellaneous Work & Clean Up	LS	1	\$	\$
31	Discretionary	LS	1		\$28,500.00
Bid "A" Anna Maria Water Line Improvements Ph 21, Ph 22, Ph 23 (Project No. 404-6002870 / 6.2) (Based on 280 Calendar Completion Time) (Addendum #1)					\$

Bidder: _____

Authorized
Signature: _____

Bid "A"

00300-3/Add.#1

BID FORM
 (Submit in Triplicate)
Addendum #1 (7/6/2011) / SECTION 00300

BID "B"

IFB #11-1867-OV / Bid "B" Based on a Completion Time of 220 Calendar Days
Anna Maria Water Line Improvements (Project No. 404-6002870 / 6.2
Ph 21 (28th St. North) / Ph 22 (Avenue B and Bayview) / Ph 23 (27th Street North
and Avenue C)

ITEM NO.	DESCRIPTION	U/M	QTY.	UNIT PRICE	EXTENDED PRICE
1	2" HDPE Waterline (C-906) (Directional Drill)	LF	678	\$	\$
2	4" DI Waterline (CL-350) (Direct Bury)	LF	4	\$	\$
3	6" HDPE Waterline (C-906) (Directional Drill)	LF	2,369	\$	\$
4	6" DI Waterline (CL-350) (Direct Bury)	LF	107	\$	\$
5	6" Gate Valve	EA	12	\$	\$
6	Ductile Iron Fittings	LB	1,022	\$	\$
7	Fire Hydrant Assembly	EA	2	\$	\$
8	Fire Hydrant Assembly - 90 Degree	EA	1	\$	\$
9	Water Service (Long) (Single)	EA	11	\$	\$
10	Water Service (Short) (Single)	EA	29	\$	\$
11	Water Service (Long) (Double)	EA	5	\$	\$
12	Water Service (Short) (Double)	EA	5	\$	\$
13	Water Service (Triple)	EA	1	\$	\$
14	Private Water Service Relocation, Complete	EA	21	\$	\$
15	Remove Existing Gate Valve Box and Pad	EA	6	\$	\$
16	Connection to Existing Water Lines	EA	7	\$	\$

Bidder: _____

Authorized
Signature: _____

Bid "B"

00300-4/Add.#1

BID FORM
(Submit in Triplicate)
Addendum #1 (7/6/2011) / SECTION 00300

BID "B"

IFB #11-1867-OV / Bid "B" Based on a Completion Time of 220 Calendar Days
Anna Maria Water Line Improvements (Project No. 404-6002870 / 6.2
Ph 21 (28th St. North) / Ph 22 (Avenue B and Bayview) / Ph 23 (27th Street North
and Avenue C)

ITEM NO.	DESCRIPTION	U/M	QTY.	UNIT PRICE	EXTENDED PRICE
17	Driveway Restoration	SY	8	\$	\$
18	Grout Fill Abandoned Pipe	CF	47	\$	\$
19	Sodding	SY	426	\$	\$
20	Erosion Control	LS	1	\$	\$
21	Concrete Curb Replacement	LF	8	\$	\$
22	Asphalt Road Restoration (Base & Resurface)	SY	62	\$	\$
23	Asphalt Road Restoration (Mill & Resurface)	SY	298	\$	\$
24	Pipe Adapter	EA	15	\$	\$
25	Pipe Joint Restraints	EA	39	\$	\$
*26	Blowoff Assembly 2" (Addendum No. 1)	EA	2	\$	\$
27	Sidewalk Restoration	SY	2	\$	\$
28	BF Preventer with Expansion Tank & Vac Breakers	EA	63	\$	\$
29	Mobilization (Maximum 10% of Bid Total)	LS	1	\$	\$
30	Miscellaneous Work & Clean Up	LS	1	\$	\$
31	Discretionary	LS	1		\$28,500.00
Bid "B" Anna Maria Water Line Improvements Ph 21, Ph 22, Ph 23 (Project No. 404-6002870 / 6.2) (Based on 220 Calendar Completion Time) (Addendum #1)					\$

Bidder: _____

Authorized
Signature: _____

Bid "B"

00300-5/Add.#1



MANATEE COUNTY FLORIDA

Date: April 1, 2011

To: All Bidders

Subject: Anna Maria Water Line Rehabilitation Phases 21 to 23 - Project # 404-6002870

The "construction cost estimate" for the Anna Maria Water Line Rehabilitation Phases 21 to 23 is \$342,646.00 three hundred forty two thousand six hundred forty six dollars.

This construction cost estimate was determined on April 1, 2011. The construction cost estimate is based on the original specifications and drawings issued. Changes to the specifications subsequent to the original documents by addenda to this bid may not be accounted for in this construction cost estimate.

Sincerely,

James D. Stockwell, PE, Sr. Project Engineer
Engineer of Record

S:\PWD_Engineering_Share\Util Eng Design\Proj\~WTR LINE Proj\AMI Water Distr Imprv\Ph-21, 28th St
N\DOCS\EngEstLetter.doc

1022 26th Avenue East, Bradenton FL 34208 * PHONE: (941) 708-7450 * FAX: (941) 708-7475
Manatee County Public Works Department/Infrastructure Engineering Division * www.myanatee.org

LARRY BUSTLE * MICHAEL GALLEN * JOHN R. CHAPPIE * ROBIN DISABATINO * DONNA HAYES * CAROL WHITMORE * JOE MCCLASH
District 1 District 2 District 3 District 4 District 5 District 6 District 7