



**INVITATION FOR BID
IFB #12-3032CD**

**MANATEE COUNTY DESOTO CENTER SHERRIFF'S OFFICE
GENERATOR DISCONNECT**

Manatee County, a political subdivision of the State of Florida, (hereinafter the "County") will receive sealed bids from individuals, corporations, partnerships, and other legal entities organized under the laws of the State of Florida or authorized to conduct business in the State of Florida.

NON-MANDATORY INFORMATION CONFERENCE

In order to insure that all prospective bidders have sufficient information and understanding of the County's needs, an information conference will be held:

Monday, November 5, 2012 at 10:00 AM

at the **Manatee County Desoto Center Sherriff's Office**, 600 U.S. 301 Boulevard West, Bradenton, Florida 34205.

DEADLINE FOR CLARIFICATION REQUESTS: November 14, 2012 at 3:00 PM
(Reference Bid Article A.06)

TIME AND DATE DUE: November 27, 2012 at 3:00 PM
Manatee County Purchasing, 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205

Important Note: Lobbying is prohibited (reference Bid Article A.08)

FOR INFORMATION CONTACT:
CHRIS DALEY, CPPB- CONTRACT SPECIALIST
Phone (941) 749-3048 - Fax (941) 749-3034
chris.daley@mymanatee.org

AUTHORIZED FOR RELEASE: 

Table of Contents

00010 Information to Bidders.....	00010-2-10
00020 Basis of Award.....	00020-1-2
00030 Terms and Conditions.....	00030-1-8
00100 Bid Summary	00100-1-3
00150 Manatee County Local Preference	00150-1-4
00300 Bid Form	00300-1-3
00430 Contractor's Questionnaire	00430-1-4
00491 Certification Form	00491-1-2
00500 Form of Agreement.....	00500-1-5
00700 General Conditions	00700-1-20
Contract Documents	186 pages
(Dated August 2, 2012)	
Plans Desoto Center	
(Signed & Sealed August 23, 2012)	4 pages

SECTION 00010
INFORMATION TO BIDDERS

A.01 OPENING LOCATION

These bids will be **publicly opened** at **Manatee County Purchasing, 1112 Manatee Avenue West, Suite 803, Bradenton, Florida 34205** in the presence of County officials at the time and date stated, or soon thereafter. All bidders or their representatives are invited to be present.

Any bids received after the stated time and date will not be considered. It shall be the sole responsibility of the bidder to have their bid **delivered to the Manatee County Purchasing Division** for receipt on or before the stated time and date. If a bid is sent by **U.S. Mail**, the bidder shall be responsible for its timely delivery to the Purchasing Division. Bids delayed by mail shall not be considered, shall not be opened at the public opening, and arrangements shall be made for their return at the respondent's request and expense.

A.02 SEALED & MARKED

One original and two copies of your **signed bid** shall be submitted in one **sealed** package, clearly marked on the outside **"Sealed Bid #12-3032CD, Manatee County Desoto Center Sherriff's Office Generator Disconnect"** with your company name.

Address package to: Manatee County Purchasing Division
1112 Manatee Avenue West, Suite 803
Bradenton, Florida 34205

A.03 SECURING OF DOCUMENTS

Complete individual copies of the bidding documents for the project and/or products can be obtained; free of charge, at the Manatee County Administration Building located at 1112 Manatee Avenue West, Suite 803, Purchasing Division: Department. Documents may be obtained between the hours of 8:00 AM to 4:00 PM Monday through Friday, exception of holidays. Complete set of the bidding document must be used in preparing bids. The County assumes no responsibility for errors and misinterpretations resulting from the use of incomplete sets of bidding document.

A.04 BID DOCUMENTS

Bids on <http://www.mymanatee.org>, Bid documents and the Notices of Source Selection related to those Bids are available for download in a portable document format (.PDF) file on the Manatee County web page on the Purchasing tab under "Bids." You may view and print these files using Adobe Acrobat software. You may download a free copy of this software (Adobe) from the Owner's web page if you do not have it.

A.04 BID DOCUMENTS (Continued)

Manatee County collaborates with the Manatee Chamber of Commerce on distributing solicitations using the RFP Tool web page on the Chambers website: <http://www.Manateechamber.com> to post Bid documents in a portable document format (.PDF) file. This step is in addition to the posting on Manatee County Government web pages.

Manatee County may also use an internet service provider to distribute Bids. A link to that service, <http://www.DemandStar.com>, is provided on this website under the Tab "DemandStar". Participation in the DemandStar system is not a requirement for doing business with Manatee County.

Note: The County posts the Notice of Source Selection seven (7) calendar days prior to the effective date of the award.

IT IS THE RESPONSIBILITY OF EACH VENDOR, PRIOR TO SUBMITTING THEIR BID, TO CONTACT THE MANATEE COUNTY PURCHASING OFFICE (see contact information on page one of this document) TO DETERMINE IF ADDENDA WERE ISSUED AND TO MAKE SUCH ADDENDA A PART OF THEIR BID .

A.05 MODIFICATION OF BID SPECIFICATIONS

If a bidder wishes to recommend changes to the bid specifications, the bidder shall furnish in writing, data and information necessary to aid the Owner in evaluating the request to modify the specifications. The Owner is not obligated to make any changes to the bid specifications. Unless an addendum is issued, the bid specifications shall remain unaltered. **Bidders must fully comply with the bid specifications, terms, and conditions.**

A.06 DEADLINE FOR CLARIFICATION REQUESTS

November 14, 2012 at 3:00 PM shall be the deadline to submit all inquiries, suggestions, or requests concerning interpretation, clarification or additional information pertaining to the Invitation for Bids to the Manatee County Purchasing Office.

This deadline has been established to maintain fair treatment for all potential bidders, while maintaining the expedited nature of the Economic Stimulus that the contracting of this work may achieve.

A.07 CLARIFICATION & ADDENDA

Each bidder shall examine all Invitation For Bid documents and shall judge all matters relating to the adequacy and accuracy of such documents. Any inquiries, suggestions or requests concerning interpretation, clarification or additional information pertaining to the Invitation for Bids shall be made through the Manatee County Purchasing Office. The County shall not be responsible for oral interpretations given by any County employee, representative, or others. The issuance of a written addendum is the only official method whereby interpretation, clarification or additional information can be given.

A.07 CLARIFICATION & ADDENDA

If any addenda are issued to this Invitation for Bid, the County will broadcast the addenda on the Demand Star distribution system to “Planholders” on this web service, and post the documents on the Purchasing Division’s web page at <http://www.mymanatee.org> which can be accessed by clicking on the “Purchasing” button and then clicking on the “Bids” button. It shall be the responsibility of each bidder, prior to submitting their bid, to contact Manatee County Purchasing (see contact on page 1) to determine if addenda were issued and to make such addenda a part of their bid.

A.08 LOBBYING

After the issuance of any Invitation For Bid, prospective bidders, or any agent, representative or person acting at the request of such bidder shall not contact, communicate with or discuss any matter relating in any way to the Invitation For Bid with any officer, agent or employee of Manatee County other than the Purchasing Official or as directed in the Invitation For Bid. This prohibition begins with the issuance of any Invitation For Bid, and ends upon execution of the final Contract or when the invitation has been canceled. Violators of this prohibition shall be subject to sanctions as provided in the Manatee County Purchasing Code.

The County reserves the right to amend or to add to the names listed as persons to contact. All amendments or additions to the names listed as persons to contact shall be issued by the Purchasing Division, in writing.

A.09 UNBALANCED BIDDING PROHIBITED

Manatee County recognizes that large and/or complex projects will often result in a variety of methods, sources and prices. However, where in the opinion of the County such variation does not appear to be justified, given bid specifications and industry and market conditions, the bid will be presumed to be unbalanced. Examples of unbalanced bids will include:

1. Bids showing omissions, alterations of form, additions not specified or required conditional or unauthorized alternate bids.
2. Bids quoting prices that substantially deviate, either higher or lower, from those included in the bids of competitive bidders for the same line item unit costs.
3. Bids where the unit costs offered are in excess of or below reasonable cost analysis values.

In the event the County determines that a bid is presumed unbalanced, it will request the opportunity to, and reserves the right to, review all source quotes, bids, price lists, letters of intent, etc., which the bidder obtained and upon which the bidder relied upon to develop the bid. The County reserves the right to reject as non-responsive any presumptive unbalanced bids where the bidder is unable to demonstrate the validity and/or necessity of the unbalanced unit costs.

A.10 FRONT END LOADING OF BID PRICING PROHIBITED

Prices offered for performance and/or acquisition activities that occur early in the project schedule such as mobilization, clearing and grubbing; or maintenance of traffic that are substantially higher than pricing of competitive bidders within the same portion of the project schedule, will be presumed to be front end loaded. Front end loaded bids could reasonably appear to be an attempt to obtain unjustified early payments creating a risk of insufficient incentive for the Contractor to complete the work or otherwise creating an appearance of an under-capitalized bidder.

In the event the County determines that a bid is presumed to be front end loaded, it will request the opportunity to, and reserves the right to, review all source quotes, bids, price lists, letters of intent, etc., which the bidder obtained and upon which the bidder relied upon to develop the pricing or acquisition timing for these bid items. The County reserves the right to reject as non-responsive any presumptive front end loaded bids where the bidder is unable to demonstrate the validity and/or necessity of the front end loaded costs.

A.11 WITHDRAWAL OF OFFERS

Vendors may withdraw offers as follows: a) Mistakes discovered before the opening of a solicitation may be withdrawn by written notice from the bidder submitting the offer. This request must be received in the office designated for receipt of offers in the solicitation document prior to the time set for delivery and opening of the offers. A copy of the request shall be retained and the unopened offer returned to that vendor. b) After the responses to a solicitation are opened or a selection has been determined, but before a Contract is signed, a vendor alleging a material mistake of fact may be permitted to withdraw their offer if the mistake is clearly evident on the solicitation document or the bidder submits evidence which clearly and convincingly demonstrates that a mistake was made. Request to withdraw an offer must be in writing and approved by the Purchasing Official.

A.12 IRREVOCABLE OFFER

Any bid may be withdrawn up until the date and time set for opening of the bid. Any bid not so withdrawn shall, upon opening, constitute an irrevocable offer for a period of ninety (90) days to sell to Manatee County the goods or services set forth in the attached specifications until one or more of the bids have been duly accepted by the County.

A.13 BID EXPENSES

All expenses for making bids to the County are to be borne by the bidder.

A.14 RESERVED RIGHTS

The County reserves the right to accept or reject any and/or all bids, to waive irregularities and technicalities and to request resubmission. Also, the County reserves the right to accept all or any part of the bid and to increase or decrease quantities to meet additional or reduced requirements of the County. Any sole response received by the first submission date may or may not be rejected by the County depending on available competition and current needs of the County. For all items combined, the bid of the lowest responsive, responsible bidder will be accepted, unless all bids are rejected. The lowest responsible bidder shall mean that bidder who makes the lowest bid to sell goods and/or services of a quality which meets or exceeds the quality of goods and/or services set forth in the attached specifications or otherwise required by the County, and who is fit and capable to perform the bid as made.

To be responsive, a bidder shall submit a bid which conforms in all material respects to the requirements set forth in the Invitation For Bid. To be a responsible bidder, the bidder shall have the capability in all respects to perform fully the Contract requirements, and the tenacity, perseverance, experience, integrity, reliability, capacity, facilities, equipment, and credit which will assure good faith performance. Also, the County reserves the right to make such investigation as it deems necessary to determine the ability of any bidder to furnish the service requested. Information the County deems necessary to make this determination shall be provided by the bidder. Such information may include, but shall not be limited to current financial statements, verification of availability of equipment and personnel, and past performance records.

A.15 APPLICABLE LAWS

Bidder must be authorized to transact business in the State of Florida. All applicable laws and regulations of the State of Florida and ordinances and regulations of Manatee County will apply to any resulting agreement. Any involvement with any Manatee County procurement shall be in accordance with Manatee County Purchasing Code of Laws as amended. Any actual or prospective bidder who is aggrieved in connection with the solicitation or award of a Contract may protest to the Board of County Commissioners of Manatee County as required in Manatee County Code of Laws.

A.16 COLLUSION

By offering a submission to this Invitation For Bid, the bidder certifies that he has not divulged, discussed or compared their bid with other bidder, and has not colluded with any other bidder or parties to this bid whatsoever. Also, bidder certifies, and in the case of a joint bid each party thereto certifies as to their own organization, that in connection with this bid:

- a. any prices and/or cost data submitted have been arrived at independently, without consultation, communication, or agreement for the purpose of restricting competition, as to any matter relating to such prices and/or cost data, with any other bidder or with any competitor;

A.16 COLLUSION (Continued)

- b. any prices and/or cost data quoted for this bid have not been knowingly disclosed by the bidder and will not knowingly be disclosed by the bidder, prior to the scheduled opening, directly or indirectly to any other bidder or to any competitor;
- c. no attempt has been made or will be made by the bidder to induce any other person or firm to submit or not to submit a bid for the purpose of restricting competition;
- d. the only person or persons interested in this bid, principal or principals is/are named therein and that no person other than therein mentioned has any interest in this bid or in the Contract to be entered into; and
- e. no person or agency has been employed or retained to solicit or secure this Contract upon an agreement or understanding or a commission, percentage, brokerage, or contingent fee excepting bona fide employees or established commercial agencies maintained by bidder for purpose of doing business.

A.17 CODE OF ETHICS

With respect to this bid, if any bidder violates or is a party to a violation of the Code of Ethics of Manatee County per Manatee County Purchasing Code Ordinance 08-43, Article 3, Ethics in Public Contracting, and/or the State of Florida per Florida Statutes, Chapter 112, Part III, Code of Ethics for Public Officers and Employees, such bidder may be disqualified from performing the work described in this bid or from furnishing the goods or services for which the bid is submitted and shall be further disqualified from submitting any future bids for work or for goods or services for Manatee County. The Owner anticipates that all statements made and materials submitted in a bid will be truthful. If a bidder is determined to be untruthful in its bid or any related presentation, such bidder may be disqualified from further consideration regarding this Invitation For Bid.

A.18 BID FORMS

Bids must be submitted on attached County forms, although additional pages may be attached. - **Bidders must fully complete all pages of the Bid Forms. Bid Forms must be executed by an authorized signatory who has the legal authority to make the offer and bind the company. Bidders must fully comply with all bid specifications, terms and conditions.** Failure to comply shall result in Contract default, whereupon, the defaulting vendor shall be required to pay for any and all re-procurement costs, damages, and attorney fees as incurred by the County.

A.19 LEGAL NAME

Bids shall clearly indicate the legal name, address and telephone number of the bidder. Bids shall be signed above the typed or printed name and title of the signer. The signer must have the authority to bind the bidder to the submitted bid.

A.20 PUBLIC CONTRACTING AND ENVIRONMENTAL CRIMES

A person or affiliate who has been placed on the State's convicted vendor list following a conviction for a public entity crime, as that term is defined in Florida Statute § 287.133, may not submit a bid, proposal, or reply on a Contract to provide any goods or services to a public entity; may not submit a bid, proposal, or reply on a Contract with a public entity for the construction or repair of a public building or public work; may not submit bids, proposals or replies on leases of real property to a public entity; may not be awarded or perform work as a Contractor, supplier, subcontractor, or consultant under a Contract with any public entity; and may not transact business with any public entity in excess of the threshold amount provided in Florida Statute § 287.017 for CATEGORY TWO for a period of thirty-six (36) months following the date of being placed on the convicted list.

In addition, the Manatee County Code prohibits the award of any Contract to any person or entity who/which has, within the past 5 years, been convicted of, or admitted to in court or sworn to under oath, a public entity crime or of any environmental law that, in the reasonable opinion of the purchasing official, establishes reasonable grounds to believe the person or business entity will not conduct business in a responsible matter. To insure compliance with the foregoing, the Code requires all persons or entities desiring to Contract with the County to execute and file with the purchasing official an affidavit, executed under the pain and penalties of perjury, confirming that person, entity and any person(s) affiliated with the entity, does not have such a record and is therefore eligible to seek and be awarded business with the County. In the case of a business entity other than a partnership or a corporation, such affidavit shall be executed by an authorized agent of the entity. In the case of a partnership, such affidavit shall be executed by the general partner(s). A Public Contracting and Environmental Crimes Certification are attached for this purpose.

A.21 DISCOUNTS

Any and all discounts must be incorporated in the prices contained in the bid and not shown separately. The prices as shown on the bid form shall be the price used in determining award.

A.22 TAXES

Manatee County is exempt from Federal Excise and State Sales Taxes. (F.E.T. Exempt Cert. No. 59-78-0089K; FL Sales Tax Exempt Cert. No. 85-8012622206C-6); therefore, the vendor is prohibited from delineating a separate line item in his bid for any sales or service taxes. Nothing herein shall affect the vendor's normal tax liability.

A.23 DESCRIPTIVE INFORMATION

Unless otherwise specifically provided in the specifications, all equipment, materials and articles incorporated in the work covered by this Contract shall be new and of the most suitable grade for the purpose intended. Unless otherwise specifically provided in the specifications, reference to any equipment, material, article or patented process, by trade name, brand name, make or catalog number, shall be regarded as establishing a standard of quality and shall not be construed as limiting competition.

A.24 AMERICANS WITH DISABILITIES ACT

The Board of County Commissioners of Manatee County, Florida, does not discriminate upon the basis of any individual's disability status. This non-discrimination policy involves every aspect of the County's functions including one's access to, participation, employment, or treatment in its programs or activities. Anyone requiring reasonable accommodation for an **Information Conference** or **Bid Opening** should contact the person named on the first page of this bid document at least twenty-four (24) hours in advance of either activity.

A.25 EQUAL EMPLOYMENT OPPORTUNITY CLAUSE

In accordance with the provisions of Title VI of the Civil Rights Act of 1964 and Title 15, Part 8 of the Code of Federal Regulations, Manatee County hereby notifies all prospective offerors that they will affirmatively ensure minority business enterprises will be afforded full opportunity to participate in response to this advertisement and will not be discriminated against on the grounds of race, color or national origin in consideration for an award of contract.

A.26 MBE/WBE

The State of Florida, **Office of Supplier Diversity** provides the certification process and the database for identifying certified MBE/WBE firms. This service may be directly accessed at: <http://www.osd.dms.state.fl.us/iframe.htm>

If you have any questions regarding this State service, please contact their office at (850) 487-0915.

A.27 MATHEMATICAL ERRORS

In the event of multiplication/extension error(s), the unit price shall prevail. In the event of addition error(s) the extension totals will prevail. All bids shall be reviewed mathematically and corrected, if necessary, using these standards, prior to additional evaluation.

A.28 DISCLOSURE

Upon receipt, all inquiries and responses to inquiries related to this Invitation For Bid becomes "Public Records", and shall be subject to public disclosure consistent with Chapter 119, Florida Statutes.

Bids become subject to disclosure 30 days after the Opening or if a notice of intended award decision is made earlier than this time as provided by Florida Statute 119.071(1)(b). No announcement or review of the offer shall be conducted at the public opening. If the County rejects all offers and concurrently notices its intent to reissue the solicitation, initial offers are exempt until the County provide notice of its intended decision or, or 30 days after the opening of the new offers.

Based on the above, Manatee County will receive bids at the date and time stated, and will make public at the opening the names of the business entities of all that submitted an offer and any amount presented as a total offer without any verification of the mathematics or the completeness of the offer. Upon the expiration of the statutory term for exemption the actual documents may be inspected or copied. When County staff have completed a mathematic validation and inspected the completeness of the offers, tabulation shall be posted on www.mymanatee.org.

NOTE: ANY OR ALL STATEMENTS CONTAINED IN THE FOLLOWING SECTIONS: BASIS OF AWARD, TERMS AND CONDITIONS OF THE CONTRACT, OR SPECIFICATIONS, WHICH VARY FROM THE INFORMATION TO BIDDERS, SHALL HAVE PRECEDENCE.

END OF SECTION A

SECTION 00020
BASIS OF AWARD

B.01 BASIS OF AWARD

Award shall be to the most responsive, responsible bidder meeting specifications and having the lowest Total Bid Price for **Bid "A"**, or the lowest total price for **Bid "B"** for the requirements listed on the Bid Form for the Work as set forth in this Invitation For Bid. Bid Prices shall include costs for furnishing all labor, equipment and/or materials for the completion of the Work in accordance with and in the manner set forth and described in the Contract Documents to the County's satisfaction within the prescribed time.

Two schedules for Completion of the Work shall be considered. Each bid for completion by the specified stated time shall be offered as a separate "Total Bid Price". The County has the sole authority to select the bid based on the Completion Time which is in the best interest of the County. Only one award shall be made.

In evaluating bids, the County shall consider the qualifications of the bidders; and if required, may also consider the qualifications of the subcontractors, suppliers, and other persons and organizations proposed. County may also consider the operating costs, maintenance requirements, performance data and guarantees of major items of materials and equipment proposed for incorporation in the Work.

Whenever two (2) or more bids are equal with respect to price, quality and service, the bid received from a local business shall be given preference in award. Whenever two (2) or more bids which are equal with respect to price, quality and service are received, and both bids and neither of these bids are received from a local business, the award shall be determined by a chance drawing conducted by the Purchasing Office and open to the public.

Local business is defined as a business duly licensed and authorized to engage in the sale of goods and/or services to be procured, which has a place of business in Manatee County with full time employees at that location.

B.02 SUBCONTRACTORS

Subcontractors shall be bound by the terms and conditions of this Contract insofar as it applies to their Work, but this shall not relieve the prime Contractor from the full responsibility of the County for the proper completion of all Work to be executed under this Contract.

The employment of unauthorized aliens by any vendor is considered a violation of Section 274 (e) of the Immigration and Employment Act. If the vendor knowingly employs unauthorized aliens, such violation shall be cause for unilateral cancellation of this agreement.

B.03 QUALIFICATIONS OF BIDDERS

Each bidder must possess all licenses required (in accordance with Chapter 489 Florida Statutes) for the Work which is the subject of this bid; and, upon request, shall submit a true copy of all applicable licenses. **The bidder shall be certified in Florida as a Certified Electrical Contractor holding an active valid Florida license for a minimum of five (5) years and have a minimum of five (5) years experience in this type of construction which is the subject of this IFB to be considered for award.** In the event that a bidder is a business organization, including a partnership, corporation, business trust or other legal entity as set forth in Florida Statutes s.489.119(2), then the bidder shall only be qualified to bid on this project if: 1) the bidder (the business organization) is on the day the bid submitted, and for at least five consecutive years immediately prior to the day the bid is submitted, has been, in continuous existence, properly licensed and registered as required by Florida law; and 2) the bidder, on the day the bid is submitted, has a certified or registered Qualifying Agent, as required by Florida Statutes s. 489.119, and that Qualifying Agent has been the same Qualifying Agent of the bidder for a period of at least five consecutive years immediately prior to the day the bid is submitted.

To demonstrate qualifications to perform the Work, each bidder must be prepared to submit within five (5) days of County's request, written evidence such as financial data; previous experience, present commitments and other such data as may be requested. Bidder must be able to provide evidence of Bidder's qualification to do business in the state of Florida. Each bidder shall submit as a portion of their bid, a completed Contractor's Questionnaire included as Section 00430.

A complete list of all subcontractors proposed for any portion of the Work may be requested of any Bidder deemed necessary by the County. Subcontracts shall be awarded only to those subcontractors considered satisfactory by the County.

B.04 PREPARATION OF CONTRACT

A written notice confirming award or recommendation thereof will be forwarded to the successful Bidder accompanied by the required number of unsigned counterparts of the Agreement. Within ten (10) days thereafter, successful Bidder shall sign and deliver the required number of counterparts of the Agreement with any other required documents to County. (Note: Contract must be approved in accordance with the Manatee County Code of Laws, Chapter 2-26, Manatee County Purchasing Ordinance and the Standard and Procedures approved by the County Administrator).

B.05 INSPECTION OF SITE

Inspection of the site is a requirement to be considered for award of this Contract. Prior to submitting a Bid Form, each bidder shall examine the site and all conditions thereon fully familiarizing themselves with the full scope of the project. Failure to become familiar with site conditions will in no way relieve the successful bidder from the necessity of furnishing any materials or performing any work that is required to complete the project in accordance with the plans and specifications. Site visit (s) shall be acknowledged in Section 00300, Bid Form page # 00300-2.

END OF SECTION B

SECTION 00030

GENERAL TERMS AND CONDITIONS OF THE CONTRACT**C.01 CONTRACT FORMS**

The agreement resulting from the acceptance of a bid shall be in the form of the agreement stated in this bid.

C.02 ASSIGNMENT OF CONTRACT

Contractor shall not assign, transfer, convey, sublet or otherwise dispose of this Contract or of his right, title, or interest therein, or his power to execute such Contract, or to assign any monies due or to become due there under to any other person, firm or corporation unless first obtaining the written consent of the County. The giving of such consent to a particular subcontractor assignment shall not dispense with the necessity of such consent to any further or other assignment.

C.03 COMPLETION OF WORK

The Work will be completed and ready for final inspection within the specified calendar days from the date the Contract Time commences to run. Two bids shall be considered based on **Bid "A" 90 calendar days** and **Bid "B" based on 60 calendar days**. The County has the sole authority to select the bid based on the Completion Time which is in the best interest of the County. Only one award shall be made.

C.04 LIQUIDATED DAMAGES

If the Contractor refuses or fails to prosecute the Work, or any separable part thereof, with such diligence as will hinder its completion within the time specified, the County may seek damages. The actual damages for delay will be impossible to determine and in lieu thereof, the Contractor shall pay to the County the sum of **three hundred eighty-eight dollars (\$388.00)** as fixed, agreed, and liquidated damages for each calendar day of the delay until the Work is finally accepted by the County and the Contractor and his Surety shall be liable for the amount thereof.

C.05 PAYMENT

Contractor may apply for partial payment on monthly estimates, based on the amount of Work done or completed in compliance with the provisions of the Contract. Contractor shall submit an application, on a standard pay application form provided or approved by the County, of an approximate estimate of the proportionate value of the Work done, items and locations of the Work performed up to and including the last day of the period then ending. The County will then review said estimate and make any necessary revisions so that the estimate can receive approval for payment. If the Contractor and the County do not agree on the approximate estimate of the proportionate value of the Work done for any pay period, the determination of the County will be binding. The amount of said estimate after deducting any required retainage and all previous payments shall be due and payable to the Contractor, twenty (20) business days if County is its own Engineer of Record (EOR) or twenty-five (25) business days if outside agent approval is required after the pay estimate has been approved by the agent for the County.

C.05 PAYMENT (Continued)

In accordance with the Prompt Payment Act, Section 218.735 (7), Florida Statutes, a punch list shall be formulated.

Time allowed for development of punch list:

1. Awarded Contracts with an estimated cost of less than \$10 million will be within thirty (30) calendar days after reaching substantial completion. Substantial completion is defined as reaching beneficial occupancy or use.
2. Awarded Contracts with a cost of \$10 million dollars or more will be within thirty (30) calendar days OR if extended by Contract: up to sixty (60) calendar days after reaching substantial completion. Substantial completion is defined as reaching beneficial occupancy or use.

The final Contract completion date must be at least thirty (30) days after delivery of the list of items. If the list is not provided to the awarded Contractor by the agreed upon date, the Contract completion time must be extended by the number of days the County exceeds the delivery date.

It is the Contractor's responsibility for care of the materials. Any damage to or loss of said materials is the full responsibility of the Contractor. Any Periodical Pay Estimate signed by the Contractor shall be final as to the Contractor for any or all Work covered by the Periodical Pay Estimate.

Any requests for payment of materials stored on site must be accompanied with a paid receipt. The Contractor warrants and guarantees that title to all work, materials and equipment covered by any application for payment, whether incorporated in the project or not, will pass to the County at the time of payment free and clear of all liens, claims, security interests and encumbrances (hereafter referred to as "Liens").

The Contractor agrees to furnish an affidavit stating that all laborers, material men, and subcontractors have been paid on the project for Work covered by the application for payment and that a partial or complete release of lien, as may be necessary, be properly executed by the material men, laborers, subcontractors on the project for Work covered by the application for payment, sufficient to secure the County from any claim whatsoever arising out of the aforesaid Work.

When the Contractor has completed the Work in compliance with the terms of the Contract Documents, he shall notify the County in writing that the project is ready for final inspection. The County will then advise the Contractor as to the arrangements for final inspection and what Work, if any, is required to prepare the project or a portion thereof for final inspection. When the County determines the project or portion thereof is ready for final inspection, the County shall perform same. Upon completion of final inspection, the County will notify Contractor of all particulars in which this inspection reveals that the Work is incomplete or defective. Contractor shall immediately take such measures as are necessary to complete such Work or remedy such deficiencies. When all such errors have been corrected, a final re-inspection will be made. The process will be repeated until, in the opinion of the County, the project has been completed in compliance with the terms of the Contract Documents.

C.05 PAYMENT (Continued)

When final acceptance has been made by the County, the County will make final payment of the Contract amount, plus all approved additions, less approved deductions and previous payments made. The Contract will be considered complete when all work has been finished, the final inspection made, approved as-builts received, and the project finally accepted in writing by the County. The Contractor's responsibility shall then terminate except as otherwise stated.

C.06 RETAINAGE

A **retainage** of 2.5% of the total contract amount shall be withheld from payments after 75% completion of the Work. Upon substantial completion, this retainage shall be reduced to 1% of the total contract amount plus such amount as the County may reasonably deem necessary to repair, replace, complete or correct any damaged, defective, incorrect or incomplete work. Upon final acceptance, the remaining retainage shall be included in the final payment.

C.07 WARRANTY AND GUARANTEE PROVISIONS

All work, materials, and equipment furnished as defined herein shall be guaranteed and warranted by the Contractor for a minimum period of three (3) years, unless otherwise specified, from final acceptance by the County to be free from defects due either to faulty materials or equipment or faulty workmanship.

All materials, equipment, and workmanship furnished and installed by the Contractor is warranted and guaranteed by the Contractor to be such as to meet the required standards and to accomplish the purposes and functions required standards and to accomplish the purposes and functions of the project as defined, detailed, and specified herein.

The County shall, following discovery thereof, promptly give written notice to the Contractor of faulty materials, equipment, or workmanship within the period of the guarantee and the Contractor shall promptly replace any part of the faulty equipment, material, or workmanship at his own cost. These warranty and guarantee provisions create no limitations on the County as to any claims or actions for breach of guaranty or breach of warranty that the County might have against parties other than the Contractor, and do not constitute exclusive remedies of the County against the Contractor.

C.08 ROYALTIES AND PATENTS

The Contractor shall pay all royalties and license fees for equipment or processes in conjunction with the equipment and/or services being furnished. Contractor shall defend all suits or claims for infringement of any patent, trademark or copyright, and shall save the County harmless from loss on account thereof, including costs and attorney's fees.

C.09 AUTHORIZED PRODUCT REPRESENTATION

The Contractor, by virtue of submitting the name and specifications of a manufacturer's product, will be required to furnish the named manufacturer's product. Failure to perform accordingly may, in the County's sole discretion, be deemed a breach of Contract, and shall constitute grounds for the County's immediate termination of the Contract.

C.10 REGULATIONS

It shall be the responsibility of the Bidder to assure compliance with any OSHA, EPA and/or other federal or state of Florida rules, regulations or other requirements as each may apply.

C.11 CANCELLATION

Any failure of the Contractor to furnish or perform the Work (including, but not limited to commencement of the Work, failure to supply sufficient skilled workers or suitable materials or equipment) in accordance with the Contract, the County may order the stop of the Work, or any portion thereof, until the cause for such order has been eliminated. If the Contractor persistently fails to perform the Work in accordance with the Contract, the County reserves the right to terminate the Contract and select the next qualified bidder or re-advertise this procurement in part or in whole. The County reserves the right to cancel all or any undelivered or unexecuted portion of this Contract with or without cause.

C.12 INDEMNIFICATION

The Contractor covenants and agrees to indemnify and save harmless the County, its agents and employees, from and against all claims, suits, actions, damages, causes of action, or judgments arising out of the terms of the resulting agreement for any personal injury, loss of life, or damage to the property sustained as a result of the performance or non-performance of services or delivery of goods; from and against any orders, judgments, or decrees, which may be entered against the County, its agents or employees; and from and against all costs, attorney's fees, expenses and other liabilities incurred in the defense of any such claim, suit or action, and the investigation thereof. Nothing in the award, resulting Agreement, Contract or Purchase Order shall be deemed to affect the rights, privileges and immunities of the County as set forth in Florida Statute Section 768.28.

C.13 MANUALS, SCHEMATICS, HANDBOOKS (IF APPLICABLE)

All manuals, schematics and handbooks shall be provided which are applicable to the equipment delivered. An operators manual, parts manual and technician manual must also be provided. Parts lists (manuals) must include OEM part numbers for items not manufactured by the bidder. Vendor shall furnish two (2) copies of each.

C.14 INSURANCE

The Contractor will not commence work under a Contract until all insurance under this section and such insurance coverage as might be required by the County has been obtained. The Contractor shall obtain, and submit to purchasing within ten (10) calendar days of request, at his expense, the following minimum amounts of insurance (inclusive of any amounts provided by an umbrella or excess policy):

a. Workers' Compensation/Employers' Liability

Part One - There shall be no maximum limit (other than as limited by the applicable statute) for liability imposed by Florida Workers' Compensation Act or any other coverage required by the Contract documents which are customarily insured under Part One of the standard Workers' Compensation Policy.

Part Two - The minimum amount of coverage required by the Contract documents which are customarily insured under Part Two of the standard Workers' Compensation Policy shall be:

<u>\$100,000</u>	(Each Accident)
<u>\$500,000</u>	(Disease-Policy Limit)
<u>\$100,000</u>	(Disease-Each Employee)

b. Commercial General Liability

The limits are to be applicable only to work performed under this Contract and shall be those that would be provided with the attachment of the Amendment of Limits of Insurance (Designated Project or Premises) endorsement (ISO Form CG 25 03) a Commercial General Liability Policy with the following minimum limits.

General Aggregate:

Products/Completed Operations Aggregate	<u>\$1,000,000</u>
Personal and Advertising Injury	<u>\$1,000,000</u>
Each Occurrence	<u>\$1,000,000</u>
Fire Damage (Any One Fire)	<u>\$Nil</u>
Medical Expense (Any One Person)	<u>\$Nil</u>

c. Business Auto Policy

Each Occurrence Bodily Injury and	
Property Damage Liability Combined	<u>\$ 300,000</u>
Annual Aggregate (if applicable):	<u>\$1,000,000</u>

d. County's Protective Liability Coverage

The minimum OPC Policy limits per occurrence and, if subject to an aggregate, annual aggregate to be provided by the Contractor shall be the same as the amounts shown above as the minimum per occurrence and general policy aggregate limits respectively required for the Commercial General Liability coverage. The limits afforded by the OPC Policy and any excess policies shall apply only to the County and the County's officials, officers, agents and employees and only to claims arising out of or in connection with the Work under this Contract.

C.14 INSURANCE (Continued)

- e. Property Insurance
If this Contract includes construction of or additions to above ground buildings or structures, Contractor shall provide "**Builder's Risk**" insurance with the minimum amount of insurance to be 100% of the value of such addition(s), building(s), or structure(s).
- f. Installation Floater
If this Contract does not include construction of or additions to above ground building or structures, **but does involve** the installation of machinery or equipment, Contractor shall provide an "**Installation Floater**" with the minimum amount of insurance to be 100% of the value of such addition(s), building(s), or structure(s).
- g. Certificates of Insurance and Copies of Policies
 Certificates of Insurance in triplicate evidencing the insurance coverage specified in the six above paragraphs a., b., c., d., e., and f., shall be filed with the Purchasing Official before operations are begun. The required certificates of insurance shall name the types of policy, policy number, date of expiration, amount of coverage, companies affording coverage, and also shall refer specifically to the bid number, project title and location of project. Insurance shall remain in force at least one (1) year after completion and acceptance of the project by the County, in the amounts and types as stated herein, with coverage for all products and services completed under this Contract.

ADDITIONAL INSURED: Manatee County, a political subdivision of the State of Florida, shall be named as additional insured on all applicable policies.

If the initial insurance expires prior to the completion of operations and/or services by the Contractor, renewal certificates of insurance and required copies of policies shall be furnished by the Contractor and delivered to the Purchasing Official thirty (30) days prior to the date of their expiration. Nothing herein shall in any manner create any liability of the County in connection with any claim against the Contractor for labor, services, or materials, or of subcontractors; and nothing herein shall limit the liability of the Contractor or Contractor's sureties to the County or to any workers, suppliers, materialmen or employees in relation to this Contract.

- h. Certification Requirements – In order for the certificate of insurance to be accepted it must comply with the following:
1. The certificate holder shall be:
Manatee County Board of Commissioners
P.O. Box 1000
Bradenton, FL 34206-1000
 2. Certificate shall be mailed to:
Manatee County Purchasing
1112 Manatee Avenue West, Suite 803
Bradenton, FL 34205
Attn: Chris Daley, Contract Specialist

C.15 BID BOND/CERTIFIED CHECK (If Total Bid Price exceeds \$100,000)

By offering a submission to this Invitation For Bid, the Bidder agrees should the Bidder's bid be accepted, **to execute the form of Contract and present the same to Manatee County for approval within ten (10) days after being notified of the awarding of the Contract.** The Bidder further agrees that failure to execute and deliver said form of Contract **within ten (10) days** will result in damages to Manatee County and as guarantee of payment of same a bid bond/certified check shall be enclosed within the submitted sealed bid in the amount of five (5%) percent of the total amount of the bid. The Bidder further agrees that in case the Bidder fails to enter into a Contract, as prescribed by Manatee County, the bid bond/certified check accompanying the bid shall be forfeited to Manatee County as agreed liquidated damages. If the County enters into a Contract with a Bidder, or if the County rejects any and/or all bids, accompanying bond will be promptly returned.

C.16 PERFORMANCE AND PAYMENT BONDS (If Total Bid Price exceeds \$100,000)

The successful Bidder shall furnish surety bonds as security for faithful performance of the Contract awarded as a result of this bid, and for the payment of all persons performing labor and/or furnishing material in connection therewith. Surety of such bonds shall be in an amount equal to the bid award (100% each) and from a duly authorized and nationally recognized surety company, authorized to do business in the State of Florida, satisfactory to this County. The attorney-in-fact who signs the bonds must file with the bonds a certificate and effective dated copy of power-of-attorney (reference Florida Statute § 255.05). Performance and Payment bonds shall be issued to Manatee County, a political subdivision of the State of Florida, within fourteen (14) calendar days after notification of intent to award. In addition, pursuant to F.S. § 255.05(1) (b), the Contractor shall be responsible and bear all costs associated to record the Performance and Payment bond with the Manatee County Clerk of the Circuit Court. A certified copy of said recording shall be furnished to the Purchasing Division upon filing. Pursuant to F.S. § 255.05(1) (b), the County will make no payment to the Contractor until the Contractor has complied with this paragraph.

Furnishing of the recorded Performance and Payment bonds shall be requisite to execution of a Contract with the County. Said Performance and Payment bonds will remain in force for the duration of the Contract with the premiums paid by the Contractor. Failure of the successful Bidder to execute such Contract and to supply the required bonds shall be just cause for cancellation of the award. The County may then contract with another acceptable Bidder or re-advertise this Invitation for Bid. If another Bidder is accepted, and notice given within ninety (90) days after the opening of bids, this acceptance shall bind the Bidder as though they were originally the successful Bidder.

C.16 PERFORMANCE AND PAYMENT BONDS (Continued)

Failure of the County at any time, to require performance by the Contractor of any provisions set out in the Contract will in no way affect the right of the County, thereafter, to enforce the provisions.

Bonds procured as required above must be in the form prescribed in F.S. § 255.05, and must not contain notice, demand or other terms and conditions, including informal pre-claim meetings, not provided for in F.S. § 255.05 absent prior written approval of the County's Purchasing Official.

C.17 NO DAMAGES FOR DELAY

No claim for damages or any claim other than for an extension of time shall be made or asserted against the County by reason of any delays. The Contractor shall not be entitled to an increase in the Total Contract Price or payment or compensation of any kind from the County or direct, indirect, consequential impact or other costs, expenses for damages, including but not limited to costs of acceleration or inefficiency arising because of delay, disruption, interference or hindrance from any cause whatsoever; provided; however, that this provision shall not preclude recovery or damages by the Contractor for hindrance or delays due solely to fraud, bad faith, or active interference on part of the County or its agents. Otherwise, the Contractor shall only be entitled to extensions of the Contract Time as the sole and exclusive remedy for such resulting delay, in accordance with and to the extent specifically provided above.

C.18 NO INTEREST

Any monies not paid by the County when claimed to be due to the Contractor under this Contract shall not be subject to interest including prejudgment interest. Any monies not paid by the County when claimed to be due to the Contractor for damages awarded in the case of construction delays shall not be subject to prejudgment interest.

C.19 CONSTRUCTION OF CONTRACT

This Contract and the rights and responsibilities hereunder shall not be construed more strongly against either party, regardless of the extent to which such party may have participated in the preparation hereof.

C.20 BE GREEN

All Vendors/Bidders/Quoters/Proposers (*as applicable*) are encouraged to use as many **environmentally preferable** "green" products, materials, supplies, etc. as possible in order to promote a safe and healthy environment. **Environmentally preferable are products or services that have a reduced adverse effect on the environment.** Provide detail of your organization's initiative and its ability to meet the goal of environmental sustainability.

END OF SECTION C

SECTION 00100
BID SUMMARY

D.01 BACKGROUND

The work included in this contract consists of the renovations and additions to the electrical systems for the generator at the Manatee County Desoto Sherriff's Office, to include but not limited to:

limited controls, electrical, power systems, lighting, generator systems, system change outs and operational turnovers, control interface, security and controls conduits and required power for security and controls devices (see power and systems plan), roof penetrations and curbs, wall penetrations, fire stopping, lift or crane, and miscellaneous work.

The Contractor shall furnish all shop drawings, working drawings, labor, materials, equipment, tools, services and incidentals necessary to complete all work required by these Specifications and as shown on the Contract Drawings.

The apparent silence of the Specifications as to any detail, or the apparent omission from them of a detailed description concerning any work to be done and materials to be furnished, shall be regarded as meaning that only the best general practice is to prevail and that only material and workmanship of the best quality is to be used, and interpretation of these Specifications shall be made upon that basis..

D.02 SUBCONTRACTORS, SUPPLIERS AND OTHERS

The identity of subcontractors, suppliers, and other persons and organizations (including those who are to furnish the principal items of material and equipment) may be requested by the County for each bid item from any of the Bidders; and the Bidder shall respond within five days after the date of such request. Such list shall be accompanied by an experience statement with pertinent information regarding similar projects and other evidence of qualification for each such subcontractor, supplier, persons or organization if requested by County. If County, after due investigation, has reasonable objection to any proposed subcontractor, supplier, other person or organization, County may, before the Notice of Award is given, request the apparent successful Bidder to submit an acceptable substitute without an increase in Contract Price or Contract Time.

If apparent successful Bidder declines to make any such substitution, County may award the Contract to the next lowest qualified Bidder that proposes to use acceptable subcontractors, suppliers, and other persons who County does not make written objection to Contractor shall not be required to employ any subcontractor, supplier, other person or organization who Contractor has reasonable objection to.

Subcontractors shall be bound by the terms and conditions of this Contract insofar as it applies to their Work, but this shall not relieve the prime Contractor from the full responsibility to the County for the proper completion of all Work to be executed under this Contract.

D.03 BIDS

Bids are to be submitted in **triplicate, one original and two copies**, upon the County supplied forms. All blank spaces must be filled in as noted with amounts extended and totaled and no changes shall be made in the wording of the forms or in the items mentioned therein. In the event a change is made in your submittal, the Bidder shall write its initials by the change. Any bid may be rejected which contains any omissions, alterations, irregularities of any kind, or which shall in any manner fail to conform to bid requirements.

A bid made by an individual, either in his/her own or proper person or under a trade or firm name, shall be executed under the individual's signature. If made by a partnership, the bid shall be executed by two or more of the general partners. If made by a corporation, the bid shall be executed by its President or other legally authorized corporate officer or agent.

D.04 EXAMINATION OF CONTRACT DOCUMENTS AND SITE

It is the responsibility of each Bidder before submitting a Bid to (a) examine the Bid Documents thoroughly; (b) visit the site to become familiar with local conditions that may affect cost, progress, performance, or furnishing of the Work; (c) consider federal, state, and local codes, laws, and regulations that may affect costs, progress, performance, or furnishing of the Work; (d) study and carefully correlate Bidder's observations with the Bid Documents; and (e) notify County of all conflicts, errors, or discrepancies in the Bid Document.

The accuracy of the existing utility locations shown on the plans is approximate and without express or implied warranty. Each Bidder may, at Bidder's own expense, make or obtain any additional examinations, investigations, explorations, tests and studies, and obtain any additional information and data which pertain to the physical conditions at or contiguous to the site or otherwise which may affect cost, progress, performance or furnishing of the Work and which Bidder deems necessary to determine his Bid for performing and furnishing the Work in accordance with the time, price and other terms and conditions of the Contract Documents. County will provide each Bidder access to the site to conduct such explorations and tests.

Bidder shall fill all holes, clean up and restore the site to its former condition upon completion of such explorations. The lands upon which the Work is to be performed, rights-of-way and easements for access thereto, and other lands designated for use by Contractor in performing the Work are identified in the Contract Documents.

All additional lands and access thereto required for temporary construction facilities or storage of materials and equipment are to be provided by Contractor. Easements for permanent structures or permanent changes in existing structures are to be obtained and paid for by County unless otherwise provided in the Contract Documents.

D.05 MATERIALS AND WORKMANSHIP

All materials and apparatus required for this Work, except as specifically specified otherwise, shall be new, of first class quality, and shall be furnished, delivered, connected and finished in every detail. Construction shall be prescribed by good industry practice and in accordance with manufacturer's recommendations for the type being installed.

Use skilled workman trained and experienced in the necessary trades and who are completely familiar with the specified requirements and the methods needed for proper performance of the Work of this section.

D.06 REGULATIONS AND MATERIAL DISPOSAL

It shall be the responsibility of the Contractor to assure compliance with any OSHA, EPA, federal, state, and/or local rules, regulations or other requirements as each may apply.

D.07 PROJECT CLOSE-OUT

Clean construction site and remove any and all excess materials. Correct any damages to property that may have occurred as a result of installation and/or delivery. Repair and patch all surfaces cut for installation. The Contractor shall remedy any deficiencies promptly should the County determine any work is incomplete or defective.

When the County determines the Work is acceptable in accordance with this Invitation for Bid, the Contractor shall provide the close out submittals, including but not necessarily limited to the following:

- | | | |
|-------|-----------------------------------|-------------------|
| 1 set | Certificate of Warranties | |
| 1 set | Manufacturer's product literature | (when applicable) |
| 1 set | Project Record Drawings | |
| 1 set | Subcontractor Information | (when applicable) |

D.08 DISCRETIONARY WORK

This Bid Item entails minor increases (that may be directed by staff) to existing bid item quantities or minor modification items not bid which were unforeseen and necessary during the construction to provide a safe, complete project in accordance with Bid Documents. (This will not affect the requirement for change orders involving major modifications to the project.) Payment for all Work under this item shall be made only at the County's discretion in order to satisfactorily complete the project. In general, this item is for unanticipated conflicts and/or design changes required during construction which are necessary to complete the project without changing the initial scope of Work and without costly delays.

D.09 PERMITS

The Contractor shall procure (unless otherwise stated) all permits and licenses, pay all charges, fees, and taxes and give all notices necessary and incidental to the due and lawful prosecution of the Work.

END OF SECTION D

SECTION 00150

MANATEE COUNTY LOCAL PREFERENCE LAW AND VENDOR REGISTRATION**E.01 Vendor Registration**

All vendors are encouraged to register with Manatee County using the on-line "Vendor Registration" web page on www.mymanatee.org.

Enclosed are a copy of the current Manatee County law that details the County's Local Preference and the County's definition of a Local Business.

If you assert that your firm meets the stated definition of a Local Business, we ask that in addition to registering on the County's web page, you fill out the attached "**Affidavit As To Local Business Form**" that is included in this section, have the completed document notarized, and mail the original to the following address: Manatee County Administration Center, 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205.

Your cooperation in registering your business with Manatee County will enhance our opportunities to identify sources for goods and services, plus identify Local Businesses. This information is used for soliciting quotations up to \$250,000.00 and for competitive solicitations of larger purchases.

You will note that Manatee County collaborates with the Manatee Chamber of Commerce, posting bids on www.manateechamber.com as well as using the same vendor categories for registration.

Our staff can assist you with your registration as needed. Our office hours are 8:00 A.M. to 5:00 P.M., Monday through Friday on regular business days. Please call (941) 749-3014 if you wish to have a purchasing staff member assist you.

Quick steps to registration: **www.mymanatee.org**

A link to "Purchasing" is listed under "Quick Links" on page one of the County web site.

On the left hand side of the Purchasing web page, click on "Vendor Registration".

This will bring up the Vendor Registration form for on-line input. Please note that the definition of a "Local Business" changed on March 17, 2009. The web page will be updated to include the current law which has been provided in this section of the bid.

Thank you for reviewing this information and considering registering your business with Manatee County. Registration is not mandatory; however, by taking the time to register, you are helping the County to provide timely notifications of quotation, bid and proposal opportunities to your business.

E.02 Section 2-26-6. Local preference, tie bids, local business defined.

- (a) Whenever a responsible local business bidder and a responsible non-local business bidder are found, upon the opening of bids, to have both submitted the lowest responsive bid, the bid of the local bidder shall be awarded the Contract. Should more than one responsible local business bidder match the responsible non-local business bidder's lowest responsive bid, or should no responsible local business bidder match the lowest responsive bid but two (2) or more responsible non-local business bidders submit lowest responsive bids for equal amounts, then the award of the Contract shall be determined by a chance drawing, coin toss, or similar tie-breaking method conducted by the Purchasing office and open to the public. Any bidders seeking to be recognized as local businesses for purposes of this local business preference provision may be required by the terms of the bid announcement to certify they meet the definition of local business set forth in this section, and to register as a local business with the County in the manner prescribed by the County to facilitate the County's ability to track the award of Contracts to local businesses and to allow the County to provide future notifications to its local businesses concerning other bidding opportunities.
- (b) Nothing herein shall be deemed to prohibit the inclusion of requirements with respect to operating and maintaining a local place of business in any Invitation For Bids when the bidder's location materially affects the provisions of the services or supplies that are required by the Invitation.
- (c) **Local business is defined as a business legally authorized to engage in the sale of the goods and/or services to be procured, and which certifies within its bid that for at least six (6) months prior to the announcement of the solicitation of bids it has maintained a physical place of business in Manatee, Desoto, Hardee, Hillsborough, Pinellas or Sarasota County with at least one (1) full-time employees at that location.**
- (d) **Each solicitation for bids made by the County shall contain terms expressly describing the local business preference policies of the County, and shall provide that by electing to submit a bid pursuant to a request for bids, all bidders are deemed to understand and agree to those policies.**
- (e) For all Contracts for architecture, professional engineering, or other professional services governed by Florida Statute § 287.055, the Consultants' Competitive Negotiation Act, the County shall include the local business status of a firm among the factors considered when selecting which firms are "most highly qualified." In determining which firm is the "most qualified" for purposes of negotiating a satisfactory Contract, preference shall be given to a local business where all other relevant factors are equal.
- (f) Local preference shall not apply to the following categories of Contracts:

1. Goods or services provided under a cooperative purchasing agreement or similar "piggyback" Contract;
2. Contracts for professional services subject to Florida Statute § 287.055, the Consultants' Competitive Negotiation Act, except as provided for in subsection (e) above;
3. Purchases or Contracts which are funded, in whole or in part, by a governmental or other funding entity, where the terms and conditions of receipt of the funds prohibit the preference;
4. Purchases or Contracts made pursuant to a non-competitive award process, unless otherwise provided by this section;
5. Any bid announcement which specifically provides that the general local preference policies set forth in this section are suspended due to the unique nature of the goods or services sought, the existence of an emergency as found by either the County commission or County administrator, or where such suspension is, in the opinion of the County attorney, required by law.

(g) To qualify for local preference under this section, **a local business must certify to the County that it:**

1. Has not within the five (5) years prior to the bid announcement admitted guilt or been found guilty by any court or state or federal regulatory enforcement agency of violation of any criminal law, or a law or administrative regulation regarding fraud;
2. Is not currently subject to an unresolved citation or notice of violation of any Manatee County Code provision, except citations or notices which are the subject of a current legal appeal, as of the date of the bid announcement;
3. Is not delinquent in the payment of any fines, liens, assessments, fees or taxes to any governmental unit or taxing authority within Manatee County, except any such sums which are the subject of a current legal appeal.

Ref: Ordinance 09-21 and 09-23 **PASSED AND DULY ADOPTED** in open session, with a quorum present and voting, on the 17th day of March, 2009.

END OF SECTION E

**MANATEE COUNTY GOVERNMENT
AFFIDAVIT AS TO LOCAL BUSINESS
(Complete and Initial Items B-F)**

A. Authorized Representative

I, [name] _____, am the [title] _____ and the duly authorized representative of: [name of business] _____, and that I possess direct personal knowledge to make informed responses to these certifications and the legal authority to make this Affidavit on behalf of myself and the business for which I am acting; and by electing to submit a bid pursuant to this Invitation for Bids, shall be deemed to understand and agree to the local business preference policies of Manatee County; and that I have the direct knowledge to state that this firm complies with all of the following conditions to be considered to be a Local Business as required by the Manatee County Code of Law, Section 2-26-6.

B. Place of Business: I certify that the above business is legally authorized to engage in the sale of goods and/or services and has a physical place of business in Manatee, DeSoto, Hardee, Hillsborough, Pinellas or Sarasota County with at least one (1) fulltime employee at that location. The physical address of the location which meets the above criteria is: _____ [Initial] _____

Business Phone Number: _____

Email Address: _____

C. Business History: I certify that business operations began at the above physical address with at least one fulltime employee on [date] _____ [Initial] _____

D. Criminal Violations: I certify that within the past five years of the date of this Bid announcement, this business has not admitted guilt nor been found guilty by any court or local, state or federal regulatory enforcement agency of violation of any criminal law or administrative regulation regarding fraud. [Initial] _____

E. Citations or Code Violations: I certify that this business is not currently subject to any unresolved citation or notice of violation of any Manatee County Code provision, with the exception of citations or notices which are the subject of a legal current appeal within the date of this bid announcement. [Initial] _____

F. Fees and Taxes: I certify that this business is not delinquent in the payment of fines, liens, assessments, fees or taxes to any governmental unit or taxing authority within Manatee County, with the exception of those which are the subject of a current legal appeal. [Initial] _____

Each of the above certifications is required to meet the qualification of "Local Business" under Manatee County Code of Law, 2-26-6.

Signature of Affiant _____

STATE OF FLORIDA
COUNTY OF _____

Sworn to (or affirmed) and subscribed before me this ____ day of _____, 20____, by (name of person making statement).

(Notary Seal) Signature of Notary: _____

Name of Notary: (Typed or Printed) _____

Personally Known ____ OR Produced Identification ____ Type of Identification Produced _____

Submit executed copy to Manatee County Purchasing - Suite 803 - 1112 Manatee Avenue West - Bradenton, FL 34205

**BID FORM
SECTION 00300
(SUBMIT IN TRIPLICATE)**

For: Manatee County Desoto Center Sherriff's Office Generator Disconnect

TOTAL BID PRICE "A": _____
(Based on a Completion Time of 90 calendar days)
TOTAL BID PRICE "B": _____
(Based on a Completion Time of 60 calendar days)

Two schedules for Completion of the Work shall be considered. Each bid for completion by the specified stated time shall be offered as a separate "Total Bid Price". The County has the sole authority to select the bid based on the Completion Time which is in the best interest of the County. Only one award shall be made.

We, the undersigned, hereby declare that we have carefully reviewed the bid documents, and with full knowledge and understanding of the aforementioned herewith submit this bid, meeting each and every specification, term, and condition contained in the Invitation for Bids.

We understand that the bid technical specifications, terms, and conditions in their entirety shall be made a part of any agreement or Contract between Manatee County and the successful bidder. Failure to comply shall result in Contract default, whereupon, the defaulting Contractor shall be required to pay for any and all re-procurement costs, damages, and attorney fees as incurred by the County.

Communications concerning this Bid shall be addressed as follows:

Person's Name: _____

Address: _____ Phone: _____

Date: _____ FL Contractor License# _____

License in the Name of: _____

Bidder is a WBE/MBE Vendor? _____ Certification _____

COMPANY'S NAME: _____

AUTHORIZED SIGNATURE(S): _____

Name and Title of Above Signer(s) _____

CO. MAILING ADDRESS: _____

STATE OF INCORPORATION _____ (if applicable)

TELEPHONE: (_____) _____ FAX: (_____) _____

Email address: _____

Acknowledge Addendum No. _____ Dated: _____ Acknowledge Addendum No. _____ Dated: _____

Acknowledge Addendum No. _____ Dated: _____ Acknowledge Addendum No. _____ Dated: _____

SIGN AND CONFIRM DATE OF PROJECT VISIT: _____ DATE _____

(BID "A")

MANATEE COUNTY DESOTO CENTER SHERRIFF'S OFFICE GENERATOR DISCONNECT
Based on a Completion Time of 90 Consecutive Calendar Days following Notice to Proceed

ITEM NO.	DESCRIPTION	EST. QTY.	U/M	UNIT PRICE	EXTENDED PRICE
1	Mobilization	1	LS	\$	\$
2	Miscellaneous Work, Clean Up, & Record Drawings	1	LS		
3	Provide and Install all electrical equipment, conduits and wires to make a complete electrical system	1	LS	\$	\$
4	Provide and Install all controls, wires, and conduit – including MTS for power supply to make a complete system.	1	LS	\$	\$
5	DISCRETIONARY WORK (USED ONLY WITH COUNTY APPROVAL)				\$10,000.00
TOTAL PRICE FOR BASE BID "A" - Based on Completion Time of <u>90</u> Consecutive Calendar Days					\$

VENDOR NAME: _____

(BID "B")

MANATEE COUNTY DESOTO CENTER SHERRIFF'S OFFICE GENERATOR DISCONNECT
Based on a Completion Time of 60 Consecutive Calendar Days following Notice to Proceed

ITEM NO.	DESCRIPTION	EST. QTY.	U/M	UNIT PRICE	EXTENDED PRICE
1	Mobilization	1	LS	\$	\$
2	Miscellaneous Work, Clean Up, & Record Drawings	1	LS		
3	Provide and Install all electrical equipment, conduits and wires to make a complete electrical system	1	LS	\$	\$
4	Provide and Install all controls, wires, and conduit – including MTS for power supply to make a complete system.	1	LS	\$	\$
5	DISCRETIONARY WORK (USED ONLY WITH COUNTY APPROVAL)				\$10,000.00
	TOTAL PRICE FOR BASE BID "B" - Based on Completion Time of <u>60</u> Consecutive Calendar Days				\$

VENDOR NAME: _____

**SWORN STATEMENT
THE FLORIDA TRENCH SAFETY ACT**

THIS FORM MUST BE SIGNED IN THE PRESENCE OF A NOTARY PUBLIC OR BY AN OFFICER AUTHORIZED TO ADMINISTER OATHS.

1. This Sworn Statement is submitted with IFB No. #12-3032CD
2. This Sworn Statement is submitted by _____
whose business address is _____
and, if applicable, its Federal Employer Identification Number (FEIN) is _____. If
the entity has no FEIN, include the Social Security Number of the individual signing this
sworn statement _____.
3. Name of individual signing this Sworn Statement is: _____,
Whose relationship to the above entity is: _____.
4. The Trench Safety Standards that will be in effect during the construction of this project shall include, but are not limited to: Laws of Florida, Chapters 90-96, TRENCH SAFETY ACT, and OSHA RULES AND REGULATIONS 29 CFR 1926.650 Subpart P, effective October 1, 1990.
5. The undersigned assures that the entity will comply with the applicable Trench Safety Standards and agrees to indemnify and hold harmless the County and Engineer, and any of their agents or employees from any claims arising from the failure to comply with said standard.
6. The undersigned has appropriated the following costs for compliance with the applicable standards:

<u>Trench Safety Measure (Description)</u>	<u>Units of Measure (LF, SY)</u>	<u>Unit Quantity</u>	<u>Unit Cost</u>	<u>Extended Cost</u>
a. _____	_____	_____	\$ _____	_____
b. _____	_____	_____	\$ _____	_____
c. _____	_____	_____	\$ _____	_____
d. _____	_____	_____	\$ _____	_____

7. The undersigned intends to comply with these standards by instituting the following procedures:

THE UNDERSIGNED, in submitting this Bid, represents that they have reviewed and considered all available geotechnical information and made such other investigations and tests as they may deem necessary to adequately design the trench safety system(s) to be utilized on this project.

(AUTHORIZED SIGNATURE / TITLE)

SWORN to and subscribed before me this _____ day of _____, 2012.

(Impress official seal)

Notary Public, State of Florida: _____

My commission expires: _____

SECTION 00430
CONTRACTOR'S QUESTIONNAIRE
(Submit in Triplicate)

The Bidder warrants the truth and accuracy of all statements and answers herein contained. (Include additional sheets if necessary.)

THIS QUESTIONNAIRE MUST BE COMPLETED AND SUBMITTED WITH YOUR BID/QUOTE.

1. LICENSE #: _____
License Issued to _____
COMPANY'S NAME: _____

CO. PHYSICAL ADDRESS _____

CITY _____

_____ STATE of INCORPORATION, IF APPLICABLE) _____ (ZIP CODE)

(_____) _____ TELEPHONE NUMBER: (____) _____ FAX

EMAIL ADDRESS: _____

2. Bidding as an individual ___ a partnership: ___ a corporation; ___ a joint venture ___

3. If a partnership: list names and addresses of partners; if a corporation: list names of officers, directors, shareholders, and state of incorporation; if joint venture: list names and address of ventures' and the same if any venture are a corporation for each such corporation, partnership, or joint venture:

4. Your organization has been in business (under this firm's name) as a

For how many years? _____ Is this firm in bankruptcy? _____

(Minimum requirement is five years holding a valid Florida Certified Electrical Contractor's License with five years performing the same type of work)

_____ **Years holding a Certified Electrical Contractors License**

_____ **Years experience performing this type of project.**

BIDDER: _____

Has license ever been suspended, revoked, removed or under investigation?

5. Describe and give the date and County of the last three government or private mitigation bank work of similar scope you've completed which are similar in cost, type, size, and nature as the one proposed (for a public entity), include contact name and phone number. Provide the Budget, Actual Cost, Size and Summary of Work for each project. "Attach additional pages as necessary".

6. Have you ever been assessed liquidated damages under a Contract during the past five (5) years? If so, state when, where (contact name, address, and phone number) and why.

7. Have you ever failed to complete work awarded to you? Or provide projects not completed within Contract time. If so, state when, where (Contact name, address, phone number) and why?

8. Have you ever been debarred or prohibited from bidding on a governmental entity's construction project? If yes, name the entity and describe the circumstances:

BIDDER: _____

9. Name three individuals, governmental entities, or corporations for which you (Bidding Entity) have performed similar work and to which you refer. Include contact name and phone number:

- 1. _____
- 2. _____
- 3. _____

10. What specific steps have you taken to examine the physical conditions at or contiguous to the site, including but not limited to, the location of existing underground facilities?

Have you visited the site (s)? _____

Provide date/ (s) of site visit: _____

11. What specific physical conditions, including, but not limited to, the location of existing underground facilities have you found which will, in any manner, affect cost, progress, performance, or finishing of the work?

12. Will you subcontract any part of this Work? If so, describe which major portion(s):

13. If any, list (with Contract amount) WBE/MBE to be utilized:

BIDDER: _____

14. What equipment do you own to accomplish this Work? (A listing may be attached)

15. What equipment will you purchase/rent for the Work? (Specify which)

16. List the following in connection with the Surety which is providing the Bond(s):

Surety's Name: _____

Surety's Address: _____

Surety's Address: _____

Name, address and phone number of Surety's resident agent for service of process in Florida:

Phone: (_____) _____

Email _____

BIDDER: _____

PUBLIC CONTRACTING AND ENVIRONMENTAL CRIMES CERTIFICATION**SWORN STATEMENT PURSUANT TO ARTICLE 6,
MANATEE COUNTY PURCHASING CODE**

THIS FORM MUST BE SIGNED AND SWORN TO IN THE PRESENCE OF A NOTARY PUBLIC OR OTHER OFFICIAL AUTHORIZED TO ADMINISTER OATHS.

This sworn statement is submitted to the Manatee County Board of County Commissioners by

_____ [Print individual's name and title]

_____ for _____ [print name of entity submitting sworn statement]

whose business address is: _____

and (if applicable) its Federal Employer Identification Number (FEIN) is _____. If the entity has no FEIN, include

the Social Security Number of the individual signing this sworn statement: _____

I understand that no person or entity shall be awarded or receive a county contract for public improvements, procurement of goods or services (including professional services) or a county lease, franchise, concession or management agreement, or shall receive a grant of county monies unless such person or entity has submitted a written certification to the County that it has not:

- (1) been convicted of bribery or attempting to bribe a public officer or employee of Manatee County, the State of Florida, or any other public entity, including, but not limited to the Government of the United States, any state, or any local government authority in the United States, in that officer's or employee's official capacity; or
- (2) been convicted of an agreement or collusion among bidders or prospective bidders in restraint of freedom of competition, by agreement to bid a fixed price, or otherwise; or
- (3) been convicted of a violation of an environmental law that, in the sole opinion of the County's Purchasing Director, reflects negatively upon the ability of the person or entity to conduct business in a responsible manner; or
- (4) made an admission of guilt of such conduct described in items (1), (2) or (3) above, which is a matter of record, but has not been prosecuted for such conduct, or has made an admission of guilt of such conduct, which is a matter of record, pursuant to formal prosecution. An admission of guilt shall be construed to include a plea of nolo contendere; or
- (5) where an officer, official, agent or employee of a business entity has been convicted of or has admitted guilt to any of the crimes set forth above on behalf of such an entity and pursuant to the direction or authorization of an official thereof (including the person committing the offense, if he is an official of the business entity), the business shall be chargeable with the conduct herein above set forth. A business entity shall be chargeable with the conduct of an affiliated entity, whether wholly owned, partially owned, or one which has common ownership or a common Board of Directors. For purposes of this Form, business entities are affiliated if, directly or indirectly, one business entity controls or has the power to control another business entity, or if an individual or group of individuals controls or has the power to control both entities. Indicia of control shall include, without limitation, interlocking management or ownership, identity of interests among family members, shared organization of a business entity following the ineligibility of a business entity under this Article, or using substantially the same management, ownership or principles as the ineligible entity.

(Cont'd.)

Any person or entity who claims that this Article is inapplicable to him/her/it because a conviction or judgment has been reversed by a court of competent jurisdiction shall prove the same with documentation satisfactory to the County's Purchasing Director. Upon presentation of such satisfactory proof, the person or entity shall be allowed to contract with the County.

I UNDERSTAND THAT THE SUBMISSION OF THIS FORM TO THE CONTRACTING OFFICER FOR MANATEE COUNTY IS VALID THROUGH DECEMBER 31 OF THE CALENDAR YEAR IN WHICH IT IS FILED. I ALSO UNDERSTAND THAT ANY CONTRACT OR BUSINESS TRANSACTION SHALL PROVIDE FOR SUSPENSION OF PAYMENTS, OR TERMINATION, OR BOTH, IF THE CONTRACTING OFFICER OR THE COUNTY ADMINISTRATOR DETERMINES THAT **SUCH PERSON OR ENTITY HAS MADE FALSE CERTIFICATION.**

[Signature]

STATE OF FLORIDA
COUNTY OF _____

Sworn to and subscribed before me this ____ day of _____, 2012 by _____

Personally known _____ OR Produced identification _____
[Type of identification]

Notary Public Signature My commission expires _____

[Print, type or stamp Commissioned name of Notary Public]

Signatory Requirement - In the case of a business entity other than a partnership or a corporation, this affidavit shall be executed by an authorized agent of the entity. In the case of a partnership, this affidavit shall be executed by the general partner(s). In the case of a corporation, this affidavit shall be executed by the corporate president.

SECTION 00500
FORM OF AGREEMENT
BETWEEN THE
COUNTY OF MANATEE, FLORIDA
AND THE CONTRACTOR AS IDENTIFIED BELOW
ON THE BASIS OF A STIPULATED UNIT COST CONTRACT PRICE

THIS AGREEMENT is made and entered into by and between the COUNTY OF MANATEE, a political subdivision of the state of Florida, hereinafter referred to as the "COUNTY" and XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX hereinafter referred to as the "CONTRACTOR," duly authorized to transact business in the state of Florida, with offices located at XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX

Phone: () _____

ARTICLE 1. WORK

CONTRACTOR shall furnish all labor, materials, supplies, and other items required to complete the Work for IFB No. **12-3032CD Manatee County Desoto Center Sherriff's Office Generator Disconnect** in strict accordance with Contract Documents and any duly authorized subsequent addenda thereto, all of which are made a part hereof.

ARTICLE 2. COMPENSATION

As compensation to the CONTRACTOR, the COUNTY shall pay and the CONTRACTOR will accept as full consideration for the performance of all Work required by **(IFB #12-3032CD Manatee County Desoto Center Sherriff's Office Generator Disconnect)** subject to additions and deductions as provided therein, the sum of _____ Dollars and xxxxxxxxxxxxxxxx Cents (\$ xxxxxxxxxxxxxxxx) for Bid "X" based on Completion Time of xxx calendar days

ARTICLE 3. LIQUIDATED DAMAGES

Time is of the essence in this Agreement. As of the date of this Agreement, the damages that will be suffered by the County in the event of the Contractor's failure to timely complete the Work are impossible to determine. In lieu thereof, it is agreed that if the Contractor fails to achieve Substantial Completion of the Work within _____ calendar days of issuance of the Notice to Proceed (accounting, however, for any extensions of time granted pursuant to approved Change Orders), the Contractor shall pay to the County, as liquidated damages (and not as a penalty), the sum of **\$388** per calendar day for each day beyond _____ days until the Contractor achieves Substantial Completion. The County shall have the option of withholding said liquidated damages from any Pay Application(s) thereafter submitted by the Contractor. Alternatively, the Contractor shall immediately pay said sums to the County upon the County's demand for same.

ARTICLE 4. ENGINEER

The County of Manatee, Property Management Department, is responsible as the COUNTY and **ATP Engineering South, P.L.** hereinafter referred to as "ENGINEER," designed this project and is responsible for technical/engineering reviews and decisions. The ENGINEER is a member of the OWNER'S project management team which is collectively responsible in ensuring the Work is completed in accordance with the Contract Documents.

All communication involving this project will be addressed to David Thompson, Building Maintenance Division Manager, Property Management Department. **All invoicing** will be addressed to the attention of David Thompson (address noted below) with **invoice copies** sent to Matt Camden, ATP Engineering South, P.L. (address noted below).

Manatee County Property Management Dept.
IFB# 12-3032CD
Attention: David Thompson
Building Maintenance Division Manager
1112 Manatee Avenue West, #803
Bradenton, Florida 34205
Phone (941) 748-4501 ext. 3016

ATP Engineering South, P.L.
IFB# 12-3032CD
Attn: Matt Camden
Project Manager
527 Office Park Blvd.
Bradenton, Florida 34203
Phone (941) 751-6485

Where the terms ENGINEER and/or COUNTY are used in the Contract Documents, it shall mean the COUNTY'S project management team.

ARTICLE 5. CONTRACTOR'S REPRESENTATIONS

In order to induce OWNER to enter into this Agreement, CONTRACTOR makes the following representations:

- 5.1 CONTRACTOR has familiarized itself with the nature and extent of the Bid Documents, Work, site, locality and all local conditions and laws and regulations that in any manner may affect cost, progress, performance or furnishing of the Work.
- 5.2 CONTRACTOR has studied carefully all drawings of the physical conditions upon which CONTRACTOR is entitled to rely.
- 5.3 CONTRACTOR has obtained and carefully studied (or assumes responsibility for obtaining and carefully studying) all such examinations, investigations, explorations, tests, reports and studies which pertain to the physical conditions at or contiguous to the site or which otherwise may affect the cost, progress, performance or furnishing of the Work as CONTRACTOR considers necessary for the performance or furnishing of the Work at the Contract Price, within the Contract Time and in accordance with the other terms and conditions of the Bid Documents; and no additional examinations, investigations, explorations, tests, reports, studies or similar information or data are or will be required by CONTRACTOR for such purposes.

- 5.4 CONTRACTOR has reviewed and checked all information and data shown or indicated on the Bid Documents with respect to existing underground facilities at or contiguous to the site and assumes responsibility for the accurate location of said underground facilities. Any additional examinations, investigations, explorations, tests, reports, studies or similar information or data in respect of said underground facilities conducted by the CONTRACTOR will be done at the CONTRACTOR'S expense.
- 5.5 CONTRACTOR has correlated the results of all such observations, examinations, investigations, explorations, tests, reports and studies with the terms and conditions of the Bid.
- 5.6 CONTRACTOR has given OWNER written notice of all conflicts, errors or discrepancies that have been discovered in the Bid Documents and the written resolution thereof by OWNER is acceptable to CONTRACTOR.
- 5.7 CONTRACTOR shall schedule and perform the Work subject to OWNER'S approval and shall hold OWNER harmless from all liabilities incurred due to CONTRACTOR'S failure to coordinate with the OWNER.

ARTICLE 6. CONTRACT DOCUMENTS

The Contract Documents which comprise the entire Agreement between COUNTY and CONTRACTOR concerning the Work consist of the following:

- 6.1 This Agreement and Bid Document (**IFB #12-3032CD**)
- 6.2 Performance and/or other Bonds and Insurance Certificate(s)
- 6.3 Drawings/Plans (not attached)
- 6.4 Addendum number _#_ to _#_ inclusive
- 6.5 CONTRACTOR'S Bid Form
- 6.6 Reports

- 6.7 The following, which may be delivered or issued after the effective date of the Agreement and are not attached hereto: all written Change Orders and other documents amending, modifying, or supplementing the Contract Documents.
- 6.8 The documents listed in paragraphs above are attached to this Agreement (except as noted otherwise above). There are no Contract Documents other than those listed above in this Article 6.

ARTICLE 7. MISCELLANEOUS

- 7.1 Terms used in this Agreement are defined in Article 1 of the General Conditions.
- 7.2 No assignment by a party hereto of any rights under or interest in the Contract Documents will be binding on another party hereto without the written consent of the party sought to be bound; and specifically but without limitation, monies that may become due and monies that are due may not be assigned without such consent (except to the extent that the effect of this restriction may be limited by law); and unless specifically stated to the contrary in any written consent to an assignment, no assignment will release or discharge the assignee from any duty or responsibility under the Contract Documents.
- 7.3 COUNTY and CONTRACTOR each binds itself, its partners, successors, assigns and legal representatives to the other party hereto, its partners, successors, assigns and legal representatives in respect of all covenants, agreements and obligations contained in the Contract Documents.

**AGREEMENT
IFB #12-3032CD**

IN WITNESS WHEREOF, the parties hereto have caused this Agreement to be duly executed by their authorized representatives.

CONTRACTOR

By: _____

Print Name & Title of Signer

Date: _____

COUNTY OF MANATEE, FLORIDA

By: _____
Melissa M. Wendel, CPPO
Purchasing Official

Date: _____

SECTION 00700
GENERAL CONDITIONS

ARTICLE I - DEFINITIONS

Whenever used in the Bid Documents, the following terms have the meaning indicated which are applicable to both the singular and plural thereof:

Addendum - Written or graphic instruments issued prior to the opening of bids which clarify or change the bidding documents or the contract documents.

Agreement - The written Agreement between Owner and Contractor covering the Work to be performed; other contract documents are attached to the Agreement and made a part thereof as provided therein.

Application for Payment - The form accepted by the Project Representative which is to be used by Contractor in requesting progress or final payments and which is to include such supporting documentation as is required by the contract documents.

Award - Acceptance of the bid from the person, firm, or corporation which in the Owner's sole and absolute judgment will under all circumstances best serve the public interest. Award shall be made in accordance with Manatee County Code of Laws.

Bid - The offer of the Bidder submitted on the prescribed form setting forth the prices for the Work to be performed.

Bidder - One who submits a bid directly to the Owner, as distinct from a sub-bidder, who submits a bid to a Bidder.

Bidding Documents - Consists of the Invitation for Bid, which includes but is not limited to: the bid form, drawings, technical specifications, terms and conditions, and the proposed contract documents (including all Addenda issued prior to receipt of bids); and becomes a part of the Agreement.

Bonds - Performance and payment bonds and other instruments of security.

Change Order - A document recommended by the Project Representative which is signed by Contractor and Owner and authorizes an addition, deletion, or revision in the Work or an adjustment in the contract price or the contract time, issued on or after the effective date of the Agreement.

Compensable Delay - Any delay beyond the control and without the fault or negligence of the Contractor resulting from Owner-caused changes in the Work, differing site conditions, suspensions of the Work, or termination for convenience by Owner.

Contract Documents - The Agreement, Addenda (which pertain to the Contract documents), Contractor's bid (including documentation accompanying the bid and any post-bid documentation submitted prior to the Notice of Award), the bonds, the specifications and the drawings, together with all amendments, modifications and supplements issued on or after the effective date of the Agreement.

Contract Price - The monies payable by Owner to Contractor under the Contract documents as stated in the Agreement.

Contract Time - The number of days or the date stated in the Notice to Proceed for the completion of the Work.

Contractor - The person, firm or corporation with whom Owner has entered into an Agreement.

Days - All references to days are to be considered calendar days except as specified differently.

Defective - An adjective which when modifying the work refers to work that is unsatisfactory, faulty or deficient, or does not conform to the Contract documents, or does not meet the requirements of any inspection, reference standard, test or approval referred to in the Contract documents, or has been damaged prior to Project Representative's recommendation of final payment (unless responsibility for the protection thereof has been assumed by Owner).

Discretionary – Payment for all work that shall be made only at the Owner's discretion in order to satisfactorily complete the project in accordance with the Plans and Specifications.

Drawings - The drawings which show the character and scope of the Work to be performed and which have been prepared or approved by Engineer and are referred to in the bidding and Contract documents.

Effective Date of the Agreement - The date indicated in the Agreement on which it becomes effective (date of execution).

Excusable Delay - Any delay beyond the control and without the negligence of the Contractor, the Owner, or any other Contractor caused by events or circumstances such as, but not limited to, acts of God or of the public enemy, fires, floods, freight embargoes, acts of government other than Owner or epidemics. Labor disputes and above average rainfall shall give rise only to excusable delays.

Field Order - A written order issued by Project Representative which orders minor changes in the Work, but which does not involve a change in the contract price or the contract time.

Float or Slack Time - The time available in the progress schedule during which an unexpected activity can be completed without delaying substantial completion of the Work.

Inexcusable Delay - Any delay caused by events or circumstances within the control of the Contractor, such as inadequate crewing, slow submittals, etc., which might have been avoided by the exercise of care, prudence, foresight, or diligence on the part of the Contractor.

Non-prejudicial Delay - Any delay impacting a portion of the Work within the available total float or slack time and not necessarily preventing completion of the Work within the Contract time.

Notice of Award - The written notice to the successful bidder stating Award has been approved by the Board of County Commissioners; or by the Purchasing Official in accordance with Manatee County Purchasing Code of Law, Chapter 2-26, Manatee County Purchasing Ordinance.

Notice of Intent to Award - The written notice to the apparent low bidder stating Award has been recommended with final Award to be authorized by the Board of County Commissioners.

Notice to Proceed - Written notice by Owner (after execution of Contract) to Contractor fixing the date on which the Contract time will commence to run and on which Contractor shall start to perform ten (10) days from date of such notice Contractor's obligations under the Contract documents.

Owner - Manatee County, Florida, Board of County Commissioners.

Preconstruction Conference - Prior to starting the Work, a meeting scheduled by Owner with Contractor to review the Work schedules, to establish procedures for handling shop drawings and other submissions, for processing periodical pay estimates, and such other matters as may be pertinent to the project.

Prejudicial Delay - Any excusable or compensable delay impacting the Work and exceeding the total float available in the progress schedule, thus preventing completion of the Work within the Contract time unless the Work is accelerated.

Pre-operation Testing - All field inspections, installation checks, water tests, performance tests and necessary corrections required of Contractor to demonstrate that individual components of the work have been properly constructed and do operate in accordance with the Contract documents for their intended purposes.

Project - The total construction of which the Work to be provided under the Contract documents may be the whole or a part as indicated elsewhere in the Contract documents.

Project Representative - The authorized representative of Owner who is assigned to the project or any part thereof.

Schedule of Values – Unit Prices shall be established for this Contract by the submission of a schedule of values. The Contractor shall submit a Schedule of Values within ten days of Notice to Proceed date. The Schedule shall include quantities and prices of items equaling the Total Bid Price and will subdivide the Work into components parts in sufficient detail to serve as the basis for progress payments during construction. Such prices will include an appropriate amount of overhead and profit applicable to each item of Work. Upon request of the County, the Contractor shall support the values with data which will substantiate their correctness.

Shop Drawings - All drawings, diagrams, illustrations, schedules and other data which are specifically prepared by or for Contractor to illustrate some portion of the Work and all illustrations, brochures, standard schedules, performance charts, instructions, diagrams and other information prepared by a supplier and submitted by Contractor to illustrate material or equipment for some portion of the Work.

Specifications - Those portions of the Contract documents consisting of written technical descriptions of materials, equipment, construction systems, standards and workmanship as applied to the Work and certain administrative details applicable thereto.

Subcontractor - An individual or corporation having a direct contact with Contractor or with any other subcontractor for the performance of a part of the Work at the site. Such person or firm has contractual relations with the Contractor, not with the Owner.

Substantial Completion - The Work (or a specified part thereof) has progressed to the point when, in the opinion of the Engineer as evidenced by Engineer's definitive certificate of Substantial Completion, it is sufficiently complete in accordance with Contract documents so that the work can be utilized for the purposes for which it is intended; or if there be no such certificate issued, when final payment is due.

Successful Bidder - The lowest qualified, responsible and responsive bidder to whom an award is made.

Supplier - A manufacturer, fabricator, supplier, distributor, materialman or vendor.

Underground Facilities - All pipelines, conduits, ducts, cables, wires, manholes, vaults, tanks, tunnels or other such facilities or attachments and any encasement containing such facilities which have been installed underground to furnish any of the following services or materials: electricity, gases, steam, liquid petroleum products, telephone or other communications, cable television, sewage and drainage removal, traffic or other control systems or water.

Unit Price Work - Work to be paid for on the basis of unit prices.

Work - The entire completed construction or the various separately identifiable parts thereof required to be furnished under the Contract documents. Work is the result of performing services, furnishing labor and furnishing and incorporating materials and equipment into the construction, all as required by the Contract documents.

Work Directive Change - A written directive to Contractor, issued on or after the effective date of the Agreement and signed by Owner and recommended by Project Representative ordering an addition, deletion or revision in the Work, or responding to differing or unforeseen physical conditions under which the Work is to be performed or to emergencies.

A work directive change may not change the Contract price or the Contract time; but is evidence that the parties expect that the change directed or documented by a work directive change will be incorporated in a subsequently issued change order following negotiations by the parties as to its effect, if any, on the Contract price or Contract time.

Written Amendment - A written amendment of the contract documents, signed by Owner and Contractor on or after the effective date of the Agreement and normally dealing with the non-engineering or non-technical rather than strictly work related aspects of the contract documents.

ARTICLE 2 - PRELIMINARY MATTERS

Computation of Time: When time is referred to in the Contract documents by days, it will be computed to exclude the first and include the last day of such period. If the last day of any such period falls on a Saturday or Sunday or legal holiday, such day will be omitted from the computation.

- 2.1 The Contractor must submit a proposed schedule of the Work at the preconstruction conference. The purpose of this schedule is to enable the Owner to govern the Work, to protect the functions of the local government and its citizens and to aid in providing appropriate surveillance. The Owner shall have the right to reschedule work provided such rescheduling is in accord with the remainder of terms of the Contract. The schedule shall show, as a minimum, the approximate dates on which each segment of the work is expected to be started and finished, the proposed traffic flows during each month, the anticipated earnings by the Contractor for each month and the approximate number of crews and equipment to be used. The Owner, after necessary rescheduling and obtaining additional information for specific purposes, shall review and approve the schedule. The Contractor shall also forward to the Owner, as soon as practicable after the first day of each month, a summary report of the progress of the various parts of the work under the Contract, in fabrication and in the field, stating the existing status, estimated time of completion and cause of delay, if any. Together with the summary report, the Contractor shall submit any necessary revisions to the original schedule for the Owner's review and approval. In addition, more detailed schedules may be required by the Owner for daily traffic control.
- 2.2 A Notice to Proceed may be given at any time within thirty (30) days after the effective date of the Agreement. The Contract time will commence at the time specified in such notice. Contractor shall start to perform the Work on the date specified in the Notice to Proceed, but no work shall be done at the site prior to the date on which the Contract time commences to run.

- 2.3 If at any time the materials and appliances to be used appear to the Owner as insufficient or improper for securing the quality of work required or the required rate of progress, the Owner may order the Contractor to increase his efficiency or to improve the character of his work and the Contractor shall conform to such an order. The failure of the Owner to demand any increase of such efficiency of any improvement shall not release the Owner from his obligation to secure the quality of work or the rate of progress necessary to complete the Work within the limits imposed by the Contract. The Owner may require the Contractor to remove from the Work such employees as the Owner deems incompetent, careless, insubordinate or otherwise objectionable, or whose continued employment on the Work is deemed to be contrary to the Owner's interest.
- 2.4 The Owner reserves the right to let other Contracts in connection with this Work. The Contractor shall afford other Contractors reasonable opportunity for the introduction and storage of their materials and execution of their Work, and promptly connect and coordinate the Work with theirs.

ARTICLE 3 - CONTRACT DOCUMENTS: INTENT, AMENDING, RE-USE

- 3.1 The Contract documents comprise the entire Agreement between Owner and Contractor concerning the work. The Contract documents are complementary; what is called for by one is as binding as if called for by all. The Contract documents will be construed in accordance with the laws and ordinances of the State of Florida and Manatee County.

Should a conflict exist within the Contract documents, the precedence in ascending order of authority are as follows: 1) Standard Printed Contract Documents, 2) Special Conditions, 3) General Conditions and 4) Drawings., Note: Computed dimensions shall govern over scaled dimensions.

- 3.2 It is the intent of the Contract documents to describe a functionally complete project (or part thereof) to be constructed in accordance with the Contract documents. Any work, materials or equipment that may reasonably be inferred from the Contract documents as being required to produce the intended result will be supplied whether or not specifically called for. When words which have a well-known technical or trade meaning are used to describe work, materials, or equipment, such words shall be interpreted in accordance with that meaning. Reference to standard specifications, manuals or codes of any technical society, organization or association, or to the laws or regulations of any governmental authority, whether such reference be specific or by implication, shall mean the latest standard specification, manual, code or laws or regulations in effect at the time of opening of bids, except as may be otherwise specifically stated. However, no provision of any referenced standard specification, manual or code (whether or not specifically incorporated by reference in the Contract documents) shall be effective to change the duties and responsibilities of Owner, Contractor or Engineer, or any of their agents or employees from those set forth in the Contract Documents

- 3.3 The Contract documents may be amended to provide for additions, deletions and revisions in the Work or to modify the terms and conditions thereof in one or more of the following ways:
- 3.3.1 Formal Written Amendment
 - 3.3.2 Change Order
 - 3.3.3 Administrative Contract Adjustment (ACA)
 - 3.3.4 Work Directive Change
- 3.4 In addition, the requirements of the Contract documents may be supplemented and minor variations and deviations in the Work may be authorized in one or more of the following ways:
- 3.4.1 Discretionary Work – Field Directive
 - 3.4.2 Engineer's Approval of a Shop Drawing or Sample.

ARTICLE 4 - CONTRACTOR'S RESPONSIBILITIES

- 4.1 Contractor shall keep on the Work at all times during its progress a competent resident superintendent; who shall be the Contractor's representative at the site and shall have authority to act on behalf of Contractor. All communications given to the superintendent shall be as binding as if given to Contractor.
- 4.2 Contractor shall provide competent, suitable qualified personnel to survey and lay out the Work and perform construction as required by the Contract documents. Contractor shall at all times maintain good discipline and order at the site. Except in connection with the safety or protection of persons or the Work or property at the site or adjacent thereto and except as otherwise indicated in the Contract documents, all Work at the site shall be performed during regular working hours and Contractor will not permit overtime work or the performance of work on Saturday, Sunday or legal holiday without Owner's written consent given after prior notice to Engineer (at least 72 hours in advance).
- 4.2.1 Contractor shall pay for all additional engineering charges to the Owner for any overtime work which may be authorized. Such additional engineering charges shall be a subsidiary obligation of Contractor and no extra payment shall be made by Owner on account of such overtime work. At Owner's option, overtime costs may be deducted from Contractor's monthly payment request or Contractor's retainage prior to release of final payment.

- 4.3 Unless otherwise specified, Contractor shall furnish and assume full responsibility for all bonds, insurance, materials, equipment, labor, transportation, construction equipment and machinery, tools, appliances, fuel, power, light, heat, telephone, water, sanitary facilities, temporary facilities and all other facilities and incidentals necessary for the furnishing, performance, testing, start-up and completion of the Work.
- 4.4 All materials and equipment shall be of good quality and new, except as otherwise provided in the Contract documents. If required by Engineer, Contractor shall furnish satisfactory evidence (including reports of required tests) as to the kind and quality of materials and equipment. All materials and equipment shall be applied, installed, connected, erected, used, cleaned and conditioned in accordance with the instruction of the applicable supplier except as otherwise provided in the Contract documents.
- 4.5 Contractor shall be fully responsible to Owner for all acts and omissions of the subcontractors, suppliers and other persons and organizations performing or furnishing any of the Work under a direct or indirect Contract with Contractor just as Contractor is responsible for Contractor's own acts and omissions. Nothing in the Contract Documents shall create any contractual relationship between Owner or Engineer and any such subcontractor, supplier or other person or organization, nor shall it create any obligation on the part of Owner to pay or to see to the payment of any monies due any such subcontractor, supplier or other person or organization.
- 4.6 Permits: Unless otherwise provided, Contractor shall obtain and pay for all construction permits and licenses. Owner shall assist Contractor, when necessary, in obtaining such permits and licenses. Contractor shall pay all governmental charges and inspection fees necessary for the prosecution of the Work.
- 4.7 During the progress of the Work, Contractor shall keep the premises free from accumulation of waste materials rubbish and other debris resulting from the Work. At the completion of the Work, Contractor shall remove all waste materials, rubbish and debris from and about the premises as well as all tools, appliances, construction equipment and machinery and surplus materials and shall leave the site clean and ready for occupancy by Owner. Contractor shall restore to original conditions all property not designated for alteration by the Contract Documents.
- 4.8 Contractor shall not load nor permit any part of any structure to be loaded in any manner that will endanger the structure, nor shall Contractor subject any part of the Work or adjacent property to stresses or pressures that will endanger it.
- 4.9 Safety and Protection: Contractor shall comply with the Florida Department of Commerce Safety Regulations and any local safety regulations. Contractor shall be responsible for initiating, maintaining and supervising all safety precautions and programs in connection with the Work. Contractor shall take all necessary precautions for the safety of and shall provide the necessary protection to prevent damage, injury or loss to:

- 4.9.1 all employees on the work and other persons and organizations who may be affected thereby;
- 4.9.2 all the work and materials and equipment to be incorporated therein, whether in storage on or off the site; and
- 4.9.3 other property at the site or adjacent thereto, including trees, shrubs, lawns, walks, pavements, roadways, structures, utilities and underground facilities not designated for removal, relocation or replacement in the course of construction.

Contractor shall comply with all applicable laws and regulations of any public body having jurisdiction for the safety of persons or property or to protect them from damage, injury or loss; and shall erect and maintain all necessary safeguards for such safety and protection. Contractor shall provide and maintain all passageways, guard fences, lights and other facilities for the protection required by public authority or local conditions. Contractor shall provide reasonable maintenance of traffic way for the public and preservation of the Owner's business, taking into full consideration all local conditions. Contractor's duties and responsibilities for the safety and protection of the work shall continue until such time as all the work is completed.

- 4.10 Emergencies: In emergencies affecting the safety or protection of persons or the Work or property at the site or adjacent thereto, Contractor, without special instruction or authorization from Engineer or Owner, is obligated to act to prevent threatened damage, injury or loss. Contractor shall give Owner prompt written notice if Contractor believes that any significant changes in the Work or variations from the Contract documents have been caused thereby. If Owner determines that a change in the Contract documents is required because of the action taken in response to an emergency, a work directive change or change order will be issued to document the consequences of the changes or variation.
- 4.11 For substitutes not included with the bid, but submitted after the effective date of the Agreement, Contractor shall make written application to Engineer for acceptance thereof, certifying that the proposed substitute will perform adequately the functions and achieve the results called for by the general design, be similar and of equal substance to that specified and be suited to the same use as that specified.

The application will also contain an itemized estimate of all costs and delays or schedule impacts that will result directly or indirectly from review, acceptance and provisions of such substitute, including costs of redesign and claims of other Contractors affected by the resulting change, all of which will be considered by the Engineer in evaluating the proposed substitute. Engineer may require Contractor to furnish at Contractor's expense, additional data about the proposed substitute. In rendering a decision, Owner/Engineer and Contractor shall have access to any available float time in the construction schedule. In the event that substitute materials or equipment not included as part of the bid, but proposed after the effective date of the agreement, are accepted and are less costly than the originally specified materials or equipment, then the net difference in cost shall be credited to the Owner and an appropriate change order executed.

- 4.11.1 If a specific means, method, technique, sequence of procedure of construction is indicated in or required by the Contract documents, Contractor may furnish or utilize a substitute means, method, sequence, technique or procedure of construction acceptable to Engineer if Contractor submits sufficient information to allow Engineer to determine that the substitute proposed is equivalent to that indicated or required by the Contract documents.
 - 4.11.2 Engineer will be allowed a reasonable time within which to evaluate each proposed substitute. Engineer will be the sole judge of acceptability and no substitute will be ordered, installed or utilized without Engineer's prior written acceptance which will be evidenced by either a change order or an approved shop drawing. Owner may require Contractor to furnish at Contractor's expense a special performance guarantee or other surety with respect to any substitute.
 - 4.11.3 Contractor shall reimburse Owner for the charges of Engineer and Engineer's Consultants for evaluating each proposed substitute submitted after the effective date of the Agreement and all costs resulting from any delays in the work while the substitute was undergoing review.
- 4.12 The Contractor shall furnish, free of charge, all labor, stakes, surveys, batter boards for structures, grade lines and other materials and supplies and shall set construction stakes and batter boards for establishing lines, position of structures, slopes and other controlling points necessary for the proper prosecution of the construction work. Where rights-of-way, easements, property lines or any other conditions which make the lay-out of the project or parts of the project critical are involved, the Contractor will employ a competent surveyor who is registered in the State of Florida for lay-out and staking. These stakes and marks shall constitute the field control by and in accord with which the Contractor shall govern and execute the Work.

The Contractor will be held responsible for the preservation of all stakes, marks and if for any reason any of the stakes or marks or batter boards become destroyed or disturbed, they will be immediately and accurately replaced by the Contractor.

- 4.13 The Contractor has, by careful examination, satisfied himself as to the nature and location of the work and all other matters which can in any way affect the work under this Contract, including, but not limited to details pertaining to boring, as shown on the drawings, are not guaranteed to be more than a general indication of the materials likely to be found adjacent to holes bored at the site of the work, approximately at the locations indicated. The Contractor shall examine boring data, where available, and make his own interpretation of the subsoil investigations and other preliminary data, and shall base his bid on his own opinion of the conditions likely to be encountered. In no event shall an extension of time be considered for any conditions that existed at the time of bidding, nor shall the Contractor receive extra compensation for completion of the project as intended by the drawings and in keeping with the contract documents. No verbal agreement or conversation with any officer, agent or employee of the Owner, before or after the execution of this Contract, shall affect or modify any of the terms or obligations herein contained.
- 4.14 If the Contractor, in the course of the Work, finds that the drawings and/or Contract Documents cannot be followed, he shall immediately inform the Owner in writing, and the Owner shall promptly check the accuracy of the information. Any work done after such discovery, until any necessary changes are authorized, will be done at the Contractor's risk.

ARTICLE 5 - OWNER'S RESPONSIBILITIES

- 5.1 Owner shall furnish the data required of Owner under the Contract documents promptly and shall make payments to the Contractor within a reasonable time {no more than twenty (20) days} after the Work has been accepted by the Owner. The form of all submittals, notices, change orders and other documents permitted or required to be used or transmitted under the Contract documents shall be determined by the Owner/Engineer. Standard County forms shall be utilized.
- 5.2 The Owner shall provide the lands upon which the Work under this Contract is to be done, except that the Contractor shall provide all necessary additional land required for the erection of temporary construction facilities and storage of his materials, together with right of access to same.
- 5.3 The Owner shall have the right to take possession of and use any completed portions of the work, although the time for completing the entire work or such portions may not have expired, but such taking possession and use shall not be deemed an acceptance of any work not completed in accordance with the Contract Documents.

ARTICLE 6 - CHANGES IN THE WORK

- 6.1 Without invalidating the Agreement and without notice to any surety, Owner may, at any time, order additions, deletions or revisions in the Work. These will be authorized by a written amendment, a change order, or a work directive change. Upon receipt of any such document, Contractor shall promptly proceed with the Work involved which will be performed under the applicable conditions of the Contract documents (except as otherwise specifically provided).
- 6.2 Contractor shall not be entitled to an increase in the Contract price or an extension of the Contract time with respect to any Work performed that is not required by the Contract documents as amended, modified and supplemented.
- 6.3 Owner and Contractor shall execute appropriate change orders (or written amendments) covering changes in the Work which are ordered by Owner, or which may be required because of acceptance of defective Work.
- 6.4 At any time Engineer may request a quotation from Contractor for a proposed change in the Work and within twenty-one (21) calendar days after receipt, Contractor shall submit a written and detailed proposal for an increase or decrease in the Contract price or Contract time for the proposed change. Engineer shall have twenty-one (21) calendar days after receipt of the detailed proposal to respond in writing. The proposal shall include an itemized estimate of all costs and time for performance that will result directly or indirectly from the proposed change. Unless otherwise directed, itemized estimates shall be in sufficient detail to reasonably permit an analysis by Engineer of all material, labor, equipment, subcontracts, overhead costs and fees, and shall cover all Work involved in the change, whether such Work was deleted, added, changed or impacted. Notwithstanding the request for quotation, Contractor shall carry on the Work and maintain the progress schedule. Delays in the submittal of the written and detailed proposal will be considered non-prejudicial.

ARTICLE 7 - CHANGE OF CONTRACT PRICE

- 7.1 The Contract price constitutes the total compensation (subject to authorized adjustments) payable to Contractor for performing the Work. All duties, responsibilities and obligations assigned to or undertaken by Contractor shall be at his expense without change in the Contract price.

- 7.2 The Contract price may only be changed by change order or by a written amendment. Any claim for an increase or decrease in the Contract price shall be based on written notice delivered by the party making the claim to the other party. Notice of the amount of the claim with supporting data shall be delivered within ten (10) days from the beginning of such occurrence and shall be accompanied by claimant's written statement that the amount claimed covers all known amounts (direct, indirect and consequential) to which the claimant is entitled as a result of the occurrence of said event.
- 7.3 The value of any Work covered by a change order or of any claim for an increase or decrease in the Contract price shall be determined in one (1) of the following ways (at Owner's discretion):
- 7.3.1 Where the Work involved is covered by unit prices contained in the Contract documents, cost will be determined by application of such unit prices to the quantities of the items involved.
- 7.3.2 By mutual acceptance of lump sum.
- 7.3.3 On the basis of the cost of the Work, plus a 15% Contractor's fee for overhead and profit. (Contractor shall submit an itemized cost breakdown together with supporting data.)
- 7.4 Either Owner or Contractor may make a claim for an adjustment in the Contract price. The unit price of an item of unit price Work shall be subject to re-evaluation and adjustment under the following conditions:
- 7.4.1 If the total cost of a particular item of unit price Work amounts to 5% or more of the Contract price and the variation in the quantity of the particular item of unit price Work performed by Contractor differs by more than 15% from the estimated quantity of such item indicated in the Agreement; and
- 7.4.2 If there is no corresponding adjustment with respect to any other item of Work; and
- 7.4.3 If a Contractor believes that it has incurred additional expense as a result thereof; or
- 7.4.4 If Owner believes that the quantity variation entitles it to an adjustment in the unit price; or
- 7.4.5 If the parties are unable to agree as to the effect of any such variations in the quantity of unit price Work performed.

ARTICLE 8 - CHANGE OF CONTRACT TIME

- 8.1 Contract time may only be changed by a change order or a written amendment. Any claim for an extension or shortening of the Contract time shall be based on written notice delivered by the party making the claim to the other party. Notice of the extent of the claim with supporting data shall be delivered within fifteen (15) days from detection or beginning of such occurrence and shall be accompanied by the claimant's written statement that the adjustment claimed is the entire adjustment to which the claimant has reason to believe it is entitled as a result of the occurrence of said event.
- 8.2 The Contract time will be extended in an amount equal to time lost due to delays beyond the control of Contractor. Such delays shall include, but not be limited to, acts or neglect by Owner or others performing additional work, or to fires, floods, epidemics, abnormal weather conditions or acts of God.
- 8.3 All time limits stated in the Contract documents are of the essence.

ARTICLE 9 - WARRANTY, TEST/INSPECTION, CORRECTION

- 9.1 Contractor warrants (for a minimum period of three (3) years or as otherwise stated herein) and guarantees to Owner that all Work will be in accordance with the Contract documents and will not be defective; that Owner, representatives of Owner, governmental agencies with jurisdictional interests will have access to the Work at reasonable time for their observation, inspecting and testing. (Contractor shall give Engineer timely notice of readiness of the work for all required approvals and shall assume full responsibility, including costs, in obtaining required tests, inspections, and approval certifications and/or acceptance, unless otherwise stated by Owner.)
- 9.2 If any work (including work of others) that is to be inspected, tested, or approved is covered without written concurrence of Engineer, it must, if requested by Engineer, be uncovered for observation. Such uncovering shall be at Contractor's expense unless Contractor has given Engineer timely notice of Contractor's intention to cover the same and Engineer has not acted with reasonable promptness in response to such notice. Neither observations by Engineer nor inspections, tests, or approvals by others shall relieve Contractor from Contractor's obligations to perform the Work in accordance with the Contract documents.
- 9.3 If the Work is defective, or Contractor fails to supply sufficient skilled workers, or suitable materials or equipment, or fails to furnish or perform the Work in such a way that the completed Work will conform to the Contract documents, Owner may order Contractor to stop the Work, or any portion thereof and terminate payments to the Contractor until the cause for such order has been eliminated.

Contractor shall bear all direct, indirect and consequential costs for satisfactory reconstruction or removal and replacement with non-defective Work, including, but not limited to fees and charges of engineers, architects, attorneys and other professionals and any additional expenses experienced by Owner due to delays to other Contractors performing additional Work and an appropriate deductive change order shall be issued. Contractor shall further bear the responsibility for maintaining schedule and shall not be entitled to an extension of the Contract time and the recovery of delay damages due to correcting or removing defective Work.

9.3.1 If Contractor fails within seven (7) days after written notice to correct defective Work, or fails to perform the Work in accordance with the Contract documents, or fails to comply with any other provision of the Contract documents, Owner may correct and remedy any such deficiency. To the extent necessary to complete corrective and remedial action, Owner may exclude Contractor from all or part of the site, take possession of all or part of the Work, Contractor's tools, construction equipment and machinery at the site or for which Owner has paid Contractor but which are stored elsewhere. All direct, indirect and costs of Owner in exercising such rights and remedies will be charged against Contractor in an amount approved as to reasonableness by Engineer and a change order will be issued incorporating the necessary revisions.

9.3.2 If within three (3) years after the date of completion or such longer period of time as may be prescribed by laws or regulations or by the terms of any applicable special guarantee required by the Contract documents, any Work is found to be defective, Contractor shall promptly, without cost to Owner and in accordance with Owner's written instructions, either correct such defective Work or if it has been rejected by Owner, remove it from the site and replace it with non-defective Work. If Contractor does not promptly comply with the terms of such instruction, Owner may have the defective Work corrected/removed and all direct, indirect and consequential costs of such removal and replacement will be paid by Contractor.

ARTICLE 10 - SUSPENSION/TERMINATION OF WORK

10.1 Owner may, at any time and without cause, suspend the Work or any portion thereof for a period of not more than ninety (90) days by written notice to Contractor, which will fix the date on which Work will be resumed. Contractor shall be allowed an increase in the Contract price or an extension of the Contract time, or both, directly attributable to any suspension if Contractor makes an approved claim therefore.

10.2 Owner may terminate the Contract if Contractor commences a voluntary case under any chapter of the Bankruptcy Code or any similar action by filing a petition under any other federal or state law relating to the bankruptcy or insolvency; if a petition is filed against the Contractor under any chapter of the Bankruptcy Code or similar relief under any other federal or state law; if Contractor persistently fails to perform the Work in accordance with the Contract documents; if Contractor disregards laws or regulations of any public body having jurisdiction or the Engineer; or otherwise violates in any substantial way any provisions of the Contract.

10.2.1 Owner may, after giving Contractor (and the surety, if there is one) seven (7) days written notice and to the extent permitted by laws and regulations, terminate the services of Contractor; exclude Contractor from the site and take possession of the Work and of all Contractor's tools, construction equipment and machinery at the site and use the same to the full extent they could be used (without liability to Contractor for trespass or conversion); incorporate in the Work all materials and equipment stored at the site or for which Owner has paid Contractor but which are stored elsewhere, and finish the Work as Owner may deem expedient. In such case, Contractor shall not be entitled to receive any further payment beyond an amount equal to the value of material and equipment not incorporated in the Work, but delivered and suitably stored, less the aggregate of payments previously made. If the direct and indirect costs of completing the Work exceed the unpaid balance of the Contract price, Contractor shall pay the difference to Owner. Such costs incurred by Owner shall be verified by Owner and incorporated in a change order; but in finishing the Work, Owner shall not be required to obtain the lowest figure for the Work performed. Contractor's obligations to pay the difference between such costs and such unpaid balance shall survive termination of the Agreement.

10.3 If, through no act or fault of Contractor, the Work is suspended for a period of more than ninety (90) days by Owner or under an order of court or other public authority, or Engineer fails to act on any application or fails to pay Contractor any sum finally determined to be due; then Contractor may, upon seven (7) days written notice to Owner terminate the Agreement and recover from Owner payment for all Work executed, any expense sustained plus reasonable termination expenses. In lieu of terminating the Agreement, if Engineer has failed to act on any application of payment or Owner has failed to make any payment as aforesaid, Contractor may upon seven (7) days written notice to Owner, stop the Work until payment is made of all amounts then due.

ARTICLE 11 - CONTRACT CLAIMS

- 11.1 The rendering of a decision by Engineer with respect to any such claim, dispute or other matter (except any which have been waived by the making or acceptance of final payment) will be a condition precedent to any exercise by Owner or Contractor of such right or remedies as either may otherwise have under the Contract documents or by laws or regulations in respect of any such claim, dispute or other matter. No action, either at law or at equity, shall be brought in connection with any such claim, dispute or other matter later than thirty (30) days after the date on which Owner/Engineer has rendered such written decision in respect thereof. Failure to bring an action within said thirty (30) day period shall result in Engineer's decision being final and binding on the Contractor. In no event may any such action be brought after the time at which instituting such proceedings would be otherwise barred by the applicable statute of limitations.
- 11.2 Before bringing any action in court pertaining to any claim, dispute or other matter in question(s) arising out of or relating to the Contract documents or the breach thereof, or Engineer's final decision, except for claims which have been waived by the making and acceptance of final payment, the Contractor shall first submit written notice(s) of Contract claims to the Purchasing Official for a decision; within the earlier of sixty (60) days after the last date on which the Contractor provided any goods or services required by the Contract or after the date on which the Contractor knew or should have known such a claim existed. The Manatee County Code of Law Section 2-26-63 Contract Claims details the requirements and process for such a claim.

ARTICLE 12 - RESIDENT PROJECT REPRESENTATIVE – DUTIES/RESPONSIBILITIES

- 12.1 Resident Project Representative is Engineer/Owner's Agent, who will act as directed by and under the supervision of the Engineer, and who will confer with Owner/Engineer regarding his actions. Resident Project Representative's dealing in matters pertaining to the on-site Work shall, in general, be only with the Owner/Engineer and Contractor and dealings with subcontractors shall only be through or with the full knowledge of Contractor.
- 12.2 Resident Project Representative will:
- 12.2.1 Review the progress schedule, schedule of shop drawing submissions and schedule of values prepared by Contractor and consult with Owner/Engineer concerning their acceptability.
 - 12.2.2 Attend preconstruction conferences. Arrange a schedule of progress meetings and other job conferences as required in consultation with Owner/Engineer and notify those expected to attend in advance. Attend meetings and maintain and circulate copies of minutes thereof.

- 12.2.3 Serve as Owner/Engineer's liaison with Contractor, working principally through Contractor's superintendent and assist him in understanding the intent of the Contract documents. As requested by Owner/Engineer, assist in obtaining additional details or information when required at the job site for proper execution of the Work.
- 12.2.4 Receive and record date of receipt of shop drawings and samples, receive samples which are furnished at the site by Contractor and notify Owner/Engineer of their availability for examination.
- 12.2.5 Advise Owner/Engineer and Contractor or his superintendent immediately of the commencement of any Work requiring a shop drawing or sample submission if the submission has not been approved by the Owner/Engineer.
- 12.2.6 Conduct on-site observations of the Work in progress to assist Owner/Engineer in determining if the Work is proceeding in accordance with the Contract documents and that completed Work will conform to the Contract documents.
- 12.2.7 Report to Owner/Engineer whenever he believes that any Work is unsatisfactory, faulty or defective or does not conform to the Contract documents, or does not meet the requirements of any inspections, tests or approvals required or if Work has been damaged prior to final payment; and advise Owner/Engineer when he believes Work should be corrected or rejected or should be uncovered of observation or requires special testing, inspection or approval.
- 12.2.8 Verify that tests, equipment and system start-ups and operating and maintenance instructions are conducted as required by the Contract documents and in the presence of the required personnel, and that Contractor maintains adequate records thereof; observe, record and report to Engineer appropriate details relative to the test procedures and start-ups.
- 12.2.9 Accompany visiting inspectors representing public or other agencies having jurisdiction over the project; record the outcome of these inspections and report to Owner/Engineer.
- 12.2.10 Transmit to Contractor, Owner/Engineer's clarifications and interpretations of the Contract documents.
- 12.2.11 Consider and evaluate Contractor's suggestions or modifications in drawings or Contract Documents and report them with recommendations to Owner/Engineer.

- 12.2.12 Maintain at the job site orderly files for correspondence, reports of job conferences, shop drawings and sample submissions, reproductions of original Contract documents including all addenda, change orders, field orders, additional drawings issued subsequent to the execution of the Contract, Owner/Engineer's clarifications and interpretations of the Contract documents, progress reports and other project related documents.
- 12.2.13 Keep a diary or log book, recording hours on the job site, weather conditions, data relative to questions of extras or deductions; list of visiting officials and representatives or manufacturers, fabricators, suppliers and distributors; daily activities, decisions, observations in general and specific observations in more detail as in the case of observing test procedures. Send copies to Owner/Engineer.
- 12.2.14 Record names, addresses and telephone numbers of all Contractors, subcontractors and major suppliers of materials and equipment.
- 12.2.15 Furnish Owner/Engineer periodic reports as required of progress of the Work and Contractor's compliance with the approved progress schedule and schedule of shop drawing submissions.
- 12.2.16 Consult with Owner/Engineer in advance of scheduling major tests, inspections or start of important phases of the Work.
- 12.2.17 Report immediately the occurrence of any accident.
- 12.2.18 Review applications for payment with Contractor for compliance with the established procedure for their submission and forward them with recommendations to Owner/Engineer, noting particularly their relation to the schedule of values, Work completed and materials and equipment delivered at the site, but not incorporated in the Work.
- 12.2.19 During the course of the Work, verify that certificates, maintenance and operations manuals and other data required to be assembled and furnished by Contractor are applicable to the items actually installed, and deliver this material to Owner/Engineer for his review prior to final acceptance of the Work.
- 12.2.20 Before Owner/Engineer issues a Certificate of Substantial Completion, submit to Contractor a list of observed items requiring completion or correction.
- 12.2.21 Conduct final inspection in the company of Owner/Engineer and Contractor and prepare a final list of items to be completed or corrected.

- 12.2.22 Verify that all items on final list have been completed or corrected and make recommendations to Owner/Engineer concerning acceptance.
- 12.3 Except upon written instructions of Owner/Engineer, Resident Project Representative.
 - 12.3.1 Shall not authorize any deviation from the Contract documents or approve any substitute materials or equipment;
 - 12.3.2 Shall not exceed limitations on Owner/Engineer's authority as set forth in the Contract documents;
 - 12.3.3 Shall not undertake any of the responsibilities of Contractor, Subcontractors or Contractor's Superintendent, or expedite the Work;
 - 12.3.4 Shall not advise on or issue directions relative to any aspect of the means, methods, techniques, sequences or procedures of construction unless such is specifically called for in the Contract documents;
 - 12.3.5 Shall not advise on or issue directions as to safety precautions and programs in connection with the Work;
 - 12.3.6 Shall not authorize Owner to occupy the project in whole or in part; and
 - 12.3.7 Shall not participate in specialized field or laboratory tests.

ARTICLE 13 - APPRENTICES

- 13.1 If Successful Contractor employs apprentices, he shall be governed and comply with the provisions of Florida State Statute 446.011.

NOTE: The form of all submittals, notices, change orders and other documents permitted or required to be used or transmitted under the Contract shall be determined by the Owner. Standard County forms shall be utilized.

END OF SECTION



Construction Document Specifications

For

Manatee County
Desoto Center Sheriff's Office Generator Disconnect WA# 66
Manatee County Government
Bradenton, Florida

Issue Date: CD Set August 23, 2012

Specification Date: August 2, 2012

ATP ENGINEERING SOUTH, P.L.
1283 Tallevast Rd.
Sarasota, FL 34243
941-360-2181
FL# 8908
Contact Person: John D. Camden, P.E.
FL# 53458

Set# _____

Table of Contents

Division CSI(2004)	Section Title	Pages
DIVISION 1 – GENERAL REQUIREMENTS		
01100	011100 Summary.....	1-4
01150	020500 Remodeling Procedures.....	1-2
01152	Request for Payment.....	1
01153	Change Order Procedures.....	1-4
01250	012600 Contract Modification Procedure.....	1-3
01290	012000 Payment Procedures.....	1-7
01310	013100 Project Management and Coordination.....	1-6
01330	013300 Submittal Procedures.....	1-10
01400	014000 Quality Requirements.....	1-5
01420	014200 References.....	1-29
01500	015000 Temporary Facilities and Controls.....	1-9
01600	016000 Product Requirements.....	1-8
01731	017329 Cutting and Patching.....	1-4
01732	024313 Selective Demolition.....	1-10
01770	017700 Closeout Procedures.....	1-8
DIVISION 2 – SITE CONSTRUCTION		
02060	024000 Demolition.....	1-3
02300	310000 Earthwork.....	1-8
02361	313116 Termite Control.....	1-5
DIVISION 3 – CONCRETE (NOT USED)		
DIVISION 4 – MASONRY (NOT USED)		
DIVISION 5 – METALS (NOT USED)		
DIVISION 6 – CARPENTRY		
06105	061000 Miscellaneous Carpentry.....	1-5
DIVISION 7 – THERMAL AND MOISTURE PROTECTION		
07270	078400 Fire Proofing.....	1
07920	079000 Joint Sealents.....	1-13
DIVISION 8 – OPENINGS (NOT USED)		

Manatee County Desoto Center
 Sheriff's Office Generator Disconnect

Division CSI(2004)	Section Title	Pages
	DIVISION 9 – FINISHES (NOT USED)	
	DIVISION 10 – SPECIALTIES (NOT USED)	
	DIVISION 11 – EQUIPMENT (NOT USED)	
	DIVISION 12 – FURNISHINGS (NOT USED)	
	DIVISION 13 – SPECIAL CONSTRUCTION (NOT USED)	
	DIVISION 14 – CONVEYING SYSTEMS (NOT USED)	
	DIVISION 15 – MECHANICAL (NOT USED)	
	DIVISION 16 – ELECTRICAL	
16000	260000 Electrical Systems Description.....	1
16110	260500 Raceways, Cable Trays, and Boxes.....	1-2
16120	260519 Wires and Cables.....	1
16140	262726 Wiring Devices.....	1
16400	262000 Service and Distribution.....	1-2
16402	262700 Low Voltage Switchboards Group Mounted Distribution.....	1-12
16440	263623 Automatic Transfer Switches.....	1-5
16441	263600 Quick Connect Generator Docking Station.....	1-3
16442	263623 Manual Transfer Switches.....	1-4
16443	263623 Disconnect Switches.....	1
16479	264300 TVSS(SPD).....	1-5
16660	262800 Ground Fault Protection Systems.....	1

SECTION 01100 – SUMMARY – 011100

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 WORK COVERED BY CONTRACT DOCUMENTS

- A. Project Identification: Project consists of renovations and additions to the Manatee County Desoto Center Sheriff's Office Evidence Storage Area.

- 1. Project Location: Manatee County Desoto Center Sheriff's Office: 600 U.S. 301 W., Bradenton, FL 34205.
- 2. Owner: Manatee County Government
- 3. Owner's Representative: Mr. Tom Roberts and Earl Hasenflu, 1112 Manatee Ave. W., Bradenton, FL 34206.

- B. Engineer Identification: The Contract Documents, dated August 23, 2012, were prepared by ATP Engineering South, 1283 Tallevast Rd, Sarasota, FL 34243. All project documents shall be transmitted and distributed by the Manatee County Purchasing Department.

- C. Identification: The Contract Documents dated August 23, 2012 were prepared for the project by ATP Engineering South.

The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by the Contractor. The Contract Documents are complementary, and what is required by the one shall be as binding as if required by all. Performance by the Contractor shall be required only to the extent consistent with the Contract Documents and reasonably inferable from them as being necessary to produce the intended results. Dimensions shall be figures rather than determined by scale or rule. In the event of a conflict or inconsistency among the Contract Documents, or between the Contract Documents and applicable codes, the Contractor shall provide the greatest quantity, largest degree of safety, highest quality or most stringent material or work.

- D. The Work consists of renovations and additions. The Work consists of renovations and additions to the electrical systems for the generator.

- 1. The Electrical Work shall include: limited controls, electrical, power systems, lighting, generator systems, system change outs and operational turnovers, control interface, security and controls conduits and required power for security and con-

trols devices (see power and systems plan), roof penetrations and curbs, wall penetrations, fire stopping, lift or crane, and miscellaneous work.

2. Construction materials and processes are to be performed to have minimum impact on the environment, using recycled materials to the greatest extent practicable, recycling construction waste material where possible and disposing of non-recyclable waste in an environmentally friendly manner.

CONTRACT

E. Bidder Qualifications:

a. Bidder shall be a Florida Licensed contractor (Electrical) with subcontractors having the minimum of 5 years of experience of renovations of similar type facilities. References shall be supplied to the purchasing department with the bid documents. Contractors shall meet all purchasing requirement for bonding, insurance, and security access for this facility. All individuals shall be cleared with the County prior to access to the facility.

F. Project will be constructed under a general construction contract.

1. Please provide a price breakdown for the base price:

- a. **The complete MSO Transfer Switch as per the plans dated August 23,2012. All items to make a complete working electrical system.**

1.3 SPECIFICATION FORMATS AND CONVENTIONS

A. Specification Format: The Specifications are organized into Divisions and Sections using the 16/ 48 -division format and CSI/CSC's "Master Format" numbering system.

1. Section Identification: The Specifications use section numbers and titles to help cross-referencing in the Contract Documents. Sections in the Project Manual are in numeric sequence; however, the sequence is incomplete. Consult the table of contents at the beginning of the Project Manual to determine numbers and names of sections in the Contract Documents.

B. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:

1. Abbreviated Language: Language used in the Specifications and other Contract Documents is abbreviated. Words and meanings shall be interpreted as appropriate. Words implied, but not stated, shall be inferred, as the sense requires. Singular words shall be interpreted as plural, and plural words shall be interpreted as singular where applicable as the context of the Contract Documents indicates.
2. Imperative mood and streamlined language are generally used in the Specifications. Requirements expressed in the imperative mood are to be performed by Contractor. Occasionally, the indicative or subjunctive mood may be used in the

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Section Text for clarity to describe responsibilities that must be fulfilled indirectly by Contractor or by others when so noted.

- a. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
- b. The word "comparable" shall mean of same quality and performance and not change any items within the design or construction of the project. If the system or component changes the electrical, structural, mechanical, fire, or architectural, the unit is not comparable.

1.4.1 USE OF PREMISES- Refer to Division 1 Section 01500 for any additional information.

- A. General: During the construction period, the Contractor shall limit his use of premises for construction operations to within the construction limits indicated or established by the Owner/ County. Any required work noted outside those limits of construction shall be coordinated with the Owner for safety and security prevention.
- B. Use of the Site: Limit the use of the premises to work in areas indicated. Confine operations to areas within the contract limits indicated. Do not disturb portions of the site beyond areas in which work is indicated. Confine Construction operations to the designated floors and areas during weekdays under normal business hours as dictated by the Owner's Representative.
- C. All personnel shall be cleared with the County facility personnel to the project site area.
- D. Driveways, walkways, and entrances: Keep driveways, loading areas, and entrances serving premises clear and available to the Owner, Owner's Employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials.
 1. Schedule deliveries to minimize use of driveways and entrances by construction operations. Hours and Notification of delivery of product: Deliveries shall be scheduled with Mr. Tom Roberts or Mr. Earl Hasenflu (Manatee County Property Management Department), they may occur during regular scheduled hours.
 2. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on site.
 3. Locate Contractor parking and staging areas as directed by the Owner's Representative and personnel.
 4. Hours of Operations for Contractors as specified by the Owner's Representative: 8:00 A.M. to 5:00 P.M., Monday through Friday, excluding County Holidays.
- E. Condition of existing Building: Maintain portions of the existing building affected by construction operations. Repair damage caused by construction operations.
- F. Contractor may use restroom facilities in the existing building.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- G. Contractor may use existing electrical power outlets at no charge.

1.5 Coordination with Occupants:

- A. Full Owner Occupancy: Owner will occupy site and existing building during the entire construction period. Cooperate with the Owner's Representative during the construction operations to minimize conflicts and facilitate Owner usage. Perform the work so not to interfere with the Owner's day-to-day operations. Maintain existing exits.
1. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities with out written permission from the Owner's Representative.
 2. Notify the Owner's Representative not less than 72 hours in advance of activities that will affect the Owner's Operations. If a major power outage is needed please notify at least 7 days prior to the outage.
 3. The Contractor shall provide construction waste collection service. Contractor shall not use the Owner's waste receptacles for construction waste.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01100

SECTION 01150 - REMODELING PROCEDURES - 020500

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Remove designated building equipment and fixtures.
- B. Remove designated partitions and components.
- C. Cap and identify utilities.

1.3 PROTECTION

- A. Conduct demolition to minimize interference with adjacent building areas. Maintain protected egress and access at all times.
- B. Prevent movement or settlement of structures. Provide and place bracing or shoring and be responsible for safety and support of structure. Assume liability for such movement, settlement, damage, or injury.
- C. Cease operations and notify the Project Manager and Engineer immediately, if safety of structure appears to be endangered. Take precautions to support structure properly. Do not resume operations until safety is restored.
- D. Provide, erect and maintain temporary barriers and security devices.

1.4 EXISTING SERVICES

- A. Arrange and pay for disconnecting, removing and capping utility services within areas of demolition. Disconnect and stub off.
- B. Place markers to indicate location of disconnected services. Identify service lines and capping locations on project record documents.

PART 2 - PRODUCTS (Not Used)

2.1 MATERIALS (Not Applicable)

PART 3 - EXECUTION

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

3.1 PREPARATION

- A. Erect weatherproof closures for exterior openings.
- B. Protect existing items which are not indicated to be altered.
- C. Locate guard rails in stairwells and around open shafts to protect workers. Post clearly visible warning signs.

3.2 DEMOLITION

- A. Demolish in an orderly and careful manner as required to accommodate new work, including that required for connection to the existing building.
- B. Except where noted otherwise, immediately remove demolished materials from site.
- C. Remove materials to be reinstalled or retained in a manner to prevent damage. Store and protect.
- D. Repair all demolition performed in excess of that required, at no cost to the Owner.
- E. Remove and promptly dispose of contaminated, vermin infested or dangerous materials encountered.
- F. Remove demolished materials, tools and equipment from site as work progresses. Upon completion of work, leave site in a condition acceptable to the Architect.

3.3 RENOVATION

- A. Make new work fit to existing work. Where a new wall is attached to an existing wall, paint the entire wall with new paint.
- B. Match new materials and systems with existing materials unless the existing materials are being removed.

END OF SECTION

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

SECTION 01152
REQUESTS FOR PAYMENT

PART 1 GENERAL

1.01 REQUIREMENTS INCLUDED

- A. Submit Applications for Payment to the Project Manager or as directed at the preconstruction meeting, in accordance with the schedule established by Conditions of the Contract and Agreement between Owner and Contractor.

1.02 FORMAT AND DATA REQUIRED

- A. Submit payment requests in the form provided by the Owner with itemized data typed in accordance with the Bid Form.
- B. Provide construction photographs in accordance with Contract Documents.

1.03 SUBSTANTIATING DATA FOR PROGRESS PAYMENTS

- A. When the Owner or the Architect/ Engineer requires substantiating data, Contractor shall submit suitable information with a cover letter.
- B. Submit one copy of data and cover letter for each copy of application.

1.04 PREPARATION OF APPLICATION FOR FINAL PAYMENT

- A. Fill in application form as specified for progress payments.

1.05 SUBMITTAL PROCEDURE

- A. Submit applications for payment at the times stipulated in the Agreement.
Number:
- B. Three (3) copies of each application; all signed and certified by the Contractor.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION

SECTION 01153
CHANGE ORDER PROCEDURES
PART 1 GENERAL

1.01 DEFINITION

- A. Change Order: Major change in contract scope or time that must be approved by the Board.
- B. Administrative Change Adjustment: Minor change order under 10% of project cost or 20% time, does not have to be Board approved.
- C. Field Directive Change: Change to contract quantity that does not require a change of scope or time extension.

1.02 REQUIREMENTS INCLUDED

- A. The Contractor shall promptly implement change order procedures:
 - 1. Provide full written data required to evaluate changes.
 - 2. Maintain detailed records of work done on a time and material/force account basis.
 - 3. Provide full documentation to Engineer or County Representative on request.
- B. The Contractor shall designate a member of the Contractor's organization who:
 - 1. Is authorized to accept changes to the Work.
 - 2. Is responsible for informing others in the Contractor's employ of the authorized changes into the Work.
- C. The Board of County Commissioners executes all Change Orders.

1.03 PRELIMINARY PROCEDURES

- A. Project Manager may initiate changes by submitting a Request to Contractor. Request will include:
 - 1. Detailed description of the change, products, costs and location of the change in the Project.
 - 2. Supplementary or revised Drawings and Specifications.
 - 3. The projected time extension for making the change.
 - 4. A specified period of time during which the requested price will be considered valid.
 - 5. Such request is for information only and is not an instruction to execute the changes, nor to stop work in progress.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

B. Contractor may initiate changes by submitting a written notice to the Project Manager, containing:

1. Description of the proposed changes.
2. Statement of the reason for making the changes.
3. Statement of the effect on the Contract Sum and the Contract Time.
4. Statement of the effect on the work of separate contractors.
5. Documentation supporting any change in Contract Sum or Contract Time, as appropriate.

1.04 FIELD DIRECTIVE CHANGE

A. In lieu of a Change Order, the Project Manager may issue a Field Directive change for the Contractor to proceed with additional work within the original intent of the Project.

B. Field Directive change will describe changes in the work, with attachments of backup information to define details of the change.

C. Contractor must sign and date the Field Directive change to indicate agreement with the terms therein.

1.05 DOCUMENTATION OF PROPOSALS AND CLAIMS

A. Support each quotation for a lump sum proposal and for each unit price; which has not previously been established, with sufficient substantiating data to allow the Engineer/Owner to evaluate the quotation.

B. On request, provide additional data to support time and cost computations:

1. Labor required.
2. Equipment required.
3. Products required.
 - a. Recommended source of purchase and unit cost.
 - b. Quantities required.
4. Taxes, insurance and bonds.
5. Credit for work deleted from Contract, similarly documented.
6. Overhead and profit.
7. Justification for any change in Contract Time.

C. Support each claim for additional costs and for work done on a time-and-material/force account basis, with documentation as required for a lump-sum proposal plus additional information.

1. Name of the Owner's authorized agent who ordered the work and date of the order.
2. Date and time work was performed and by whom.
3. Time record, summary of hours work and hourly rates paid.
4. Receipts and invoices for:
 - a. Equipment used, listing dates and time of use.
 - b. Products used, listing of quantities.
 - c. Subcontracts.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

1.06 PREPARATION OF CHANGE ORDERS

- A. Project Manager will prepare each Change Order.
- B. Change Order will describe changes in the Work, both additions and deletions, with attachments as necessary to define details of the change.
- C. Change Order will provide an accounting of the adjustment in the Contract Sum and in the Contract Time.

1.07 LUMP SUM/FIXED PRICE CHANGE ORDER

- A. Project Manager initiates the form, including a description of the changes involved and attachments based upon documents and proposals submitted by the Contractor, or requests from the Owner, or both.
- B. Once the form has been completed, a ll copies should be sent to Contractor for approval. After approval by Contractor, all copies should be sent to Owner for approval. The Owner will distribute executed copies after approval by the Board of County Commissioners.

1.08 UNIT PRICE CHANGE ORDER

- A. Contents of Change Orders will be based on, either:
 - 1. Owner's definition of the scope of the required changes.
 - 2. Contractor's Proposal for a change, as approved by the Owner.
 - 3. Survey of completed work.
- B. The amounts of the unit prices to be:
 - 1. Those stated in the Agreement.
 - 2. Those mutually agreed upon between Owner and Contractor.

1.09 TIME AND MATERIAL/FORCE ACCOUNT CHANGE ORDER/CONSTRUCTION CHANGE AUTHORIZATION

- A. At completion of the change, Contractor shall submit itemized accounting and supporting data as provided in the Article "Documentation of Proposals and Claims" of this Section.
- B. Architect/Engineer will determine the allowable cost of such work, as provided in General Conditions and Supplementary Conditions.
- C. Architect/ Engineer will sign and date the Change Order to establish the change in Contract Sum and in Contract Time.
- D. Owner and Contractor will sign and date the Change Order to indicate their agreement therewith.

1.10 CORRELATION WITH CONTRACTOR'S SUBMITTALS

- A. Periodically revise Schedule of Values and Application for Payment forms to record each change as a separate item of work, and to record the adjusted Contract Sum.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

B. Periodically revise the Construction Schedule to reflect each change in Contract Time. Revise sub schedules to show changes for other items of work affected by the changes.

C. Upon completion of work under a Change Order, enter pertinent changes in Record Documents.

PART 2 PRODUCTS (NOT USED)

PART 3 EXECUTION (NOT USED)

END OF SECTION

SECTION 01250 - CONTRACT MODIFICATION PROCEDURES -012600

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section specifies administrative and procedural requirements for handling and processing Contract modifications.
- B. Related Sections include the following:
 - 1. Division 1 Section "Product Requirements" for administrative procedures for handling requests for substitutions made after Contract award.
 - 2. Refer to County Purchasing requirements for any contract items.

1.3 MINOR CHANGES IN THE WORK

- A. Architect/Engineer and Project Manager will issue supplemental instructions authorizing Minor Changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710, "Architect's Supplemental Instructions."

1.4 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
 - 1. Proposal Requests issued by Architect/Engineer are for information only. Do not consider them instructions either to stop work in progress or to execute the proposed change.
 - 2. Within time specified after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
 - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - c. Include an updated Contractor's Construction Schedule that indicates the effect of the change, including, but not limited to, changes in activity dura-

tion, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.

- B. Contractor-Initiated Proposals: If latent or unforeseen conditions require modifications to the Contract, Contractor may propose changes by submitting a request for a change.
 - 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
 - 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - 4. Include an updated Contractor's Construction Schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
 - 5. Comply with requirements in Division 1 Section "Product Requirements" if the proposed change requires substitution of one product or system for product or system specified.

- C. Proposal Request Form: Use AIA Document G709 for Proposal Requests.

1.5 CHANGE ORDER PROCEDURES

- A. On Owner's approval of a Proposal Request, Engineer or Project Manager will issue a Change Order for signatures of Owner and Contractor on AIA Document G701.

1.6 CONSTRUCTION CHANGE DIRECTIVE

- A. Construction Change Directive: Project Manager/ Owner may issue a Construction Change Directive on AIA Document G714. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
 - 1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.

- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
 - 1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

PART 3 - EXECUTION (Not Used)

END OF SECTION 01250

SECTION 01290 - PAYMENT PROCEDURES -012000

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section specifies administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Sections include the following:
 - 1. Division 1 Section "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
 - 2. Division 1 Section "Construction Progress Documentation" for administrative requirements governing preparation and submittal of Contractor's Construction Schedule and Submittals Schedule.
 - 3. Refer to County Purchasing requirements for additional directives and clarification.

1.3 DEFINITIONS

- A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

1.4 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the Schedule of Values with preparation of Contractor's Construction Schedule.
 - 1. Correlate line items in the Schedule of Values with other required administrative forms and schedules, including the following:
 - a. Application for Payment forms with Continuation Sheets.
 - b. Submittals Schedule.
 - 2. Submit the Schedule of Values to Engineer and Project Manager at earliest possible date but no later than seven days before the date scheduled for submittal of initial Applications for Payment.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- B. Format and Content: Use the Project Manual table of contents as a guide to establish line items for the Schedule of Values. Provide at least one line item for each Specification Section.
1. Identification: Include the following Project identification on the Schedule of Values:
 - a. Project name and location.
 - b. Name of Architect/ Engineer.
 - c. Engineer's or Architect's project number.
 - d. Contractor's name and address.
 - e. Date of submittal.
 2. Arrange the Schedule of Values in tabular form with separate columns to indicate the following for each item listed:
 - a. Related Specification Section or Division.
 - b. Description of the Work.
 - c. Name of subcontractor.
 - d. Name of manufacturer or fabricator.
 - e. Name of supplier.
 - f. Change Orders (numbers) that affect value.
 - g. Dollar value.
 - 1) Percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent.
 3. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with the Project Manual table of contents. Provide several line items for principal subcontract amounts, where appropriate.
 4. Round amounts to nearest whole dollar, total shall equal the Contract Sum.
 5. Provide a separate line item in the Schedule of Values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
 - a. Differentiate between items stored on-site and items stored off-site. Include evidence of insurance or bonded warehousing if required.
 6. Provide separate line items in the Schedule of Values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
 7. Each item in the Schedule of Values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.
 - a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the Schedule of Values or distributed as general overhead expense, at Contractor's option.

8. Schedule Updating: Update and resubmit the Schedule of Values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

1.5 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.
 1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.
- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction Work covered by each Application for Payment is the period indicated in the Agreement.
- C. Payment Application Forms: Use AIA Document G702 and AIA Document G703 Continuation Sheets as form for Applications for Payment.
- D. Transmittal: Submit 3 signed and notarized original copies of each Application for Payment to Architect/Engineer and Project Manager by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
 1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- E. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from every entity who is lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.
 1. Submit partial waivers on each item for amount requested, before deduction for retainage, on each item.
 2. When an application shows completion of an item, submit final or full waivers.
 3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
 4. Waiver Delays: Submit each Application for Payment with Contractor's waiver of mechanic's lien for construction period covered by the application.
 - a. Submit final Application for Payment with or preceded by final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
 5. Waiver Forms: Submit waivers of lien on forms, executed in a manner acceptable to Owner.
- F. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
 1. List of subcontractors.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

2. Schedule of Values.
 3. Contractor's Construction Schedule (preliminary if not final).
 4. Products list.
 5. Schedule of unit prices.
 6. Submittals Schedule (preliminary if not final).
 7. List of Contractor's staff assignments.
 8. List of Contractor's principal consultants.
 9. Copies of building permits.
 10. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
 11. Initial progress report.
 12. Report of preconstruction conference.
 13. Certificates of insurance and insurance policies.
 14. Performance and payment bonds.
 15. Data needed to acquire Owner's insurance.
- G. Application for Payment at Substantial Completion: After issuing the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
 2. This application shall reflect Certificates of Partial Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
- H. Final Payment Application: Submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
1. Evidence of completion of Project closeout requirements.
 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 3. Updated final statement, accounting for final changes to the Contract Sum.
 4. AIA Document G706, "Contractor's Affidavit of Payment of Debts and Claims."
 5. AIA Document G706A, "Contractor's Affidavit of Release of Liens."
 6. AIA Document G707, "Consent of Surety to Final Payment."
 7. Evidence that claims have been settled.
 8. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
- I. Separate Pricing and Lump Sum Payments
Separate pricing and lump sum payments shall follow the following payment schedule below and meet the required specifications, meet the requirements of the Engineer's plans, and must be accepted by the Owner's Representative and the Engineer.

SCOPE:

The scope of this section of the Contract Documents is to further define the items included in each Bid Item in the Bid Form section of the Contract Documents. Payment will be made based on the specified items included in the description in this section for each bid item. All contract prices included in the Bid Form section will be full compensation for all shop drawings, working

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

drawings, labor, materials, tools, equipment and incidentals necessary to complete the construction as shown on the Drawings and/or as specified in the Contract Documents to be performed under this Contract. Actual quantities of each item bid on a unit price basis will be determined upon completion of the construction in the manner set up for each item in this section of the Specifications. Payment for all items listed in the Bid Form will constitute full compensation for all work shown and/or specified to be performed under this Contract.

GENERAL

All contract lump sum prices included in the Bid Proposal section will be full compensation for all labor, equipment, and incidental to construct the Manatee County Desoto Center Sheriff's Office Evidence Room as specified in the Contract Documents under this contract.

WORK OUTSIDE AUTHORIZED LIMITS

No payment will be made for work constructed outside the authorized limits of work.

LUMP SUM PAYMENT

Where payment for items are shown to be paid for on a lump sum basis, no separate payment will be made for any item of work required to complete the lump sum items.

Lump sum contracts shall be complete, tested and fully operable prior to request for final payment. Contractor may be required to provide a break-down of the lump sum totals.

Payment shall be made for the items listed on the Bid Form on the basis of the work actually performed, completed, and accepted by the Engineer. Such work includes but is not limited to the furnishing of all necessary labor, materials, equipment, transportation, clean up, restoration of disturbed areas, all other appurtenances to complete the construction and installation of the work as shown on the drawings, as described in the specifications, and as directed by the Architect/Engineer. Measurement and Payment for Lump Sum bid items will be based on a percentage of completion, as approved by the Owner and recommended by the Engineer, on a monthly basis for the Lump Sum bid items listed on the Bid Form of the Contract Documents. Partial payments will be based on the breakdown of the Bid Item in accordance with the Schedule of Values submitted by the Contractor and approved by the Engineer. Payment shall also include full compensation for project photographs, as-built record drawings, project signs, rubbish and spoil removal, repair, replacement or relocation of all signs, walls, and any and all other items required to complete the project in accordance with Contract Documents.

No separate payment will be made for the following items and the cost of such work shall be included in the applicable pay items of work. Final payments shall not be requested by the Contractor or made by the Owner until as-built (record) drawings have been submitted and approved by the Architect/Engineer.

1. Shop Drawings, Working Drawings.
2. Cleanup and miscellaneous work.
3. Testing and placing system in operation.
4. Any material and equipment required to be installed and utilized for the tests.
5. Pipe, structures, pavement replacement, asphalt and shell driveways and/or appurtenances included within the limits of lump sum work, unless otherwise shown.
6. Maintaining the existing quality of service during construction.
7. Appurtenant work as required for a complete and operable system.
8. As-built Record Drawings.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Base Bid

Provide and install all electrical wiring/conductors, conduits, panels, ATS, MTS, breakers, switches, fuses, and switchgear per the plans for the Manatee County Desoto Center Sheriff's Office Generator Disconnect as required to meet the Florida Building Code and the National Electrical Code Requirements. All items must meet the Florida Building Code and the National Electrical Code.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01290

SECTION 01310 - PROJECT MANAGEMENT AND COORDINATION -013100

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
 - 1. General project coordination procedures.
 - 2. Coordination Drawings.
 - 3. Administrative and supervisory personnel.
 - 4. Project meetings.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Division 1 Section "Construction Progress Documentation" for preparing and submitting the Contractor's Construction Schedule.
 - 2. Division 1 Section "Execution Requirements" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.
 - 3. Division 1 Section "Closeout Procedures" for coordinating Contract closeout.

1.3 COORDINATION

- A. Coordination: Coordinate construction operations included in various Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections, that depend on each other for proper installation, connection, and operation.
 - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
 - 2. Coordinate installation of different components with other contractors to ensure maximum accessibility for required maintenance, service, and repair.
 - 3. Make adequate provisions to accommodate items scheduled for later installation.
- B. If necessary, prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.
- C. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities and activities of other contractors to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
1. Preparation of Contractor's Construction Schedule.
 2. Preparation of the Schedule of Values.
 3. Installation and removal of temporary facilities and controls.
 4. Delivery and processing of submittals.
 5. Progress meetings.
 6. Preinstallation conferences.
 7. Project closeout activities.
- D, County Project Manager : The County Project Manager(denoted in all specifications as Project Manager) shall review all items on schedule and perform the interface activities with the end users, Scheduled outages, equipment replacements, construction demolition in public access areas, and review all contract items for final approval.

1.4 SUBMITTALS

- A. Coordination Drawings: Prepare Coordination Drawings if limited space availability necessitates maximum utilization of space for efficient installation of different components or if coordination is required for installation of products and materials fabricated by separate entities.
1. Indicate relationship of components shown on separate Shop Drawings.
 2. Indicate required installation sequences.
 3. Refer to Division 15 Section "Basic Mechanical Materials and Methods" and Division 16 Section "Basic Electrical Materials and Methods" for specific Coordination Drawing requirements for mechanical and electrical installations.
- B. Staff Names: Within 15 days of starting construction operations, submit a list of principal staff assignments, including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses and telephone numbers, including home and office telephone numbers. Provide names, addresses, and telephone numbers of individuals assigned as standbys in the absence of individuals assigned to Project.
1. Post copies of list in Project meeting room, in temporary field office, and by each temporary telephone.

1.5 ADMINISTRATIVE AND SUPERVISORY PERSONNEL

- A. General: In addition to Project superintendent, provide other administrative and supervisory personnel as required for proper performance of the Work.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

1. Include special personnel required for coordination of operations with other contractors.

1.6 PROJECT MEETINGS

- A. General: Schedule and conduct meetings and conferences at Project site, unless otherwise indicated.

1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner, Project Manager, and Engineer of scheduled meeting dates and times.
2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
3. Minutes: Record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner and Engineer, within 3 days of the meeting.

- B. Preconstruction Conference: Schedule a preconstruction conference before starting construction, at a time convenient to Owner and Engineer, but no later than 15 days after execution of the Agreement. Hold the conference at Project site or another convenient location. Conduct the meeting to review responsibilities and personnel assignments.

1. Attendees: Authorized representatives of Owner, County Project Manager, Engineer, and their consultants; Contractor and its superintendent; major subcontractors; manufacturers; suppliers; and other concerned parties shall attend the conference. All participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
2. Agenda: Discuss items of significance that could affect progress, including the following:
 - a. Tentative construction schedule.
 - b. Phasing.
 - c. Critical work sequencing.
 - d. Designation of responsible personnel.
 - e. Procedures for processing field decisions and Change Orders.
 - f. Procedures for processing Applications for Payment.
 - g. Distribution of the Contract Documents.
 - h. Submittal procedures.
 - i. Preparation of Record Documents.
 - j. Use of the premises.
 - k. Responsibility for temporary facilities and controls.
 - l. Parking availability.
 - m. Office, work, and storage areas.
 - n. Equipment deliveries and priorities.
 - o. First aid.
 - p. Security.
 - q. Progress cleaning.
 - r. Working hours.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction.
1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Engineer of scheduled meeting dates.
 2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:
 - a. Contract Documents.
 - b. Options.
 - c. Related Change Orders.
 - d. Purchases.
 - e. Deliveries.
 - f. Submittals.
 - g. Review of mockups.
 - h. Possible conflicts.
 - i. Compatibility problems.
 - j. Time schedules.
 - k. Weather limitations.
 - l. Manufacturer's written recommendations.
 - m. Warranty requirements.
 - n. Compatibility of materials.
 - o. Acceptability of substrates.
 - p. Temporary facilities and controls.
 - q. Space and access limitations.
 - r. Regulations of authorities having jurisdiction.
 - s. Testing and inspecting requirements.
 - t. Required performance results.
 - u. Protection of construction and personnel.
 3. Record significant conference discussions, agreements, and disagreements.
 4. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.
- D. Progress Meetings: Conduct progress meetings at regular intervals. Coordinate dates of meetings with preparation of payment requests.
1. Attendees: In addition to representatives of Owner, County Project Manager, and Engineer, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
 2. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's Construction Schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - b. Review present and future needs of each entity present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.
 - 3) Status of submittals.
 - 4) Status of recycling and waste disposal.
 - 5) Deliveries.
 - 6) Off-site fabrication.
 - 7) Access.
 - 8) Site utilization.
 - 9) Temporary facilities and controls.
 - 10) Work hours.
 - 11) Hazards and risks.
 - 12) Progress cleaning.
 - 13) Quality and work standards.
 - 14) Change Orders.
 - 15) Documentation of information for payment requests.
3. Reporting: Distribute minutes of the meeting to each party present and to parties who should have been present. Include a brief summary, in narrative form, of progress since the previous meeting and report.
- a. Schedule Updating: Revise Contractor's Construction Schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.
4. Coordination Meetings: Conduct coordination meetings at regular intervals
- Project coordination meetings are in addition to specific meetings held for other purposes , such as progress meetings and preinstallation conferences.
- a. Safety meetings : The contractor shall provide to the Owner's representative/ County Project Manager a copy of in-house written safety policies. Copies of weekly safety meetings shall be retained on site for periodic review.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

END OF SECTION 01310

SECTION 01330 - SUBMITTAL PROCEDURES -013300

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other miscellaneous submittals.
- B. Related Sections include the following:
 - 1. Division 1 Section "Payment Procedures" for submitting Applications for Payment.
 - 2. Division 1 Section "Project Management and Coordination" for submitting Coordination Drawings.
 - 3. Division 1 Section "Construction Progress Documentation" for submitting schedules and reports, including Contractor's Construction Schedule and the Submittals Schedule.
 - 4. Division 1 Section "Quality Requirements" for submitting test and inspection reports and Delegated-Design Submittals.
 - 5. Division 1 Section "Closeout Procedures" for submitting warranties Project Record Documents and operation and maintenance manuals.

1.3 DEFINITIONS

- A. Action Submittals: Written and graphic information that requires Engineer's responsive action.
- B. Informational Submittals: Written information that does not require Engineer's approval. Submittals may be rejected for not complying with requirements.

1.4 SUBMITTAL PROCEDURES

- A. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
 - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
 - 2. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- a. Engineer reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- B. Submittals Schedule: Comply with requirements in Division 1 Section "Construction Progress Documentation" for list of submittals and time requirements for scheduled performance of related construction activities.
- C. Processing Time: Allow enough time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal.
 1. Initial Review: Allow 15 days for initial review of each submittal. Allow additional time if processing must be delayed to permit coordination with subsequent submittals. Engineer will advise Contractor when a submittal being processed must be delayed for coordination.
 2. Concurrent Review: Where concurrent review of submittals by Engineer's consultants, Owner, or other parties is required, allow 21 days for initial review of each submittal.
 3. If intermediate submittal is necessary, process it in same manner as initial submittal.
 4. Allow 15 days for processing each resubmittal.
 5. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing.
- D. Identification: Place a permanent label or title block on each submittal for identification.
 1. Indicate name of firm or entity that prepared each submittal on label or title block.
 2. Provide a space approximately 4 by 5 inches on label or beside title block to record Contractor's review and approval markings and action taken by Engineer.
 3. Include the following information on label for processing and recording action taken:
 - a. Project name.
 - b. Date.
 - c. Name and address of Architect/ Engineer.
 - d. Name and address of Contractor.
 - e. Name and address of subcontractor.
 - f. Name and address of supplier.
 - g. Name of manufacturer.
 - h. Unique identifier, including revision number.
 - i. Number and title of appropriate Specification Section.
 - j. Drawing number and detail references, as appropriate.
 - k. Other necessary identification.
- E. Deviations: Highlight, encircle, or otherwise identify deviations from the Contract Documents on submittals.
- F. Additional Copies: Unless additional copies are required for final submittal, and unless Architect observes noncompliance with provisions of the Contract Documents, initial submittal may serve as final submittal.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

1. Additional copies submitted for maintenance manuals will not be marked with action taken and will be returned.
- G. Transmittal: Package each submittal individually and appropriately for transmittal and handling. Transmit each submittal using a transmittal form. Engineer/ Architect will discard submittals received from sources other than Contractor.
1. On an attached separate sheet, prepared on Contractor's letterhead, record relevant information, requests for data, revisions other than those requested by Engineer on previous submittals, and deviations from requirements of the Contract Documents, including minor variations and limitations. Include the same label information as the related submittal.
 2. Include Contractor's certification stating that information submitted complies with requirements of the Contract Documents.
 3. Transmittal Form: Use AIA Document G810.
 4. Transmittal Form: Provide locations on form for the following information:
 - a. Project name.
 - b. Date.
 - c. Destination (To:).
 - d. Source (From:).
 - e. Names of subcontractor, manufacturer, and supplier.
 - f. Category and type of submittal.
 - g. Submittal purpose and description.
 - h. Submittal and transmittal distribution record.
 - i. Remarks.
 - j. Signature of transmitter.
- H. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- I. Use for Construction: Use only final submittals with mark indicating action taken by Architect/Engineer in connection with construction.

PART 2 - PRODUCTS

2.1 ACTION SUBMITTALS

- A. General: Prepare and submit Action Submittals required by individual Specification Sections.
- B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment. Please note substitutions or comparable products are reviewed in accordance with Div 1 criteria and may be rejected.
 1. If information must be specially prepared for submittal because standard printed data are not suitable for use, submit as Shop Drawings, not as Product Data.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

2. Mark each copy of each submittal to show which products and options are applicable.
 3. Include the following information, as applicable:
 - a. Manufacturer's written recommendations.
 - b. Manufacturer's product specifications.
 - c. Manufacturer's installation instructions.
 - d. Standard color charts.
 - e. Manufacturer's catalog cuts.
 - f. Wiring diagrams showing factory-installed wiring.
 - g. Printed performance curves.
 - h. Operational range diagrams..
 - i. Standard product operating and maintenance manuals.
 - j. Compliance with recognized trade association standards.
 - k. Compliance with recognized testing agency standards.
 - l. Application of testing agency labels and seals.
 - m. Notation of coordination requirements.
 - n. Compliance with environmental requirements or standards.
 - o. Compliance with sustainable construction practices requirements or standards.
 - p. Compliance with VOC requirements.
 4. Number of Copies: Submit copies of each submittal, as follows:
 - a. Submittal: Submit the number of copies the contractor requires plus one copy which will be retained by the Engineer; plus two additional copies where required for maintenance manuals. Engineer will return the submittals marked with action taken and corrections and modifications required.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data.
1. Preparation: Include the following information, as applicable:
 - a. Dimensions.
 - b. Identification of products.
 - c. Fabrication and installation drawings.
 - d. Roughing-in and setting diagrams.
 - e. Wiring diagrams showing field-installed wiring, including power, signal, and control wiring.
 - f. Shopwork manufacturing instructions.
 - g. Templates and patterns.
 - h. Schedules.
 - i. Design calculations.
 - j. Compliance with specified standards.
 - k. Notation of coordination requirements.
 - l. Notation of dimensions established by field measurement.
 2. Wiring Diagrams: Differentiate between manufacturer-installed and field-installed wiring.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

3. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least **8-1/2 by 11 inches** but no larger than **36 by 24 inches** . Emailed adobe PDF's are not allowed.
 4. Number of Copies: Submit copies of each submittal, as follows:
 - a. Initial Submittal: Submit one correctable, translucent, reproducible print and one blue- or black-line print. Architect will return the reproducible print.
 - b. Final Submittal: Submit one correctable, translucent, reproducible print and three blue- or black-line prints, unless prints are required for operation and maintenance manuals. Submit five prints where prints are required for operation and maintenance manuals. Architect will retain two prints; remainder will be returned. Mark up and retain one returned print as a Project Record Drawing.
- D. Coordination Drawings: Comply with requirements in Division 1 Section "Project Management and Coordination."
- E. Samples: Prepare physical units of materials or products, including the following:
1. Comply with requirements in Division 1 Section "Quality Requirements" for mockups.
 2. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units showing the full range of colors, textures, and patterns available.
 3. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from the same material to be used for the Work, cured and finished in manner specified, and physically identical with the product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.
 4. Preparation: Mount, display, or package Samples in manner specified to facilitate review of qualities indicated. Prepare Samples to match Architect's sample where so indicated. Attach label on unexposed side that includes the following:
 - a. Generic description of Sample.
 - b. Product name or name of manufacturer.
 - c. Sample source.
 5. Additional Information: On an attached separate sheet, prepared on Contractor's letterhead, provide the following:
 - a. Size limitations.
 - b. Compliance with recognized standards.
 - c. Availability.
 - d. Delivery time.
 6. Submit Samples for review of kind, color, pattern, and texture for a final check of these characteristics with other elements and for a comparison of these characteristics between final submittal and actual component as delivered and installed.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- a. If variation in color, pattern, texture, or other characteristic is inherent in the product represented by a Sample, submit at least three sets of paired units that show approximate limits of the variations.
 - b. Refer to individual Specification Sections for requirements for Samples that illustrate workmanship, fabrication techniques, details of assembly, connections, operation, and similar construction characteristics.
7. Number of Samples for Initial Selection: Submit one full set of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Architect will return submittal with options selected.
 8. Number of Samples for Verification: Submit three sets of Samples. Architect will retain one Sample set; remainder will be returned. Mark up and retain one returned Sample set as a Project Record Sample.
 - a. Submit a single Sample where assembly details, workmanship, fabrication techniques, connections, operation, and other similar characteristics are to be demonstrated.
 9. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
 - a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
 - b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.
- F. Product Schedule or List: Prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
1. Type of product. Include unique identifier for each product.
 2. Number and name of room or space.
 3. Location within room or space.
- G. Delegated-Design Submittal: Comply with requirements in Division 1 Section "Quality Requirements."
- H. Contractor's Construction Schedule: Comply with requirements in Division 1 Section "Construction Progress Documentation" for Project Manager's action.
- I. Submittals Schedule: Comply with requirements in Division 1 Section "Construction Progress Documentation."
- J. Application for Payment: Comply with requirements in Division 1 Section "Payment Procedures."

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- K. Schedule of Values: Comply with requirements in Division 1 Section "Payment Procedures."
- L. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:
 - 1. Name, address, and telephone number of entity performing subcontract or supplying products.
 - 2. Number and title of related Specification Section(s) covered by subcontract.
 - 3. Drawing number and detail references, as appropriate, covered by subcontract.

2.2 INFORMATIONAL SUBMITTALS

- A. General: Prepare and submit Informational Submittals required by other Specification Sections.
 - 1. Number of Copies: Submit two copies of each submittal, unless otherwise indicated. Engineer will not return copies.
 - 2. Certificates and Certifications: Provide a notarized statement that includes signature of Contractor, testing agency, or design professional responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of the company.
 - 3. Test and Inspection Reports: Comply with requirements in Division 1 Section "Quality Requirements."
- B. Contractor's Construction Schedule: Comply with requirements in Division 1 Section "Construction Progress Documentation."
- C. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
- D. Product Certificates: Prepare written statements on manufacturer's letterhead certifying that product complies with requirements.
- E. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements. Submit record of Welding Procedure Specification (WPS) and Procedure Qualification Record (PQR) on AWS forms. Include names of firms and personnel certified.
- F. Installer Certificates: Prepare written statements on manufacturer's letterhead certifying that Installer complies with requirements and, where required, is authorized for this specific Project.
- G. Manufacturer Certificates: Prepare written statements on manufacturer's letterhead certifying that manufacturer complies with requirements. Include evidence of manufacturing experience where required.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- H. Material Certificates: Prepare written statements on manufacturer's letterhead certifying that material complies with requirements.
- I. Material Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements.
- J. Preconstruction Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements.
- K. Compatibility Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.
- L. Field Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements.
- M. Product Test Reports: Prepare written reports indicating current product produced by manufacturer complies with requirements. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
- N. Research/Evaluation Reports: Prepare written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:
 - 1. Name of evaluation organization.
 - 2. Date of evaluation.
 - 3. Time period when report is in effect.
 - 4. Product and manufacturers' names.
 - 5. Description of product.
 - 6. Test procedures and results.
 - 7. Limitations of use.
- O. Maintenance Data: Prepare written and graphic instructions and procedures for operation and normal maintenance of products and equipment. Comply with requirements in Division 1 Section "Closeout Procedures."
- P. Design Data: Prepare written and graphic information, including, but not limited to, performance and design criteria, list of applicable codes and regulations, and calculations. Include list of assumptions and other performance and design criteria and a summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Include page numbers.
- Q. Manufacturer's Instructions: Prepare written or published information that documents manufacturer's recommendations, guidelines, and procedures for installing or operating

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

a product or equipment. Include name of product and name, address, and telephone number of manufacturer. Include the following, as applicable:

1. Preparation of substrates.
 2. Required substrate tolerances.
 3. Sequence of installation or erection.
 4. Required installation tolerances.
 5. Required adjustments.
 6. Recommendations for cleaning and protection.
- R. **Manufacturer's Field Reports:** Prepare written information documenting factory-authorized service representative's tests and inspections. Include the following, as applicable:
1. Name, address, and telephone number of factory-authorized service representative making report.
 2. Statement on condition of substrates and their acceptability for installation of product.
 3. Statement that products at Project site comply with requirements.
 4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
 5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 6. Statement whether conditions, products, and installation will affect warranty.
 7. Other required items indicated in individual Specification Sections.
- S. **Insurance Certificates and Bonds:** Prepare written information indicating current status of insurance or bonding coverage. Include name of entity covered by insurance or bond, limits of coverage, amounts of deductibles, if any, and term of the coverage.
- T. **Construction Photographs:** Comply with requirements in Division 1 Section "Construction Photographs."
- U. **Material Safety Data Sheets:** Submit information directly to Contracting Officer. If submitted to Project Manager, Engineer will not review this information but will return it with no action taken. Comply with requirements in Division 1 Section "Safety Requirements."

PART 3 - EXECUTION

3.1 CONTRACTOR'S REVIEW

- A. Review each submittal and check for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Engineer.
- B. **Approval Stamp:** Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name

of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

3.2 ARCHITECT'S /ENGINEER'S ACTION

- A. General: Architect/Engineer will not review submittals that do not bear Contractor's approval stamp and will return them without action.
- B. Action Submittals: Architect/Engineer will review each submittal, make marks to indicate corrections or modifications required, and return it. Architect will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action taken, as follows:
 - 1. Submittals will be marked "Approved," "Approved as Noted," "Revise as Noted and Resubmit," "Rejected/Resubmit as Specified," "No Action Required," "Reviewed." Those marked "Revise as Noted and Resubmit" or "Rejected/Resubmit as Specified" and returned for correction shall be corrected and resubmitted. Upon receiving submittal marked "Approved" or "Approved as Noted" from the Architect/Engineer, the Contractor shall have sufficient sets of prints made from them for distribution.
 - a. Do not use, or allow others to use, submittals marked "Revise as Noted and Resubmit" or "Rejected/Resubmit as Specified" at the Project Site or elsewhere where work is in progress..
- C. Informational Submittals: Architect / Engineer will review each submittal and will not return it, or will reject and return it if it does not comply with requirements. Architect/Engineer will forward each submittal to appropriate party.
- D. Submittals not required by the Contract Documents will not be reviewed and may be discarded.

END OF SECTION 01330

SECTION 01400 - QUALITY REQUIREMENTS -014000

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Owner will hire and pay for independent laboratory services.
- C. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
 - 1. Specific quality-control requirements for individual construction activities are specified in the Sections that specify those activities. Requirements in those Sections may also cover production of standard products.
 - 2. Specified tests, inspections, and related actions do not limit Contractor's quality-control procedures that facilitate compliance with the Contract Document requirements.
 - 3. Requirements for Contractor to provide quality-control services required by the Architect, Engineer, Owner, or authorities having jurisdiction are not limited by provisions of this Section.
- D. Related Sections include the following:
 - 1. Division 1 Section "Construction Progress Documentation" for developing a schedule of required tests and inspections.
 - 2. Division 1 Section "Cutting and Patching" for repair and restoration of construction disturbed by testing and inspecting activities.
 - 3. Divisions 2 through 16 Sections for specific test and inspection requirements.

1.3 DEFINITIONS

- A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and ensure that proposed construction complies with requirements.
- B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that completed construction complies with requirements. Services do not include contract enforcement activities performed by Architect.

- C. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.

1.4 DELEGATED DESIGN

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
 - 1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Engineer..

1.5 SUBMITTALS

- A. Qualification Data: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.
- B. Delegated-Design Submittal: In addition to Shop Drawings, Product Data, and other required submittals, submit a statement, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional, indicating that the products and systems are in compliance with performance and design criteria indicated. Include list of codes, loads, and other factors used in performing these services.
- C. Schedule of Tests and Inspections: Prepare in tabular form and include the following:
 - 1. Specification Section number and title.
 - 2. Description of test and inspection.
 - 3. Identification of applicable standards.
 - 4. Identification of test and inspection methods.
 - 5. Number of tests and inspections required.
 - 6. Time schedule or time span for tests and inspections.
 - 7. Entity responsible for performing tests and inspections.
 - 8. Requirements for obtaining samples.
 - 9. Unique characteristics of each quality-control service.
- D. Reports: Prepare and submit certified written reports that include the following:
 - 1. Date of issue.
 - 2. Project title and number.
 - 3. Name, address, and telephone number of testing agency.
 - 4. Dates and locations of samples and tests or inspections.
 - 5. Names of individuals making tests and inspections.
 - 6. Description of the Work and test and inspection method.
 - 7. Identification of product and Specification Section.
 - 8. Complete test or inspection data.

9. Test and inspection results and an interpretation of test results.
10. Ambient conditions at time of sample taking and testing and inspecting.
11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
12. Name and signature of laboratory inspector.
13. Recommendations on retesting and reinspecting.

- E. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.

1.6 QUALITY ASSURANCE

- A. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- B. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- C. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.
- D. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance.
- E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that are similar to those indicated for this Project in material, design, and extent.
- F. Testing Agency Qualifications: An agency with the experience and capability to conduct testing and inspecting indicated, as documented by ASTM E 548, and that specializes in types of tests and inspections to be performed.

1.7 QUALITY CONTROL

- A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of the types of testing and inspecting they are engaged to perform.
 2. Costs for retesting and reinspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor, and the Contract Sum will be adjusted by Change Order.
- B. Contractor Responsibilities: Unless otherwise indicated, provide quality-control services specified and required by authorities having jurisdiction.
1. Where services are indicated as Contractor's responsibility, engage a qualified testing agency to perform these quality-control services.
 - a. Contractor shall not employ the same entity engaged by Owner, unless agreed to in writing by Owner.
 2. Notify testing agencies at least [24] <Insert number> hours in advance of time when Work that requires testing or inspecting will be performed.
 3. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
 4. Testing and inspecting requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
 5. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- C. Manufacturer's Field Services: Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing.
- D. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and re-inspecting, for construction that revised or replaced Work that failed to comply with requirements established by the Contract Documents.
- E. Testing Agency Responsibilities: Cooperate with Project Manager, Engineer, and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
1. Notify Project Manager, Engineer, and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
 2. Interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
 3. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
 4. Do not release, revoke, alter, or increase requirements of the Contract Documents or approve or accept any portion of the Work.
 5. Do not perform any duties of Contractor.
- F. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as re-

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

quested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:

1. Access to the Work.
 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
 4. Facilities for storage and field-curing of test samples.
 5. Delivery of samples to testing agencies.
 6. Preliminary design mix proposed for use for material mixes that require control by testing agency.
 7. Security and protection for samples and for testing and inspecting equipment at Project site.
- G. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and quality-control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
1. Schedule times for tests, inspections, obtaining samples, and similar activities.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.
1. Provide materials and comply with installation requirements specified in other Sections of these Specifications. Restore patched areas and extend restoration into adjoining areas in a manner that eliminates evidence of patching.
 2. Comply with the Contract Document requirements for Division 1 Section "Cutting and Patching."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 01400

SECTION 01420 – REFERENCES -014200

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": The term "approved," when used in conjunction with Engineer's action on Contractor's submittals, applications, and requests, is limited to Engineer's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Directed": Terms such as "directed," "requested," "authorized," "selected," "approved," "required," and "permitted" mean directed by Engineer, requested by Engineer, and similar phrases.
- D. "Indicated": The term "indicated" refers to graphic representations, notes, or schedules on Drawings; or to other paragraphs or schedules in Specifications and similar requirements in the Contract Documents. Terms such as "shown," "noted," "scheduled," and "specified" are used to help the user locate the reference.
- E. "Regulations": The term "regulations" includes laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, as well as rules, conventions, and agreements within the construction industry that control performance of the Work.
- F. "Furnish": The term "furnish" means to supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": The term "install" describes operations at Project site including unloading, temporary storage, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations.
- H. "Provide": The term "provide" means to furnish and install, complete and ready for the intended use.
- I. "Installer": An installer is Contractor or another entity engaged by Contractor, as an employee, subcontractor, or contractor of lower tier, to perform a particular construction operation, including installation, erection, application, and similar operations.
- J. The term "experienced," when used with the term "installer," means having successfully completed a minimum of five previous projects similar in size and scope to this Project; being familiar with the special requirements indicated; and having complied with requirements of authorities having jurisdiction.

1. Using a term such as "carpentry" does not imply that certain construction activities must be performed by accredited or unionized individuals of a corresponding generic name, such as "carpenter." It also does not imply that requirements specified apply exclusively to tradespeople of the corresponding generic name.
- K. "Project site" is the space available for performing construction activities, either exclusively or in conjunction with others performing other work as part of Project. The extent of Project site is shown on the Drawings and may or may not be identical with the description of the land on which Project is to be built.

1.3 INDUSTRY STANDARDS

- A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.
- B. Publication Dates: Comply with standards in effect as of the date of the Contract Documents, unless otherwise indicated.
- C. Conflicting Requirements: Where compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer uncertainties and requirements that are different, but apparently equal, to Architect for a decision before proceeding.
 1. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of the requirements. Refer uncertainties to Architect for a decision before proceeding.
- D. Copies of Standards: Each entity engaged in construction on Project must be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.
 1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from the publication source and make them available on request.
- E. Abbreviations and Names: Abbreviations and acronyms are frequently used in the Specifications and other Contract Documents to represent the name of a trade association, standards-developing organization, authorities having jurisdiction, or other entity in the context of referencing a standard or publication. Where abbreviations and acronyms are used in the Specifications or other Contract Documents, they mean the recognized name of these entities. Refer to Gale Research's "Encyclopedia of Associations" or Columbia Books' "National Trade & Professional Associations of the U.S.," which are available in most libraries.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Reference publications are cited in other sections of the specifications along with identification of their sponsoring organizations. The addresses of the sponsoring organizations are listed below, and if the source of the publications is different from the address of the sponsoring organization, that information is also provided.

ACI INTERNATIONAL (ACI)
P.O. Box 9094
Farmington Hills, MI 48333-9094
Ph: 248-848-3700
Fax: 248-848-3701
Internet: <http://www.aci-int.org>

AIR CONDITIONING AND REFRIGERATION INSTITUTE (ARI)
4301 North Fairfax Dr., Suite 425
ATTN: Pubs Dept.
Arlington, VA 22203
Ph: 703-524-8800
Fax: 703-528-3816
E-mail: ari@dgsys.com
Internet: <http://www.ari.org>

AIR CONDITIONING CONTRACTORS OF AMERICA (ACCA)
1712 New Hampshire Avenue, NW
Washington, DC 20009
Ph: 202-483-9370
FAX: 202-232-8545

AIR DIFFUSION COUNCIL (ADC)
104 So. Michigan Ave., No. 1500
Chicago, IL 60603
Ph: 312-201-0101
Fax: 312-201-0214

AIR MOVEMENT AND CONTROL ASSOCIATION INTERNATIONAL (AMCA)
30 W. University Dr.
Arlington Heights, IL 60004-1893
Ph: 847-394-0150
Fax: 847-253-0088

ALUMINUM ASSOCIATION (AA)
900 19th Street N.W.
Washington, DC 20006
Ph: 202-862-5700
Fax: 202-862-5164
Internet: <http://www.aluminum.org>

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)
1827 Walden Ofc. Sq.
Suite 104
Schaumburg, IL 60173-4268
Ph: 847-303-5664
Fax: 847-303-5774
Internet: <http://www.aamanet.org>

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

(AASHTO)
AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS
444 N. Capital St., NW, Suite 249
Washington, DC 20001
Ph: 800-231-3475 or 202-624-5800
Fax: 800-525-5562 or 202-624-5806
Internet: <http://www.aashto.org>

AMERICAN ASSOCIATION OF TEXTILE CHEMISTS AND COLORISTS (AATCC)
P.O. Box 12215
1 Davis Drive
Research Triangle Park, NC 27709-2215
Ph: 919-549-8141
Fax: 919-549-8933

AMERICAN BEARING MANUFACTURERS ASSOCIATION (ABMA)
1101 Connecticut Ave., NW, Suite 300
Washington, DC 20036-2422
SECTION 01420 Page 3
Ph: 202-429-5155
Fax: 202-828-6042

AMERICAN BOILER MANUFACTURERS ASSOCIATION (ABMA)
1200 19th Street, NW, Suite 300
Washington, DC 20036
Ph: 202-429-5155 Fax: 202-828-6042

AMERICAN CONCRETE PIPE ASSOCIATION (ACPA)
222 West Las Colinas Blvd., Suite 641
Irving, TX 75039-5423
Ph: 972-506-7616
Fax: 972-506-7682
Internet: <http://www.concrete-pipe.org>
e-mail: info@concrete-pipe.org

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)
1330 Kemper Meadow Dr.
Suite 600
Cincinnati, OH 45240
Ph: 513-742-2020
Fax: 513-742-3355
Internet: <http://www.acgih.org>
E-mail: pubs@acgih.org

AMERICAN FOREST & PAPER ASSOCIATION (AF&PA)
American Wood Council
ATTN: Publications Dept.
1111 Nineteenth St. NW, Suite 800
Washington, DC 20036
Ph: 800-294-2372
Fax: 202-463-2785
Internet: <http://www.afandpa.org>
Order From: American Wood Council
P.O. Box 5364
Madison, WI 53705-5364
Ph: 800-890-7732

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Fax: 608-231-2152

AMERICAN GAS ASSOCIATION (AGA)
400 North Capitol Street N.W.
Washington, D.C. 20001
Ph: 202-824-7000
Fax: 202-824-7115
E-mail: webmaster@aga.org
Internet: <http://www.aga.org>

AMERICAN GEAR MANUFACTURERS ASSOCIATION (AGMA)
1500 King St., Suite 201
Alexandria, VA 22314-2730
Ph: 703-684-0211
Fax: 703-684-0242

AMERICAN HARDBOARD ASSOCIATION (AHA)
1210 W. Northwest Highway
Palatine, IL 60067
Ph: 708-934-8800
Fax: 708-934-8803

AMERICAN INSTITUTE OF ARCHITECTS
606-288-4960
<http://www.aiaonline.org>

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)
One East Wacker Dr., Suite 3100
Chicago, IL 60601-2001
Ph: 312-670-2400
Publications: 800-644-2400
Fax: 312-670-2400
Internet: <http://www.aiscweb.com>

AMERICAN INSTITUTE OF TIMBER CONSTRUCTION (AITC)
7012 S. Revere Parkway, Suite 140
Centennial, CO 80112
Ph: 303-792-9559
Fax: 303-792-0669
Internet: <http://www.aitc-glulam.org>

AMERICAN IRON AND STEEL INSTITUTE (AISI)
ATTN: Publication Orders
P.O. Box 4321
Chestertown, MD 21690
Ph: 800-277-3850
Fax: 410-810-0910

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)
11 West 42nd St
New York, NY 10036
Ph: 212-642-4900
Fax: 212-302-1286
Internet: <http://www.ansi.org>

AMERICAN NURSERY AND LANDSCAPE ASSOCIATION (ANLA)

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

1250 I St., NW, Suite 500
Washington, DC 20005
Ph: 202-789-2900 Ext 3010
Fax: 202-962-4776

AMERICAN PETROLEUM INSTITUTE (API)

1220 L St., NW
Washington, DC 20005-4070
Ph: 202-682-8000
Fax: 202-962-4776
Internet: <http://www.api.org>

(AREMA)

AMERICAN RAILWAY ENGINEERING AND MAINTENANCE-OF-WAY ASSOCIATION

8201 Corporate Dr., Suite 1125
SECTION 01420 Page 5
Landover, MD 20785
Ph: 301-459-3200
Fax: 301-459-8077

AMERICAN SOCIETY FOR NONDESTRUCTIVE TESTING (ASNT)

1711 Arlingate Lane
P.O. Box 28518
Columbus, OH 43228-0518
Ph: 800-222-2768
Fax: 614-274-6899

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

1801 Alexander Bell Drive
Reston, VA 20190-4400
Ph: 703-295-6300
Fax: 703-295-6222
Internet: <http://www.pubs.asce.org>
e-mail: marketing@asce.org

ENGINEERS (ASHRAE)

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING

1791 Tullie Cir., NE
Atlanta, GA 30329-2305
Ph: 800-527-4723 or 404-636-8400
Fax: 404-321-5478
Internet: <http://www.ashrae.org>

AMERICAN SOCIETY OF SANITARY ENGINEERING (ASSE)

28901 Clemens Rd, Ste 100
Westlake, OH 44145
Ph: 440-835-3040
Fax: 440-835-3488
E-mail: asse@ix.netcom.com

AMERICAN SOCIETY OF SAFETY ENGINEERS (ASSE)

1800 East Oakton Street
Des Plaines, IL 60018-2187
Ph: 847-699-2929
Fax: 847-196-3769
Internet: <http://www.asse.org>

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

AMERICAN WATER WORKS ASSOCIATION (AWWA)

6666 West Quincy
Denver, CO 80235
Ph: 800-926-7337
Fax: 303-795-2114
Internet: <http://www.awwa.org>
Current as of December 27, 2004

AMERICAN WELDING SOCIETY (AWS)

550 N.W. LeJeune Road
Miami, FL 33126
SECTION 01420 Page 6
Ph: 800-443-9353
Fax: 305-443-7559
Internet: <http://www.amweld.org>

AMERICAN WOOD-PRESERVERS' ASSOCIATION (AWPA)

3246 Fall Creek Highway, Suite 1900
Grandbury, TX 76049-7979
Ph: 817-326-6300
Fax: 817-326-6306

AMERICAN WOOD PRESERVERS BUREAU (AWPB)

P.O. Box 5283
Springfield, VA 22150
Ph: 703-339-6660
Fax: 703-339-6711

APA - THE ENGINEERED WOOD ASSOCIATION (APA)

P.O.Box 11700
Tacoma, WA 98411-0700
Ph: 253-565-6600
Fax: 253-565-7265
Internet: <http://www.apawood.org>

ARCHITECTURAL WOODWORK INSTITUTE (AWI)

1952 Isaac, Newton Square West
Reston, VA 20190
Ph: 703-733-0600
Fax: 703-733-0584
Internet: <http://www.awinet.org>

ASBESTOS CEMENT PRODUCT PRODUCERS ASSOCIATION (ACPPA)

1745 Jefferson Davis Highway
Suite 406
Arlington, VA 22202
Ph: 703-412-1153
Fax: 703-412-1152

ASM INTERNATIONAL (ASM)

9639 Kinsman Road
Materials Park, OH 44073-0002
Ph: 440-338-5151
Fax: 440-338-4634
Internet: <http://www.asm-intl.org>

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Order Publications From:
ASM International
ATTN: MSC/Book Order
P.O. Box 473
Novelty, OH 44072-9901

ASME INTERNATIONAL (ASME)
Three Park Avenue
New York, NY 10016-5990
SECTION 01420 Page 7
Ph: 212-591-7722
Fax: 212-591-7674
Internet: <http://www.asme.org>

ASPHALT INSTITUTE (AI)
Research Park Dr.
P.O. Box 14052
Lexington, KY 40512-4052
Ph: 606-288-4960
Fax: 606-288-4999
Internet: <http://www.asphaltinstitute.org>
e-mail: asphalt@asphaltinstitute.org

ASPHALT ROOFING MANUFACTURER'S ASSOCIATION (ARMA)
1156-15TH Street, NW, Suite 900
Washington D.C. 20005
Ph: 202-207-0917
Fax: 202-223-9741
Internet: <http://www.asphaltroofing.org>

ASSOCIATED AIR BALANCE COUNCIL (AABC)
1518 K St., NW, Suite 503
Washington, DC 20005
Ph: 202-737-0202
Fax: 202-638-4833

ASSOCIATION FOR THE ADVANCEMENT OF MEDICAL INSTRUMENTATION (AAMI)
3330 Washington Blvd., Suite 400
Arlington, VA 22201-4598
Ph: 703-525-4890
Fax: 703-276-0793
Internet: <http://www.aami.org>

ASSOCIATION OF EDISON ILLUMINATING COMPANIES (AEIC)
600 No. 18th St.
P.O. Box 2641
Birmingham, AL 35291-0992
Ph: 205-257-2530
Fax: 205-257-2540
Internet: <http://www.aeic.org>
E-Mail: veazey-white@apc.com

ASSOCIATION OF HOME APPLIANCE MANUFACTURERS (AHAM)
20 No. Wacker Dr., Suite 1500
Chicago, IL 60606
Ph: 312-984-5800
Fax: 312-984-5823

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Internet: <http://www.aham.org>

ASTM INTERNATIONAL (ASTM)
100 Barr Harbor Drive
West Conshohocken, PA 19428-2959
SECTION 01420 Page 8
Ph: 610-832-9500
Fax: 610-832-9555
Internet: <http://www.astm.org>

BIFMA INTERNATIONAL (BIFMA)
2680 Horizon Drive SE, Suite A-1
Grand Rapids, MI 49546-7500
Ph: 616-285-3963
Fax: 616-285-3765
Internet: <http://www.bifma.com>
E-mail: email@bifma.com

BRICK INDUSTRY ASSOCIATION (BIA)
11490 Commerce Park Dr., Suite 308
Reston, VA 22091
Ph: 703-620-0010
Fax: 703-620-3928

BRITISH STANDARDS INSTITUTE (BSI)
Linford Wood
Milton Keynes, United Kingdom MK1446LE
Ph: 44908 220022
Fax: 44908 320856

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)
355 Lexington Ave.
New York, NY 10017-6603
Ph: 212-297-2100
Fax: 212-370-9047
Internet: <http://www.buildershardware.com>

BUILDING INDUSTRY CONSULTING SERVICE INTERNATIONAL (BICSI)
8610 Hidden River Parkway
Tampa, Florida 33637-1000
Ph: 1-800-242-7405 or 813-979-1991
Fax: 813-971-4311
Internet: <http://www.bicsi.org>
e-mail: bicsi@bicsi.org

CARPET AND RUG INSTITUTE (CRI)
310 Holiday Ave.
P.O. Box 2048
Dalton, GA 30722-2048
Ph: 706-278-0232
Fax: 706-278-8835
Internet: <http://www.carpet-rug.com>

CAST IRON SOIL PIPE INSTITUTE (CISPI)
5959 Shallowford Rd., Suite 419
Chattanooga, TN 37421

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Ph: 423-892-0137
Fax: 423-892-0817

CEILINGS & INTERIOR SYSTEMS CONSTRUCTION ASSOCIATION (CISCA)
1500 Lincoln Highway, Suite 202
St. Charles, IL 60174
Ph: 708-584-1919
Fax: 708-584-2003

CHLORINE INSTITUTE (CI)
2001 L St., NW
Washington, DC 20036
Ph: 202-775-2790
Fax: 202-223-7225

COMMERCIAL ITEM DESCRIPTIONS (CID)
Order from:
General Services Administration
Federal Supply Service Bureau
470 E L'Enfant Plaza, S.W.
Washington, DC 20407
Ph: 202-619-8925
Internet: <http://apps.fss.gsa.gov/pub/fedspecs/indexcfm>

COMPRESSED GAS ASSOCIATION (CGA)
1725 Jefferson Davis Highway, Suite 1004
Arlington, VA 22202-4102
Ph: 703-412-0900
Fax: 703-412-0128
e-mail: Customer_Service@cganet.com

CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
933 No. Plum Grove Rd.
Schaumburg, IL 60173-4758
Ph: 847-517-1200
Fax: 847-517-1206
Internet: <http://www.crsi.org>

CONSUMER PRODUCT SAFETY COMMISSION (CPSC)
Washington, DC 20207
Ph: 301-504-0580

CONVEYOR EQUIPMENT MANUFACTURERS ASSOCIATION (CEMA)
9384-D Forestwood Lane
Manassas, VA 22110
Ph: 703-330-7079
Fax: 703-330-7984

COOLING TOWER INSTITUTE (CTI)
530 Wells Fargo Drive
Suite 218
Houston, TX 77090
Ph: 281-583-4087
SECTION 01420 Page 10
Fax: 281-537-1721

COPPER DEVELOPMENT ASSOCIATION (CDA)

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

260 Madison Ave.
New York, NY 10016
Ph: 212-251-7200
Fax: 212-251-7234
E-mail: <http://www.copper.org>

CRANE MANUFACTURERS ASSOCIATION OF AMERICA (CMAA)
8720 Red Oak Blvd, Ste 210
Charlotte, NC 28217
Ph: (704) 522-8644
800-722-6832
FAX: (704) 522-7826

CSA INTERNATIONAL (CSA)
8501 East Pleasant Valley Road
Cleveland, Ohio 44131-5575
Ph: 216-524-4990
Fax: 216-642-3463

DOOR AND ACCESS SYSTEM MANUFACTURERS ASSOCIATION (DASMA)
1300 Sumner Avenue
Cleveland, OH 44115-2851
Ph: 216-241-7333
Fax: 216-241-0105
Internet: <http://www.dasma.com>
e-mail: dasma@taol.com

DOOR AND HARDWARE INSTITUTE (DHI)
14170 Newbrook Dr.
Chantilly, VA 20151-2232
Ph: 703-222-2010
Fax: 703-222-2410
Internet: <http://www.dhi.org>
E-mail: techdept@dhi.org

DUCTILE IRON PIPE RESEARCH ASSOCIATION (DIPRA)
245 Riverchase Parkway East, Suite 0
Birmingham, AL 35244-1856
Ph: 205-402-8700
Fax: 205-402-8730
Internet: <http://www.dipra.org>

EIFS INDUSTRY MEMBERS ASSOCIATION (EIMA)
402 No. 4th St., Suite 102
Yakima, WA 98901-2470
Ph. 509-457-3500
Fax: 509-457-0169

ELECTRONIC INDUSTRIES ALLIANCE (EIA)
2500 Wilson Blvd.
Arlington, VA 22201-3834
Ph: 703-907-7500
Fax: 703-907-7501
Internet: <http://www.eia.org>

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

ENVIRONMENTAL PROTECTION AGENCY (EPA)

Public Information Center

401 M St., SW

Washington, DC 20460

Ph: 800-490-9198

FAX: 202-260-6257

Internet: <http://www.epa.gov>

NOTE: Some documents are available only from:

National Technical Information Services (NTIS)

5285 Port Royal Rd.

Springfield, VA 22161

Ph: 800-553-6847

Fax: 703-321-8547

Internet: <http://www.nraes.org>

EXPANSION JOINT MANUFACTURERS ASSOCIATION (EJMA)

25 No. Broadway

Tarrytown, NY 10591

Ph: 914-332-0040

FLAT GLASS MARKETING ASSOCIATION (FGMA)

White Lakes Professional Bldg.

3310 Harrison St.

Topeka, KS 66611-2279

Ph: 913-266-7013

Fax: 913-266-0272

FLORIDA ADMINISTRATIVE CODE (FAC)

Darby Printing Co.

6215 Purdue Drive

Atlanta, GA 30336

Ph: 1-800-241-5292

Fax: 404-346-3332

STANDARDS (FBC)

FLORIDA DEPARTMENT OF COMMUNITY AFFAIRS BUILDING CODES AND

2555 Shumard Oak Boulevard

Tallahassee, FL 32399-2100

Ph: 805-487-1824

Internet: <http://www.dca.state.fl.us>

FLORIDA STATUTES (FL-STAT)

Law Book Distribution Office

Room LL14, The Capitol

Tallahassee, FL 32399-1400

SECTION 01420 Page 12

Ph: 904-488-2323

FLUID SEALING ASSOCIATION (FSA)

2017 Walnut St

Philadelphia, PA 19103

Ph: 215-569-3650

FM GLOBAL (FM)

1301 Atwood Avenue

P.O. Box 7500

Johnston, RI 02919

Ph: (for publications) 781-255-6681

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Ph: (Toll-Free): 877-364-6726
Fax: 781-255-0181
Internet: <http://www.fmglobal.com>

FORESTRY SUPPLIERS (FSUP)
205 West Rankin St
Jackson, MS 39284-8397
Ph: 800-647-5368
Fax: 800-543-4203
Internet: <http://www.forestry-suppliers.com>

(FCCCHR)
FOUNDATION FOR CROSS-CONNECTION CONTROL AND HYDRAULIC RESEARCH
USC
KAP-200 University Park MC-2531
Los Angeles, CA 90089-2531
Ph: 213-740-2032
Fax: 213-740-8399

GEOLOGICAL SOCIETY OF AMERICA (GSA)
P.O. Box 9140
Boulder, CO 80301
Ph: 800-472-1988
Fax: 303-447-1133

GEOSYNTHETIC RESEARCH INSTITUTE (GRI)
475 Kedron Ave.
Folsom, PA 19033-1208
Ph: 610-522-8440
Fax: 610-522-8441

GLASS ASSOCIATION OF NORTH AMERICA (GANA)
3310 S.W. Harrison St.
Topeka, KS 66611-2279
Ph: 913-266-7013
Fax: 913-266-0272
Internet: <http://www.cssinfo.com/info/gana.html>

GYPSUM ASSOCIATION (GA)
SECTION 01420 Page 13
GYPSUM ASSOCIATION (GA)
810 First St. NE, Suite 510
Washington, DC 20002
Ph: 202-289-5440
Fax: 202-289-3707

HARDWOOD PLYWOOD & VENEER ASSOCIATION (HPVA)
1825 Michael Faraday Dr.
P.O. Box 2789
Reston, VA 22090-2789
Ph: 202-435-2900
Fax: 703-435-2537

HEAT EXCHANGE INSTITUTE (HEI)
1300 Sumner Ave
Cleveland, OH 44115-9830

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Ph: 216-241-7333
Fax: 216-241-0105

H.P. WHITE LABORATORY (HPW)
3114 Scarboro Rd.
Street, MD 21154
Ph: 410-838-6550

HYDRAULIC INSTITUTE (HI)
9 Sylvan Way, Suite 180
Parsippany, NJ 07054-3802
Ph: 888-786-7744 or 973-267-9700
Fax: 973-267-9053

HYDRONICS INSTITUTE DIVISION OF GAMA (HYI)
35 Russo Pl.
P.O. Box 218
Berkeley Heights, NJ 07922-0218
Ph: 908-464-8200
Fax: 908-464-7818
Internet: <http://www.gamanet.org>

IBM CORPORATION (IBM)
Publications
P.O. Box 29570
Raleigh, NC 27626-0570
Ph: 800-879-2755, Option 1
Fax: 800-445-9269
Internet: <http://www.ibm.com/shop/publications/order>

ILLUMINATING ENGINEERING SOCIETY OF NORTH AMERICA (IESNA)
120 Wall St., 17 Floor
New York, NY 10005-4001
Ph: 212-248-5000
Fax: 212-248-5017
Internet: <http://www.iesna.org>

INDUSTRIAL FASTENERS INSTITUTE (IFI)
1717 East 9th St., Suite 1105
Cleveland, OH 44114-2879
Ph: 216-241-1482
Fax: 216-241-5901
Internet: <http://www.industrial-fasteners.org>
E-mail: indfast@aol.com

INSECT SCREENING WEAVERS ASSOCIATION (ISWA)
P.O. Box 1018
Ossining, NY 10562
Ph: 914-962-9052
Fax: 914-923-3031

INSTITUTE OF CLEAN AIR COMPANIES (ICAC)
1660 L St., NW, Suite 1100
Washington, DC 20036-5603
Ph: 202-457-0911
Fax: 202-331-1388

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

E-mail: sjenkins@icac.com
Internet: <http://www.icac.com>

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)
445 Hoes Ln, P. O. Box 1331
Piscataway, NJ 08855-1331
Ph: 732-981-0060 OR 800-701-4333
Fax: 732-981-9667
Internet: <http://www.standards.ieee.org>
E-mail: customer.service@ieee.org

INSTITUTE OF ENVIRONMENTAL SCIENCES AND TECHNOLOGY (IEST)
940 East Northwest Highway
Mount Prospect, IL 60056
Ph: 847-255-1561
Fax: 847-255-1699

INSULATED CABLE ENGINEERS ASSOCIATION (ICEA)
P.O. Box 440
South Yarmouth, MA 02664
Ph: 508-394-4424
Fax: 508-394-1194
Internet: <http://www.electricnet.com/orgs/insucbl.htm>

INTERNATIONAL CODE COUNCIL (ICC)
Headquarters
5203 Leesburg Pike, Suite 600
Falls Church, VA 22041
Ph: 1-888-ICC-SAFE (422-7233)
Fax: 703-379-1546
Internet: <http://www.iccsafe.org>
SouthEast Regional Office
900 Montclair Road
Birmingham, AL 35213-1206
Customer Service 1-800-786-4452
IT Product Support 1-888-ICC-SAFE, x33804
Internet: <http://www.iccsafe.org>

INTERNATIONAL CONFERENCE OF BUILDING OFFICIALS (ICBO)
5360 Workman Mill Rd.
Whittier, CA 90601-2298
Ph: 310-699-0541
Fax: 310-692-3853

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)
P.O. BOX 687
106 STONE STREET
MORRISON, COLORADO 08465
PH: 303-697-8441
FAX: 303-697-8431
INTERNET: <http://www.netaworld.org>

INTERNATIONAL ELECTROTECHNICAL COMMISSION (IEC)
3, rue de Varembe, Case Postale 131
CH-1211 Geneva 20, Switzerland
Ph: 41-22-919-0211

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Fax: 41-22-919-0300
Internet: <http://www.iec.ch>
e-mail: custserv@iec.ch

INTERNATIONAL INSTITUTE OF AMMONIA REFRIGERATION (IIAR)
1200 Nineteenth St., NW, Suite 300
Washington, DC 20036-2912
Ph: 202-857-1110
Fax: 202-223-4579

INTERNATIONAL MUNICIPAL SIGNAL ASSOCIATION (IMSA)
165 East Union St. P.O. Box 539
Newark, NY 14513
Ph: 315-331-2182
Fax: 315-331-8505

INTERNATIONAL ORGANIZATION FOR STANDARDIZATION (ISO))
1, rue de Varembe'
Case Postale 56
CH-1211 Geneve 20
Switzerland
Internet: <http://www.iso.ch>

INTERNATIONAL SLURRY SURFACING ASSOCIATION (ISSA)
1200 Nineteenth St., NW, Suite 300
Washington, DC 20036-2401
SECTION 01420 Page 16
Ph: 202-857-1160
Fax: 202-223-4579
Internet: <http://www.rochester.edu/issa>

INTERNATIONAL TELECOMMUNICATION UNION (ITU)
Order from:
U.S. Dept of Commerce
National Technical Information Service
585 Port Royal Road.
Springfield, VA 22161
Ph: 703-487-4660
FAX: 703-321-8547
For documents not avail from Dept of Commerce:
E-Mail: sales@itu.ch
Fax: 41.22.730.5194

IPI - ASSOCIATION CONNECTING ELECTRONICS INDUSTRIES (IPC)
2215 Sanders Rd.
Northbrook, IL 60062-6135
Ph: 847-509-9700
Fax: 847-509-9798
Internet: <http://www.ipc.org>
e-mail: orderipc@ipc.org

(FORMERLY: IRON & STEEL SOCIETY (ISS))
ASSOCIATION FOR IRON AND STEEL TECHNOLOGY (AIST)
18 Thorn Hill Road
Warrendale, PA 15086-7528

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Ph: 724-776-6040
Fax: 724-776-1880
E-mail: info@aistech.org
Internet: <http://www.aistech.org>

ISA - THE INSTRUMENTATION, SYSTEMS AND AUTOMATION SOCIETY (ISA)
67 Alexander Drive
P.O. Box 12277
Research Triangle Park, NC 27709
Ph: 919-549-8411
Fax: 919-549-8288
e-mail: ISA@isa.org
Internet: <http://www.isa.org>

JOINT INDUSTRIAL COUNCIL (JIC)
Association for Manufacturing Technology
7901 Westpark Dr.
McLean, VA 22102
Ph: 703-893-2900
SECTION 01420 Page 17
Fax: 703-893-1151

KITCHEN CABINET MANUFACTURERS ASSOCIATION (KCMA)
1899 Preston White Dr.
Reston, VA 20191-5435
Ph: 703-264-1690
Fax: 703-620-6530
Internet: <http://www.kcma.org>

INDUSTRY (MSS)
MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS
127 Park St., NE
Vienna, VA 22180-4602
Ph: 703-281-6613
Fax: 703-281-6671
Internet: <http://www.cssinfo.com/info/mss/html>

MAPLE FLOORING MANUFACTURERS ASSOCIATION (MFMA)
60 Revere Dr., Suite 500
Northbrook, IL 60062
Ph: 847-480-9138
Fax: 847-480-9282
e-mail: mfma@maplefloor.com

MARBLE INSTITUTE OF AMERICA (MIA)
33505 State St.
Farmington, MI 48335
Ph: 810-476-5558
Fax: 810-476-1630

MASTER PAINTERS INSTITUTE (MPI)
4090 Graveley Street
Burnaby, BC Canada V5C 3T6
Ph: 888-674-8937
Fax: 888-211-8708
e-mail: info@paintinfo.com

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Internet: <http://www.paintinfo.com/mpi>

METAL BUILDING MANUFACTURERS ASSOCIATION (MBMA)
1300 Sumner Ave.
Cleveland, OH 44115-2851
Ph: 216-241-7333
Fax: 216-241-0105

MIDWEST INSULATION CONTRACTORS ASSOCIATION (MICA)
2017 So. 139th Cir.
Omaha, NE 68144
Ph: 402-342-3463
Fax: 402-330-9702

MIDWEST ROOFING CONTRACTORS ASSOCIATION (MRCA)
4840 Bob Billings Parkway, Suite 1000
Lawrence, Kansas 66094-3862
Ph: 785-843-4888 or 800-497-6722
Fax: 785-843-7555
Internet: General Information: <http://www.mrca.org/home/html/>

MONORAIL MANUFACTURERS ASSOCIATION (MMA)
1326 Freeport Road
Pittsburgh, PA 15238

NACE INTERNATIONAL (NACE)
1440 South Creek Drive
Houston, TX 77084-4906
Ph: 221-228-6200
Fax: 281-228-6300
Internet: <http://www.nace.org>

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)
8 So. Michigan Ave, Suite 100
Chicago, IL 60603
Ph: 312-782-4951
Fax: 312-332-0706
Internet: <http://www.naamm.org>

NATIONAL BOARD OF BOILER AND PRESSURE VESSEL INSPECTORS (NBBPVI)
1055 Crupper Ave.
Columbus, OH 43229-1183
Ph: 614-888-2463
Fax: 614-847-1147
e-mail: orders @ nationalboard.org

NATIONAL CABLE TELCOMMUNICATIONS ASSOCIATION (NCTA)
1724 Massachusetts Ave. NW
Washington, DC 20036-1969
Ph: 202-775-3550
Fax: 202-775-3698

NATIONAL COUNCIL ON RADIATION PROTECTION AND MEASUREMENTS (NCRP)
7910 Woodmont Ave., Suite 800
Bethesda, MD 20814-3095
Ph: 800-229-2652

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Fax: 301-907-8768
NATIONAL DRILLING ASSOCIATION (NDA)
3008 Millwood Avenue
Columbia, SC 29205
Ph: 800-445-8629 or 803-252-5646
Fax: 803-765-0860
Email: info@nda4U.com
Internet: <http://www.nda4U.com>

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)
1300 N. 17th St., Suite 1847
Rosslyn, VA 22209
Ph: 703-841-3200
Fax: 202-841-3300
Internet: <http://www.nema.org>

NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB)
8575 Grovemont Circle
Gaithersburg, MD 20877-4121
Ph: 301-977-3698
Fax: 301-977-9589

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)
One Batterymarch Park
P.O. Box 9101
Quincy, MA 02269-9101
Ph: 800-344-3555
Fax: 800-593-6372
Internet: <http://www.nfpa.org>

NATIONAL FLUID POWER ASSOCIATION (NFLPA)
3333 No. Mayfair Rd.
Milwaukee, WI 53222-3219
Ph: 414-778-3363
Fax: 414-778-3361
Internet: <http://www.nflpa.com>
E-mail: nflpa@nflpa.com

NATIONAL FOREST PRODUCTS ASSOCIATION (NFOPA)
1250 Connecticut Ave., NW, Suite 200
Washington, DC 20036
Ph: 202-463-2766
Fax: 202-463-2791

NATIONAL HARDWOOD LUMBER ASSOCIATION (NHLA)
P.O. Box 34518
SECTION 01420 Page 20
Memphis, TN 38184-0518
Ph: 901-377-1818
Fax: 901-382-6419
e-mail: nhla@natlhardwood.org

(NICET)
NATIONAL INSTITUTE FOR CERTIFICATION IN ENGINEERING TECHNOLOGIES
1420 King Street
Alexandria, VA 22314-2794

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Ph: 888-476-4238

Internet: <http://www.nicet.org>

NATIONAL INSTITUTE FOR OCCUPATIONAL SAFETY AND HEALTH (NIOSH)

Mail Stop C-13

4676 Columbia Parkway

Cincinnati, OH 45226-1998

Ph: 800-356-4676

Internet: <http://www.cdc.gov/niosh/homepage.html>

To order pubs for which a fee is charged, order from:

Superintendent of Documents

Government Printing Office

Washington, DC 20402-9325

Ph: 202-512-1800

Fax: 202-512-2250

NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST)

Department of Commerce

Gaithersburg, MD 20899-0001

Ph: 301-975-4025

Fax: 301-926-1630

Order From:

Superintendent of Documents

U.S. Government Printing Office (GPO)

Washington, DC 20402

Ph: 202-512-1800

Fax: 202-512-2250

or

National Technical Information Services (NTIS)

5285 Port Royal Rd.

Springfield, VA 22161

Ph: 800-553-6847

Fax: 703-321-8547

Internet: <http://www.ntis.gov>

NATIONAL INSTITUTE OF JUSTICE (NIJ)

National Law Enforcement and Corrections Technology Center

277 Research Blvd. - Mailstop 1E

Rockville, MD 20850

Ph: 800-248-2742 or 301-519-5060

Fax: 301-519-5179

Internet: <http://www.nlectc.org>

e-mail: nlectc@aspensys.com

NATIONAL LIME ASSOCIATION (NLA)

200 No. Glebe Rd., Suite 800

Arlington, VA 22203-3728

Ph: 703-243-5463

Fax: 703-243-5489

NATIONAL OAK FLOORING MANUFACTURERS ASSOCIATION (NOFMA)

P.O. Box 3009

Memphis, TN 38173-0009

Ph: 901-526-5016

Fax: 901-526-7022

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

NATIONAL READY-MIXED CONCRETE ASSOCIATION (NRMCA)
900 Spring St.
Silver Spring, MD 20910
Ph: 301-587-1400
Fax: 301-585-4219

NATIONAL ROOFING CONTRACTORS ASSOCIATION (NRCA)
P.O. Box 809261
Chicago, IL 60680-9261
Ph: 800-323-9545
Fax: 708-299-1183

NATIONAL TERRAZZO & MOSAIC ASSOCIATION (NTMA)
3166 DesPlaines Ave., Suite 132
DesPlaines, IL 60018
Ph: 708-635-7744
Fax: 708-635-9127

NORTH AMERICAN INSULATION MANUFACTURERS ASSOCIATION (NAIMA)
44 Canal Center Plaza, Suite 310
Alexandria, VA 22314
Ph: 703-684-0084
Fax: 703-684-0427

NORTHEASTERN LUMBER MANUFACTURERS ASSOCIATION (NELMA)
272 Tuttle Road
Cumberland Center, ME 04021
Ph: 207-829-6901
Fax: 207-829-4293

NATURAL RESOURCE, AGRICULTURE, ENGINEERING SERVICE (NRAES)
Cooperative Extension
152 Riley-Robb Hall
Ithaca, NY 14853-5701
Ph: 607-255-7654
Fax: 607-254-8770
Internet: <http://www.rcwpsun.cas.psu.edu/nraes>
E-mail: nraes@cornell.edu

NSF INTERNATIONAL (NSF)
ATTN: Publications
789 Dixboro Rd.
Ann Arbor, MI 48113-0140
Ph: 734-769-8010
Fax: 734-769-0109
Toll Free: 800-NSF-MARK
Internet: <http://www.nsf.org>

PIPE FABRICATION INSTITUTE (PFI)
3211 Jermantown Rd
Suite 100
Fairfax, VA 22030
Ph: 514-634-3434
Fax: 514-634-9736

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

PLASTIC PIPE AND FITTINGS ASSOCIATION (PPFA)
800 Roosevelt Rd., Bldg C, Suite 20
Glen Ellyn, IL 60137
Ph: 630-858-6540
Fax: 630-790-3095

PLASTICS PIPE INSTITUTE (PPI)
1801 L St. NW, Suite 600K
Washington, D. C. 20006-1301
Ph: 888-314-6774
Fax: 202-293-0048
Internet: <http://www.plasticpipe.org>
Order Publications from:
SPI
P. O. Box 753
Waldorf, MD 20604
Ph: 202-974-5332
Fax: 800-541-0736 or 202-296-7359

PLUMBING AND DRAINAGE INSTITUTE (PDI)
45 Bristol Dr., Suite 101.
South Easton, MA 02375
Ph: 508-230-3516
Fax: 508-230-3529
E-Mail: pdhw@tiac.net

PORCELAIN ENAMEL INSTITUTE (PEI)
4004 Hillsboro Pike, Suite 224B
Nashville, TN 37215
Ph: 615-385-5357
Fax: 615-385-5463
Internet: <http://www.porcelainenamel.com>

PRECAST/PRESTRESSED CONCRETE INSTITUTE (PCI)
175 West Jackson Blvd., Suite 1859
Chicago, IL 60604
SECTION 01420 Page 23
Ph: 312-786-0300
Fax: 312-786-0353
Internet: <http://www.pci.org>
e-mail: info@pci.org

REDWOOD INSPECTION SERVICE (RIS)
591 Redwood Highway, Suite 3100
Mill Valley, CA 94941

RUBBER MANUFACTURERS ASSOCIATION (RMA)
1400 K St., NW
Washington, DC 20005
Ph: 202-682-4800
Fax: 202-682-4854
Order Publications from:
The Mail Room
P. O. Box 3147
Medina, OH 44258

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Ph: 800-325-5098 or 330-723-2987

Fax: 330-725-0576

RURAL ELECTRIFICATION ADMINISTRATION (REA)

Order from:

USDA-REA-ASD

ATTN: Publications

14th and Independence Ave., SW, Room 0180

Washington, DC 20250

Ph: 202-720-8674

SCIENTIFIC APPARATUS MAKERS ASSOCIATION (SAMA)

Order from:

American National Standards Institute (ANSI)

11 West 42nd St.

New York, NY 10036

Ph: 212-642-4900

Fax: 212-302-1286

SCREEN MANUFACTURERS ASSOCIATION (SMA)

850 South Ocean Boulevard

Suite 114

Palm Beach, FL 33480-5535

Ph: 561-533-0991

Fax: 561-533-7466

e-mail: fscottfitzgerald@compuserve.com

SEMICONDUCTOR EQUIPMENT AND MATERIALS INTERNATIONAL (SEMI)

ATTN: Standards Department

805 East Middlefield Road

Mountain View, CA 44043

Ph 415-940-6944

SHEET METAL & AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION
(SMACNA)

4201 Lafayette Center Drive

Chantilly, VA 20151-1209

Ph: 703-803-2980

Fax: 703-803-3732

Internet: <http://www.smacna.org>

SINGLE PLY ROOFING INSTITUTE (SPRI)

200 Reservoir St., Suite 309A

Needham, MA 02194

Ph: 781-444-0242

Fax: 781-444-6111

Internet: <http://www.spri.org>

e-mail: lkspri@aol.com

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

400 Commonwealth Dr.

Warrendale, PA 15096-0001

Ph: 412-776-4841

Fax: 412-776-5760

Internet: <http://www.sae.org>

e-mail: publications @sae.org

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

SOUTHERN CYPRESS MANUFACTURERS ASSOCIATION (SCMA)
400 Penn Center Boulevard, Suite 530
Pittsburgh, PA 15235
Ph: 412-829-0770
Fax: 412-829-0844

SOUTHERN PINE INSPECTION BUREAU (SPIB)
4709 Scenic Highway
Pensacola, FL 32504-9094
Ph: 850-434-2611
Fax: 850-433-5594
e-mail: spib@spib.org

STEEL DECK INSTITUTE (SDI)
P.O. Box 25
Fox River Grove, IL 60021-0025
Ph: 847-462-1930
Fax: 847-462-1940
Internet: <http://www.sdi.org>
e-mail: janet@sdi.org

STEEL DOOR INSTITUTE (SDI)
30200 Detroit Rd.
Cleveland, OH 44145-1967
Ph: 216-899-0010
Fax: 216-892-1404

STEEL JOIST INSTITUTE (SJI)
3127 Tenth Ave., North Ext.
Myrtle Beach, SC 29577-6760
Ph: 803-626-1995
Fax: 803-626-5565

STEEL TANK INSTITUTE (STI)
570 Oakwood Rd.
Lake Zurich, IL 60047
Ph: 847-438-8265
Fax: 847-438-8766
Internet: <http://www.steeltank.com>
e-mail: technic@interaccess.com

STEEL WINDOW INSTITUTE (SWI)
1300 Sumner Ave.
Cleveland, OH 44115-2851
Ph: 216-241-7333
Fax: 216-241-0105

TECHNICAL MANUAL (TM)
Army Adjutant General Publication Center
1655 Woodson Road
Saint Louis, MO 63114

THE SOCIETY FOR PROTECTIVE COATINGS (SSPC)
40 24th Street, 6th Floor
Pittsburgh, PA 15222-4656

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Ph: 412-281-2331
Fax: 412-281-9992
Internet: <http://www.sspc.org>

TILE COUNCIL OF AMERICA (TCA)
P.O. Box 1787
Clemson, SC 29633-1787
Ph: 864-646-8453
FAX: 864-646-2821

TRUSS PLATE INSTITUTE (TPI)
583 D'Onofrio Dr., Suite 200
Madison, WI 53719
Ph: 608-833-5900
Fax: 608-833-4360

TUBULAR EXCHANGE MANUFACTURERS ASSOCIATION (TEMA)
25 N. Broadway
Tarrytown, NY 10591
Ph: 914-332-0040
Fax: 914-332-1541

UNDERWRITERS LABORATORIES (UL)
333 Pfingsten Rd.
Northbrook, IL 60062-2096
Ph: 847-272-8800
Fax: 847-272-8129
Internet: <http://www.ul.com/>
Order from:
Global Engineering Documents
15 Inverness Way East
Englewood, CO 80112-5776
Ph: 800-569-7128
Fax: 303-397-7945
Internet: <http://www.global.ihs.com>
E-mail: global@ihs.com

UNI-BELL PVC PIPE ASSOCIATION (UBPPA)
2655 Villa Creek Dr., Suite 155
Dallas, TX 75234
Ph: 214-243-3902
Fax: 214-243-3907

U.S. AIR FORCE TECHNICAL ORDERS (TO)
Air Force Logistics Command, ATTN: D.A.D.
Wright-Patterson Air Force Base, OH 45433
U.S. ARMY CORPS OF ENGINEERS (USACE)
Order from:
U.S. Army Engineer Waterways Experiment Station
ATTN: Technical Report Distribution Section
Services Branch, TIC
3909 Halls Ferry Rd.
Vicksburg, MS 39180-6199
Ph: 601-634-2571
Fax: 601-634-2506

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

U.S. DEPARTMENT OF AGRICULTURE (USDA)
14TH STREET & INDEPENDENCE AVE. S.W.
WASHINGTON, D.C. 20250
Ph: (202) 720-2791
Publications: 301-344-2340
U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT (HUD)
Order from:
HUD User
P.O. Box 6091
Rockville, MD 20850
SECTION 01420 Page 27
Ph: 800-245-2691
e-mail: Huduser@aspensys.com

U.S. DEPARTMENT OF COMMERCE (DOC)
Order From:
National Technical Information Service
5285 Port Royal Road
Springfield, VA 22161
Ph: 703-605-6000
Fax: 703-605-6900
Internet: <http://www.ntis.gov>

U.S. DEPARTMENT OF DEFENSE (DOD)
Order DOD Documents from:
National Technical Information Service
5285 Port Royal Road
Springfield, VA 22161
Ph: 703-605-6000
FAX: 703-605-6900
Internet: <http://www.ntis.gov>
Order Military Specifications, Standards and Related Publications
from:
Department of Defense Single Stock Point for (DODSSP)
Defense Automation and Production Service (DAPS)
Bldg 4D
700 Robbins AV
Philadelphia, PA 19111-5094
Ph: 215-697-2179
Fax: 215-697-1462
Internet: <http://dodssp.daps.dla.mil>

U.S. DEPARTMENT OF ENERGY (DOE)
Order from:
1000 Independence Avenue Southwest
Washington, D.C. 20585
Ph: 800-363-3732
Internet: <http://www.eren.doe.gov/femp/procurement>

U.S. DEPARTMENT OF STATE (SD)
ATTN: DS/PSP/SEP
SA-6, Room 804
Washington, DC 20522-0602
Ph: 703-875-6537

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

U.S. DEPARTMENT OF TRANSPORTATION (DOT)

400 Seventh St., SW
Washington, DC 20590
Ph: 202-366-4000
Internet: <http://www.dot.gov/index.cfm>
Order from:
U.S. Government Printing Office
Superintendent of Documents
732 North Capitol St., NW
Washington, DC 20401
Ph: 202-512-0000
Internet: <http://www.gpo.gov>

U.S. FEDERAL AVIATION ADMINISTRATION (FAA)

Order for sale documents from:
Superintendent of Documents
P.O. Box 371954
Pittsburgh, PA 15250-7954
PH: 202-512-1800 (order desk)
Internet: <http://www.gpo.gov>
Order free documents from:
Federal Aviation Administration
Dept. of Transportation
Ardmore East Business Center
33410 75th Avenue
Landover, MD 20785
Ph:
FAX: 301-386-5394
Internet: <http://www.faa.gov>

U.S. FEDERAL COMMUNICATIONS COMMISSION (FCC)

445 12th Street SW
Washington, DC 20554
Phone: 888-CALL-FCC
Fax: 202-418-0232
Internet: <http://www.fcc.gov>
E-mail: fccinfo@fcc.gov

U.S. FEDERAL HIGHWAY ADMINISTRATION (FHWA)

400 Seventh St., SW
Washington, DC 20590
Ph: 202-366-0660
<http://www.fhwa.dot.gov/index.html>
Order from:
U.S. Government Printing Office
Superintendent of Documents
732 North Capitol St., NW
Washington, DC 20401
Ph: 202-512-0000
Internet: <http://www.gpo.gov>

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

General Services Administration

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

1800 F Street, NW
Washington, DC 20405
PH: 202-501-0705
Order from:
General Services Administration
Federal Supply Service Bureau
1941 Jefferson Davis Highway
Arlington, VA 22202
PH: 703-605-5400
Internet: <http://www.fss.gsa.gov/pub/fed-specs.cfm>

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)
700 Pennsylvania Avenue, N.W.
Washington, D.C. 20408
Phone: 866-325-7208
Internet: <http://www.archives.gov>
Order documents from:
Superintendent of Documents
U.S. Government Printing Office
732 North Capitol Street, NW
Washington, DC 20401
Mailstop: SDE
Ph: 866-512-1800 or 202-512-1800
Fax: 202-512-2250
Internet: <http://www.gpo.gov>
E-mail: gpoaccess@gpo.gov

U.S. WATER ENVIRONMENT FEDERATION (WEF)
601 Wythe St.
Alexandria, VA 22314-1994
Ph: 703-684-2400
Fax: 703-684-2492
Internet: <http://www.wef.org>

U.S. WATER QUALITY ASSOCIATION (WQA)
4151 Naperville Rd.
Lisle, IL 60532
Ph: 630-505-0160
Fax: 630-505-9637

WEST COAST LUMBER INSPECTION BUREAU (WCLIB)
P.O. Box 23145
Portland, OR 97281
Ph: 503-639-0651
Fax: 503-684-8928

WESTERN WOOD PRESERVERS INSTITUTE (WWPI)
7017 N.E. Highway 99 # 108
Vancouver, WA 98666
Ph: 360-693-9958
Fax: 360-693-9967

WESTERN WOOD PRODUCTS ASSOCIATION (WWPA)
Yeon Bldg.
522 SW 5th Ave.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

Portland, OR 97204-2122
Ph: 503-224-3930
Fax: 503-224-3934

WINDOWS AND DOOR MANUFACTURERS ASSOCIATION (WDMA)
1400 East Touhy Ave., Suite G-54
Des Plaines, IL 60018
Ph: 847-299-5200 or 800-223-2301
Fax: 708-299-1286

WOOD MOULDING AND MILLWORK PRODUCERS ASSOCIATION (WMMPA)
507 First Street
Woodland, CA 95695
Ph: 916-661-9591
Fax: 916-661-9586

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01420

SECTION 01500 - TEMPORARY FACILITIES AND CONTROLS -015000

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes requirements for temporary facilities and controls, including temporary utilities, support facilities, and security and protection facilities. Coordinate all temporary, security, and support facilities and use with Project Manager prior to start of any work.
- B. Temporary utilities include, but are not limited to, the following:
 - 1. Sewers and drainage.
 - 2. Water service and distribution.
 - 3. Sanitary facilities.
 - 4. Heating and cooling facilities.
 - 5. Ventilation.
 - 6. Electric power service.
 - 7. Lighting.
 - 8. Telephone service.
- C. Support facilities include, but are not limited to, the following:
 - 1. Dewatering facilities and drains.
 - 2. Project identification and temporary signs.
 - 3. Waste disposal facilities.
 - 4. Field offices.
 - 5. Storage and fabrication sheds.
 - 6. Lifts and hoists.
 - 7. Temporary stairs.
 - 8. Construction aids and miscellaneous services and facilities.
 - 9. Cranes, scaffolding, and support structures.
- D. Security and protection facilities include, but are not limited to, the following:
 - 1. Environmental protection.
 - 2. Stormwater control.
 - 3. Pest control.
 - 4. Site enclosure fence.
 - 5. Security enclosure and lockup.
 - 6. Barricades, warning signs, and lights.
 - 7. Temporary enclosures.

8. Fire protection.

E. Related Sections include the following:

1. Division 1 Section "Submittal Procedures" for procedures for submitting copies of implementation and termination schedule and utility reports.
2. Division 1 Section "Execution Requirements" for progress cleaning requirements.
3. Divisions 2 through 16 for temporary heat, ventilation, and humidity requirements for products in those Sections.

1.3 USE CHARGES

- A. Water Service: Use water from Owner's existing water system without metering and without payment of use charges.
- B. Electric Power Service: Use electric power from Owner's existing system without metering and without payment of use charges.

1.4 QUALITY ASSURANCE

- A. Standards: Comply with ANSI A10.6, NECA's "Temporary Electrical Facilities," and NFPA 241.
 1. Trade Jurisdictions: Assigned responsibilities for installation and operation of temporary utilities are not intended to interfere with trade regulations and union jurisdictions.
 2. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.

1.5 PROJECT CONDITIONS

- A. Conditions of Use: The following conditions apply to use of temporary services and facilities by all parties engaged in the Work:
 1. Keep temporary services and facilities clean and neat.
 2. Relocate temporary services and facilities as required by progress of the Work.
 3. Coordinate use of the facilities with the Project Manager prior to the start of the project work.

PART 2 - PRODUCTS

2.1 MATERIALS

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- A. General: Provide new materials. Undamaged, previously used materials in serviceable condition may be used if approved by Architect. Provide materials suitable for use intended.
- B. Portable Chain-Link Fencing: Minimum 2-inch (50-mm) 9-gage, galvanized steel, chain-link fabric fencing; minimum 6 feet (1.8 m) high with galvanized steel pipe posts; minimum 2-3/8-inch- (60-mm-) OD line posts and 2-7/8-inch- (73-mm-) OD corner and pull posts, with 1-5/8-inch- (42-mm-) OD top and bottom rails. Provide [concrete] [galvanized steel] bases for supporting posts.
- C. Paint: Comply with requirements in Division 9 Section "Painting."
- D. Tarpaulins: Fire-resistive labeled with flame-spread rating of 15 or less.
- E. Water: Potable.

2.2 EQUIPMENT

- A. General: Provide equipment suitable for use intended.
- B. Field Offices: Prefabricated with lockable entrances, operable windows, and serviceable finishes; heated and air conditioned; on foundations adequate for normal loading.
- C. Fire Extinguishers: Hand carried, portable, UL rated. Provide class and extinguishing agent as indicated or a combination of extinguishers of NFPA-recommended classes for exposures.
 - 1. Comply with NFPA 10 and NFPA 241 for classification, extinguishing agent, and size required by location and class of fire exposure.
- D. Self-Contained Toilet Units: Single-occupant units of chemical, aerated recirculation, or combustion type; vented; fully enclosed with a glass-fiber-reinforced polyester shell or similar nonabsorbent material.
- E. Heating Equipment: Unless Owner authorizes use of permanent heating system, provide vented, self-contained, liquid-propane-gas or fuel-oil heaters with individual space thermostatic control.
 - 1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
 - 2. Heating Units: Listed and labeled, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use for type of fuel being consumed.
- F. Electrical Outlets: Properly configured, NEMA-polarized outlets to prevent insertion of 110- to 120-V plugs into higher-voltage outlets; equipped with ground-fault circuit interrupters, reset button, and pilot light.
- G. Power Distribution System Circuits: Where permitted and overhead and exposed for surveillance, wiring circuits, not exceeding 125-V ac, 20-A rating, and lighting circuits may be nonmetallic sheathed cable.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required.
- B. Provide each facility ready for use when needed to avoid delay. Maintain and modify as required. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.2 TEMPORARY UTILITY INSTALLATION

- A. Sewers and Drainage:
 - 1. Filter out excessive soil, construction debris, chemicals, oils, and similar contaminants that might clog sewers or pollute waterways before discharge.
 - 2. Provide temporary filter beds, settlement tanks, separators, and similar devices to purify effluent to levels acceptable to authorities having jurisdiction.
- B. Water Service: Use of Owner's existing water service facilities will be permitted, as long as facilities are cleaned and maintained in a condition acceptable to Owner. At Substantial Completion, restore these facilities to condition existing before initial use.
 - 1. Provide rubber hoses as necessary to serve Project site.
- C. Sanitary Facilities: Provide temporary toilets. Comply with regulations and health codes for type, number, location, operation, and maintenance of fixtures and facilities.
 - 1. Disposable Supplies: Provide toilet tissue and similar disposable materials for each facility. Maintain adequate supply. Provide covered waste containers for disposal of used material.
 - 2. Toilets: Install self-contained toilet units. Shield toilets to ensure privacy.
- D. Heating and Cooling: Provide temporary heating and cooling required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment from that specified that will not have a harmful effect on completed installations or elements being installed.
- E. Ventilation and Humidity Control: Provide temporary ventilation required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of high humidity. Select equipment from that specified that will not have a harmful effect on completed installations or elements being installed. Coordinate ventilation requirements to produce ambient condition required and minimize energy consumption.
- F. Electric Power Service: Provide weatherproof, grounded electric power service and distribution system of sufficient size, capacity, and power characteristics during con-

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

struction period. Include transformers, overload-protected disconnecting means, automatic ground-fault interrupters, and main distribution switchgear.

- G. Electric Power Service: Use of Owner's existing electric power service will be permitted, as long as equipment is maintained in a condition acceptable to Owner.
- H. Electric Distribution: Provide receptacle outlets adequate for connection of power tools and equipment.
 - 1. Provide waterproof connectors to connect separate lengths of electrical power cords if single lengths will not reach areas where construction activities are in progress. Do not exceed safe length-voltage ratio.
 - 2. Provide warning signs at power outlets other than 110 to 120 V.
- I. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations and traffic conditions.
 - 1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.
- J. Telephone Service: Provide temporary telephone service throughout construction period for common-use facilities used by all personnel engaged in construction activities. Install separate telephone line for each field office and first-aid station.
 - 1. Provide additional telephone lines for the following:
 - a. In field office with more than two occupants, install a telephone for each additional occupant or pair of occupants.
 - b. Provide a dedicated telephone line for each facsimile machine and computer with modem in each field office.
 - c. In Architect's field office provide a dedicated telephone line for telephone, facsimile machine and computer with modem.
 - 2. At each telephone, post a list of important telephone numbers.
 - a. Police and fire departments.
 - b. Ambulance service.
 - c. Contractor's home office.
 - d. Architect's office.
 - e. Engineers' offices.
 - f. Owner's office.
 - g. Principal subcontractors' field and home offices.
 - 3. Provide an answering machine or voice-mail service on superintendent's telephone.

3.3 SUPPORT FACILITIES INSTALLATION

- A. General: Comply with the following:

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

1. Locate field offices, storage sheds, sanitary facilities, and other temporary construction and support facilities for easy access.
 2. Provide incombustible construction for offices, shops, and sheds located within construction area or within **30 feet (9 m)** of building lines. Comply with NFPA 241.
 3. Maintain support facilities until near Substantial Completion. Remove before Substantial Completion. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.
- B. Dewatering Facilities and Drains: Maintain Project site, excavations, and construction free of water.
1. Dispose of rainwater in a lawful manner that will not result in flooding Project or adjoining property nor endanger permanent Work or temporary facilities.
 2. Remove snow and ice as required to minimize accumulations.
- C. Project Identification and Temporary Signs: Prepare Project identification and other signs in sizes indicated. Install signs where indicated to inform public and persons seeking entrance to Project. Do not permit installation of unauthorized signs.
1. Engage an experienced sign painter to apply graphics for Project identification signs. Comply with details indicated.
 2. Prepare temporary signs to provide directional information to construction personnel and visitors.
 3. Construct signs of exterior-type Grade B-B high-density concrete form overlay plywood in sizes and thicknesses indicated. Support on posts or framing of preservative-treated wood or steel.
 4. Paint sign panel and applied graphics with exterior-grade alkyd gloss enamel over exterior primer.
- D. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Containerize and clearly label hazardous, dangerous, or unsanitary waste materials separately from other waste. Comply with Division 1 Section "Execution Requirements" for progress cleaning requirements.
1. If required by authorities having jurisdiction, provide separate containers, clearly labeled, for each type of waste material to be deposited.
- E. Storage and Fabrication Sheds: Provide sheds sized, furnished, and equipped to accommodate materials and equipment involved, including temporary utility services. Sheds may be open shelters or fully enclosed spaces within building or elsewhere on-site.
1. Construct framing, sheathing, and siding using fire-retardant-treated lumber and plywood.
 2. Paint exposed lumber and plywood with exterior-grade acrylic-latex emulsion over exterior primer.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- F. Lifts and Hoists: Provide facilities for hoisting materials and personnel. Truck cranes and similar devices used for hoisting materials are considered "tools and equipment" and not temporary facilities.
- G. Existing Stair Usage: Use of Owner's existing stairs will be permitted, as long as stairs are cleaned and maintained in a condition acceptable to Owner. At Substantial Completion, restore stairs to condition existing before initial use.
 - 1. Provide protective coverings, barriers, devices, signs, or other procedures to protect stairs and to maintain means of egress. If, despite such protection, stairs become damaged, restore damaged areas so no evidence remains of correction work.

3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction in ways and by methods that comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects. Avoid using tools and equipment that produce harmful noise. Restrict use of noisemaking tools and equipment to hours that will minimize complaints from persons or firms near Project site.
 - 1. Erosion Control: Provide synthetic thermoplastic fibers, woven or nonwoven, 4 oz/sq. yd., breaking load in either machine or cross-machine direction, having capability of passing ground water without transporting soil placed around the fabric. Place filter fabric fence around the site.
- B. Stormwater Control: Provide earthen embankments and similar barriers in and around excavations and subgrade construction, sufficient to prevent flooding by runoff of stormwater from heavy rains.
- C. Site Enclosure Fence: Before construction operations begin, install portable chain-link enclosure fence with lockable entrance gates. Locate where indicated, or enclose entire Project site or portion determined sufficient to accommodate construction operations. Install in a manner that will prevent people, dogs, and other animals from easily entering site except by entrance gates.
 - 1. Provide gates in sizes and at locations necessary to accommodate delivery vehicles and other construction operations.
- D. Barricades, Warning Signs, and Lights: Comply with standards and code requirements for erecting structurally adequate barricades. Paint with appropriate colors, graphics, and warning signs to inform personnel and public of possible hazard. Where appropriate and needed, provide lighting, including flashing red or amber lights.
 - 1. For safety barriers, sidewalk bridges, and similar uses, provide minimum 5/8-inch- (16-mm-) thick exterior plywood.
- E. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities. Provide temporary weathertight enclosure for building exterior.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

1. Where heating or cooling is needed and permanent enclosure is not complete, provide insulated temporary enclosures. Coordinate enclosure with ventilating and material drying or curing requirements to avoid dangerous conditions and effects.
 2. Vertical Openings: Close openings of **25 sq. ft. (2.3 sq. m)** or less with plywood or similar materials.
 3. Horizontal Openings: Close openings in floor or roof decks and horizontal surfaces with load-bearing, wood-framed construction.
 4. Install tarpaulins securely using fire-retardant-treated wood framing and other materials.
 5. Where temporary wood or plywood enclosure exceeds **100 sq. ft. (9.2 sq. m)** in area, use fire-retardant-treated material for framing and main sheathing.
- F. Temporary Fire Protection: Until fire-protection needs are supplied by permanent facilities, install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241.
1. Provide fire extinguishers, installed on walls on mounting brackets, visible and accessible from space being served, with sign mounted above.
 - a. Field Offices: Class A stored-pressure water-type extinguishers.
 - b. Other Locations: Class ABC dry-chemical extinguishers or a combination of extinguishers of NFPA-recommended classes for exposures.
 - c. Locate fire extinguishers where convenient and effective for their intended purpose; provide not less than one extinguisher on each floor at or near each usable stairwell.
 2. Store combustible materials in containers in fire-safe locations.
 3. Maintain unobstructed access to fire extinguishers, fire hydrants, temporary fire-protection facilities, stairways, and other access routes for firefighting. Prohibit smoking in hazardous fire-exposure areas.
 4. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition.
 5. Develop and supervise an overall fire-prevention and first-aid fire-protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.

3.5 OPERATION, TERMINATION, AND REMOVAL

- A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.
- B. Maintenance: Maintain facilities in good operating condition until removal. Protect from damage caused by freezing temperatures and similar elements.
 1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

2. Prevent water-filled piping from freezing. Maintain markers for underground lines. Protect from damage during excavation operations.
- C. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
1. Materials and facilities that constitute temporary facilities are the property of Contractor. Owner reserves right to take possession of Project identification signs.
 2. At Substantial Completion, clean and renovate permanent facilities used during construction period. Comply with final cleaning requirements in Division 1 Section "Closeout Procedures."

END OF SECTION 01500

SECTION 01600 - PRODUCT REQUIREMENTS -016000

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following administrative and procedural requirements: selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; product substitutions; and comparable products.
- B. Related Sections include the following:
 - 1. Division 1 Section "References" for applicable industry standards for products specified.
 - 2. Division 1 Section "Closeout Procedures" for submitting warranties for contract closeout.
 - 3. Divisions 2 through 16 Sections for specific requirements for warranties on products and installations specified to be warranted.

1.3 DEFINITIONS

- A. Products: Items purchased for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
 - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation, shown or listed in manufacturer's published product literature, that is current as of date of the Contract Documents.
 - 2. New Products: Items that have not previously been incorporated into another project or facility, except that products consisting of recycled-content materials are allowed, unless explicitly stated otherwise. Products salvaged or recycled from other projects are not considered new products.
 - 3. Comparable Product: Product that is demonstrated and approved through submittal process, or where indicated as a product substitution, to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- C. Basis-of-Design Product Specification: Where a specific manufacturer's product is named and accompanied by the words "basis of design," including make or model number or other designation, to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics for purposes of evaluating comparable products of other named manufacturers.
- D. Manufacturer's Warranty: Preprinted written warranty published by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
- E. Special Warranty: Written warranty required by or incorporated into the Contract Documents, either to extend time limit provided by manufacturer's warranty or to provide more rights for Owner.

1.4 SUBMITTALS

- A. Product List: Submit a list, in tabular form, showing specified products. Include generic names of products required. Include manufacturer's name and proprietary product names for each product.
 - 1. Coordinate product list with Contractor's Construction Schedule and the Submittals Schedule.
 - 2. Form: Tabulate information for each product under the following column headings:
 - a. Specification Section number and title.
 - b. Generic name used in the Contract Documents.
 - c. Proprietary name, model number, and similar designations.
 - d. Manufacturer's name and address.
 - e. Supplier's name and address.
 - f. Installer's name and address.
 - g. Projected delivery date or time span of delivery period.
 - h. Identification of items that require early submittal approval for scheduled delivery date.
 - 3. Completed List: Within 30 days after date of commencement of the Work, submit 3 copies of completed product list. Include a written explanation for omissions of data and for variations from Contract requirements.
 - 4. Engineer's Action: Engineer will respond in writing to Contractor within 15 days of receipt of completed product list. Engineer's response will include a list of unacceptable product selections and a brief explanation of reasons for this action. Engineer's response, or lack of response, does not constitute a waiver of requirement that products comply with the Contract Documents.
- B. Substitution Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Substitution Request Form: Use CSI Form 13.1A.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
 - a. Statement indicating why specified material or product cannot be provided.
 - b. VOC content, recycled content and additional sustainable product requirements specified.
 - c. Coordination information, including a list of changes or modifications needed to other parts of the Work and to construction performed by Owner and separate contractors, that will be necessary to accommodate proposed substitution.
 - d. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
 - e. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
 - f. Samples, where applicable or requested.
 - g. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners.
 - h. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
 - i. Research/evaluation reports evidencing compliance with building code in effect for Project, from a model code organization acceptable to authorities having jurisdiction.
 - j. Detailed comparison of Contractor's Construction Schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating lack of availability or delays in delivery.
 - k. Cost information, including a proposal of change, if any, in the Contract Sum.
 - l. Contractor's certification that proposed substitution complies with requirements in the Contract Documents and is appropriate for applications indicated.
 - m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
 - n. If the substitution requires additional or changes in electrical, mechanical, structural, plumbing, fire protection, and or architectural elements, the contractor is responsible for all modifications at their cost.

3. Engineer's Action: If necessary, Engineer will request additional information or documentation for evaluation within one week of receipt of a request for substitution. Engineer will notify Contractor through Construction Manager of acceptance or rejection of proposed substitution within 15 days of receipt of request, or 7 days of receipt of additional information or documentation, whichever is later.
 - a. Form of Acceptance: Change Order.
 - b. Use product specified if Architect cannot make a decision on use of a proposed substitution within time allocated.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- C. Basis-of-Design Product Specification Submittal: Comply with requirements in Division 1 Section "Submittal Procedures." Show compliance with requirements.

1.5 QUALITY ASSURANCE

- A. Provide products with energy efficient designs and with materials complying with environmental protection considerations.
- B. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, product selected shall be compatible with products previously selected, even if previously selected products were also options. Comparable or equal products shall be evaluated as substitutions.

1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft. Comply with manufacturer's written instructions.
 - 1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
 - 2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
 - 3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
 - 4. Inspect products on delivery to ensure compliance with the Contract Documents and to ensure that products are undamaged and properly protected.
 - 5. Store products to allow for inspection and measurement of quantity or counting of units.
 - 6. Store materials in a manner that will not endanger Project structure.
 - 7. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
 - 8. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
 - 9. Protect stored products from damage.
- B. Storage: Provide a secure location and enclosure at Project site for storage of materials and equipment by Owner's construction forces. Coordinate location with Owner.

1.7 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution. Submit a draft for approval before final execution.
 - 1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
 - 2. Specified Form: Forms are included with the Specifications. Prepare a written document using appropriate form properly executed.
 - 3. Refer to Divisions 2 through 16 Sections for specific content requirements and particular requirements for submitting special warranties.
- C. Submittal Time: Comply with requirements in Division 1 Section "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT OPTIONS

- A. General Product Requirements: Provide products that comply with the Contract Documents, that are undamaged, and unless otherwise indicated, that are new at time of installation.
 - 1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
 - 2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
 - 3. Owner reserves the right to limit selection to products with warranties not in conflict with requirements of the Contract Documents.
 - 4. Where products are accompanied by the term "as selected," Architect will make selection.
 - 5. Where products are accompanied by the term "match sample," sample to be matched is Architect's.
 - 6. Descriptive, performance, and reference standard requirements in the Specifications establish "salient characteristics" of products.
 - 7. Or Equal: Where products are specified by name and accompanied by the term "or equal" or "or approved equal" or "or approved," comply with provisions in "Comparable Products" Article to obtain approval for use of an unnamed product.
- B. Product Selection Procedures: Procedures for product selection include the following:
 - 1. Product: Where Specification paragraphs or subparagraphs titled "Product" name a single product and manufacturer, provide the product named.
 - a. Substitutions may be considered, unless otherwise indicated.
 - 2. Manufacturer/Source: Where Specification paragraphs or subparagraphs titled "Manufacturer" or "Source" name single manufacturers or sources, provide a product by the manufacturer or from the source named that complies with requirements.

- a. Substitutions may be considered, unless otherwise indicated.
3. Products: Where Specification paragraphs or subparagraphs titled "Products" introduce a list of names of both products and manufacturers, provide one of the products listed that complies with requirements.
 - a. Substitutions may be considered, unless otherwise indicated.
4. Manufacturers: Where Specification paragraphs or subparagraphs titled "Manufacturers" introduce a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements.
 - a. Substitutions may be considered, unless otherwise indicated.
5. Basis-of-Design Products: Where Specification paragraphs or subparagraphs titled "Basis-of-Design Products" are included and also introduce or refer to a list of manufacturers' names, provide either the specified product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with provisions in "Comparable Products" Article to obtain approval for use of an unnamed product.
 - a. Substitutions may be considered, unless otherwise indicated.
6. Visual Matching Specification: Where Specifications require matching an established Sample, select a product (and manufacturer) that complies with requirements and matches Architect's sample. Architect's decision will be final on whether a proposed product matches satisfactorily.
 - a. If no product available within specified category matches satisfactorily and complies with other specified requirements, comply with provisions of the Contract Documents on "substitutions" for selection of a matching product.
7. Visual Selection Specification: Where Specifications include the phrase "as selected from manufacturer's colors, patterns, textures" or a similar phrase, select a product (and manufacturer) that complies with other specified requirements.
 - a. Standard Range: Where Specifications include the phrase "standard range of colors, patterns, textures" or similar phrase, Architect will select color, pattern, or texture from manufacturer's product line that does not include premium items.
 - b. Full Range: Where Specifications include the phrase "full range of colors, patterns, textures" or similar phrase, Architect will select color, pattern, or texture from manufacturer's product line that includes both standard and premium items.
8. Allowances: Refer to individual Specification Sections and "Allowance" provisions in Division 1 for allowances that control product selection and for procedures required for processing such selections.

2.2 PRODUCT SUBSTITUTIONS

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- A. Timing: Engineer will consider requests for substitution if received within 30 days after commencement of the Work. Requests received after that time may be considered or rejected at discretion of Engineer.
- B. Conditions: Engineer will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Engineer will return requests without action, except to record noncompliance with these requirements:
 - 1. Requested substitution offers Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Owner must assume. Owner's additional responsibilities may include compensation to Engineer for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.
 - 2. Requested substitution does not require extensive revisions to the Contract Documents.
 - 3. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - 4. Substitution request is fully documented and properly submitted.
 - 5. Requested substitution will not adversely affect Contractor's Construction Schedule.
 - 6. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - 7. Requested substitution is compatible with other portions of the Work.
 - 8. Requested substitution has been coordinated with other portions of the Work.
 - 9. Requested substitution provides specified warranty.
 - 10. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

2.3 COMPARABLE PRODUCTS

- A. Where products or manufacturers are specified by name, submit the following, in addition to other required submittals, to obtain approval of an unnamed product:
 - 1. Evidence that the proposed product does not require extensive revisions to the Contract Documents, that it is consistent with the Contract Documents and will produce the indicated results, and that it is compatible with other portions of the Work.
 - 2. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant qualities include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
 - 3. Evidence that proposed product provides specified warranty.
 - 4. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
 - 5. Samples, if requested.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

PART 3 - EXECUTION (Not Used)

END OF SECTION 01600

SECTION 01731 - CUTTING AND PATCHING -017329

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes procedural requirements for cutting and patching.
- B. Related Sections include the following:
 - 1. Divisions 2 through 16 Sections for specific requirements and limitations applicable to cutting and patching individual parts of the Work.
 - a. Requirements in this Section apply to mechanical and electrical installations. Refer to Divisions 15 and 16 Sections for other requirements and limitations applicable to cutting and patching mechanical and electrical installations.

1.3 DEFINITIONS

- A. Cutting: Removal of existing construction necessary to permit installation or performance of other Work.
- B. Patching: Fitting and repair work required to restore surfaces to original conditions after installation of other Work.

1.4 SUBMITTALS

- A. Cutting and Patching Proposal: Submit a proposal describing procedures at least 10 days before the time cutting and patching will be performed, requesting approval to proceed. Include the following information:
 - 1. Extent: Describe cutting and patching, show how they will be performed, and indicate why they cannot be avoided.
 - 2. Changes to Existing Construction: Describe anticipated results. Include changes to structural elements and operating components as well as changes in building's appearance and other significant visual elements.
 - 3. Products: List products to be used and firms or entities that will perform the Work.
 - 4. Dates: Indicate when cutting and patching will be performed.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

5. Utilities: List utilities that cutting and patching procedures will disturb or affect. List utilities that will be relocated and those that will be temporarily out of service. Indicate how long service will be disrupted.
6. Structural Elements: Where cutting and patching involve adding reinforcement to structural elements, submit details and engineering calculations showing integration of reinforcement with original structure.
7. Architect's Approval: Obtain approval of cutting and patching proposal before cutting and patching. Approval does not waive right to later require removal and replacement of unsatisfactory work.

1.5 QUALITY ASSURANCE

- A. Structural Elements: Do not cut and patch structural elements in a manner that could change their load-carrying capacity or load-deflection ratio.
- B. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety.
- C. Miscellaneous Elements: Do not cut and patch the following elements or related components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety.
- D. Visual Requirements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch construction exposed on the exterior or in occupied spaces in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.
 1. If possible, retain original Installer or fabricator to cut and patch exposed Work listed below. If it is impossible to engage original Installer or fabricator, engage another recognized, experienced, and specialized firm.
- E. Cutting and Patching Conference: Before proceeding, meet at Project site with parties involved in cutting and patching, including mechanical and electrical trades. Review areas of potential interference and conflict. Coordinate procedures and resolve potential conflicts before proceeding.

1.6 WARRANTY

- A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during cutting and patching operations, by methods and with materials so as not to void existing warranties.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections of these Specifications.
- B. Existing Materials: Use materials identical to existing materials. For exposed surfaces, use materials that visually match existing adjacent surfaces to the fullest extent possible.
 - 1. If identical materials are unavailable or cannot be used, use materials that, when installed, will match the visual and functional performance of existing materials.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine surfaces to be cut and patched and conditions under which cutting and patching are to be performed.
 - 1. Compatibility: Before patching, verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
 - 2. Proceed with installation only after unsafe or unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Temporary Support: Provide temporary support of Work to be cut.
- B. Protection: Protect existing construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- C. Adjoining Areas: Avoid interference with use of adjoining areas or interruption of free passage to adjoining areas.
- D. Existing Services: Where existing services are required to be removed, relocated, or abandoned, bypass such services before cutting to minimize interruption of services to occupied areas.

3.3 PERFORMANCE

- A. General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
 - 1. Cut existing construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- B. Cutting: Cut existing construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.
1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots as small as possible, neatly to size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
 2. Existing Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
 3. Concrete: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
 4. Excavating and Backfilling: Comply with requirements in applicable Division 2 Sections where required by cutting and patching operations.
 5. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
 6. Proceed with patching after construction operations requiring cutting are complete.
- C. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other Work. Patch with durable seams that are as invisible as possible. Provide materials and comply with installation requirements specified in other Sections of these Specifications.
1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate integrity of installation.
 2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will eliminate evidence of patching and refinishing.
 3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance. Remove existing floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.
 - a. Where patching occurs in a painted surface, apply primer and intermediate paint coats over the patch and apply final paint coat over entire unbroken surface containing the patch. Provide additional coats until patch blends with adjacent surfaces.
 4. Ceilings: Patch, repair, or rehang existing ceilings as necessary to provide an even-plane surface of uniform appearance.
 5. Exterior Building Enclosure: Patch components in a manner that restores enclosure to a weathertight condition.

END OF SECTION 01731

SECTION 01732 - SELECTIVE DEMOLITION - 024313

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:

1. Demolition and removal of selected portions of a building or structure.
2. Repair procedures for selective demolition operations.
3. Coordinate all work with the Project Manager prior to start of work. The facility is occupied at all times. Weekend and nite work may be required to establish areas of work due to noise and dirt generation in the spaces. Area isolation and temporary facilities shall be required to prevent migration of any dust or dirt moving into the computer room areas in operation. Traffic control may be required due to access to the site by Owner employees. .

- B. Related Sections include the following:

1. Division 1 Section "Summary" for use of the premises and phasing requirements.
2. Division 1 Section "Work Restrictions" for restrictions on use of the premises due to Owner or tenant occupancy..
3. Division 1 Section "Temporary Facilities and Controls" for temporary construction and environmental-protection measures for selective demolition operations.
4. Division 1 Section "Cutting and Patching" for cutting and patching procedures for selective demolition operations.
5. Division 15 Sections for demolishing, cutting, patching, or relocating mechanical items.
6. Division 16 Sections for demolishing, cutting, patching, or relocating electrical items.

1.3 DEFINITIONS

- A. Remove: Detach items from existing construction and legally dispose of them off-site, unless indicated to be removed and salvaged or removed and reinstalled.
- B. Remove and Salvage: Detach items from existing construction and deliver them to Owner ready for reuse, if required.
- C. Remove and Reinstall: Detach items from existing construction, prepare them for reuse, and reinstall them where indicated.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- D. Existing to Remain: Existing items of construction that are not to be removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and re-installed.

1.4 MATERIALS OWNERSHIP

- A. Except for items or materials indicated to be reused, salvaged, reinstalled, or otherwise indicated to remain Owner's property, demolished materials shall become Contractor's property and shall be removed from Project site.
- B. Historic items, relics, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques and tablets, antiques, and other items of interest or value to Owner that may be encountered during selective demolition remain Owner's property. Carefully remove and salvage each item or object in a manner to prevent damage and deliver promptly to Owner.
 - 1. Coordinate with Owner's Project Manager, who will establish special procedures for removal and salvage.

1.5 SUBMITTALS

- A. Qualification Data: For firms and persons specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
- B. Proposed Dust-Control and Noise-Control Measures: Submit statement or drawing that indicates the measures proposed for use, proposed locations, and proposed time frame for their operation. Identify options if proposed measures are later determined to be inadequate.
- C. Schedule of Selective Demolition Activities: Indicate the following:
 - 1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity. Ensure Owner's on-site operations are uninterrupted.
 - 2. Interruption of utility services.
 - 3. Coordination for shutoff, capping, and continuation of utility services.
 - 4. Use of elevator and stairs.
 - 5. Locations of temporary partitions and means of egress.
 - 6. Coordination of Owner's continuing occupancy of portions of existing building and of Owner's partial occupancy of completed Work.
- D. Inventory: After selective demolition is complete, submit a list of items that have been removed and salvaged.
- E. Predemolition Photographs or Videotape: Show existing conditions of adjoining construction and site improvements, including finish surfaces, that might be misconstrued as damage caused by selective demolition operations. Submit before Work begins.

- F. Landfill Records: Indicate receipt and acceptance of hazardous wastes by a landfill facility licensed to accept hazardous wastes. Maintain weight tickets from all solid waste disposal sites (C&D landfills and recycling yards) as well as for hazardous waste disposal slips.

1.6 QUALITY ASSURANCE

- A. Demolition Firm Qualifications: An experienced firm that has specialized in demolition work similar in material and extent to that indicated for this Project.
- B. Professional Engineer Qualifications: Comply with Division 1 Section "Quality Requirements."
- C. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- D. Standards: Comply with ANSI A10.6 and NFPA 241.
- E. Predemolition Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Management and Coordination."
- F. Predemolition Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Management and Coordination." Review methods and procedures related to selective demolition including, but not limited to, the following:
 - 1. Inspect and discuss condition of construction to be selectively demolished.
 - 2. Review structural load limitations of existing structure.
 - 3. Review and finalize selective demolition schedule and verify availability of materials, demolition personnel, equipment, and facilities needed to make progress and avoid delays.
 - 4. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.

1.7 PROJECT CONDITIONS

- A. Owner will occupy portions of building immediately adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted. Provide not less than 72 hours' notice to Owner of activities that will affect Owner's operations.
- B. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities.
 - 1. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from authorities having jurisdiction.
- C. Owner assumes no responsibility for condition of areas to be selectively demolished.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

1. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.
- D. Hazardous Materials: It is not expected that hazardous materials will be encountered in the Work.
1. Hazardous materials will be removed by Owner before start of the Work.
 2. If materials suspected of containing hazardous materials are encountered, do not disturb; immediately notify Architect and Owner. Hazardous materials will be removed by Owner under a separate contract.
- E. Hazardous Materials: Hazardous materials are present in building to be selectively demolished. A report on the presence of hazardous materials is on file for review and use. Examine report to become aware of locations where hazardous materials are present.
1. Hazardous material remediation is specified elsewhere in the Contract Documents.
 2. Do not disturb hazardous materials or items suspected of containing hazardous materials except under procedures specified elsewhere in the Contract Documents.
- F. Storage or sale of removed items or materials on-site will not be permitted.
- G. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.
1. Maintain fire-protection facilities in service during selective demolition operations.
- 1.8 WARRANTY
- A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials so as not to void existing warranties.
1. If possible, retain original Installer or fabricator to patch the exposed Work listed below that is damaged during selective demolition. If it is impossible to engage original Installer or fabricator, engage another recognized experienced and specialized firm.
 - a. Processed concrete finishes.
 - b. Matched-veneer woodwork.
 - c. Preformed metal panels.
 - d. Roofing.
 - e. Firestopping.
 - f. Stucco and ornamental plaster.
 - g. Aggregate wall coating.
 - h. Wall covering.
 - i. HVAC enclosures, cabinets, or covers.
 - j. Drywall panels

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- k. Accoustical tile
- l. Computer floor systems

PART 2 - PRODUCTS

2.1 REPAIR MATERIALS

- A. Use repair materials identical to existing materials.
 - 1. If identical materials are unavailable or cannot be used for exposed surfaces, use materials that visually match existing adjacent surfaces to the fullest extent possible.
 - 2. Use materials whose installed performance equals or surpasses that of existing materials.
- B. Comply with material and installation requirements specified in individual Specification Sections.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that utilities have been disconnected and capped.
- B. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.
- C. Inventory and record the condition of items to be removed and reinstalled and items to be removed and salvaged.
- D. When unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Architect.
- E. Engage a professional engineer to survey condition of building to determine whether removing any element might result in structural deficiency or unplanned collapse of any portion of structure or adjacent structures during selective demolition operations.
- F. Perform surveys as the Work progresses to detect hazards resulting from selective demolition activities.

3.2 UTILITY AND BUILDING SERVICES

- A. Existing Utilities: Maintain services indicated to remain and protect them against damage during selective demolition operations.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- B. Do not interrupt existing utilities and building services serving occupied or operating facilities unless authorized in writing by Owner and authorities having jurisdiction. Provide temporary services during interruptions to existing utilities, as acceptable to Owner and to authorities having jurisdiction.
 - 1. Provide at least 72 hours' notice to Owner if shutdown of service is required during changeover.
- C. Utility and Building Services Requirements: Locate, identify, disconnect, and seal or cap off indicated utilities serving areas to be selectively demolished.
 - 1. Owner will arrange to shut off indicated utilities/building service when requested by Contractor.
 - 2. Arrange to shut off indicated utilities with utility companies and facility personnel.
 - 3. If utility services are required to be removed, relocated, or abandoned, before proceeding with selective demolition provide temporary utilities that bypass area of selective demolition and that maintain continuity of service to other parts of building.
 - 4. Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit after bypassing.
- D. Utility/ Building Service Requirements: Refer to Division 15 and 16 Sections for shutting off, disconnecting, removing, and sealing or capping utilities. Do not start selective demolition work until utility building service disconnecting and sealing have been completed and verified in writing.

3.3 PREPARATION

- A. Dangerous Materials: Drain, purge, or otherwise remove, collect, and dispose of chemicals, gases, explosives, acids, flammables, or other dangerous materials before proceeding with selective demolition operations.
- B. Pest Control: Employ a certified, licensed exterminator to treat building and to control rodents and vermin before and during selective demolition operations.
- C. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
 - 1. Do not close or obstruct streets, walks, walkways, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction. Provide alternate routes around closed or obstructed traffic ways if required by governing regulations.
 - 2. Erect temporary protection, such as walks, fences, railings, canopies, and covered passageways, where required by authorities having jurisdiction.
 - 3. Protect existing site improvements, appurtenances, and landscaping to remain.
 - 4. Erect a plainly visible fence around drip line of individual trees or around perimeter drip line of groups of trees to remain.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- D. Temporary Facilities: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.
 - 1. Provide protection to ensure safe passage of people around selective demolition area and to and from occupied portions of building.
 - 2. Provide temporary weather protection, during interval between selective demolition of existing construction on exterior surfaces and new construction, to prevent water leakage and damage to structure and interior areas.
 - 3. Protect walls, ceilings, floors, and other existing finish work that are to remain or that are exposed during selective demolition operations.
 - 4. Cover and protect furniture, furnishings, and equipment that have not been removed.

- E. Temporary Enclosures: Provide temporary enclosures for protection of existing building and construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities. Provide temporary weathertight enclosure for building exterior.
 - 1. Where heating or cooling is needed and permanent enclosure is not complete, provide insulated temporary enclosures. Coordinate enclosure with ventilating and material drying or curing requirements to avoid dangerous conditions and effects.

- F. Temporary Shoring: Provide and maintain shoring, bracing, or structural support to preserve stability and prevent movement, settlement, or collapse of construction to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.
 - 1. Strengthen or add new supports when required during progress of selective demolition.

3.4 POLLUTION CONTROLS

- A. Disposal: Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
 - 1. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.

- B. Cleaning: Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

3.5 SELECTIVE DEMOLITION

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

1. Proceed with selective demolition systematically, from higher to lower level. Complete selective demolition operations above each floor or tier before disturbing supporting members on the next lower level.
 2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping, to minimize disturbance of adjacent surfaces. Temporarily cover openings to remain.
 3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
 4. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain portable fire-suppression devices during flame-cutting operations.
 5. Maintain adequate ventilation when using cutting torches.
 6. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
 7. Remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation.
 8. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
 9. Dispose of demolished items and materials promptly.
 10. Return elements of construction and surfaces that are to remain to condition existing before selective demolition operations began.
- B. Existing Facilities: Comply with County Project Manager's requirements for using and protecting elevators, stairs, walkways, loading docks, building entries, and other building facilities during selective demolition operations.
- C. Removed and Salvaged Items: Comply with the following:
1. Clean salvaged items.
 2. Pack or crate items after cleaning. Identify contents of containers.
 3. Store items in a secure area until delivery to Owner.
 4. Transport items to Owner's storage area designated by Owner.
 5. Protect items from damage during transport and storage.
- D. Removed and Reinstalled Items: Comply with the following:
1. Clean and repair items to functional condition adequate for intended reuse. Paint equipment to match new equipment.
 2. Pack or crate items after cleaning and repairing. Identify contents of containers.
 3. Protect items from damage during transport and storage.
 4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.
- E. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition and reinstalled in their original locations after selective demolition operations are complete.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- F. Concrete: Demolish in small sections. Cut concrete to a depth of at least **3/4 inch (19 mm)** at junctures with construction to remain, using power-driven saw. Dislodge concrete from reinforcement at perimeter of areas being demolished, cut reinforcement, and then remove remainder of concrete indicated for selective demolition. Neatly trim openings to dimensions indicated.
- G. Crush and re-use demolished concrete as clean fill, or provide to a recycler in accordance with Section 01350.
- H. Masonry: Demolish in small sections. Cut masonry at junctures with construction to remain, using power-driven saw, then remove masonry between saw cuts.
- I. Concrete Slabs-on-Grade: Saw-cut perimeter of area to be demolished, then break up and remove.
- J. Resilient Floor Coverings: Remove floor coverings and adhesive according to recommendations in RFCI-WP and its Addendum.
 - 1. Remove residual adhesive and prepare substrate for new floor coverings by one of the methods recommended by RFCI.
- K. Roofing: Remove no more existing roofing than can be covered in one day by new roofing. Refer to applicable Division 7 Section for new roofing requirements.
- L. Air-Conditioning Equipment: Remove equipment without releasing refrigerants.

3.6 PATCHING AND REPAIRS

- A. General: Promptly repair damage to adjacent construction caused by selective demolition operations.
- B. Patching: Comply with Division 1 Section "Cutting and Patching."
- C. Repairs: Where repairs to existing surfaces are required, patch to produce surfaces suitable for new materials.
 - 1. Completely fill holes and depressions in existing masonry walls that are to remain with an approved masonry patching material applied according to manufacturer's written recommendations.
- D. Finishes: Restore exposed finishes of patched areas and extend restoration into adjoining construction in a manner that eliminates evidence of patching and refinishing.
- E. Floors and Walls: Where walls or partitions that are demolished extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish color, texture, and appearance. Remove existing floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

1. Patch with durable seams that are as invisible as possible. Provide materials and comply with installation requirements specified in other Sections of these Specifications.
 2. Where patching occurs in a painted surface, apply primer and intermediate paint coats over patch and apply final paint coat over entire unbroken surface containing patch. Provide additional coats until patch blends with adjacent surfaces.
 3. Where feasible, test and inspect patched areas after completion to demonstrate integrity of installation.
- F. Ceilings: Patch, repair, or rehang existing ceilings as necessary to provide an even-plane surface of uniform appearance.

3.7 DISPOSAL OF DEMOLISHED MATERIALS

- A. General: Promptly recycle or dispose of demolished materials. Do not allow demolished materials to accumulate on-site.
- B. Burning: Do not burn demolished materials.
- C. Disposal: Transport demolished materials and legally dispose of them.

END OF SECTION 01732

SECTION 01770 - CLOSEOUT PROCEDURES -017700

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
 - 1. Inspection procedures.
 - 2. Project Record Documents.
 - 3. Operation and maintenance manuals.
 - 4. Warranties.
 - 5. Instruction of Owner's personnel.
 - 6. Final cleaning.
- B. Related Sections include the following:
 - 1. Division 1 Section "Payment Procedures" for requirements for Applications for Payment for Substantial and Final Completion.
 - 2. Divisions 2 through 16 Sections for specific closeout and special cleaning requirements for products of those Sections.

1.3 SUBSTANTIAL COMPLETION

- A. Preliminary Procedures: Before requesting inspection for determining date of Substantial Completion, complete the following. List items below that are incomplete in request.
 - 1. Prepare a list of items to be completed and corrected (punch list), the value of items on the list, and reasons why the Work is not complete.
 - 2. Advise Owner of pending insurance changeover requirements.
 - 3. Submit specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
 - 4. Obtain and submit releases permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
 - 5. Prepare and submit Project Record Documents, operation and maintenance manuals, Final Completion construction photographs, damage or settlement surveys, property surveys, and similar final record information.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

6. Deliver tools, spare parts, extra materials, and similar items to location designated by Owner. Label with manufacturer's name and model number where applicable.
7. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
8. Complete startup testing of systems.
9. Submit test/adjust/balance records.
10. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
11. Advise Owner of changeover in heat and other utilities.
12. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
13. Complete final cleaning requirements, including touchup painting.
14. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.

B. Inspection: Submit a written request for inspection for Substantial Completion. On receipt of request, Architect/ Engineer will either proceed with inspection or notify Contractor of unfulfilled requirements. Engineer will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect/Engineer, that must be completed or corrected before certificate will be issued.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
2. Results of completed inspection will form the basis of requirements for Final Completion.

1.4 FINAL COMPLETION

A. Preliminary Procedures: Before requesting final inspection for determining date of Final Completion, complete the following:

1. Submit a final Application for Payment according to Division 1 Section "Payment Procedures."
2. Submit certified copy of Architect's, Engineer's, and Project Manager's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by the Project Manager.. The certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
3. Submit evidence of final, continuing insurance coverage complying with insurance requirements.
4. Submit pest-control final inspection report and warranty.
5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems.

B. Inspection: Submit a written request for final inspection for acceptance. On receipt of request, Architect/Engineer will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect/Engineer will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued. "Work list" type observations shall not occur. If

the process becomes multiple "work list" observations, the contractor shall pay the Engineer for multiple observations.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.5 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

- A. Preparation: Submit three copies of list. Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
 1. Organize list of spaces in sequential order, starting with exterior areas first and proceeding from lowest floor to highest floor.
 2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.
 3. Include the following information at the top of each page:
 - a. Project name.
 - b. Date.
 - c. Name of Architect/ Engineer and Project Manager.
 - d. Name of Contractor.
 - e. Page number.

1.6 PROJECT RECORD DOCUMENTS

- A. General: Do not use Project Record Documents for construction purposes. Protect Project Record Documents from deterioration and loss. Provide access to Project Record Documents for Engineer's reference during normal working hours.
- B. Record Drawings: Maintain and submit one set of blue- or black-line white prints of Contract Drawings and Shop Drawings.
 1. Mark Record Prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to prepare the marked-up Record Prints.
 - a. Give particular attention to information on concealed elements that cannot be readily identified and recorded later.
 - b. Accurately record information in an understandable drawing technique.
 - c. Record data as soon as possible after obtaining it. Record and check the markup before enclosing concealed installations.
 - d. Mark Contract Drawings or Shop Drawings, whichever is most capable of showing actual physical conditions, completely and accurately. Where Shop Drawings are marked, show cross-reference on Contract Drawings.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

2. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at the same location.
 3. Mark important additional information that was either shown schematically or omitted from original Drawings.
 4. Note Construction Change Directive numbers, Change Order numbers, alternate numbers, and similar identification where applicable.
 5. Identify and date each Record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location. Organize into manageable sets; bind each set with durable paper cover sheets. Include identification on cover sheets.
- C. Record Specifications: Submit one copy of Project's Specifications, including addenda and contract modifications. Mark copy to indicate the actual product installation where installation varies from that indicated in Specifications, addenda, and contract modifications.
1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 2. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
 3. Note related Change Orders, Record Drawings, and Product Data, where applicable.
- D. Record Product Data: Submit one copy of each Product Data submittal. Mark one set to indicate the actual product installation where installation varies substantially from that indicated in Product Data.
1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
 3. Note related Change Orders, Record Drawings, and Record Specifications, where applicable.
- E. Miscellaneous Record Submittals: Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.
- 1.7 OPERATION AND MAINTENANCE MANUALS
- A. Assemble a complete set of operation and maintenance data indicating the operation and maintenance of each system, subsystem, and piece of equipment not part of a system. Provide a copy of all operation and maintenance manuals in PDF format to the Owner's Representative on a CD or DVD disc. Include operation and maintenance data required in individual Specification Sections and as follows:
1. Operation Data:
 - a. Emergency instructions and procedures.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- b. System, subsystem, and equipment descriptions, including operating standards.
 - c. Operating procedures, including startup, shutdown, seasonal, and weekend operations.
 - d. Description of controls and sequence of operations.
 - e. Piping diagrams.
2. Maintenance Data:
- a. Manufacturer's information, including list of spare parts.
 - b. Name, address, and telephone number of Installer or supplier.
 - c. Maintenance procedures.
 - d. Maintenance and service schedules for preventive and routine maintenance.
 - e. Maintenance record forms.
 - f. Sources of spare parts and maintenance materials.
 - g. Copies of maintenance service agreements.
 - h. Copies of warranties and bonds.
- B. Organize operation and maintenance manuals into suitable sets of manageable size. Bind and index data in heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, in thickness necessary to accommodate contents, with pocket inside the covers to receive folded oversized sheets. Identify each binder on front and spine with the printed title "OPERATION AND MAINTENANCE MANUAL," Project name, and subject matter of contents.

1.8 WARRANTIES

- A. Submittal Time: Submit written warranties on request of Engineer for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated.
- B. Partial Occupancy: Submit properly executed warranties within 15 days of completion of designated portions of the Work that are completed and occupied or used by Owner during construction period by separate agreement with Contractor.
- C. Organize warranty documents into an orderly sequence based on the table of contents of the Project Manual.
 1. Bind warranties and bonds in heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch (115-by-280-mm) paper.
 2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
 3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- D. Provide additional copies of each warranty to include in operation and maintenance manuals.
- E. Project shall have a warranty for two years after the final complete written acceptance of the Owner's representative.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

PART 3 - EXECUTION

3.1 DEMONSTRATION AND TRAINING

- A. Instruction: Instruct Owner's personnel to adjust, operate, and maintain systems, sub-systems, and equipment not part of a system.
 - 1. Provide instructors experienced in operation and maintenance procedures. Incorporate nontoxic cleaning methods and sustainable maintenance.
 - 2. Provide instruction at mutually agreed-on times. For equipment that requires seasonal operation, provide similar instruction at the start of each season.
 - 3. Schedule training with Owner, through Engineer with at least seven days' advance notice.
 - 4. Coordinate instructors, including providing notification of dates, times, length of instruction, and course content.
- B. Program Structure: Develop an instruction program that includes individual training modules for each system and equipment not part of a system, as required by individual Specification Sections. For each training module, develop a learning objective and teaching outline. Include instruction for the following:
 - 1. System design and operational philosophy.
 - 2. Review of documentation.
 - 3. Operations.
 - 4. Adjustments.
 - 5. Troubleshooting.
 - 6. Maintenance.
 - 7. Repair.
 - 8. Recycling.
 - 9. Provide a list of all attendees that training was completed with date time and manufacturer's representative's name, and phone number.

3.2 FINAL CLEANING

- A. General: Provide final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and anti-pollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
 - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a portion of Project:
 - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
 - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
 - c. Rake grounds that are neither planted nor paved to a smooth, even-textured surface.
 - d. Remove tools, construction equipment, machinery, and surplus material from Project site..
 - e. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
 - f. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
 - g. Sweep concrete floors broom clean in unoccupied spaces.
 - h. Vacuum carpet and similar soft surfaces, removing debris and excess nap; shampoo if visible soil or stains remain.
 - i. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Replace chipped or broken glass and other damaged transparent materials. Polish mirrors and glass, taking care not to scratch surfaces.
 - j. Remove labels that are not permanent.
 - k. Touch up and otherwise repair and restore marred, exposed finishes and surfaces. Replace finishes and surfaces that cannot be satisfactorily repaired or restored or that already show evidence of repair or restoration.
 - 1) Do not paint over "UL" and similar labels, including mechanical and electrical nameplates.
 - l. Wipe surfaces of mechanical and electrical equipment, elevator equipment, and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
 - m. Replace parts subject to unusual operating conditions.
 - n. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- o. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
 - p. Clean ducts, blowers, and coils if units were operated without filters during construction.
 - q. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency. Replace burned-out bulbs, and those noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.
 - r. Leave Project clean and ready for occupancy.
- C. Comply with safety and environmental standards for cleaning. Do not burn waste materials. Do not bury debris or excess materials on Owner's property. Do not discharge volatile, harmful, or dangerous materials into drainage systems. Remove waste materials from Project site and dispose of lawfully. Use non-toxic and low-VOC cleaning products to the extent possible while complying with manufacturer's recommendations.

END OF SECTION 01770

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

SECTION 02060 – DEMOLITION, 024000 – 2004 CSI

1.1- GENERAL

1.2 RELATED DOCUMENTS

A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.3 SUMMARY

A. This Section requires removal and disposal, off site, of the following:

1. Walls, Building demolition, to limits indicated on drawings for piping, conduit, and wall penetrations.

1.4 JOB CONDITIONS

A. Condition of Structures: Owner/ County assumes no responsibility for actual condition of structures to be demolished.

1. Conditions existing at time of inspection for bidding purpose will be maintained by Owner insofar as practicable.

B. Salvaged Materials: Items of salvable value to Contractor may be removed from structure as work progresses. Transport salvaged items from site as they are removed.

1. Storage or sale of removed items will not be permitted on site.

C. Explosives: Use of explosives will not be permitted.

D. Traffic: Conduct demolition operations and removal of debris to ensure minimum interference with roads, streets, walks, and other adjacent occupied and used facilities.

1. Owner will coordinate shut off utilities serving structures. Disconnecting and sealing indicated utilities before starting demolition operations is part of this work by the contractor.

2.1 – PRODUCTS

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

3.1 – EXECUTION

3.2 DEMOLITION

A. Pollution Controls: Use water sprinkling, temporary enclosures, and other suitable methods to limit dust and dirt rising and scattering in air. Comply with governing regulations pertaining to environmental protection.

B. Building Demolition: Demolish building completely and remove from site. Use such methods as required to complete work within limitations of governing regulations.

1. Proceed with demolition in systematic manner, from top of structure to ground. Complete demolition work above each floor or tier before disturbing supporting members on lower levels.

2. Demolish concrete and masonry in small sections.

3. Remove structural framing members and lower to ground by hoists, derricks, or other suitable methods.

Break up and remove concrete slabs-on-grade, unless otherwise shown to remain.

4. Locate demolition equipment throughout structure and remove materials so as to not impose excessive loads to supporting walls, floors, or framing.

C. Below-Grade Construction: Demolish foundation walls and other below-grade construction, including concrete slabs, to a depth of not less than 12 inches below lowest foundation level.

3.3 DISPOSAL OF DEMOLISHED MATERIALS

A. General: Remove weekly from site accumulated debris, rubbish, and other materials resulting from demolition operations.

1. Burning of combustible materials from demolished structures will not be permitted on site.

B. Removal: Transport materials removed from demolished structures and legally dispose of, off site. The demolition contractor shall be required to secure all necessary permits for hauling and disposal of debris at legal "dump" sites.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

3.4 SUPPLEMENTAL REQUIREMENTS

- A. Submit pre-demolition photos showing adjacent areas and extent of demolition.
- B. Submit schedules for all demolition work for coordination with Owner.

END OF SECTION 02060

SECTION 02300 – EARTHWORK, 310000 – 2004 CSI

PART 1 - GENERAL

1.1 SUMMARY

A. This Section includes the following:

1. Preparing subgrades for slabs-on-grade, walks, pavements and exterior grades.
2. Excavating and backfilling for buildings and structures.
3. Drainage course for slabs-on-grade.
4. Subbase course for concrete walks and pavements.
5. Excavating and backfilling for utility trenches.
6. Call 811 prior any excavation .
7. All dewatering shall be by the excavation contractor .

1.2 DEFINITIONS

A. Backfill: Soil material used to fill an excavation.

1. Initial Backfill: Backfill placed beside and over pipe in a trench, including haunches to support sides of pipe.
2. Final Backfill: Backfill placed over initial backfill to fill a trench.

B. Base Course: Course placed between the subbase course and hot-mix asphalt paving.

C. Bedding Course: Course placed over the excavated subgrade in a trench before laying pipe.

D. Borrow Soil: Satisfactory soil imported from off-site for use as fill or backfill.

E. Drainage Course: Course supporting the slab-on-grade that also minimizes upward capillary flow of pore water.

F. Excavation: Removal of material encountered above subgrade elevations and to lines and dimensions indicated.

1. Authorized Additional Excavation: Excavation below subgrade elevations or beyond indicated lines and dimensions as directed by Engineer. Authorized additional excavation and replacement material will be paid for according to Contract provisions changes in the Work.
2. Unauthorized Excavation: Excavation below subgrade elevations or beyond indicated lines and dimensions without direction by Engineer. Unauthorized excavation, as well as remedial work directed by Engineer, shall be without additional compensation.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- G. Fill: Soil materials used to raise existing grades.
- H. Structures: Buildings, footings, foundations, retaining walls, slabs, tanks, curbs, mechanical and electrical appurtenances, or other man-made stationary features constructed above or below the ground surface.
- I. Subbase Course: Course placed between the subgrade and base course for hot-mix asphalt pavement, or course placed between the subgrade and a cement concrete pavement or a cement concrete or hot-mix asphalt walk.
- J. Subgrade: Surface or elevation remaining after completing excavation, or top surface of a fill or backfill immediately below subbase, drainage fill, or topsoil materials.
- K. Utilities: On-site underground pipes, conduits, ducts, and cables, as well as underground services within buildings.
- L. Trenching; excavation for piping and utilities shall meet the Florida Trench Act form safety and soil erosion control. Dewatering shall be completed by the excavation contractor.

1.3 PROJECT CONDITIONS

- A. Existing Utilities: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted in writing by Architect and then only after arranging to provide temporary utility services according to requirements indicated.

PART 2 - PRODUCTS

2.1 SOIL MATERIALS

- A. General: Provide borrow soil materials when sufficient satisfactory soil materials are not available from excavations.
- B. Satisfactory Soils: ASTM D 2487 Soil Classification Groups GW, GP, GM, SW, SP, and SM, or a combination of these groups; free of rock or gravel larger than 3 inches in any dimension, debris, waste, frozen materials, vegetation, and other deleterious matter.
- C. Unsatisfactory Soils: Soil Classification Groups GC, SC, CL, ML, OL, CH, MH, OH, and PT according to ASTM D 2487, or a combination of these groups.
 - 1. Unsatisfactory soils also include satisfactory soils not maintained within 2 percent of optimum moisture content at time of compaction.
- D. Subbase Material: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; with at least 90 percent passing a 1-1/2-inch sieve and not more than 12 percent passing a No. 200 sieve.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- E. Base Course: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; with at least 95 percent passing a 1-1/2-inch sieve and not more than 8 percent passing a No. 200 sieve.
- F. Engineered Fill: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; with at least 90 percent passing a 1-1/2-inch sieve and not more than 12 percent passing a No. 200 sieve.
- G. Bedding Course: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; except with 100 percent passing a 1-inch sieve and not more than 8 percent passing a No. 200 sieve.
- H. Drainage Course: Narrowly graded mixture of washed crushed stone, or crushed or uncrushed gravel; ASTM D 448; coarse-aggregate grading Size 57; with 100 percent passing a 1-1/2-inch sieve and 0 to 5 percent passing a No. 8 sieve.

2.2 ACCESSORIES

- A. Warning Tape: Acid- and alkali-resistant polyethylene film warning tape manufactured for marking and identifying underground utilities, 6 inches wide and 4 mils thick, continuously inscribed with a description of the utility.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Protect structures, utilities, sidewalks, pavements, and other facilities from damage caused by settlement, lateral movement, undermining, washout, and other hazards created by earthwork operations.
- B. Preparation of subgrade for earthwork operations including removal of vegetation, topsoil, debris, obstructions, and deleterious materials from ground surface is specified in Division 2 Section "Site Clearing."
- C. Protect and maintain erosion and sedimentation controls, which are specified in Division 2 Section "Site Clearing," during earthwork operations.

3.2 EXCAVATION

- A. Unclassified Excavation: Excavate to subgrade elevations regardless of the character of surface and subsurface conditions encountered. Unclassified excavated materials may include rock, soil materials, and obstructions. No changes in the Contract Sum or the Contract Time will be authorized for rock excavation or removal of obstructions.
 - 1. If excavated materials intended for fill and backfill include unsatisfactory soil materials and rock, replace with satisfactory soil materials.

3.3 EXCAVATION FOR STRUCTURES

- A. Excavate to indicated elevations and dimensions within a tolerance of plus or minus 1 inch. If applicable, extend excavations a sufficient distance from structures for placing and removing concrete formwork, for installing services and other construction, and for inspections.
 - 1. Excavations for Footings and Foundations: Do not disturb bottom of excavation. Excavate by hand to final grade just before placing concrete reinforcement. Trim bottoms to required lines and grades to leave solid base to receive other work.

3.4 EXCAVATION FOR WALKS AND PAVEMENTS

- A. Excavate surfaces under walks and pavements to indicated lines, cross sections, elevations, and subgrades.

3.5 EXCAVATION FOR UTILITY TRENCHES

- A. Excavate trenches to indicated gradients, lines, depths, and elevations.
- B. Excavate trenches to uniform widths to provide the following clearance on each side of pipe or conduit. Excavate trench walls vertically from trench bottom to 12 inches higher than top of pipe or conduit, unless otherwise indicated.
 - 1. Clearance: 12 inches each side of pipe or conduit.
- C. Trench Bottoms: Excavate and shape trench bottoms to provide uniform bearing and support of pipes and conduit. Shape subgrade to provide continuous support for bells, joints, and barrels of pipes and for joints, fittings, and bodies of conduits. Remove projecting stones and sharp objects along trench subgrade.
 - 1. Excavate trenches 6 inches deeper than elevation required in rock or other unyielding bearing material, 4 inches deeper elsewhere, to allow for bedding course.

3.6 SUBGRADE INSPECTION

- A. Proof-roll subgrade below the building slabs and pavements with heavy pneumatic-tired equipment to identify soft pockets and areas of excess yielding. Do not proof-roll wet or saturated subgrades.
- B. Reconstruct subgrades damaged by freezing temperatures, frost, rain, accumulated water, or construction activities, as directed by Engineer, without additional compensation.

3.7 UNAUTHORIZED EXCAVATION

- A. Fill unauthorized excavation under foundations or wall footings by extending bottom elevation of concrete foundation or footing to excavation bottom, without altering top elevation. Lean concrete fill, with 28-day compressive strength of 2500 psi may be used when approved by Engineer.
 - 1. Fill unauthorized excavations under other construction or utility pipe as directed by Engineer.

3.8 STORAGE OF SOIL MATERIALS

- A. Stockpile borrow soil materials and excavated satisfactory soil materials without intermixing. Place, grade, and shape stockpiles to drain surface water. Cover to prevent windblown dust.
 - 1. Stockpile soil materials away from edge of excavations. Do not store within drip line of remaining trees.

3.9 UTILITY TRENCH BACKFILL

- A. Place backfill on subgrades free of mud, frost, snow, or ice.
- B. Place and compact bedding course on trench bottoms and where indicated. Shape bedding course to provide continuous support for bells, joints, and barrels of pipes and for joints, fittings, and bodies of conduits.
- C. Backfill trenches excavated under footings and within 18 inches of bottom of footings with satisfactory soil; fill with concrete to elevation of bottom of footings. Concrete is specified in Division 3 Section " Concrete."
- D. Provide 4-inch-thick, concrete-base slab support for piping or conduit less than 30 inches below surface of roadways. After installing and testing, completely encase piping or conduit in a minimum of 4 inches of concrete before backfilling or placing roadway subbase.
- E. Place and compact initial backfill of subbase material, free of particles larger than 1 inch in any dimension, to a height of 12 inches over the utility pipe or conduit.
 - 1. Carefully compact initial backfill under pipe haunches and compact evenly up on both sides and along the full length of utility piping or conduit to avoid damage or displacement of piping or conduit. Coordinate backfilling with utilities testing.
- F. Place and compact final backfill of satisfactory soil to final subgrade elevation.
- G. Install warning tape directly above utilities, 12 inches below finished grade, except 6 inches below subgrade under pavements and slabs.

3.10 SOIL FILL

- A. Plow, scarify, bench, or break up sloped surfaces steeper than 1 vertical to 4 horizontal so fill material will bond with existing material.
- B. Place and compact fill material in layers to required elevations as follows:
 - 1. Under grass and planted areas, use satisfactory soil material.
 - 2. Under walks and pavements, use satisfactory soil material.
 - 3. Under steps and ramps, use engineered fill.
 - 4. Under building slabs, use engineered fill.
 - 5. Under footings and foundations, use engineered fill.

3.11 SOIL MOISTURE CONTROL

- A. Uniformly moisten or aerate subgrade and each subsequent fill or backfill soil layer before compaction to within 2 percent of optimum moisture content.
 - 1. Do not place backfill or fill soil material on surfaces that are muddy, frozen, or contain frost or ice.
 - 2. Remove and replace, or scarify and air dry otherwise satisfactory soil material that exceeds optimum moisture content by 2 percent and is too wet to compact to specified dry unit weight.

3.12 COMPACTION OF SOIL BACKFILLS AND FILLS

- A. Place backfill and fill soil materials in layers not more than 8 inches in loose depth for material compacted by heavy compaction equipment, and not more than 4 inches in loose depth for material compacted by hand-operated tampers.
- B. Place backfill and fill soil materials evenly on all sides of structures to required elevations, and uniformly along the full length of each structure.
- C. Compact soil materials to not less than the following percentages of maximum dry unit weight according to ASTM D 1557:
 - 1. Under structures, building slabs, steps, and pavements, scarify and recompact top 12 inches of existing subgrade and each layer of backfill or fill soil material at 95 percent.
 - 2. Under walkways, scarify and recompact top 6 inches below subgrade and compact each layer of backfill or fill soil material at 92 percent.
 - 3. Under lawn or unpaved areas, scarify and recompact top 6 inches below subgrade and compact each layer of backfill or fill soil material at 85 percent.
 - 4. For utility trenches, compact each layer of initial and final backfill soil material at 85 percent.

3.13 GRADING

- A. General: Uniformly grade areas to a smooth surface, free of irregular surface changes. Comply with compaction requirements and grade to cross sections, lines, and elevations indicated.
- B. Site Grading: Slope grades to direct water away from buildings and to prevent ponding. Finish subgrades to required elevations within the following tolerances:
 - 1. Lawn or Unpaved Areas: Plus or minus 1 inch.
 - 2. Walks: Plus or minus 1 inch.
 - 3. Pavements: Plus or minus 1/2 inch.
 - 4. Grading inside Building Lines: Finish subgrade to a tolerance of 1/2 inch when tested with a 10-foot straightedge.

3.14 SUBBASE AND BASE COURSES

- A. Place subbase and base course on subgrades free of mud, frost, snow, or ice.
- B. On prepared subgrade, place subbase and base course under pavements and walks as follows:
 - 1. Shape subbase and base course to required crown elevations and cross-slope grades.
 - 2. Compact subbase and base course at optimum moisture content to required grades, lines, cross sections, and thickness to not less than 95 percent of maximum dry unit weight according to ASTM D 1557.

3.15 DRAINAGE COURSE

- A. Place drainage course on subgrades free of mud, frost, snow, or ice.
- B. On prepared subgrade, place and compact drainage course under cast-in-place concrete slabs-on-grade as follows:
 - 1. Place drainage course that exceeds 6 inches in compacted thickness in layers of equal thickness, with no compacted layer more than 6 inches thick or less than 3 inches thick.
 - 2. Compact each layer of drainage course to required cross sections and thicknesses to not less than 95 percent of maximum dry unit weight according to ASTM D 698.

3.16 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified independent geotechnical engineering testing agency to perform field quality-control testing.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- B. Allow testing agency to inspect and test subgrades and each fill or backfill layer. Proceed with subsequent earthwork only after test results for previously completed work comply with requirements.
- C. Footing Subgrade: At footing subgrades, at least one test of each soil stratum will be performed to verify design bearing capacities. Subsequent verification and approval of other footing subgrades may be based on a visual comparison of subgrade with tested subgrade when approved by Architect.
- D. Testing agency will test compaction of soils in place according to ASTM D 1556, ASTM D 2167, ASTM D 2922, and ASTM D 2937, as applicable.
- E. When testing agency reports that subgrades, fills, or backfills have not achieved degree of compaction specified, scarify and moisten or aerate, or remove and replace soil to depth required; recompact and retest until specified compaction is obtained.

3.17 PROTECTION

- A. Protecting Graded Areas: Protect newly graded areas from traffic, freezing, and erosion. Keep free of trash and debris.
- B. Repair and reestablish grades to specified tolerances where completed or partially completed surfaces become eroded, rutted, settled, or where they lose compaction due to subsequent construction operations or weather conditions.
- C. Where settling occurs before Project correction period elapses, remove finished surfacing, backfill with additional soil material, compact, and reconstruct surfacing.
 - 1. Restore appearance, quality, and condition of finished surfacing to match adjacent work, and eliminate evidence of restoration to greatest extent possible.

3.18 DISPOSAL OF SURPLUS AND WASTE MATERIALS

- A. Disposal: Remove surplus satisfactory soil and waste material, including unsatisfactory soil, trash, and debris, and legally dispose of it off Owner's property.

END OF SECTION 02300

SECTION 02361 - TERMITE CONTROL, 313116 – 2004 CSI

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following for termite control:
 - 1. Soil treatment for new construction and where existing slabs are removed for below slab work.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Division 1 Section "Environmental Impact of Materials" for guidelines to VOC content and recommended recycled content of products.

1.3 DEFINITIONS

- A. EPA: Environmental Protection Agency.
- B. PCO: Pest control operator.

1.4 SUBMITTALS

- A. Product Data: Treatments and application instructions, including EPA-Registered Label.
- B. Product Certificates: Signed by manufacturers of termite control products certifying that treatments furnished comply with requirements.
- C. Qualification Data: For firms and persons specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
- D. Soil Treatment Application Report: After application of termiticide is completed, submit report for Owner's record information, including the following as applicable:
 - 1. Date and time of application.
 - 2. Moisture content of soil before application.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

3. Brand name and manufacturer of termiticide.
4. Quantity of undiluted termiticide used.
5. Dilutions, methods, volumes, and rates of application used.
6. Areas of application.
7. Water source for application.

E. Warranties: Special warranties specified in this Section.

1.5 QUALITY ASSURANCE

- A. Applicator Qualifications: A PCO who is licensed according to regulations of authorities having jurisdiction to apply termite control treatment in jurisdiction where Project is located and who is experienced and has completed termite control treatment similar to that indicated for this Project and whose work has a record of successful in-service performance.
- B. Regulatory Requirements: Formulate and apply termiticides, and label with a Federal registration number, to comply with EPA regulations and authorities having jurisdiction.

1.6 PROJECT CONDITIONS

- A. Environmental Limitations: To ensure penetration, do not treat soil that is water saturated or frozen. Do not treat soil while precipitation is occurring. Comply with EPA-Registered Label requirements and requirements of authorities having jurisdiction.

1.7 COORDINATION

- A. Coordinate soil treatment application with excavating, filling, and grading and concreting operations. Treat soil under footings, grade beams, and ground-supported slabs, before construction.

1.8 WARRANTY

- A. General Warranty: Special warranty specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.
- B. Special Warranty: Written warranty, signed by applicator and Contractor certifying that termite control work, consisting of applied soil termiticide treatment, will prevent infestation of subterranean termites. If subterranean termite activity or damage is discovered during warranty period, re-treat soil and repair or replace damage caused by termite infestation.
- C. Warranty Period: Three years from date of Substantial Completion.

1.9 MAINTENANCE SERVICE

- A. Continuing Service: Provide a proposal for continuing service, including monitoring, inspection, and retreatment for occurrences of termite activity, from applicator to Owner, in the form of a standard yearly (or other period) continuing service agreement, starting on the date of Substantial Completion. State services, obligations, conditions, and terms for agreement period and for future renewal options.

PART 2 - PRODUCTS

2.1 SOIL TREATMENT

- A. Termiticide: Provide an EPA-registered termiticide complying with requirements of authorities having jurisdiction, in a soluble or emulsible, concentrated formulation that dilutes with water or foaming agent, and formulated to prevent termite infestation. Use only soil treatment solutions that are not harmful to plants. Provide quantity required for application at the label volume and rate for the maximum termiticide concentration allowed for each specific use, according to the product's EPA-Registered Label.
- B. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. AgrEvo Environmental Health, Inc.; a Company of Hoechst and Schering, Berlin.
 - 2. American Cyanamid Co.; Agricultural Products Group; Specialty Products Department.
 - 3. Bayer Corp.; Garden & Professional Care.
 - 4. DowElanco.
 - 5. FMC Corp.; Pest Control Specialties.
 - 6. Zeneca Professional Products.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Applicator present, for compliance with requirements for moisture content of the soil, interfaces with earthwork, slab and foundation work, landscaping, and other conditions affecting performance of termite control. Proceed with application only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. General: Comply with the most stringent requirements of authorities having jurisdiction and with manufacturer's written instructions for preparing substrate. Remove all extraneous sources of wood cellulose and other edible materials such as wood debris, tree

stumps and roots, stakes, formwork, and construction waste wood from soil and around foundations.

- B. Soil Treatment Preparation: Remove foreign matter and impermeable soil materials that could decrease treatment effectiveness on areas to be treated. Loosen, rake, and level soil to be treated, except previously compacted areas under slabs and footings. Termiticides may be applied before placing compacted fill under slabs if recommended by termiticide manufacturer.
- C. Fit filling hose connected to water source at the site with a backflow preventer, complying with requirements of authorities having jurisdiction.

3.3 APPLICATION, GENERAL

- A. General: Comply with the most stringent requirements of authorities having jurisdiction and with manufacturer's EPA-Registered Label for products.

3.4 APPLYING SOIL TREATMENT

- A. Application: Mix soil treatment termiticide solution to a uniform consistency. Provide quantity required for application at the label volume and rate for the maximum specified concentration of termiticide, according to manufacturer's EPA-Registered Label, to the following so that a continuous horizontal and vertical termiticidal barrier or treated zone is established around and under building construction. Distribute the treatment evenly.
 - 1. Slabs-on-Grade and Basement Slabs: Under ground-supported slab construction, including footings, building slabs, and attached slabs as an overall treatment. Treat soil materials before concrete footings and slabs are placed.
 - 2. Foundations: Adjacent soil including soil along entire inside perimeter of foundation walls, along both sides of interior partition walls, around plumbing pipes and electric conduit penetrating slab, and around interior column footers, piers, and chimney bases; and along entire outside perimeter, from grade to bottom of footing. Avoid soil washout around footings.
 - 3. Penetrations: At expansion joints, control joints, and areas where slabs will be penetrated.
- B. Avoid disturbance of treated soil after application. Keep off treated areas until completely dry.
- C. Protect termiticide solution, dispersed in treated soils and fills, from being diluted until ground-supported slabs are installed. Use waterproof barrier according to EPA-Registered Label instructions.
- D. Post warning signs in areas of application.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- E. Reapply soil treatment solution to areas disturbed by subsequent excavation, grading, landscaping, or other construction activities following application.

END OF SECTION 02361

SECTION 06105 - MISCELLANEOUS CARPENTRY –061000 2004 CSI

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Rooftop equipment bases and support curbs, nailers, blocking.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Division 1 Section "Environmental Impact of Materials" for guidelines to VOC content and recommended recycled content of products.
 - 2. Division 7 Section "Roofing"

1.3 SUBMITTALS

- A. General: Submit each item in this Article according to the Conditions of the Contract and Division 1 Specification Sections.
- B. Wood treatment data as follows, including chemical treatment manufacturer's instructions for handling, storing, installing, and finishing treated materials:
 - 1. For each type of preservative-treated wood product, include certification by treating plant stating type of preservative solution and pressure process used, net amount of preservative retained, and compliance with applicable standards.
 - 2. For waterborne-treated products, include statement that moisture content of treated materials was reduced to levels indicated before shipment to Project site.
- C. Material test reports from a qualified independent testing agency indicating and interpreting test results relative to compliance of fire-retardant-treated wood products with performance requirements indicated.
- D. Warranty of chemical treatment manufacturer for each type of treatment.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Keep materials under cover and dry. Protect from weather and contact with damp or wet surfaces. Stack lumber, plywood, and other panels. Provide for air circulation within and around stacks and under temporary coverings.

1. For lumber and plywood pressure treated with waterborne chemicals, place spacers between each bundle to provide air circulation.

PART 2 - PRODUCTS

2.1 LUMBER, GENERAL

- A. Lumber Standards: Comply with DOC PS 20, "American Softwood Lumber Standard," and with applicable grading rules of inspection agencies certified by American Lumber Standards Committee's (ALSC) Board of Review.
- B. Inspection Agencies: Inspection agencies, and the abbreviations used to reference them, include the following:
 1. NELMA - Northeastern Lumber Manufacturers Association.
 2. SPIB - Southern Pine Inspection Bureau.
 3. WCLIB - West Coast Lumber Inspection Bureau.
 4. WWPA - Western Wood Products Association.
- C. Grade Stamps: Provide lumber with each piece factory marked with grade stamp of inspection agency evidencing compliance with grading rule requirements and identifying grading agency, grade, species, moisture content at time of surfacing, and mill.
 1. For exposed lumber, furnish pieces with grade stamps applied to ends or back of each piece.
- D. Where nominal sizes are indicated, provide actual sizes required by DOC PS 20 for moisture content specified. Where actual sizes are indicated, they are minimum dressed sizes for dry lumber.
 1. Provide dressed lumber, S4S, unless otherwise indicated.
 2. Provide dry lumber with 19 percent maximum moisture content at time of dressing for 2-inch nominal (38-mm actual) thickness or less, unless otherwise indicated.

2.2 WOOD-PRESERVATIVE-TREATED MATERIALS

- A. General: Where lumber or plywood is indicated as preservative treated or is specified to be treated, comply with applicable requirements of AWPA C2 (lumber) and AWPA C9 (plywood). Mark each treated item with the Quality Mark Requirements of an inspection agency approved by ALSC's Board of Review.
 1. Do not use chemicals containing chromium or arsenic.
 2. For exposed items indicated to receive stained finish, use chemical formulations that do not bleed through, contain colorants, or otherwise adversely affect finishes.
- B. Pressure treat aboveground items with waterborne preservatives to a minimum retention of 0.25 lb/cu. ft. (4.0 kg/cu. m). After treatment, kiln-dry lumber and plywood to a

maximum moisture content of 19 and 15 percent, respectively. Treat indicated items and the following:

1. Wood cants, nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.

2.3 DIMENSION LUMBER

- A. General: Provide dimension lumber of grades indicated according to the ALSC National Grading Rule (NGR) provisions of the inspection agency indicated.

2.4 BOARDS

- A. Exposed Boards: Where boards will be exposed in the finished work, provide the following:

1. Moisture Content: 19 percent maximum.
2. Species and Grade: Eastern white pine, D Select per NELMA rules.
3. Species and Grade: Southern pine, C Finish per SPIB rules.
4. Species and Grade: Spruce-pine-fir, C & Btr per WCLIB rules or C Select per WWPA rules.

- B. Concealed Boards: Where boards will be concealed by other work, provide lumber with 19 percent maximum moisture content and of following species and grade:

1. Species and Grade: Eastern softwoods, No. 3 Common per NELMA rules.
2. Species and Grade: Mixed southern pine, No. 2 per SPIB rules.
3. Species and Grade: Spruce-pine-fir, Standard per WCLIB rules or No. 3 Common per WWPA rules.

2.5 MISCELLANEOUS LUMBER

- A. General: Provide lumber for support or attachment of other construction, including rooftop equipment curbs and support bases, cant strips, bucks, nailers, blocking, furring, grounds, stripping, and similar members.
- B. Fabricate miscellaneous lumber from dimension lumber of sizes indicated and into shapes shown.
- C. Moisture Content: 19 percent maximum for lumber items are not specified to receive wood preservative treatment.
- D. Grade: For dimension lumber sizes, provide No. 3 or Standard grade lumber per ALSC's NGRs of any species. For board-size lumber, provide No. 3 Common grade per NELMA, or WWPA; No. 2 grade per SPIB; or Standard grade per WCLIB or WWPA of any species.

2.6 WOOD-BASED STRUCTURAL-USE PANELS

- A. Structural-Use Panel Standards: Provide plywood panels complying with DOC PS 1, "U.S. Product Standard for Construction and Industrial Plywood," where plywood is indicated.
- B. Trademark: Factory mark structural-use panels with APA trademark evidencing compliance with grade requirements.
- C. Miscellaneous Concealed Plywood: C-C Plugged Exterior, thickness as indicated but not less than **1/2 inch (12.7 mm)**.
- D. Miscellaneous Concealed Panels: APA-rated sheathing, Exposure 1, span rating to suit framing in each location.
- E. Plywood Backing Panels: For mounting electrical or telephone equipment, provide fire-retardant-treated plywood panels with grade, C-D Plugged Exposure 1, in thickness indicated or, if not otherwise indicated, not less than **15/32 inch (11.9 mm)** thick.

2.7 FASTENERS

- A. General: Provide fasteners of size and type indicated that comply with requirements specified in this Article for material and manufacture.
 - 1. Provide fasteners with a hot-dip zinc coating per ASTM A 153 or of Type 304 stainless steel.
- B. Nails, Wire, Brads, and Staples: FS FF-N-105.
- C. Power-Driven Fasteners: CABO NER-272.
- D. Bolts: Steel bolts complying with **ASTM A 307, Grade A (ASTM F 568, Property Class 4.6)**; with **ASTM A 563 (ASTM A 563M)** hex nuts and, where indicated, flat washers.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Discard units of material with defects that impair quality of carpentry and that are too small to use with minimum number of joints or optimum joint arrangement.
- B. Set carpentry to required levels and lines, with members plumb, true to line, cut, and fitted.
- C. Fit carpentry to other construction; scribe and cope as required for accurate fit. Correlate location of furring, nailers, blocking, grounds, and similar supports to allow attachment of other construction.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- D. Apply field treatment complying with AWPA M4 to cut surfaces of preservative-treated lumber and plywood.
- E. Securely attach carpentry work as indicated and according to applicable codes and recognized standards.
- F. Use fasteners of appropriate type and length. Pre-drill members when necessary to avoid splitting wood.

3.2 WOOD GROUNDS, NAILERS, BLOCKING, AND SLEEPERS

- A. Install where shown and where required for screeding or attaching other work. Cut and shape to required size. Coordinate locations with other work involved.
- B. Attach to substrates to support applied loading. Recess bolts and nuts flush with surfaces, unless otherwise indicated.

3.3 INSTALLATION OF STRUCTURAL-USE PANELS

- A. General: Comply with applicable recommendations contained in APA Form No. E30, "APA Design/Construction Guide: Residential & Commercial," for types of structural-use panels and applications indicated.

END OF SECTION 06105

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

07270 FIRE PROOFING –078400 2004 CSI

Part One - General

1.1 Summary

Penetrations through fire resistive construction rated floor /roof /wall construction
And smoke barriers by ducts, conduits, bus way, and other penetrating items shall
be fireproofed.

1.2 System Performance

A. General: Provide and install fire stopping systems that are produced and
installed to resist the spread of fire and passage of smoke.

1.3 Quality Assurance

A. Provide manufacturer, and UL paperwork providing a copy of the test data
showing the materials meet the 2-hour rating form floor to floor, and 1 hour
rating for interior walls.

Part Two – Products

2.1 Fire stopping General

A. Provide fire stopping compounds of components that are compatible with each
Other, the substrate forming openings and any items penetrating walls/roof/ and
ceiling assemblies.

2.2 Materials

A. Materials which can be used are: Ceramic fiber sealants, silicon foam, mortar,
Flame-safe coating products, meta caulk products, elastomeric standard
sealant that complies with ASTM C920, Dow Corning 790 silicone sealants,
Maneco Vulken 922 urethane sealants, and General Electric Fire break
assemblies for bus way.

Part Three – Execution

3.1 General: Comply with the requirements of the part 1.01.

A. Apply materials and assemblies so that they fill and remain in place and
Produce a smooth uniform surface.

3.2 Quality Control

A. Provide the paperwork for the installation, which includes UL assembly
application and testing data.

B. Where deficiencies are found, repair or replace the fire-proofing in compliance
With the manufacturer's specifications and UL listing book.

End of Section

SECTION 07920 - JOINT SEALANTS -079000

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes sealants for the following applications, including those specified by reference to this Section:
- B. This Section includes sealants for the following applications:
 - 1. Exterior joints in vertical surfaces and nontraffic horizontal surfaces:
 - 2. Exterior joints in horizontal traffic surfaces:
 - 3. Interior joints in vertical surfaces and horizontal nontraffic surfaces:
 - 4. Interior joints in horizontal traffic surfaces:

1.3 PERFORMANCE REQUIREMENTS

- A. Provide elastomeric joint sealants for exterior applications that establish and maintain watertight and airtight continuous joint seals without staining or deteriorating joint substrates.
- B. Provide joint sealants for interior applications that establish and maintain airtight and water-resistant continuous joint seals without staining or deteriorating joint substrates.

1.4 SUBMITTALS

- A. Product Data: For each joint-sealant product indicated.
- B. Samples for Initial Selection: Manufacturer's color charts consisting of strips of cured sealants showing the full range of colors available for each product exposed to view.
- C. Samples for Verification: For each type and color of joint sealant required. Install joint sealants in **1/2-inch- (13-mm-)** wide joints formed between two **6-inch- (150-mm-)** long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- D. Product Certificates: Signed by manufacturers of joint sealants certifying that products furnished comply with requirements and are suitable for the use indicated.
- E. SWRI Validation Certificate: For each elastomeric sealant specified to be validated by SWRI's Sealant Validation Program.
- F. Qualification Data: For firms and persons specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
- G. Preconstruction Field Test Reports: Indicate which sealants and joint preparation methods resulted in optimum adhesion to joint substrates based on preconstruction testing specified in "Quality Assurance" Article.
- H. Field Test Report Log: For each elastomeric sealant application. Include information specified in "Field Quality Control" Article.
- I. Product Test Reports: From a qualified testing agency indicating sealants comply with requirements, based on comprehensive testing of current product formulations.
- J. Warranties: Special warranties specified in this Section.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer who has specialized in installing joint sealants similar in material, design, and extent to those indicated for this Project and whose work has resulted in joint-sealant installations with a record of successful in-service performance.
- B. Source Limitations: Obtain each type of joint sealant through one source from a single manufacturer.
- C. Product Testing: Obtain test results for "Product Test Reports" Paragraph in "Submittals" Article from a qualified testing agency based on testing current sealant formulations within a 36-month period.
 - 1. Testing Agency Qualifications: An independent testing agency qualified according to ASTM C 1021 to conduct the testing indicated, as documented according to ASTM E 548.
 - 2. Test elastomeric joint sealants for compliance with requirements specified by reference to ASTM C 920, and where applicable, to other standard test methods.
- D. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Meetings."

1.6 DELIVERY, STORAGE, AND HANDLING

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- A. Deliver materials to Project site in original unopened containers or bundles with labels indicating manufacturer, product name and designation, color, expiration date, pot life, curing time, and mixing instructions for multicomponent materials.
- B. Store and handle materials in compliance with manufacturer's written instructions to prevent their deterioration or damage due to moisture, high or low temperatures, contaminants, or other causes.

1.7 PROJECT CONDITIONS

- A. Environmental Limitations: Do not proceed with installation of joint sealants under the following conditions:
 - 1. When ambient and substrate temperature conditions are outside limits permitted by joint sealant manufacturer.
 - 2. When ambient and substrate temperature conditions are outside limits permitted by joint sealant manufacturer or are below 40 deg F (4.4 deg C).
 - 3. When joint substrates are wet.
- B. Joint-Width Conditions: Do not proceed with installation of joint sealants where joint widths are less than those allowed by joint sealant manufacturer for applications indicated.
- C. Joint-Substrate Conditions: Do not proceed with installation of joint sealants until contaminants capable of interfering with adhesion are removed from joint substrates.

1.8 WARRANTY

- A. General Warranty: Special warranties specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.
- B. Special Installer's Warranty: Written warranty, signed by Installer agreeing to repair or replace elastomeric joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.
 - 1. Warranty Period: Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PRODUCTS AND MANUFACTURERS

- A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the products specified in the sealant schedules at the end of Part 3.

2.2 MATERIALS, GENERAL

- A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by sealant manufacturer based on testing and field experience.
- B. Colors of Exposed Joint Sealants: As selected by Architect from manufacturer's full range for this characteristic.

2.3 ELASTOMERIC JOINT SEALANTS

- A. Elastomeric Sealant Standard: Comply with ASTM C 920 and other requirements indicated for each liquid-applied chemically curing sealant in the Elastomeric Joint-Sealant Schedule at the end of Part 3, including those referencing ASTM C 920 classifications for type, grade, class, and uses.
- B. Additional Movement Capability: Where additional movement capability is specified in the Elastomeric Joint-Sealant Schedule, provide products with the capability, when tested for adhesion and cohesion under maximum cyclic movement per ASTM C 719, to withstand the specified percentage change in the joint width existing at the time of installation and remain in compliance with other requirements of ASTM C 920 for uses indicated.
- C. Stain-Test-Response Characteristics: Where elastomeric sealants are specified in the Elastomeric Joint-Sealant Schedule to be nonstaining to porous substrates, provide products that have undergone testing according to ASTM C 1248 and have not stained porous joint substrates indicated for Project.
- D. Continuous-Immersion-Test-Response Characteristics: Where elastomeric sealants will be immersed continuously in water, provide products that have undergone testing according to ASTM C 1247, including initial six-week immersion period and additional immersion periods specified below, and have not failed in adhesion or cohesion when tested with substrates indicated for Project.
 - 1. One additional four-week immersion period.
 - 2. Two additional four-week immersion periods.
 - 3. Three additional four-week immersion periods.
- E. Suitability for Contact with Food: Where elastomeric sealants are indicated for joints that will come in repeated contact with food, provide products that comply with 21 CFR 177.2600.

2.4 SOLVENT-RELEASE JOINT SEALANTS

- A. Acrylic-Based Solvent-Release Joint-Sealant Standard: Comply with ASTM C 1311 for each product of this description indicated in the Solvent-Release Joint-Sealant Schedule at the end of Part 3.

- B. Acrylic-Based Solvent-Release Joint-Sealant Standard: Comply with FS TT-S-00230 for each product of this description indicated in the Solvent-Release Joint-Sealant Schedule at the end of Part 3.
- C. Butyl-Rubber-Based Solvent-Release Joint-Sealant Standard: Comply with ASTM C 1085 for each product of this description indicated in the Solvent-Release Joint-Sealant Schedule at the end of Part 3.
- D. Pigmented Narrow Joint Sealant: For each product of this description indicated in the Solvent-Release Joint-Sealant Schedule at the end of Part 3 provide manufacturer's standard, solvent-release-curing, pigmented, synthetic-rubber sealant complying with AAMA 803.3 and formulated for sealing joints 3/16 inch (5 mm) or smaller in width.

2.5 LATEX JOINT SEALANTS

- A. Latex Sealant Standard: Comply with ASTM C 834 for each product of this description indicated in the Latex Joint-Sealant Schedule at the end of Part 3.

2.6 ACOUSTICAL JOINT SEALANTS

- A. Acoustical Sealant for Exposed and Concealed Joints: For each product of this description indicated in the Acoustical Joint-Sealant Schedule at the end of Part 3, provide manufacturer's standard nonsag, paintable, nonstaining latex sealant complying with ASTM C 834 and the following:
 - 1. Product effectively reduces airborne sound transmission through perimeter joints and openings in building construction as demonstrated by testing representative assemblies according to ASTM E 90.
- B. Acoustical Sealant for Concealed Joints: For each product of this description indicated in the Acoustical Joint-Sealant Schedule at the end of Part 3, provide manufacturer's standard, nondrying, nonhardening, nonskinning, nonstaining, gunnable, synthetic-rubber sealant recommended for sealing interior concealed joints to reduce airborne sound transmission.

2.7 PREFORMED JOINT SEALANTS

- A. Preformed Silicone-Sealant System: For each product of this description indicated in the Preformed Joint-Sealant Schedule at the end of Part 3, provide manufacturer's standard system consisting of precured low-modulus silicone extrusion, in sizes to fit joint widths indicated, combined with a neutral-curing silicone sealant for bonding extrusions to substrates.
- B. Preformed Foam Sealants: For each product of this description indicated in the Preformed Joint-Sealant Schedule at the end of Part 3, provide manufacturer's standard preformed, precompressed, impregnated, open-cell foam sealant manufactured from high-density urethane foam impregnated with a nondrying, water-repellent agent; factory produced in precompressed sizes and in roll or stick form to fit joint widths indi-

cated and to develop a watertight and airtight seal when compressed to the degree specified by manufacturer; and complying with the following:

1. Properties: Permanently elastic, mildew resistant, nonmigratory, nonstaining, and compatible with joint substrates and other joint sealants.
2. Impregnating Agent: Manufacturer's standard.
3. Impregnating Agent: Latex-modified asphalt.
4. Impregnating Agent: Chemically stabilized acrylic.
5. Impregnating Agent: Neoprene rubber suspended in water-based emulsion.
6. Density: Manufacturer's standard.
7. Density: 5 to 6 lb/cu. ft. (80 to 96 kg/cu. m).
8. Backing: Pressure-sensitive adhesive, factory applied to one side with protective wrapping.

2.8 JOINT-SEALANT BACKING

- A. General: Provide sealant backings of material and type that are nonstaining; are compatible with joint substrates, sealants, primers, and other joint fillers; and are approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.
- B. Cylindrical Sealant Backings: ASTM C 1330, of type indicated below and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance:
 1. Type C: Closed-cell material with a surface skin.
 2. Type O: Open-cell material.
 3. Type B: Bicellular material with a surface skin.
 4. Type: Any material indicated above.
- C. Elastomeric Tubing Sealant Backings: Neoprene, butyl, EPDM, or silicone tubing complying with ASTM D 1056, nonabsorbent to water and gas, and capable of remaining resilient at temperatures down to minus 26 deg F (minus 32 deg C). Provide products with low compression set and of size and shape to provide a secondary seal, to control sealant depth, and otherwise contribute to optimum sealant performance.
- D. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint where such adhesion would result in sealant failure. Provide self-adhesive tape where applicable.

2.9 MISCELLANEOUS MATERIALS

- A. Primer: Material recommended by joint sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.
- B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capa-

ble of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants with joint substrates.

- C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting joint-sealant performance.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint sealant manufacturer's written instructions and the following requirements:
 - 1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
 - 2. Clean porous joint substrate surfaces by brushing, grinding, blast cleaning, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining from above cleaning operations by vacuuming or blowing out joints with oil-free compressed air. Porous joint surfaces include the following:
 - a. Concrete.
 - b. Masonry.
 - c. Unglazed surfaces of ceramic tile.
 - 3. Remove laitance and form-release agents from concrete.
 - 4. Clean nonporous surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants.
 - a. Metal.
 - b. Glass.
 - c. Porcelain enamel.
 - d. Glazed surfaces of ceramic tile.

- B. Joint Priming: Prime joint substrates where recommended in writing by joint sealant manufacturer, based on preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.
- C. Masking Tape: Use masking tape where required to prevent contact of sealant with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF JOINT SEALANTS

- A. General: Comply with joint sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.
- B. Sealant Installation Standard: Comply with recommendations of ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.
- C. Acoustical Sealant Application Standard: Comply with recommendations of ASTM C 919 for use of joint sealants in acoustical applications as applicable to materials, applications, and conditions indicated.
- D. Install sealant backings of type indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
 - 1. Do not leave gaps between ends of sealant backings.
 - 2. Do not stretch, twist, puncture, or tear sealant backings.
 - 3. Remove absorbent sealant backings that have become wet before sealant application and replace them with dry materials.
- E. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and back of joints.
- F. Install sealants by proven techniques to comply with the following and at the same time backings are installed:
 - 1. Place sealants so they directly contact and fully wet joint substrates.
 - 2. Completely fill recesses provided for each joint configuration.
 - 3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.
- G. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.
 - 1. Remove excess sealants from surfaces adjacent to joint.

2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
3. Provide concave joint configuration per Figure 5A in ASTM C 1193, unless otherwise indicated.
4. Provide flush joint configuration, per Figure 5B in ASTM C 1193, where indicated.
5. Provide recessed joint configuration, per Figure 5C in ASTM C 1193, of recess depth and at locations indicated.
 - a. Use masking tape to protect adjacent surfaces of recessed tooled joints.

H. Installation of Preformed Silicone-Sealant System: Comply with the following requirements:

1. Apply masking tape to each side of joint, outside of area to be covered by sealant system.
2. Apply a bead of silicone sealant to each side of joint to produce a bead of size complying with preformed silicone-sealant system manufacturer's printed schedule and covering a bonded area of not less than a **3/8 inch (10 mm)**. Hold edge of sealant bead inside of masking tape by **1/4 inch (6 mm)**.
3. Within 10 minutes of sealant application, press silicone extrusion into sealant to wet extrusion and substrate. Use a roller to apply consistent pressure and ensure uniform contact between sealant and both extrusion and substrate.
4. Complete installation of horizontal joints before installing vertical joints. Lap vertical joints over horizontal joints. At end of joints, cut silicone extrusion with a razor knife.

I. Installation of Preformed Foam Sealants: Install each length of sealant immediately after removing protective wrapping, taking care not to pull or stretch material, to produce seal continuity at ends, turns, and intersections of joints. For applications at low ambient temperatures where expansion of sealant requires acceleration to produce seal, apply heat to sealant to comply with sealant manufacturer's written instructions.

3.4 FIELD QUALITY CONTROL

A. Field-Adhesion Testing: Field-test joint-sealant adhesion to joint substrates as follows:

1. Extent of Testing: Test completed elastomeric sealant joints as follows:
 - a. Perform 10 tests for the first **1000 feet (300 m)** of joint length for each type of elastomeric sealant and joint substrate.
 - b. Perform one test for each **1000 feet (300 m)** of joint length thereafter or one test per each floor per elevation.
2. Test Method: Test joint sealants by hand-pull method described below:
 - a. Make knife cuts from one side of joint to the other, followed by two cuts approximately **2 inches (50 mm)** long at sides of joint and meeting cross cut at one end. Place a mark **1 inch (25 mm)** from cross-cut end of **2-inch (50-mm)** piece.

- b. Use fingers to grasp **2-inch (50-mm)** piece of sealant between cross-cut end and **1-inch (25-mm)** mark; pull firmly at a 90-degree angle or more in direction of side cuts while holding a ruler along side of sealant. Pull sealant out of joint to the distance recommended by sealant manufacturer for testing adhesive capability, but not less than that equaling specified maximum movement capability in extension; hold this position for 10 seconds.
 - c. For joints with dissimilar substrates, check adhesion to each substrate separately. Do this by extending cut along one side, checking adhesion to opposite side, and then repeating this procedure for opposite side.
 3. Inspect joints for complete fill, for absence of voids, and for joint configuration complying with specified requirements. Record results in a field adhesion test log.
 4. Inspect tested joints and report on the following:
 - a. Whether sealants in joints connected to pulled-out portion failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each type of product and joint substrate. Compare these results to determine if adhesion passes sealant manufacturer's field- adhesion hand-pull test criteria.
 - b. Whether sealants filled joint cavities and are free from voids.
 - c. Whether sealant dimensions and configurations comply with specified requirements.
 5. Record test results in a field adhesion test log. Include dates when sealants were installed, names of persons who installed sealants, test dates, test locations, whether joints were primed, adhesion results and percent elongations, sealant fill, sealant configuration, and sealant dimensions.
 6. Repair sealants pulled from test area by applying new sealants following same procedures used to originally seal joints. Ensure that original sealant surfaces are clean and new sealant contacts original sealant.
- B. Evaluation of Field-Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements, will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to comply with other requirements. Retest failed applications until test results prove sealants comply with indicated requirements.
- 3.5 CLEANING
- A. Clean off excess sealants or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.
- 3.6 PROTECTION
- A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If,

despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from the original work.

3.7 ELASTOMERIC JOINT-SEALANT SCHEDULE

A. Low-Modulus Nonacid-Curing Silicone Sealant: Provide products complying with the following:

1. Products:
 - a. 790; Dow Corning.
 - b. Silpruf; GE Silicones.
 - c. 890; Pecora Corporation.
2. Type and Grade: S (single component) and NS (nonsag).
3. Class: 25.
4. Additional Movement Capability: **50** percent movement in extension and 50 percent movement in compression for a total of **100** percent movement.
5. Use Related to Exposure: NT (nontraffic).
6. Uses Related to Joint Substrates: M, G, A, and, as applicable to joint substrates indicated, O.
7. Stain-Test-Response Characteristics: Nonstaining to porous substrates per ASTM C 1248.
8. Applications: Exterior vertical surface joints and interior vertical surface joints on exterior walls and those subject to movement.

B. Mildew-Resistant Silicone Sealant: Provide products formulated with fungicide that are intended for sealing interior ceramic tile joints and other nonporous substrates that are subject to in-service exposures of high humidity and temperature extremes, and that comply with the following:

1. Products:
 - a. 786 Mildew Resistant; Dow Corning.
 - b. Sanitary 1700; GE Silicones.
 - c. 898 Silicone Sanitary Sealant; Pecora Corporation.
2. Type and Grade: S (single component) and NS (nonsag).
3. Class: 25.
4. Use Related to Exposure: NT (nontraffic).
5. Uses Related to Joint Substrates: G, A, and, as applicable to joint substrates indicated, O.
6. Applications: Interior, at plumbing fixtures, water pipe penetrations, shower stalls, other locations of high humidity.

C. Pourable Silicone Sealant: Provide products complying with the following:

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

1. Products:
 - a. 890-SL; Dow Corning.
 - b. FC Parking Structure Sealant; Dow Corning.
2. Type and Grade: **S (single component)]** and P (pourable).
3. Class: 25.
4. Additional Movement Capability: 100 percent movement in extension and **50** percent in compression for a total of **150** percent movement.
5. Uses Related to Joint Substrates: M and, as applicable to joint substrates indicated, O.
6. Applications: Exterior and interior horizontal surface joints subject to traffic.

3.8 LATEX JOINT-SEALANT SCHEDULE

- A. Latex Sealant: Provide products complying with the following:

1. Products:
 - a. Chem-Calk 600; Bostik Inc.
 - b. AC-20; Pecora Corporation.
 - c. Sonolac; Sonneborn Building Products Div., ChemRex, Inc.
2. Applications: Interior vertical surface joints not subject to movement.

3.9 ACOUSTICAL JOINT-SEALANT SCHEDULE

- A. Acoustical Sealant for Exposed and Concealed Joints: Provide products complying with the following:

1. Products:
 - a. AC-20 FTR Acoustical and Insulation Sealant; Pecora Corporation.
 - b. SHEETROCK Acoustical Sealant; USG Corp., United States Gypsum Co.
2. Applications: Where detailed and where required to achieve scheduled STC ratings.

3.10 PREFORMED JOINT-SEALANT SCHEDULE

- A. Preformed Foam Sealant: Provide products complying with the following:

1. Products:
 - a. Emseal 25V; Emseal Joint Systems, Ltd.
 - b. Polytite B; Polytite Manufacturing Corporation.
 - c. Wilseal 600; Sealform, Ltd.
2. Applications: As detailed.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

END OF SECTION 07920

Division 16000 - SECTION 26 00 00 - ELECTRICAL SYSTEMS DESCRIPTIONS

A. PROJECT INCLUDES

1. Electrical Systems for the Following Applications:
 - a. Power and distribution.
 - b. Empty conduit system.
 - c. Modifications to existing systems.

2. Preliminary Connected Loads:
 - a. See electrical drawings for loads being disconnected.
 - b. See electrical drawings for loads being added.

3. Additional Requirements:
 - a. On site factory training for all switchboards, motor control centers, automatic transfer switches, and generators.
 - b. All switchgear and equipment shall meet or exceed the Short Circuit Values on the drawings.
 - c. Perform controls work for the generator. All controls shall work with the existing generator and possible portable generator. See signal diagrams and controls on the electrical drawings.

4. Additional information is included in the construction documents and shall be included in this project. It is the responsibility of the contractor to obtain the latest and most updated set of documents.

B. PRODUCTS

1. Systems, products, and standards are listed in individual specification sections, which follow.

END OF SECTION

**Division 16110 SECTION 26 05 00 – COMMON WORK RESULTS FOR ELECTRICAL:
ELECTRICAL RACEWAYS, CABLE TRAYS, AND BOXES**

A. PROJECT INCLUDES

1. Electrical conduit, tubing, surface raceways, wireways, cable trays, boxes, and cabinets for electrical power and signal distribution.

B. PRODUCTS

1. Wiring Methods:

- a. Exposed Indoor Wiring: Electrical metallic tubing, rigid nonmetallic conduit, and/or galvanized steel conduit.
- b. Concealed Indoor Wiring: Electrical metallic tubing, electrical nonmetallic tubing, or rigid nonmetallic conduit.
- c. Exposed Outdoor Wiring: GRC steel conduit.
- d. Concealed Outdoor Wiring: GRC steel conduit.
- e. Underground Wiring, Single Run: Rigid nonmetallic conduit.
- f. Underground Wiring, Grouped: Rigid nonmetallic conduit.
- g. Connection to Vibrating Equipment: Flexible liquidtight conduit.

2. Metal Conduit and Tubing:

- a. Rigid Steel Conduit: ANSI C80.1.
- b. PVC Externally Coated Rigid Steel Conduit and Fittings: ANSI C80.1 and NEMA RN 1.
- c. Electrical Metallic Tubing (EMT) and Fittings: ANSI C80.3.
- d. PVC Externally Coated Electrical Metallic Tubing and Fittings: ANSI C80.3 and NEMA RN 1.
- e. Liquidtight Flexible Metal Conduit and Fittings: UL 360.

3. Nonmetallic Conduit and Ducts:

- a. Electrical Nonmetallic Tubing (ENT): NEMA TC 13.
- b. Rigid Nonmetallic Conduit (RNC): NEMA TC 2 and UL 651, Schedule 40 or 80 PVC.
- c. Underground PVC and ABS Plastic Utilities Duct: NEMA TC 6, Type I for encased burial in concrete, Type II for direct burial.
- d. PVC and ABS Plastic Utilities Duct Fittings: NEMA TC9.
- e. Liquidtight Flexible Nonmetallic Conduit and Fittings: UL 1660.

4. Raceway Accessory Materials:
 - a. Conduit Bodies: NEC requirements.
 - b. Wireways: NEC requirements.
 - c. Surface Raceways, Metallic: Galvanized steel, with snap-on covers.
 - d. Surface Raceways, Nonmetallic: Rigid PVC, UL 94.
5. Boxes and Fittings:
 - a. Cabinet Boxes: UL 50, sheet steel, NEMA 1 or NEMA 3 dependent on location.
 - b. Pull and Junction Boxes: UL 50, steel boxes, NEMA 1 or NEMA 3 dependent upon location.
 - c. Metal Outlet, Device and Small Wiring Boxes: UL 514A and OS 1.
 - d. Nonmetallic Outlet, Device and Small Wiring Boxes: NEMA OS 2.
6. Identification of Electrical Systems: Systems shall have a clearly marked schedule, typed, and given to the Owner's Representative. All disconnects shall be clearly marked with an engraved type plastic placard as described in the electrical documents. The electrical input and output shall be clearly marked.
7. Specifications: The electrical drawings have specifications. Review all specifications on the electrical drawings.

END OF SECTION

Division 16120 SECTION 26 05 19 – ELECTRICAL WIRES AND CABLES

A. PROJECT INCLUDES

1. Wires, cables, and connectors for power, lighting, signal, control and related systems rated 600 volts and less.

B. QUALITY ASSURANCE

2. Compliance: National Electrical Code; UL 4, 83, 486A, 486B, 854; NEMA/ICEA WC-5, WC-7, WC-8; IEEE 82.

C. PRODUCTS

1. Wire Components:

- a. Conductors for Power and Lighting Circuits: Solid or Stranded conductors for No. 10 AWG and smaller; stranded conductors for No. 8 AWG and larger.
- b. Conductor Material: Copper.
- c. Insulation: THHN/THWN for conductors size 500MCM and larger and No. 8 AWG and smaller, THW, THHN/THWN or XHHW insulation for other sizes based on location.
- d. Jackets: Factory-applied nylon or PVC.

2. Cables:

- a. Portable Cord for Flexible Pendant Leads to Outlets and Equipment: UL Type SO.
- b. Control/Signal Transmission Media: Single conductor, coaxial type, or others as required by the equipment manufacture.
- c. Fiber Optic Cables: Single channel low-loss glass type, fiber optic multimode graded-index cables, including connectors, couples, transmitters, receivers, sources and detectors.

3. Connectors: UL listed connectors for the appropriate cable type with appropriate temperature ratings.

END OF SECTION

Division 16140 SECTION 26 27 26 – ELECTRICAL WIRING DEVICES

A. PROJECT INCLUDES

1. Wiring devices for electrical service.

B. QUALITY ASSURANCE

1. Compliance: National Electrical Code, NEMA WD 1, and UL.

C. PRODUCTS

1. Wiring Devices and Components:
 - a. Receptacles: UL 498 and NEMA WD 1, exterior are NEMA 3 with covers.
 - b. Industrial Receptacles: UL 498 pin and sleeve type; UL 1010 at hazardous locations.
 - c. Ground-Fault Interrupter (GFI) Receptacles: Feed-thru type ground-fault circuit interrupter with integral duplex receptacles.
 - d. Plugs: 15 amperes, 125 volts, 3 wire, grounding, armored cap plugs.
 - e. Plug Connectors: 15 amperes, 125 volts, bakelite-body armored connectors, 3 wire, grounding with cord clamp.
 - f. Snap Switches: UL 20 and NEMA WD 1, AC switches.
 - g. Combination Switch and Receptacles: 3-way switch, 20 amperes, AC with toggle switch handle, 3 wire grounding receptacle, 15 amperes, 120 volts.
 - h. Wall Plates: Single and combination types, match existing types.

END OF SECTION

Division 16400 SECTION 26 20 00 – ELECTRICAL SERVICE AND DISTRIBUTION

A. PROJECT INCLUDES

1. Electrical service and distribution including service entrance, switchboards, low-voltage power switchgear, grounding, transformers, busways, panelboards, overcurrent protective devices, and motor controllers.

B. PRODUCTS

1. Service Entrance: Service and Distribution Requirements: Refer to project "E" series drawings.
 - a. Circuit Breakers: Solid-state trip circuit breakers.
 - b. Meter Sockets: Acceptable to local utility company.
 - c. Switches: Heavy-duty safety switches with NEMA Type 4X enclosure.
2. Switchboards:
 - a. Refer to: SECTION 26 27 00 – LOW VOLTAGE GROUP MOUNTED DISTRIBUTION
3. Low-Voltage Power Switchgear:
 - a. Refer to: SECTION 26 27 00 – LOW VOLTAGE GROUP MOUNTED DISTRIBUTION
4. Grounding:
 - a. Grounding Equipment: UL 467; copper conductors; NEC Table 8, and article 250 wire and cable conductors; connectors.
 - b. Grounding Electrodes: Copper-clad steel ground rods; copper plate electrodes.
5. Transformers if shown:
 - a. Control and Signal Transformers: NEMA ST 1, UL 506, self-cooled, two-winding dry type; continuous duty rating.
6. Busways if shown:
 - a. Busways: General-purpose plug-in type, ANSI/UL 857, NEMA BU 1, enclosed, non-ventilated, suitable for indoor installation, copper conductors.

- b. Plug-In Devices: Circuit breaker plugs, fusible switch plugs, fuse plugs, combination starter plugs; compatible with connected busway.
7. Panelboards:
- a. Panelboards: NEMA PB 1, UL 50, 61, with overcurrent protective devices, enclosure suitable for use, copper bus, compression type main and neutral lugs, IEEE C62.1 surge arresters.
 - b. Panelboard Type: Load-center-type panelboards; lighting and appliance branch circuit panelboards; distribution panelboards.
8. Overcurrent Protective Devices:
- a. Overcurrent Protective Devices: Integral to panelboards, switchboards, and motor control centers.
 - b. Cartridge Fuses: NEMA FU 1, class suitable for use.
 - c. Fusible Switches: UL 98, NEMA KS 1, rating suitable for use.
 - d. Fused Power Circuit Devices: UL 977, operation suitable for use; ground fault protection; open fuse trip device; minimum fault current rating suitable for use.
 - e. Molded Case Circuit Breakers: UL 489, NEMA AB 1; combination circuit breaker and ground fault circuit interrupters type; current-limiting circuit breaker type; integrally fused circuit breaker type; solid-state trip device circuit breaker type; rating suitable for use.
 - f. Insulated Case Circuit Breakers: UL 489, NEMA AB 1; rating suitable for use.
9. Fuses:
- a. Cartridge Fuses: ANSI/IEEE FU 1, nonrenewable cartridge type, non-interchangeable type.
10. Motor Controllers: (NOT USED)

END OF SECTION

Division 16402

**SECTION 26 27 00-LOW VOLTAGE SWITCHBOARDS GROUP MOUNTED
DISTRIBUTION**

A. SECTION INCLUDES

1. Low Voltage, Front-Accessible and Front/Rear-Accessible switchboards with circuit breaker for mains and feeders and/or fusible switches for mains as specified below and shown on the contract drawings.

B. RELATED SECTIONS

1. 26 43 00 Transient Voltage Suppression Systems.

C. REFERENCES

1. The low voltage switchboards and protection devices in this specification are designed and manufactured according to latest revision of the following standards (unless otherwise noted).
 - a. ANSI 61
 - b. ANSI/NEMA PB 2, Deadfront Distribution Switchboards
 - c. ANSI/NEMA PB 2.1, General Instructions for Proper Handling, Installation, Operation, and Maintenance of Deadfront Distribution Switchboards Rated 600 Volts or Less
 - d. ANSI/NFPA 70, National Electrical Code
 - e. NEMA AB 1, Molded Case Circuit Breakers and Molded Case Switches
 - f. NEMA KS 1, Fused and Non - fused Switches
 - g. UL 489, Molded Case Circuit Breakers and Circuit Breaker Enclosures
 - h. UL 891, Dead Front Switchboards
 - i. UL 98, Enclosed and Dead Front Switches
 - j. UL 977, Fused Power Circuit Devices

D. DEFINITIONS

1. Front-Accessible only shall be as defined by UL 891 standard which requires that all line and load connections for phase, neutral, and ground conductors can be made and maintained from the front of the switchboard without access to the rear.

E. SYSTEM DESCRIPTION

1. The power system feeding the Switchboards is either 480/277 or 208/120 volts, 60 Hertz, 3 phase, 4-wire, solidly grounded Wye. All exterior switch boards shall be Nema 3R minimum.
2. Switchboard(s) shall have front access and rear alignment for mounting against a wall.

F. SUBMITTALS

1. Manufacturer shall provide 3 copies of the following documents to owner for review and evaluation in accordance with general requirements of Division 16.
 - a. Product Data on specified product;
 - b. Shop Drawings on specified product;
 - c. Trip curves for each specified product.

G. INSTALLATION, OPERATION AND MAINTENANCE DATA

1. Manufacturer shall provide 3 copies of installation, operation and maintenance procedures to owner in accordance with general requirements of Division 16.

H. QUALITY ASSURANCE (QUALIFICATIONS)

1. Manufacturer shall have specialized in the manufacture and assembly of low voltage switchboards for 25 years or more.
2. Low voltage switchboards shall be listed and/or classified by Underwriters Laboratories in accordance with standards listed in Article C-1 of this specification.
3. Equipment shall be qualified for use in seismic areas as follows:

- a. High seismic loading as defined in IEEE Std 693-1997, with 1.33 amplification factor.

I. DELIVERY, STORAGE, AND HANDLING

1. Contractor shall store, protect, and handle products in accordance with recommended practices listed in manufacturer's Installation and Maintenance Manuals.
2. Ship each switchboard section in individual shipping splits for ease of handling. Each section shall be mounted on shipping skids and wrapped for protection.
3. Contractor shall inspect and report concealed damage to carrier within 48 hours.
4. Contractor shall store in a clean, dry space. Cover with heavy canvas or plastic to keep out dirt, water, construction debris, and traffic. Heat enclosures to prevent condensation.
5. Contractor shall handle in accordance with manufacturer's recommendations to avoid damaging equipment, installed devices, and finish.

J. PROJECT CONDITIONS (SITE ENVIRONMENTAL CONDITIONS)

1. Follow (standards) service conditions before, during and after switchboard installation.
2. Low voltage switchboards shall be located in well - ventilated areas, free from excess humidity, dust and dirt and away from hazardous materials. Ambient temperature of area will be between minus 30 and plus 40 degrees C. Indoor locations shall be protected to prevent moisture from entering enclosure.

K. WARRANTY

1. Manufacturer warrants equipment to be free from defects in materials and workmanship for 1 year from date of installation or 18 months from date of purchase, whichever occurs first.

L. FIELD MEASUREMENTS

1. Contractor shall make all necessary field measurements to verify that equipment shall fit in allocated space in full compliance with minimum required clearances specified in National Electrical Code.

M. MANUFACTURER

1. General Electric Company products have been used as the basis for design. Other manufacturers' products of equivalent quality, dimensions and operating features may be acceptable, at the Architect's/ Engineer's discretion, if they comply with all requirements specified or indicated in these Contract documents.

N. EQUIPMENT

1. The equipment shall contain the following components and features.
 - a. Refer to Contract Drawings for actual layout and location of equipment and components; current ratings of devices, bus bars, and components; voltage ratings of devices, components and assemblies; interrupting and withstand ratings of devices, buses, and components; and other required details.
 - b. Furnish GE Type Spectra Bolt-On™ Switchboards (or approved equal).
 - c. Switchboards shall be fully self-supporting structures with 90 inch tall vertical sections (excluding lifting eyes and pull boxes) bolted together to form required arrangement.
 - d. Switchboard frame shall be die formed, 12 gauge steel with reinforced corner gussets. Frame shall be rigidly bolted to support cover plates (code gauge steel), bus bars and installed devices during shipment and installation.
 - e. All sections may be rolled, moved or lifted into position. Switchboards shall be capable of being bolted directly to the floor without the use of floor sills.
 - f. All switchboard sections shall have open bottoms and removable top plate(s) to install conduit.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- g. Front-Access only switchboard sections shall be rear aligned for placement against a wall.
 - h. Switchboards shall be UL listed, and MSB-3 shall be Service Entrance rated.
 - i. Switchboards that are series rated to short circuit requirements shall be appropriately labeled. Tested UL listed combination ratings shall be included in UL recognized Component Directory (DKSY2).
 - j. All covers shall be fastened by hex or standard screw head bolts. No special tools shall be required to access this equipment.
 - k. Provide hinged doors over metering compartments and individually mounted device compartments. All doors shall have concealed hinges and be fastened by hex or standard screw head bolts.
 - l. Switchboard protective devices shall be furnished as listed on drawings and specified herein, including interconnections, instrumentation and control wiring. Switchboards and devices shall be rated for the voltage and frequency listed on the drawings.
 - m. Switchboard current ratings, including all devices, shall be based on a maximum ambient temperature of 25 degree C per UL Standard 891. With no derating required, temperature rise of switchboards and devices shall not exceed 65 degrees C in a 25 degree C ambient environment.
 - n. Switchboard Service Entrance sections shall comply with UL Service Entrance requirements including a UL service entrance label, incoming line isolation barriers, and a removable neutral bond to switchboard ground for solidly grounded Wye systems.
 - o. The group mounted feeder breaker and/or main devices within switchboards shall be circuit breakers only. Mounting for the group mounted devices shall be by bolted connections. No plug-in type connections shall be used for current carrying components.
2. Incoming Section
- a. Incoming section shall be direct cable connection to main breaker.

- b. Furnish switchboard arranged for bottom entry of incoming cable.
 - c. Provide mechanical lugs in the quantity and size required per the contract drawings. All lugs shall be tin-plated aluminum and UL listed for use with copper cable. Lugs shall be rated for 75 degree C. Cable.
3. Bus Bars
- a. All bus bars shall be silver plated copper. The bus bars shall have sufficient cross sectional area to meet UL 891 temperature rise requirements. Phase and neutral bus ampacity shall be as shown on the plans. The neutral bus shall have the same ampacity as the phase bus.
 - b. Bus bars shall be mounted on high impact, non-tracking insulated supports. Joints in the vertical bus are not permitted.
 - c. Bus bars shall be braced to withstand mechanical forces exerted during short circuit conditions as indicated in drawings, but in no case less than 100KA RMS SYM.
 - d. Bus joints shall be bolted with high tensile steel Grade 5 bolts. Belleville type washers shall be provided with aluminum bus. Welded connections are unacceptable.
 - e. Ground Bus shall be sized to meet UL 891. Ground bus shall extend full length of switchboard. Ground bus shall be copper.
 - f. A-B-C bus arrangement left to right, top to bottom, front to rear shall be used throughout to assure convenient and safe testing and maintenance. Where special circuitry precludes this arrangement, bus bars shall be labeled.
 - g. All feeder device line and load connection straps shall be rated to carry current rating of device frame (not trip rating).
 - h. The main incoming bus bars shall be rated for the main protection device frame size or main incoming conductors, if there is no main device.

- i. Main horizontal bus bars shall be fully rated and arranged for future extensions.
4. Enclosure
- a. Switchboard shall be NEMA 1 non walk-in deadfront construction or as indicated on drawings.
5. User Metering
- a. Provide a UL listed and digital multifunction power monitor. The monitor case shall be fully enclosed and shielded
 - b. The monitor shall accept a voltage monitoring range of up to 600 volts, phase to phase. Monitor shall withstand 200% rated current continuously. It shall withstand 10X rated current for at least 3 seconds. Isolation shall be no less than 2500V AC. Surge withstand shall conform to IEEE C37.90.1,62.41 and IEEE 1000-4 Shall have a standard ANSI C39.1 case mount.
 - c. The Monitor shall provide true RMS measurements of voltage, phase to neutral and phase to phase; current, per phase and neutral; real power, reactive power, apparent power, power factor and frequency. The Monitor must be capable of providing readings for both instantaneous and average readings.
 - 1. The Monitor must also be capable of providing all single phase real, apparent, reactive power and power factor values.
 - 2. The Monitor shall record and store total bi-directional energy. It shall include separate registers for positive and negative energy.
 - 3. The Monitor shall record and store total bi-directional accumulated energy and total accumulated apparent energy.
 - 4. The Monitor shall monitor max/min average demand values for all current and power readings. The demand interval shall be user programmable. Meter shall be model EPM6000 or approved equal.

6. Main Devices

- a. Main device shall be individually mounted, draw out type, insulated case or AIR type circuit breaker, and 100% rated.
- b. Tie device(s), if included, shall be the same as the main device.
- c. Where indicated provide the following with the main device:
 1. Electronic ground fault detection
 2. Shunt trip
 3. Undervoltage release
 4. Auxiliary contacts

7. Feeder devices

- a. Feeder devices shall be group mount molded case circuit breakers or when larger than 1200 amps shall be individually mounted insulated case circuit breakers. Provide devices as indicated on drawings.
- b. All circuit protective devices shall have the following minimum symmetrical current interrupting capacity: 100kA, or as listed on the contract drawings.
- c. Where indicated provide the following with the feeder device(s):
 1. Shunt trip
 2. Undervoltage release
 3. Auxiliary contacts
 4. Bell alarm

8. Molded Case Circuit Breakers

- a. Furnish GE Spectra RMS™ Molded Case Circuit Breakers. Thermal magnetic molded case circuit breakers may be provided for trip ratings 150 amps and below.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- b. Group mounted breakers shall be connected to the vertical bus by bolted connections.
- c. Individually mounted molded case circuit breakers shall be stationary mounted.
- d. Circuit breaker frames shall be constructed of a high-strength, molded, glass-reinforced polyester case and cover. Breakers shall have an overcenter, toggle handle-operated, trip free mechanism with quick make, quick break action independent of the speed of the toggle handle operation. The design shall provide common tripping of all poles. Breakers shall be suitable for reverse feeding.
- e. Breakers shall have ON and OFF position clearly marked on escutcheon. Breakers shall include a trip-to-test means on the escutcheon for manually tripping the breaker and exercising the mechanism and trip latch.
- f. Breakers shall include factory installed mechanical lugs. Lugs shall be UL listed and rated 75 or 60/75 degrees C as appropriate. Breakers shall be standard, or 80 percent rated.
- g. Breakers larger than 400 amps shall use digital true RMS sensing trip units and a rating plug to determine the breaker trip rating. The breaker shall be adjusted to the proper trip settings by electrical contractor to meet the inrush of the largest piece of equipment. The time and trip settings shall be obtained from the manufacturer of the equipment by the electrical contractor.
- h. Each main, feeder, and tie breaker with a frame size 400 amps and larger shall have digital electronic trip units.
- i. Where indicated on the drawings, circuit breakers with trip ratings greater than 250 amperes to 1000 amperes shall be UL listed as 100 percent continuous duty rated.

9. Insulated Case Circuit Breakers

- a. Insulated case circuit breakers shall be individually mounted.
- b. Main and tie breakers shall be manually operated, draw out type mounting. Feeder breakers (larger than 1200 amps) shall be manually operated, stationary mounted.
- c. Breakers shall be constructed of a high dielectric strength, glass reinforced insulating case. The interrupting mechanism shall be arc chutes. Steel vent grids shall be used to suppress arcs and cool vented gases. Interphase barriers shall be furnished as to isolate completely each pole.
- d. Breakers shall contain a true two-step stored energy operating mechanism, which shall provide quick make, quick break operation with a maximum five-cycle closing time. Breakers shall be trip free at all times. Common tripping of all poles shall be standard.
- e. Insulated Case circuit breakers shall be rated to carry 100 percent of their frame ampacity continuously.
- f. A charging handle, close push-button, open push-button, and Off/On/Charge indicator shall be located on the breaker escutcheon and shall be visible with the breaker compartment door closed.
- g. Where drawout breakers are specified, the drawout design shall permit the breaker to be withdrawn from an engaged position, to a test position, and to a disengaged position.
- h. Breaker digital electronic trip units shall be as described in Article 10 below.

10. Digital Electronic Trip Unit For Circuit Breakers

- a. Furnish GE MicroVersaTrip® Plus, or PM, or approved equal, digital electronic trip units as specified below.
- b. Each main, feeder, and tie circuit breaker shall be equipped with a digital electronic trip unit. The trip unit shall provide protection from overloads, short circuits and ground faults (for Main circuit breaker). The protective trip unit shall consist of a solid state, microprocessor

based programmer, tripping means, current sensors, power supply and other devices as required for proper operation.

- c. As a minimum, the trip unit shall have the following protective functions:
 - 1. Adjustable current setting or long time pickup;
 - 2. Adjustable long time delay;
 - 3. Adjustable instantaneous pickup;
 - 4. Adjustable ground fault pickup and delay for main.
 - 5. Adjustable short time pickup and delay.

- d. As a minimum, the trip unit shall include the following features:
 - 1. Long time and short time protective functions, if provided, shall have true RMS sensing technology.
 - 2. Ground fault protective function, if provided, shall contain a memory circuit to integrate low level arcing fault currents with time, to sum the intermittent ground fault spikes.
 - 3. High contrast liquid crystal display (LCD) unit shall display settings, trip targets, and the specified metering displays.
 - 4. Multi-button keypad to provide local setup and readout of all trip settings on the LCD.
 - 5. UL Listed interchangeable rating plug. It shall not be necessary to remove the trip unit to change the rating plug.
 - 6. An integral test jack for testing via a portable test set and connection to a battery source.
 - 7. A mechanism for sealing the rating plug and the trip unit.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

8. Noise immunity shall meet the requirements of IEEE C37.90.
 9. Display trip targets for long time, short time, and ground fault, if included.
 10. The trip unit shall include the following metering functions, which shall be displayed on the LCD (if the manufacturer's trip unit can not incorporate the specified functions, separate device(s) with equal function shall be provided for each breaker): Current, RMS, each phase.
11. Finish
- a. All steel surfaces shall be chemically cleaned prior to painting.
 - b. Exterior paint color shall be ANSI 61 Light Gray over phosphate - type rust inhibitor.
12. Accessories
- a. Provide the following UL listed accessories:
 1. Integral, self-powered ground fault protection relay with mechanical ground fault indicator, test function, adjustable current pick - up and time delay, and current sensors as required. Ground fault relay shall have an internal memory circuit that integrates intermittent arcing ground faults with time.
 2. Furnish nameplates for each device as indicated in drawings.
Color schemes shall be as indicated on drawings.
 3. Provide Transient Voltage Surge Suppression system as specified in Section 16479.
13. EXAMINATION
- a. The following procedures shall be performed by the Contractor.

1. Examine installation area to assure there is enough clearance to install switchboard.
2. Check concrete pads for uniformity and level surface.
3. Verify that Spectra Series™ switchboards are ready to install.
4. Verify field measurements that are as shown on Drawings and instructed by manufacturer.
5. Verify that required utilities are available, in proper location and ready for use.
6. Beginning of installation means installer accepts conditions.

14. INSTALLATION

a. Installation shall be performed by the Contractor.

1. Install per manufacturer's instructions.
2. Install required safety labels.

END OF SECTION

Division 16440 Section 26 36 23 Automatic Transfer Switches

PART 1 GENERAL

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Related Sections: Separate electrical components and materials required for field installation and electrical connections are specified in Division 16 (26).

1.01 Scope

Furnish and install automatic transfer switches (ATS) with number of poles, amperage, voltage, and withstand current ratings as shown on the plans. Each automatic transfer shall consist of an inherently double throw power transfer switch unit and a microprocessor controller, interconnected to provide complete automatic operation. All transfer switches and control panels shall be the product of the same manufacturer.

1.02 Acceptable Manufacturers

Automatic transfer switches shall be ASCO, General Electric, Liebert/Emerson, Siemens, Baldor, or Square D. See general and supplementary conditions and Division-1 Specification sections for the way to provide alternates and the way to provide documentation for approvals.

1.03 Codes and Standards

The automatic transfer switches and accessories shall conform to the requirements of:

- A. UL 1008 - Standard for Automatic Transfer Switches
- B. NFPA 70 - National Electrical Code
- C. NFPA 110 - Emergency and Standby Power Systems
- D. IEEE Standard 446 - IEEE Recommended Practice for Emergency and Standby Power Systems for Commercial and Industrial Applications
- E. NEMA Standard ICS10-1993 (formerly ICS2-447) - AC Automatic Transfer Switches
- F. NEC Articles 700, 701, 702
- G. International Standards Organization ISO 9001

PART 2 PRODUCTS

2.01 Mechanically Held Transfer Switch

A. The transfer switch unit shall be electrically operated and mechanically held. The electrical operator shall be a single-solenoid mechanism, momentarily energized. Main operators which include overcurrent disconnect devices will not be accepted. The switch shall be mechanically interlocked to ensure only one of two possible positions, normal or emergency.

B. The switch shall be positively locked and unaffected by momentary outages so that contact pressure is maintained at a constant value and temperature rise at the contacts is minimized for maximum reliability and operating life.

C. All main contacts shall be silver composition. Switches rated 600 amperes and above shall have segmented, blow-on construction for high withstand current capability and be protected by separate arcing contacts.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

D. Inspection of all contacts shall be possible from the front of the switch without disassembly of operating linkages and without disconnection of power conductors. A manual operating handle shall be provided for maintenance purposes. The handle shall permit the operator to manually stop the contacts at any point throughout their entire travel to inspect and service the contacts when required.

E. Designs utilizing components of molded-case circuit breakers, contactors, or parts thereof which are not intended for continuous duty, repetitive switching or transfer between two active power sources are not acceptable.

F. Where neutral conductors must be switched, the ATS shall be provided with fully rated neutral transfer contacts.

G. Where neutral conductors are to be solidly connected, a neutral terminal plate with fully-rated Copper pressure connectors shall be provided.

2.02 Microprocessor Controller with Membrane Interface Panel

A. The controller shall direct the operation of the transfer switch. The controller's sensing and logic shall be controlled by a built-in microprocessor for maximum reliability, minimum maintenance, and inherent serial communications capability. The controller shall be connected to the transfer switch by an interconnecting wiring harness. The harness shall include a keyed disconnect plug to enable the controller to be disconnected from the transfer switch for routine maintenance.

B. The controller shall be enclosed with a protective cover and be mounted separate from the transfer switch unit for safety and ease of maintenance. Sensing and control logic shall be provided on printed circuit boards. Interfacing relays shall be industrial grade plug-in type with dust covers.

C. The controller shall meet or exceed the requirements for Electromagnetic Compatibility (EMC) as follows:

1. ANSI C37.90A/IEEE 472 Voltage Surge Test
2. NEMA ICS – 109.21 Impulse Withstand Test
3. IEC801-2 Electrostatic discharge (ESD) immunity
4. ENV50140 and IEC 801 – 3 Radiated electromagnetic field immunity
5. IEC 801 – 4: Electrical fast transient (EFT) immunity
6. ENV50142: Surge transient immunity
7. ENV50141: Conducted radio-frequency field immunity
8. EN55011: Group 1, Class A conducted and radiated emissions
9. EN61000 –4 – 11 Voltage dips and interruptions immunity

2.03 Enclosure

A. The ATS shall be furnished in a NEMA type 3R enclosure unless otherwise shown on the plans.

B. Provide strip heater with thermostat for Type 3R enclosure requirements.

C. Controller shall be flush-mounted display with LED indicators for switch position and source availability. It shall also include test and time delay bypass switches.

PART 3 OPERATION

3.01 Voltage and Frequency Sensing

- A. The voltage of each phase of the normal source shall be monitored, with pickup adjustable to 95% of nominal and dropout adjustable from 70% to 90% of pickup setting.
- B. Single and three-phase voltage and frequency sensing of the emergency source shall be provided.
- C. All settings shall be adjusted prior to final review of ATS.

3.02 Time Delays

- A. An adjustable time delay shall be provided to override momentary normal source outages and delay all transfer and engine starting signals.
- B. An adjustable time delay shall be provided on transfer to emergency, adjustable from 0 to 5 minutes for controlled timing of transfer of loads to emergency.
- C. An adjustable time delay shall be provided on retransfer to normal, adjustable to 30 minutes. Time delay shall be automatically bypassed if emergency source fails and normal source is acceptable.
- D. A 5-minute cooldown time delay shall be provided on shutdown of engine generator.
- E. All adjustable time delays shall be field adjustable without the use of tools.

3.03 Additional Features

- A. A set of gold-flashed contacts rated 10 amps, 32 VDC shall be provided for a low voltage engine start signal. The start signal shall prevent dry cranking of the engine by requiring the generator set to reach proper output, and run for the duration of the cool down setting, regardless of whether the normal source restores before the load is transferred.
- B. A push-button type test switch shall be provided to simulate a normal source failure.
- C. A push-button type switch to bypass the time delay on transfer to emergency, the engine exerciser period on the retransfer to normal time delay whichever delay is active at the time the push-button is activated.
- D. Terminals shall be provided for a remote contact which opens to signal the ATS to transfer to emergency and for remote contacts which open to inhibit transfer to emergency and/or retransfer to normal.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

E. Auxiliary contacts, rated 10 amps, 480 VAC shall be provided consisting of one contact, closed when the ATS is connected to the normal source and one contact, closed, when the ATS is connected to the emergency source.

F. Indicating lights shall be provided, one to indicate when the ATS is connected to the normal source (green) and one to indicate when the ATS is connected to the emergency source (red). Also provide indicating lights for both normal and emergency source availability.

G. Terminals shall be provided to indicate actual availability of the normal and emergency sources, as determined by the voltage sensing pickup and dropout settings for each source.

H. Engine Exerciser - An engine generator exercising timer shall be provided, including a selector switch to select exercise with or without load transfer. A remote generator start switch shall be provided with the unit.

I. Phase Monitor - A Phase monitor shall be inherently built into the controls. The monitor shall control transfer so that motor load inrush currents do not exceed normal starting currents, and shall not require external control of power sources. The phase monitor shall be specifically designed for and be the product of the ATS manufacturer.

J. Selective Load Disconnect - A double throw contact shall be provided to operate after a time delay, adjustable to 20 seconds prior to transfer and reset 0 to 20 seconds after transfer. This contact can be used to selectively disconnect specific load(s) when the transfer switch is transferred. Output contacts shall be rated 6 amps at 28 VDC or 120 VAC.

Optional Accessories (Options have to be approved by Owner's Representative)

K. Communications Interface - A full duplex RS485 interface to provide remote monitoring and control by communications products.

L. Programmable Engine Exerciser - A seven day electronic time switch for automatic weekly testing of the engine - generator set. The exerciser shall be fully programmable and backed up by a permanent battery.

M. Enclosure Heater - A 125 watt enclosure heater with transformer and thermostat (adjustable from 30° to 140 °F).

N. Networked Computer Monitoring System

A PC based Automatic Transfer Switch (ATS) monitoring system designed to communicate with other ATSS located in remote locations shall be provided. System shall utilize serial communications capability inherent with the ATS microprocessor-based control panel product offering.

PART 4 ADDITIONAL REQUIREMENTS

4.01 Withstand and Closing Ratings

A. The ATS shall be rated to close on and withstand the available rms symmetrical short circuit current at the ATS terminals with the type of overcurrent protection shown on the plans. WCR ATS ratings as be as follows when used with specific circuit breakers:

Rating MCCB	ATS Size Withstand & Closing AIC Rating	W/CLF
30 – 200A	22,000A	200,000
225 – 400A	42,000A	200,000
600 – 1200A	65,000A	200,000
1600 – 2000A	85,000A	200,000
2600 – 3000 A	100,000A	200,000

4.02 Tests and Certification

A. The complete ATS shall be factory tested to ensure proper operation of the individual components and correct overall sequence of operation and to ensure that the operating transfer time, voltage, frequency and time delay settings are in compliance with the specification requirements.

B. Upon request, the manufacturer shall provide a notarized letter certifying compliance with all of the requirements of this specification including compliance with the above codes and standards, and withstand and closing ratings. The certification shall identify, by serial number(s), the equipment involved. No exceptions to the specifications, other than those stipulated at the time of the submittal, shall be included in the certification.

C. The ATS manufacturer shall be certified to ISO 9001 International Quality Standard and the manufacturer shall have third party certification verifying quality assurance in design/development, production, installation and servicing in accordance with ISO 9001.

4.03 Service Representation

A. The ATS manufacturer shall maintain a national service organization of company employed personnel located throughout the contiguous United States. The service center's personnel must be factory trained and must be on call 24 hours a day, 365 days a year.

B. The manufacturer shall maintain records of each switch, by serial number, for a minimum of 20 years.

C. For ease of maintenance and parts replacement, the switch nameplate shall include drawing numbers, part numbers for main coil and control.

End of Section

SECTION 16441 DIVISION 26 36 00 QUICK-CONNECT GENERATOR DOCKING STATIONS

PART 1 GENERAL

1.01 SCOPE

- A. The Contractor shall furnish and install the low-voltage docking station as specified herein and as shown on the contract drawings.

1.02 RELATED SECTIONS

1.03 REFERENCES

- A. The switches and all components shall be designed, manufactured and tested in accordance with the latest applicable standards:
 - 1. NEMA KS-1
 - 2. UL 98

1.04 SUBMITTALS – FOR REVIEW/APPROVAL

- A. The following information shall be submitted to the Engineer:
 - 1. Dimensioned outline drawing
 - 2. Conduit entry/exit locations
 - 3. Switch ratings including:
 - a. Short-circuit rating
 - b. Voltage
 - c. Continuous current
 - 4. Cable terminal sizes
 - 5. Product data sheets

1.05 SUBMITTALS – FOR CONSTRUCTION

- A. The following information shall be submitted for record purposes:
 - 1. Final as-built drawings and information for items listed in Paragraph 1.04, and shall incorporate all changes made during the manufacturing process

1.06 QUALIFICATIONS

- A. The manufacturer of the assembly shall be the manufacturer of the major components within the assembly.
- B. For the equipment specified herein, the manufacturer shall be ISO 9001 or 9002 certified.
- C. The manufacturer of this equipment shall have produced similar electrical equipment for a minimum period of two (2) years. When requested by the Engineer, an acceptable list of installations with similar equipment shall be provided demonstrating compliance with this requirement.

1.07 REGULATORY REQUIREMENTS

- A. The connection docking system shall bear a UL label.

1.08 DELIVERY, STORAGE AND HANDLING

- A. Equipment shall be handled and stored in accordance with manufacturer's instructions. One (1) copy of these instructions shall be included with the equipment at time of shipment.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Eaton / Cutler-Hammer products
- B. Trystar
- C. Siemens

The listing of specific manufacturers above does not imply acceptance of their products that do not meet the specified ratings, features and functions. Manufacturers listed above are not relieved from meeting these specifications in their entirety. Products in compliance with the specification and manufactured by others not named will be considered only if pre-approved by the Engineer and Owner's Representative ten (10) days prior to bid date.

2.02 HEAVY-DUTY DOCKING STATION

- A. Provide switches as shown on drawings, with the following ratings:
 - 1. 2000 amperes
 - 2. 480 volts ac, dc; 600 volts ac
 - 3. 4 poles.
 - 4. Mechanical lugs suitable for aluminum or copper conductors.
- B. Construction
 - 1. Docking Station shall be equipped with a separate interlocked receptacle compartment containing receptacles for quick-connection and disconnection of portable cord-connected equipment.
 - a. Interlock shall prevent the lower generator switch from being closed while cable compartment door is open, and shall prevent the door from being opened while the switch is closed.
 - b. Compartment shall be equipped with a spring-assisted door to allow portable cords to exit the compartment while in use, but shall close when not in use to effectively seal the compartment to prevent insects and small animals from entry.
 - c. Compartment shall be equipped with receptacles for sufficient cable connection for the ampacity of the switch.
 - d. Receptacles for switches 200 amps and greater shall be of the single cable per phase design – utilizing quarter turn cam type connections.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

- e. Receptacles shall be: Either *Posi-Lok* or *Cam-Lok* type. 800 amp switches shall employ parallel receptacles.
 2. Renewal parts data shall be shown on the inside of the door
- C. Enclosures
1. All enclosures shall be NEMA 3R rainproof
 2. Paint color shall be ANSI 61 gray or "Owner's Representative's" Choice.
- D. The following factory modifications are to be included:
1. *Plastic* or *Phenolic* nameplates
 2. Special paint color as request by "Owner's Representative."
 3. Lock ON provisions
 4. Key interlock system
 5. Factory installed neutral assemblies
 6. Factory installed copper lugs
 7. Factory installed auxiliary contacts
 8. Cover mounted controls *indicating lights, selector switches, or pushbuttons.
 9. Factory installed UL listed switching neutral bonding kit for 3 or 4pole systems that require a switching neutral.

PART 3 EXECUTION

3.01 FACTORY TESTING

- A. Standard factory tests shall be performed on the equipment provided under this section. All tests shall be in accordance with the latest version of UL and NEMA standards.

3.02 INSTALLATION

- A. The equipment shall be installed per the manufacturer's recommendations and all NEC and local code requirements.

End of Section 16441 Division 26 36 00

Division 16442 Section 26 36 22 Manual Transfer Switches

PART 1 GENERAL

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Related Sections: Separate electrical components and materials required for field installation and electrical connections are specified in Division 16 (26).

1.01 Scope

Furnish and install manual transfer switches (MTS) with number of poles, amperage, voltage, and withstand current ratings as shown on the plans. Each manual transfer switch shall consist of an inherently double throw power transfer switch. All transfer switches and control panels shall be the product of the same manufacturer.

1.02 Acceptable Manufacturers

Automatic transfer switches shall be ASCO, General Electric, Liebert/Emerson, Siemens, Baldor, Caterpillar, or Square D. See general and supplementary conditions and Division-1 Specification sections for the way to provide alternates and the way to provide documentation for approvals.

1.03 Codes and Standards

The transfer switches and accessories shall conform to the requirements of:

- A. UL Standard for Transfer Switches
- B. NFPA 70 - National Electrical Code
- C. NFPA 110 - Emergency and Standby Power Systems
- D. IEEE Standard 446 - IEEE Recommended Practice for Emergency and Standby Power Systems for Commercial and Industrial Applications
- E. NEC Articles 700, 701, 702
- F. International Standards Organization ISO 9001

PART 2 PRODUCTS

2.01 Mechanically Held Transfer Switch

A. The transfer switch unit shall be electrically operated and mechanically held. The electrical operator shall be a single-solenoid mechanism, momentarily energized. Main operators which include overcurrent disconnect devices will not be accepted. The switch shall be mechanically interlocked to ensure only one of two possible positions, normal or emergency.

B. The switch shall be positively locked and unaffected by momentary outages so that contact pressure is maintained at a constant value and temperature rise at the contacts is minimized for maximum reliability and operating life.

C. All main contacts shall be silver composition. Switches rated 600 amperes and above shall have segmented, blow-on construction for high withstand current capability and be protected by separate arcing contacts.

D. Inspection of all contacts shall be possible from the front of the switch without

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

disassembly of operating linkages and without disconnection of power conductors. A manual operating handle shall be provided for maintenance purposes. The handle shall permit the operator to manually stop the contacts at any point throughout their entire travel to inspect and service the contacts when required.

E. Designs utilizing components of molded-case circuit breakers, contactors, or parts thereof which are not intended for continuous duty, repetitive switching or transfer between two active power sources are not acceptable.

F. Where neutral conductors must be switched, the MTS shall be provided with fully rated neutral transfer contacts.

G. Where neutral conductors are to be solidly connected, a neutral terminal plate with fully-rated Copper pressure connectors shall be provided.

2.02 Enclosure

A. The MTS shall be furnished in a NEMA type 3R enclosure unless otherwise shown on the plans.

B. Provide strip heater, if required, with thermostat for Type 3R enclosure requirements.

C. Controller shall be flush-mounted display with LED indicators for switch position and source availability. It shall also include test and time delay bypass switches.

PART 3 OPERATION

3.01 Voltage and Frequency Sensing

A. The voltage of each phase of the normal source shall be monitored, with pickup adjustable to 95% of nominal and dropout adjustable from 70% to 90% of pickup setting.

B. Single and three-phase voltage and frequency sensing of the emergency source shall be provided.

C. All settings shall be adjusted prior to final review of MTS.

3.02 Time Delays

A. An adjustable time delay shall be provided to override momentary normal source outages and delay all transfer and engine starting signals.

B. An adjustable time delay shall be provided on transfer to emergency, adjustable from 0 to 5 minutes for controlled timing of transfer of loads to emergency.

C. A 5-minute cooldown time delay shall be provided on shutdown of engine generator.

D. All adjustable time delays shall be field adjustable without the use of tools.

Manatee County Desoto Center
Sheriff's Office Generator Disconnect

3.03 Additional Features

A. A set of gold-flashed contacts rated 10 amps, 32 VDC shall be provided for a low voltage engine start signal. The start signal shall prevent dry cranking of the engine by requiring the generator set to reach proper output, and run for the duration of the cool down setting, regardless of whether the normal source restores before the load is transferred.

B.. Terminals shall be provided for a signal to show main and emergency power options.

C. Auxiliary contacts, rated 10 amps, 480 VAC shall be provided consisting of one contact, closed when the MTS is connected to the normal source and one contact, closed, when the MTS is connected to the emergency source.

D. Indicating lights shall be provided, one to indicate when the MTS is connected to the normal source (green) and one to indicate when the MTS is connected to the emergency source (red). Also provide indicating lights for both normal and emergency source availability.

E. Terminals shall be provided to indicate actual availability of the normal and emergency sources, as determined by the voltage sensing pickup and dropout settings for each source.

F. Engine Exerciser - An engine generator exercising timer shall be provided, including a selector switch to select exercise with or without load transfer. A remote generator start switch shall be provided with the unit.

G. Phase Monitor - A Phase monitor shall be inherently built into the controls. The monitor shall control transfer so that motor load inrush currents do not exceed normal starting currents, and shall not require external control of power sources. The phase monitor shall be specifically designed for and be the product of the ATS manufacturer.

Optional Accessories (Options have to be approved by Owner's Representative)

H. Communications Interface - A full duplex RS485 interface to provide remote monitoring and control by communications products.

I. Programmable Engine Exerciser - A seven day electronic time switch for automatic weekly testing of the engine - generator set. The exerciser shall be fully programmable and backed up by a permanent battery.

J. Enclosure Heater - A 125 watt enclosure heater with transformer and thermostat (adjustable from 30°to 140.°F).

K. Networked Computer Monitoring System

A PC based Manual Transfer Switch (MTS) monitoring system designed to communicate with other ATSS located in remote locations shall be provided. System shall utilize serial communications capability inherent with the MTS microprocessor-based control panel product offering.

PART 4 ADDITIONAL REQUIREMENTS

4.01 Withstand and Closing Ratings

A. The MTS shall be rated to close on and withstand the available rms symmetrical short circuit current at the ATS terminals with the type of overcurrent protection shown on the plans. WCR MTS ratings as be as follows when used with specific circuit breakers or fuses:

Rating MCCB	MTS Size Withstand & Closing AIC Rating	W/CLF
30 – 200A	22,000A	200,000
225 – 400A	42,000A	200,000
600 – 1200A	65,000A	200,000
1600 – 2000A	85,000A	200,000
2600 – 3000 A	100,000A	200,000

4.02 Tests and Certification

A. The complete MTS shall be factory tested to ensure proper operation of the individual components and correct overall sequence of operation and to ensure that the operating transfer time, voltage, frequency and time delay settings are in compliance with the specification requirements.

B. Upon request, the manufacturer shall provide a notarized letter certifying compliance with all of the requirements of this specification including compliance with the above codes and standards, and withstand and closing ratings. The certification shall identify, by serial number(s), the equipment involved. No exceptions to the specifications, other than those stipulated at the time of the submittal, shall be included in the certification.

C. The MTS manufacturer shall be certified to ISO 9001 International Quality Standard and the manufacturer shall have third party certification verifying quality assurance in design/development, production, installation and servicing in accordance with ISO 9001.

4.03 Service Representation

A. The MTS manufacturer shall maintain a national service organization of company employed personnel located throughout the contiguous United States. The service center's personnel must be factory trained and must be on call 24 hours a day, 365 days a year.

B. The manufacturer shall maintain records of each switch, by serial number, for a minimum of 20 years.

C. For ease of maintenance and parts replacement, the switch nameplate shall include drawing numbers, part numbers for main coil and control.

End of Section

Division 16443 Section 26 36 23 - Disconnect Switches

Introduction

Disconnect switches shall be used where required to meet OSHA standards for a disconnecting means within line of sight and no more than fifty feet of the actual piece of equipment being controlled.

1. All disconnect switches shall be heavy duty motor rated switches.
2. All disconnect switches required for compliance with OSHA shall be lockable.
3. A disconnect switch is not to be used as a substitute for a motor starter but should be used in conjunction with all motor starters where required as a disconnecting means.

Part 1 - General

- Acceptable manufacturer's should include GE, Square D, Cutler Hammer, Allen Bradley and approved equal. Try to accommodate the County by matching existing manufactured products.

Part 2 - Products

- Safety switches shall be heavy-duty motor rated with fuses provided to protect downline equipment where required.
- Switches shall be fused, if required.
- The extra fuses (minimum of 2 per phase) shall be supplied by the contractor.
- The neutral shall be switched.
- NEMA 3R Environments shall be specified as NEMA 3R/12 gasketed.

Part 3 - Execution

- The maximum mounting height for safety switches should be 6'0" to the top. Safety switches should be rigidly mounted in place.
- Must be *readily* accessible per NEC
- Label per NEC Requirements and specification documents.

End of Section 16443

Division 16479 SECTION 26 43 00 – TRANSIENT VOLTAGE SURGE SUPPRESSION (SPD)

A. SECTION INCLUDES

1. Transient voltage surge suppression systems integrated into electrical distribution equipment.

B. RELATED SECTIONS

1. 26 20 00 (16400) Low Voltage Switchgear
2. 26 27 00 (16402) Low Voltage Group Mounted Switchboards
3. 26 29 19 Motor Control Centers (Not Used)

C. REFERENCES

1. The equipment and components in this specification shall be designed and manufactured according to latest revision of the following standards (unless otherwise noted).
 - a. ANSI/IEEE C62.41.1-2002, Guide on the Surge Environment in Low Voltage AC Power Circuits.
 - b. ANSI/IEEE C62.41.2-2002, Recommended Practice on Characterization of Surges in Low Voltage AC Power Circuits.
 - c. ANSI/IEEE C62.45-2002, Recommended Practice on Surge Testing for Equipment Connected to Low Voltage AC Power Circuits.
 - d. UL 1449, Third Edition - Transient Voltage Surge Suppressors
 - e. UL 1283, Electromagnetic Interference Filters
 - f. UL 67, Panelboards
 - g. UL 891, Dead-Front Switchboards
 - h. NEMA LS-1 (1992), Low Voltage Surge Protective Devices
 - i. NFPA 70 National Electrical Code – Article 285

D. SYSTEM DESCRIPTION

1. Transient voltage surge suppression devices shall be applied on a 277/ 480 volt or 120/208 volt, 60 Hertz, 3 phase, 4- wire, solidly grounded WYE system, as indicated on drawings.

E. SUBMITTALS

1. Manufacturer shall provide 3 copies of the following documents to owner for review and evaluation.
 - a. Product Data on specified product:
 1. Maximum surge current rating
 2. Repetitive surge current rating
 3. UL1449 Third Edition Suppressed Voltage Ratings
 - b. Upon request, provide copies of third party test reports for maximum surge current rating and repetitive surge current rating.

F. INSTALLATION, OPERATION AND MAINTENANCE DATA

1. Manufacturer shall provide 3 copies of installation, operation and maintenance procedures to owner.
2. Transient voltage surge suppression systems shall be listed/or recognized by Underwriters Laboratories in accordance with the applicable standards found in Section C-1 of this specification. UL recognized TVSS assemblies are allowed provided they have been investigated by UL as suitable for use within the specified electrical panel or gear and do not require additional testing or field investigation to maintain the equipment's UL listing.
3. Manufacturer warrants equipment to be free from defects in materials and workmanship for 5 years from date of purchase.

G. PRODUCTS

1. General Electric Company products have been used as the basis for design. Other manufacturers' products of equivalent quality, dimensions and operating features may be acceptable, at the Engineer's discretion; if they comply with all requirements specified or indicated in these Contract documents.

2. Furnish General Electric internally or equal external mounted TVSS systems as indicated in drawings.
3. Refer to Drawings for: actual layout and location of equipment and components; current ratings of devices, bus bars, and components; voltage ratings of devices, components and assemblies; and other required details.

a. Electrical Requirements

1. The maximum surge current rating shall be based on testing of a complete TVSS unit including fuses and all components that make up the TVSS system. Devices that derive a maximum surge current rating by adding test results of individual components are not acceptable.
2. The TVSS device repetitive surge current capacity shall be tested utilizing an 8x20us, 10kA short circuit Category C High test waveform (as defined by ANSI/IEEE C62.41.2-2002) at one-minute intervals. A failure is defined as either performance degradation or more than 10% deviation of clamping voltage at the specified surge current
3. Maximum surge current and repetitive surge current ratings shall be as follows:

For Switchgear and switchboards rated 1600A and greater:

- a. Maximum surge current rating: 150/300kA per mode.
- b. Repetitive surge current rating: 20,000 C High impulses.

For Motor Control Centers rated 1200A and below:

- a. Maximum surge current rating: 150 kA SCCR.
- b. Repetitive surge current rating: 5,000 C High impulses

For Lighting panels rated 1200A and below:

- a. Maximum surge current rating: 65 kA per mode.
- b. Repetitive surge current rating: 5,000 C High impulses

4. The Suppression Voltage Rating (SVR) shall be tested in accordance with UL-1449, Third Edition. Where an integral disconnect is provided, the TVSS SVR shall be determined with the integral disconnect. The SVR values shall not exceed the following: L-N, N-G, L-G-800; L-L--1500.
5. The TVSS fault current rating shall be marked on the TVSS in accordance with the requirements of UL1449 and NEC Article 285.
6. The use of electronic grade MOV's is not acceptable. Systems using gas tubes, silicon avalanche diodes, selenium rectifiers, or printed circuit board technology in surge current path are not acceptable.
7. The TVSS shall provide protection in each of the following modes: L-N, L-G, N-G, and L-L for WYE Systems. L-G and L-L for Delta Systems.
8. The Maximum Continuous Operating Voltage (MCOV) for all voltage configurations shall be at least 115% of nominal on 480/277 volt systems and 125% of nominal on 240-208/120 volt systems.
9. The fusing system shall be capable of allowing the rated maximum surge current to pass through without fuse operation. Systems utilizing a fusing system that opens below the maximum surge current level are unacceptable. The complete TVSS fusing system shall be included in the surge current testing.
10. TVSS systems shall include integral fusing for all suppression components. TVSS designs that rely solely on an electrical panel's main breaker to interrupt phase currents resulting from a shorted suppression component are not allowed.
11. Use of plug-in modules, gas discharge devices or selenium rectifiers is unacceptable.
12. TVSS installed in switchgear, switchboards, and power panels shall have an integral non-fused disconnect, tested to the maximum surge current rating of the device. TVSS installed in lighting panels shall be direct connected to the main bus.

13. Standard Monitoring features
 - a. One operational status indicating light per each protected phase.
 - b. Audible alarm and alarm indicating light and test switch, enabled via a front panel pushbutton switch.
 - c. Dry contacts for remote monitoring purposes, 1NO & 1NC contact. Change in state on MOV failure.
 - d. Transient voltage surge counter with battery backup.

b. Mounting

1. TVSS shall be mounted integral or external, and shall not violate the equipment manufacturer's UL label.

END OF SECTION

Division 16660 SECTION 26 28 00 - GROUND-FAULT PROTECTION SYSTEMS

A. PROJECT INCLUDES

1. Ground-fault sensing, relaying, tripping, and alarm devices for installation in distribution switchboards and panelboards rated 600 volts and less.

B. PRODUCTS

1. Ground-Fault Sensing Devices:

- a. Outgoing-Circuit Current Sensors: Current transformer with circuits requiring outgoing-circuit sensing method.
- b. Ground-Return Current Sensors: Current transformer for encircling main bonding jumper connection.
- c. Short Circuit Rating: 200,000 amperes RMS symmetrical.
- d. Outputs: Compatible with relay inputs.

2. Ground-Fault Relays and Monitors:


- a. Ground-Fault Relay: Solid-state type without external electrical power supply required for relay.
- b. Monitor Panels: Ground-fault indicators, control-power indicators, test and reset buttons.

3. Manufacturers


- a. Eaton
- b. Siemens
- c. GE
- d. Square D
- e. or approved equal

END OF SECTION

DESOTO CENTER MANATEE COUNTY GOVERNMENT 600 301 BOULEVARD WEST BRADENTON, FLORIDA 34205 IFAS# W1200286, WORK ASSIGNMENT #66



LOCATION MAP
FLORIDA



SITE MAP

SHEET SCHEDULE

SHEET	DESCRIPTION
COVER	PROJECT NAME, LOCATION & SITE MAP
E0.0	LEGEND, SYMBOLS, GENERAL NOTES & SPECIFICATIONS
E1.0	ELECTRICAL EQUIPMENT LAYOUT, ONE-LINE RISER DIAGRAM
E2.0	FEEDER SCHEDULE AND DETAILS

To the best of the engineer's knowledge, said plans and specifications comply with the applicable building codes and the applicable minimum fire safety standards as determined in accordance with Chapters 553 and 633, Florida Statutes.

 ATP ENGINEERING SOUTH, PL SARASOTA, FLORIDA ENGR. BUSINESS #8908 941-360-2181	SEAL
--	------

ELECTRICAL SYMBOLS AND ABBREVIATIONS

NOTE:

THESE ARE STANDARD SYMBOLS AND MAY NOT ALL APPEAR ON THE PROJECT DRAWINGS; HOWEVER WHEREVER THE SYMBOL APPEARS ON THE PROJECT DRAWINGS, THE ITEM SHALL BE PROVIDED AND INSTALLED.

ABBREVIATIONS

A	AMPERE
AC	AIR CONDITIONING OR ALTERNATING CURRENT
ACC	ACCESS
AF	AMPERE FRAME
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AHJ	AUTHORITY HAVING JURISDICTION
AHU	AIR HANDLER UNIT
AM	AMMETER
ARCH	ARCHITECT
AT	AMPERE TRIP
ATC	AUTOMATIC TEMPERATURE CONTROL
ATS	AUTOMATIC TRANSFER SWITCH
AWG	AMERICAN WIRE GAUGE
C	CONDUIT
CAT	CATEGORY
CB	CIRCUIT BREAKER
CH	CHILLER
CKT	CIRCUIT
CL	CENTER LINE
CLF	CURRENT-LIMITING FUSE
CM	CEILING MOUNTED
CNTL	CONTROL
CU	COPPER
DWG(S)	DRAWING(S)
EC	ELECTRICAL CONTRACTOR
EF	EXHAUST FAN
EM	EMERGENCY
EMS	ENERGY MANAGEMENT SYSTEM
EMT	ELECTRICAL METALLIC TUBING
EPO	EMERGENCY POWER OFF
EW	ELECTRIC WATER COOLER
EMH	ELECTRIC WATER HEATER
EX	EXISTING TO REMAIN
FA	FIRE ALARM
FACP	FIRE ALARM CONTROL PANEL
FACC	FIRE ALARM COMMAND CENTER
FATC	FIRE ALARM TERMINAL CABINET
FLR	FLOOR
FMC	FURNISHED BY MECHANICAL CONTRACTOR
FO	FIBER OPTIC
FOTC	FIBER OPTIC TERMINAL CABINET
FSS	FIRE SUPPRESSION SYSTEM
FWE	FURNISHED WITH EQUIPMENT
GFI	GROUND FAULT INTERRUPTER
GND,G	GROUND
GRS	GALVANIZED RIGID STEEL CONDUIT
HOA	HAND-OFF-AUTO
HACR	HEATING/AIR CONDITIONING-RATED
HID	HIGH INTENSITY DISCHARGE
HPF	HIGH POWER FACTOR
HPS	HIGH PRESSURE SODIUM
HZ	HERTZ
HP	HORSEPOWER
IG	ISOLATED GROUND
IMC	INTERMEDIATE METALLIC CONDUIT
JB	JUNCTION BOX
KCMIL	THOUSAND CIRCULAR MILS
KVA	KILOVOLT AMPERE
KW	KILOWATT
LC	LIGHTING CONTACTOR
MC	MECHANICAL CONTRACTOR
MCC	MOTOR CONTROL CENTER
M-G	MOTOR GENERATOR
MDP	MAIN DISTRIBUTION PANEL
MH	METAL HALIDE
MOD	MOTOR OPERATED DAMPER OR DOOR
MTD	MOUNTED
NC	NORMALLY CLOSED
NEC	NATIONAL ELECTRICAL CODE
NEMA	NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION
NF	NON-FUSED
NFPA	NATIONAL FIRE PROTECTION ASSOCIATION
NIC	NOT IN CONTRACT
NL	NIGHT LIGHT
NO	NORMALLY OPEN
NTS	NOT TO SCALE
OCPO	OVER CURRENT PROTECTIVE DEVICE
PNL	PANEL
Ø	PHASE
PB	PUSHBUTTON
PE	PHOTOELECTRIC CONTROLLER
PP	PATCH PANEL
PVC	POLYVINYL CHLORIDE CONDUIT
R	RELOCATED
RTU	ROOF TOP UNIT
SCH	SCHEDULE
SEC	SECURITY
SW	SWITCH
SWGR	SWITCHGEAR
TEL,T	TELEPHONE
TBB	TELEPHONE BACKBOARD
TVSS	TRANSIENT VOLTAGE SURGE SUPPRESSOR
TC	TIME CLOCK
XFMR	TRANSFORMER
XFR	TRANSFER
TYP	TYPICAL
UG	UNDERGROUND
UH	UNIT HEATER
UL,U.L.	UNDERWRITERS LABORATORIES
UPS	UNINTERRUPTIBLE POWER SUPPLY
U.O.N.	UNLESS OTHERWISE NOTED
VT	VAPORTIGHT
VAV	VARIABLE AIR VOLUME
VFD	VARIABLE FREQUENCY DRIVE
VSD	VARIABLE SPEED DRIVE
V	VOLT
VM	VOLTMETER
W	WATT
WHM	WATTHOUR METER
WM	WATTMETER
WP	WEATHER PROOF

EQUIPMENT

SYMBOL	DESCRIPTION
	DISTRIBUTION PANELBOARD AND CABINET - RECESSED MOUNT
	DISTRIBUTION PANELBOARD AND CABINET - SURFACE MOUNT
	BRANCH PANELBOARD AND CABINET - RECESSED MOUNT
	BRANCH PANELBOARD AND CABINET - SURFACE MOUNT
	LOAD CENTER - SURFACE MOUNT
	LOAD CENTER - RECESSED MOUNT
	DENOTES PANEL/PANELBOARD DESIGNATION
	DISCONNECT SWITCH - FUSED "X" = RATING, "Y" = FUSE SIZE
	DISCONNECT SWITCH - NON-FUSED
	DISCONNECT SWITCH - CIRCUIT BREAKER
	DRY TYPE TRANSFORMER - "XX" INDICATES KVA
	GROUND CONNECTION
	MOLDED CASE CIRCUIT BREAKER
	FUSE
	SPECIAL RECEPTACLE - SEE DRAWINGS AND SPECIFICATIONS.
	DATA OUTLET

RACEWAY SYSTEM

SYMBOL	DESCRIPTION
	CONCEALED CONDUIT
	4" CONDUIT SLEEVE WITH BUSHINGS THRU WALL ABOVE CEILING
	FLOOR BOX TYPE 1. SEE TYPICAL DETAILS FOR CONDUIT REQUIREMENTS
	LETTER DESIGNATION REFERS TO SYSTEM (SEE ABBREVIATIONS)
	PHASE CONDUCTORS QUANTITY OF CONDUCTORS OR CABLES IN CONDUIT
	"FSO" DENOTES THE FEEDER SIZE
	"A-XX" DENOTES PANEL AND CIRCUIT #
	CONDUIT TURNED UP
	CONDUIT TURNED DOWN
	JUNCTION OR PULL BOX
	CABLE TRAY
	U/G CONDUIT TURNED UP
	U/G CONDUIT TURNED DOWN

DRAWING SYMBOLS

	DETAIL NUMBER
	DRAWING NUMBER WHERE DRAWN
	SECTION LETTER
	DRAWING NUMBER WHERE DRAWN
	REFER TO LIKE NUMBER NOTES.
	REFER TO LIKE NUMBER NOTES.

SPECIFICATIONS:

(APPLY TO ALL ELECTRICAL SHEETS)

- PROVIDE AND INSTALL NEW GREEN INSULATED COPPER GROUNDING CONDUCTORS AS THE EQUIPMENT GROUNDING MEANS FOR ALL ELECTRICAL EQUIPMENT.
- PROVIDE LABELING FOR ALL PANELBOARDS, SWITCHBOARDS, AND DISCONNECT SWITCHES TO INCLUDE AN ENGRAVED PLASTIC LABEL IDENTIFYING THE EQUIPMENT AND WHERE IT IS FED FROM. ALL BRANCH DEVICES IN THE MAIN SWITCHBOARD SHALL HAVE AN ENGRAVED PLASTIC LABEL. ALL PANELBOARDS SHALL INCLUDE A TYPEWRITTEN DIRECTORY. ALL JUNCTION BOX COVERS SHALL BE IDENTIFIED TO INDICATE CIRCUITS CONTAINED.
- ALL CONDUIT INSTALLED ABOVE GRADE OUTSIDE THE BUILDING SHALL BE GALVANIZED RIGID STEEL. NO PVC CONDUIT SHALL BE USED ABOVE THE FLOOR SLAB.
- ALL ELECTRICAL CONNECTORS, LUGS, BREAKERS, EQUIPMENT, ETC. SHALL BE RATED AT A MINIMUM OF 75 DEG. C.
- WIRING METHODS:
ALL WIRING SHALL BE COPPER. NO ALUMINUM WIRING WILL BE ALLOWED.
MC TYPE CABLE SHALL NOT BE USED.

CIRCUIT WIRING AND PANELBOARD FEEDERS SHALL BE TYPE THHN/THWN WIRING INSTALLED IN CONDUIT.

GENERAL NOTES:

(APPLY TO ALL ELECTRICAL SHEETS)

- PROVIDE COMPLETE AND OPERATIONAL ELECTRICAL SYSTEM.
- ALL WORK SHALL CONFORM TO OR EXCEED THE MINIMUM REQUIREMENTS OF THE CURRENT ANSI/NFPA 70 WITH STATE OF FLORIDA AMENDMENTS, ANSI/IEEE C2 AND ALL FEDERAL, STATE, LOCAL, AND MUNICIPAL CODES AND ORDINANCES. THE ELECTRICAL SUBCONTRACTOR SHALL COMPLY WITH THE DIRECTIONS OF ALL AUTHORITIES HAVING JURISDICTION.
- INSTALL WORK USING PROCEDURES DEFINED IN NEC STANDARDS OF INSTALLATION. ALL WORK SHALL PRESENT A NEAT MECHANICAL APPEARANCE WHEN COMPLETED.
- THE ELECTRICAL SUBCONTRACTOR SHALL PROVIDE ALL FLOOR, WALL, AND CEILING PENETRATIONS TO COMPLETE HIS WORK. PROVIDE APPROPRIATE SEALANT (I.E. FIRESAFTING) TO MAINTAIN CONSTRUCTION INTEGRITY FOR ANY PENETRATIONS THROUGH FLOORS, STRUCTURAL CEILINGS, AND FIRE WALLS.
- COORDINATE ALL ELECTRICAL SYSTEM DOWNTIME WITH THE OWNER, PERFORMANCE SERVICES, AND OTHER TRADES. DOWNTIME OF THE SYSTEM SHALL BE MINIMIZED. WEEKEND AND AFTER HOUR WORK SHALL BE REQUIRED TO PREVENT OR MINIMIZE INTERFERENCE WITH THE OWNER'S OPERATION.
- THE LOCATIONS OF NEW EQUIPMENT SHOWN ON THESE DRAWINGS ARE APPROXIMATE. FINAL LOCATIONS WILL BE DETERMINED DURING THE CONSTRUCTION PHASE.
- ALL NEW EQUIPMENT SHALL BE SUBMITTED FOR APPROVAL PRIOR TO ORDERING.
- ALL BRANCH CIRCUITS SHALL UTILIZE SEPARATE INDEPENDENT NEUTRAL CONDUCTOR, AND INSULATED GROUNDING CONDUCTOR. DO NOT COMBINE NEUTRAL CONDUCTORS.
- ALL FEEDER NEUTRAL/GROUNDED CONDUCTORS SHALL BE CONSIDERED CURRENT CARRYING. DERATE MULTIPLE CONDUCTORS IN A RACEWAY ACCORDINGLY WITH NEC TABLES.
- INSTALL ALL CONDUITS, RACEWAYS, AND CABLE TRAY FOR MAXIMUM HEAD CLEARANCE IN MECHANICAL AREAS, AND ATTIC. COORDINATE CLEARANCES WITH PERFORMANCE SERVICES AND THE OWNER.
- ALL ELECTRICAL SERVICE WORK SHALL COMPLY WITH THE LOCAL UTILITY. COORDINATE ALL REQUIREMENTS AND MAXIMUM AVAILABLE FAULT CURRENT PRIOR TO BID AND INCLUDE ALL NECESSARY MATERIAL AND LABOR REQUIRED FOR THE ADDITION TO THE ELECTRICAL SERVICE. ADD UTILITY FEES TEXT.

GENERAL NOTES:


(APPLY TO ALL ELECTRICAL SHEETS)

- THE WORK INDICATED ON THESE DRAWINGS IS DIAGRAMMATIC AND IS INTENDED TO CONVEY THE SCOPE OF WORK AND INDICATE THE GENERAL ARRANGEMENT OF EQUIPMENT AND DEVICES FOR A COMPLETE SYSTEM IN EVERY RESPECT AND DETAIL. TESTED AND LEFT READY IN PERFECT OPERATING CONDITION FOR THE OWNER'S USE. MATERIALS AND EQUIPMENT SHALL BE LISTED BY UNDERWRITERS' LABORATORIES AND SHALL BE INSTALLED IN ACCORDANCE WITH SUCH LISTINGS. INSTALLATIONS SHALL BE MADE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. WORK SHALL MEET THE REQUIREMENTS OF THE SPECIFICATIONS AND CONFORM TO THE NEC (NFPA 70 & 72) AND ALL APPLICABLE CODES, AND BE COMPLETED BY A QUALIFIED, EXPERIENCED, LICENSED ELECTRICAL CONTRACTOR.
- WHEN A CONFLICT OCCURS BETWEEN THE SPECIFICATIONS AND DRAWINGS, THE ITEMS OF GREATER QUANTITY AND/OR COST SHALL BE PROVIDED.
- ALL OPENINGS IN FIRE AND SMOKE PARTITIONS SHALL BE SEALED AS REQUIRED BY THE NEC/ FLORIDA BUILDING CODE. PROVIDE UL LISTED COMPOUND TO MATCH PARTITION RATING.
- DO NOT SCALE DRAWINGS. VERIFY FIELD CONDITIONS PRIOR TO AND DURING CONSTRUCTION FOR EXACT DEVICE / EQUIPMENT LOCATION.
- CONTRACTOR SHALL PROVIDE TO LOCAL AHJ OR PERMITTING AGENCY A COPY OF ALL MAJOR EQUIPMENT CUT SHEETS AT TIME OF APPLICATION IF REQUESTED.

THESE DOCUMENTS HAVE BEEN PREPARED BASED ON INFORMATION PROVIDED BY OTHERS. THE CONSULTANT HAS NOT VERIFIED THE ACCURACY AND/OR COMPLETENESS OF THIS INFORMATION AND SHALL NOT BE RESPONSIBLE FOR ANY ERRORS OR OMISSIONS THAT MAY BE INCORPORATED AS A RESULT OF ERRONEOUS INFORMATION PROVIDED BY OTHERS. NOTIFY THIS ENGINEER IMMEDIATELY OF ANY DISCREPANCIES FOUND.

SCALE

ATP ENGINEERING SOUTH, FL
SARASOTA, FLORIDA
ENGR. BUSINESS #8908
941-360-2181



DATE	DESCRIPTION

DE SOTO CENTER

MANATEE COUNTY GOVERNMENT

600 301 BOULEVARD WEST

BRADENTON, FLORIDA 34205


IFAS# W1200286, WORK ASSIGNMENT #66

DRAWING TITLE:

ELECTRICAL SYMBOLS, LEGEND, SPECIFICATIONS AND GENERAL NOTES


FILE:	M.C. DeSoto Center
JOB NO.:	2012.63
DATE :	08/23/2012
PLOT SIZE:	1:1
DRAWN BY:	CMD
CHECKED BY:	JDC
SHEET No.:	

E0.0




3 PARTIAL ONE-LINE RISER DIAGRAM
PORTABLE GENERATOR CONNECTION ONLY

ALL NEW EQUIPMENT SHALL BE RATED AT MINIMUM 65KAIC TO MATCH EXISTING EQUIPMENT.



4 GENERATOR SIGNAL SWITCH DIAGRAM
NTS



2 PORTABLE GENERATOR CONNECTION
1/4" = 1'-0"

LEGEND:

- ITEMS IN GRAYSSCALE ARE EXISTING.
- ITEMS BOLD ARE NEW.
- TO BE REMOVED
- CONTROL WIRING - 3/4" C W/
18AWG HOT & NEUTRAL

PLAN NOTES:


- 1 REMOVE EXISTING GENERATOR DISTRIBUTION PANEL.
- 2 PORTABLE GENERATOR DISCONNECT. LABEL "PORTABLE GENERATOR DISCONNECT, NEUTRAL IS SWITCHED".
- 3 DISCONNECT FOR HEATER. LABEL "HEATER DISCONNECT" AND WITH LOCATION OF HEATER.
- 4 MANUAL TRANSFER SWITCH. LABEL WITH SIZE AND "PORTABLE GENERATOR TRANSFER SWITCH"
- 5 GENERATOR DISTRIBUTION PANEL WITH 1000A AND 600A CIRCUIT BREAKERS. LABEL "GENERATOR DISTRIBUTION PANEL".
- 6 REMOVE EXISTING DOOR AND REINSTALL TO SWING OUT.
- 7 CONNECTION TO BUSS BAR ON GENERATOR BY GENERATOR SERVICE COMPANY.
- 8 WALL PENETRATION THROUGH ENCLOSURE. PENETRATION INTO THE ENCLOSURE SHALL BE MADE THROUGH THE WALL. NO PENETRATIONS SHALL BE MADE THROUGH THE ROOF OF THE ENCLOSURE. SEAL ENCLOSURE WALL PENETRATIONS AND FLASH WITH 22 GA. PAINTED COVER.
- 9 TERMINAL STRIP IN NEMA 3R ENCLOSURE, FOR PORTABLE GENERATOR START SIGNAL.
- 10 MANUAL DOUBLE POLE / DOUBLE THROW SWITCH WITH LOCKABLE PLASTIC COVER FOR GENERATOR START SIGNALS. SEE DETAIL 4 ON THIS SHEET.

GENERAL NOTES:

- PORTABLE GENERATOR CONNECTION**
- PROVIDE AND INSTALL:
 - (1) 2000A DISCONNECT SWITCH, NEMA 3R
 - (1) NON-AUTOMATIC TRANSFER SWITCH 2000A 4-POLE 480V WITH SOURCE AVAIL. LIGHTS (MTS)
 - (1) 2000A DISTRIBUTION BOARD
 - PROVIDE 1000A AND 600A CIRCUIT BREAKERS
 - CONDUITS AND CONDUCTORS AS SHOWN
 - GROUND NEUTRAL ON PORTABLE GENERATOR IN GENERATOR CONNECTION BOX.
 - CONNECT "PORTABLE GENERATOR DISCONNECT" TO EMERGENCY SIDE OF NEW 2000A MTS.
 - CONNECT EXISTING GENERATOR TO THE NORMAL SIDE OF THE NEW 2000A MTS.
 - CONNECT NEW MTS TO DISTRIBUTION BOARD.
 - CONNECT DISTRIBUTION BOARD CIRCUITS TO (2) EXISTING AUTOMATIC TRANSFER SWITCHES.
 - PROVIDE POWER TO INTEGRAL TRANSFORMERS FOR SPACE HEATER IN "PORTABLE GENERATOR DISCONNECT" VIA NEMA 3R DISCONNECT WITH CONDUITS AND CONDUCTORS FROM THE CIRCUIT FOR THE EXISTING BATTERY CHARGER. VERIFY CIRCUIT PRIOR TO INSTALLATION.
 - PROVIDE SWITCHABLE GENERATOR START SIGNAL FOR EITHER EXISTING GENERATOR OR PORTABLE GENERATOR.

ALL NEW CONDUIT IS TO BE INSTALLED OVERHEAD. VERIFY LOCATIONS WITH OWNER PRIOR TO INSTALLATION. CONDUITS SHOWN ARE DIAGRAMMATICAL. CONDUITS MAY RUN EXTERIOR OR INTERIOR, USE BEST PRACTICE.

PROVIDE 6" CONCRETE HOUSEKEEPING PAD UNDER ALL NEW FLOOR MOUNTED EQUIPMENT.



1 KEY PLAN
NO TO SCALE

SEAL
ATP ENGINEERING SOUTH, FL
SARASOTA, FLORIDA
ENGR. BUSINESS #8908
941-360-2181

REV #	DESCRIPTION	DATE


DESOTO CENTER
MANATEE COUNTY GOVERNMENT
600 301 BOULEVARD WEST
BRADENTON, FLORIDA 34205
IFAS# W1200286, WORK ASSIGNMENT #66

DRAWING TITLE:
**ELECTRICAL
EQUIPMENT LAYOUT
PORTABLE GENERATOR
CONNECTION**

FILE: M.C. DeSoto Center
JOB NO.: 2012.63
DATE: 08/23/2012
PLOT SIZE: 1:1
DRAWN BY: CMD
CHECKED BY: JDC
SHEET No.:
E1.0

SYSTEM NO. C-AJ-2002

May 18, 2005
 F Rating - 2 Hr
 T Ratings - 0 and 2 Hr
 L Rating at Ambient - 7 CFM/sq ft
 L Rating at 400 F - less than 1 CFM/sq ft (See Item 3C)
 W Rating - Class I (See Item 3)



SECTION A-A

1. FLOOR OR WALL ASSEMBLY - MIN 2-1/2 IN. (64 MM) THICK LIGHTWEIGHT OR NORMAL WEIGHT (100-150 PCF OR 1600-2400 KG/M3) CONCRETE. WALL MAY ALSO BE CONSTRUCTED OF ANY UL CLASSIFIED CONCRETE BLOCKS*. MAX DIAM OF CIRCULAR OPENING IS 6-1/2 IN. (165 MM).

SEE CONCRETE BLOCKS (CAZT) CATEGORY IN THE FIRE RESISTANCE DIRECTORY FOR NAMES OF MANUFACTURERS.

2. NONMETALLIC PIPE OR CONDUIT - NOM 4 IN. (102 MM) DIAM (OR SMALLER) SCHEDULE 40 SOLID CORE OR CELLULAR CORE, POLYVINYL CHLORIDE (PVC) PIPE FOR USE IN CLOSED (PROCESS OR SUPPLY) OR VENTED (DRAIN, WASTE OR VENT) PIPING SYSTEMS OR RIGID NONMETALLIC CONDUIT++ OR SDR 13.5 CHLORINATED POLYVINYL CHLORIDE (CPVC) PIPE FOR USE IN CLOSED (PROCESS OR SUPPLY) PIPING SYSTEMS. A MAX OF ONE PIPE OR CONDUIT IS PERMITTED IN THE FIRESTOP SYSTEM. EXCEPT AS NOTED IN ITEM B, THE PIPE OR CONDUIT SHALL BE CENTERED IN THE THROUGH OPENING. PIPE OR CONDUIT TO BE RIGIDLY SUPPORTED ON BOTH SIDES OF FLOOR OR WALL ASSEMBLY.

SEE RIGID NONMETALLIC CONDUIT (DZKT) CATEGORY IN THE UL ELECTRICAL CONSTRUCTION MATERIALS DIRECTORY FOR NAMES OF MANUFACTURERS.

3. FIRESTOP SYSTEM - THE HOURLY T RATINGS FOR THE FIRESTOP SYSTEM ARE DEPENDENT UPON THE FIRESTOP ORIENTATION (WALL OR FLOOR), THE SIZE OF THE NONMETALLIC PIPE OR CONDUIT, AND THE FLOOR THICKNESS, AS TABULATED BELOW:

ORIENTATION (a)	NOMINAL PIPE DIAMETER In. (mm)	ANNULAR SPACE In. (mm)	F RATING HR	T RATING HR
F(b)	1/2-2 (13-51 mm)	1/4-1 (6-25 mm)	2	0
F(b)	2-1/2, 3 (64, 76 mm)	1/2-1 (13-25 mm)	2	0
W,F	1/2-2 (13-51 mm)	1/4-1 (6-25 mm)	2	2
W,F	2-1/2, 3 (64, 76 mm)	1/2-1 (13-25 mm)	2	2
W,F	3-1/2, 4 (89, 102 mm)	3/4-1 (19-25 mm)	2	2

(a) W = WALL, F = FLOOR
 (b) MIN CONCRETE FLOOR THICKNESS IS 2-1/2 IN. (64 MM).
 THE DETAILS OF THE FIRESTOP SYSTEM SHALL BE AS FOLLOWS:


A. STEEL SUPPORT CLIPS - NOM 1 IN. (25 MM) WIDE BY NOM 0.019 IN. (0.5 MM) THICK (28 GAUGE) GALV STEEL STRIPS FIELD-FORMED INTO "Z"-SHAPE WITH HEIGHT OF Z-SHAPE EQUAL TO THE FLOOR THICKNESS AND WITH WIDTH OF BOTTOM (AS INSTALLED) LEG OF SUFFICIENT LENGTH TO SPAN ANNULAR SPACE. TOP (AS INSTALLED) LEG OF Z-SHAPE TO BE MIN 2 IN. (51 MM) LONG AND MAY OR MAY NOT BE SECURED TO TOP SURFACE OF FLOOR WITH MASONRY ANCHORS. AS AN ALTERNATE TO THE Z-SHAPE CLIPS, THE GALV STEEL STRIPS MAY BE FORMED INTO "L"-SHAPE WITH HEIGHT EQUAL TO 2 IN. (51 MM) AND WITH BOTTOM (AS INSTALLED) LEG OF SUFFICIENT LENGTH TO SPAN ANNULAR SPACE. CLIPS SECURED TO OUTERMOST WRAP STRIP LAYER WITH STEEL WIRE TIE PRIOR TO INSERTION IN THROUGH OPENING. MIN OF THREE STEEL SUPPORT CLIPS TO BE USED, SYMMETRICALLY LOCATED, WITH BOTTOM LEG OF CLIPS FLUSH WITH BOTTOM PLANE OF FLOOR. WHEN ANNULAR SPACE AROUND NOM 1/2 IN. TO 2 IN. (13 MM TO 51 MM) DIAM PIPE IN FLOOR ASSEMBLY IS 1/4 IN. TO 3/8 IN. (6 MM TO 10 MM), STEEL SUPPORT CLIPS ARE NOT REQUIRED.

B. FILL, VOID OR CAVITY MATERIALS* - WRAP STRIP - NOM 1/4 IN. (6 MM) THICK INTUMESCENT ELASTOMERIC MATERIAL FACED ON ONE SIDE WITH ALUMINUM FOIL, SUPPLIED IN 2 IN. (51 MM) WIDE STRIPS. NOM 2 IN. (51 MM) WIDE STRIPS TIGHTLY WRAPPED AROUND NONMETALLIC PIPE (FOIL SIDE EXPOSED) TO FILL ANNULAR SPACE AROUND PIPE. A MIN OF ONE LAYER OF WRAP STRIP IS REQUIRED FOR NOM 1/2 IN. TO 2 IN. (13 MM TO 51 MM) DIAM PIPES. A MIN OF TWO LAYERS OF WRAP STRIP IS REQUIRED FOR NOM 2-1/2 IN. AND 3 IN. (64 MM AND 76 MM) DIAM PIPES. A MIN OF THREE LAYERS OF WRAP STRIP IS REQUIRED FOR NOM 3-1/2 IN. AND 4 IN. (89 MM AND 102 MM) DIAM PIPES. EACH LAYER OF WRAP STRIP TO BE INSTALLED WITH BUTTED SEAM WITH BUTTED SEAMS IN SUCCESSIVE LAYERS STAGGERED. WRAP STRIP LAYERS SECURELY BOUND WITH STEEL WIRE OR ALUMINUM FOIL TAPE AND SLID INTO THROUGH OPENING SUCH THAT THE BOTTOM EDGES ARE FLUSH WITH THE BOTTOM PLANE OF THE FLOOR AND ARE RESTING ON THE STEEL SUPPORT CLIP LEGS. WHEN NOM 2 IN. TO 4 IN. (51 MM TO 102 MM) DIAM PVC PIPE IS USED IN MIN 4-1/2 IN. (114 MM) THICK CONCRETE FLOOR, THE PIPE MAY BE INSTALLED ECCENTRICALLY IN THE THROUGH OPENING (MIN ZERO CLEARANCE AT POINT CONTACT LOCATION) PROVIDED THAT (1) THE INSIDE DIAM OF THE THROUGH OPENING IS 1.3 TO 1.5 TIMES LARGER THAN THE OUTSIDE DIAM OF THE PIPE, (2) THE ANNULAR SPACE BETWEEN THE PIPE AND THE SIDES OF THE OPENING AT THE BOTTOM 2 IN. (51 MM) OF THE THROUGH OPENING IS COMPLETELY FILLED WITH WRAP STRIP LAYERS INSTALLED FOLLOWING THE CONTOUR OF THE PIPE AND (3) THE BOTTOM EDGES OF THE WRAP STRIP LAYERS ARE RELIABLY SUPPORTED BY "Z"-SHAPED STEEL SUPPORT CLIPS ANCHORED TO THE TOP SURFACE OF THE CONCRETE FLOOR. IN WALL ASSEMBLIES, THE WRAP STRIP LAYERS ON THE NONMETALLIC PIPE ARE TO BE INSTALLED IN THE SAME MANNER USED FOR FLOOR ASSEMBLIES, BUT SHALL BE INSTALLED SYMMETRICALLY ON BOTH SIDES OF THE WALL WITH THE EXPOSED EDGES OF THE WRAP STRIP LAYERS FLUSH WITH THE WALL SURFACES.

C. FILL, VOID OR CAVITY MATERIALS* - CAULK OR SEALANT - MIN 1/4 IN. (6 MM) DIAM CONTINUOUS BEAD APPLIED TO INSIDE WALLS OF THROUGH OPENING PRIOR TO INSTALLATION OF STEEL SUPPORT CLIPS AND/OR WRAP STRIP. CAULK BEAD TO BE RECESSED 1 IN. (25 MM) FROM THE BOTTOM PLANE OR FLOOR. IN WALL ASSEMBLIES, CAULK BEAD TO BE RECESSED 1 IN. (25 MM) FROM WALL SURFACE ON BOTH SIDES OF WALL. IN FLOOR ASSEMBLIES, A NOM 1/2 IN. (13 MM) THICK COATING OF CAULK IS TO BE APPLIED TO THE TOP EDGES OF THE WRAP STRIP LAYERS AND TO FILL ALL GAPS AT THE WRAP STRIP / CONCRETE INTERFACE. IN WALL ASSEMBLIES, THE EXPOSED EDGES OF THE WRAP STRIP LAYERS AND ALL GAPS AT THE WRAP STRIP / CONCRETE INTERFACE ON BOTH SIDES OF THE WALL TO BE COATED WITH THIN LAYER OF CAULK.

(NOTE: W RATING APPLIES ONLY WHEN FB-3000 WT SEALANT IS USED. CP 25WB+ NOT SUITABLE FOR USE WITH CPVC PIPES.)
 *BEARING THE UL CLASSIFICATION MARKING
 ++BEARING UL LISTING MARK

1 **CONCRETE WALL OR FLOOR PENETRATION DETAIL**
 E2.0 NOT TO SCALE



STANDARD COLORS:
 1. NORMAL POWER- BLACK BACKGROUND, WHITE LETTERS
 2. EMERGENCY POWER- RED BACKGROUND, WHITE LETTERING
 3. IN ADDITION TO THE FUNCTION LABELS, PROVIDE LABELS IDENTIFYING ALL "MAIN SERVICE LABEL DISCONNECTS"- RED BACKGROUND, WHITE LETTERING

5 **EQUIPMENT LABELING DETAIL**
 E2.0 NOT TO SCALE

FEEDER AND BRANCH CIRCUIT SCHEDULE


FEEDER BRANCH CIRCUIT DESIGNATION	COPPER CONDUCTOR THHN, THWN, & THWN-2		CONDUIT SIZE AND QUANTITY [QUANTITY IS 1, UNLESS NOTED IN ()]							
	PHASE	EQUIPMENT NEUTRAL GROUND	1P, 1N, 1G, 2P, 1G	2P, 1N, 1G, 3P, 1G	3P, 1N, 1G	3P, 2N, 1G	3P, 3N, 1G	3P, 1N, 2G		
F20	12	12	3/4"	3/4"	3/4"	3/4"	3/4"	3/4"	3/4"	
F30	10	10	3/4"	3/4"	3/4"	1"	1"	1"	1"	
F40-50	8	10	3/4"	1"	1"	1 1/4"	1 1/4"	1 1/4"	1 1/4"	
F60	6	10	1"	1 1/4"	1 1/4"	1 1/4"	1 1/4"	1 1/4"	1 1/4"	
F70-F80	4	8	1"	1 1/4"	1 1/4"	1 1/2"	1 1/2"	1 1/2"	1 1/2"	
F90-F100	3	8	1 1/4"	1 1/4"	1 1/2"	2"	2"	2"	2"	
F110	2	6	1 1/4"	1 1/2"	1 1/2"	2"	2"	2"	2"	
F125	1	6	1 1/2"	2"	2"	2"	2 1/2"	2"	2"	
F150	1/0	6	1 1/2"	2"	2"	2 1/2"	2 1/2"	2 1/2"	2 1/2"	
F175	2/0	6	2"	2"	2 1/2"	2 1/2"	3"	2 1/2"	2 1/2"	
F200	3/0	6	2"	2 1/2"	2 1/2"	3"	3"	3"	3"	
F225	4/0	4	2"	2 1/2"	3"	3"	3"	3"	3"	
F250	250	4	2 1/2"	3"	3"	3 1/2"	3 1/2"	3-1/2"	3-1/2"	
F300	350	4	3"	3"	3 1/2"	3 1/2"	4"	3 1/2"	3 1/2"	
F350	2/0	3	(2) 2"	(2) 2 1/2"	(2) 2 1/2"	(2) 2 1/2"	(2) 3"	(2) 2 1/2"	(2) 2 1/2"	
F400	3/0	3	(2) 2"	(2) 2 1/2"	(2) 2 1/2"	(2) 3"	(2) 3"	(2) 2 1/2"	(2) 2 1/2"	
F450	4/0	2	(2) 2"	(2) 2 1/2"	(2) 2 1/2"	(2) 3"	(2) 3"	(2) 3"	(2) 3"	
F500	250	2	(2) 2 1/2"	(2) 3"	(2) 3"	(2) 3"	(2) 3 1/2"	(2) 3 1/2"	(2) 3 1/2"	
F600	350	1	(2) 2 1/2"	(2) 3"	(2) 3"	(2) 3"	(2) 3 1/2"	(2) 3"	(2) 3"	
F800	300	1/0	(3) 2 1/2"	(3) 3"	(3) 3"	(3) 3 1/2"	(3) 3 1/2"	(3) 3 1/2"	(3) 3 1/2"	
F900	350	2/0	(3) 3"	(3) 3"	(3) 3 1/2"	(3) 3 1/2"	(3) 4"	(3) 3 1/2"	(3) 3 1/2"	
F1000	400	2/0	(3) 3"	(3) 3"	(3) 3 1/2"	(3) 3 1/2"	(3) 4"	(3) 4"	(3) 4"	
F1200	350	3/0	(4) 3"	(4) 3"	(4) 3 1/2"	(4) 3 1/2"	(4) 4"	(4) 4"	(4) 4"	
F1600	400	4/0	(5) 3"	(5) 3"	(5) 3 1/2"	(5) 3 1/2"	(5) 4"	(5) 4"	(5) 4"	
F2000	400	250	(6) 3"	(6) 3"	(6) 3 1/2"	(6) 3 1/2"	(6) 4"	(6) 4"	(6) 4"	
F2500	500	350	(7) 3"	(7) 3 1/2"	(7) 4"	(7) 4"	(7) 4"	(7) 4"	(7) 4"	
F3000	500	400	(8) 3"	(8) 3 1/2"	(8) 4"	(8) 4"	(8) 4"	(8) 4"	(8) 4"	
F3500	500	500	(10) 3"	(10) 3 1/2"	(10) 4"	(10) 4"	(10) 4"	(10) 4"	(10) 4"	

NOTES:
 1. DO NOT COMBINE NEUTRAL CONDUCTORS FOR ALL CIRCUITS. USE SEPARATE INDEPENDENT NEUTRAL CONDUCTORS FOR ALL CIRCUITS.

VOLTAGE DROP FOR 1φ, 20A BRANCH CIRCUITS


FEEDER SIZE TO USE	DISTANCE ALLOWED			
	120V	208V	277V	480V
F20	0 - 45 FEET	0 - 79 FEET	0 - 105 FEET	0 - 182 FEET
F30	45 - 72 FEET	79 - 126 FEET	105 - 168 FEET	182 - 290 FEET
F40-50	72 - 115 FEET	126 - 201 FEET	168 - 267 FEET	290 - 463 FEET
F60	115 - 183 FEET	201 - 318 FEET	267 - 423 FEET	463 - 733 FEET
F70-80	183 - 292 FEET	318 - 506 FEET	423 - 675 FEET	733 - 1169 FEET
F90-100	292 - 367 FEET	506 - 637 FEET	675 - 848 FEET	1169 - 1469 FEET
F110	367 - 464 FEET	637 - 804 FEET	848 - 1071 FEET	1469 - 1856 FEET
F125	464 - 584 FEET	804 - 1013 FEET	1071 - 1349 FEET	1856 - 2338 FEET
F150	584 - 738 FEET	1013 - 1279 FEET	1349 - 1703 FEET	2338 - 2951 FEET

NOTES:
 1. 20 A BRANCH CIRCUITS SHALL BE SIZED FOR VOLTAGE DROP. WIRE SIZES ARE NOT INDICATED ON THE DRAWINGS TO COMPENSATE FOR VOLTAGE DROP FOR THESE CIRCUITS. CONTRACTOR SHALL UTILIZE WIRE SIZE SHOWN ABOVE FOR DISTANCES LISTED ABOVE.
 2. VOLTAGE DROP WIRE SIZES WILL BE STRICTLY ENFORCED. CONTRACTOR SHALL SUBMIT A LIST OF CIRCUITS THAT WILL EXCEED THE DISTANCES ALLOWED AND INDICATE WIRE SIZE TO BE USED PRIOR TO ANY WIRE BEING INSTALLED.




- LEGEND
- ① EXISTING 8" CONCRETE BLOCK
 - ② 3"X 3"X 3/8" ANGLE 24" LONG
 - ③ 1/2" GALVANIZED BOLTS WITH NUTS AND LOCK WASHERS
 - ④ 3/8"- 316 STAINLESS STEEL PLATE DRILLED FOR ANGLE WALL MOUNTING 12" HIGH BY MIN. 24" WIDE
 - ⑤ 3"X 2 1/2" - 316 STAINLESS STEEL UNISTRUT PIPE SUPPORT WELDED TO PLATE 24" LONG.
 - ⑥ CAULK AND SEAL WITH RED BUTYL RUBBER CAULK

4 **WALL PIPE SUPPORT DETAIL**
 E2.0 NOT TO SCALE



3 **HOUSEKEEPING PAD DETAIL**
 E2.0 NOT TO SCALE



2 **WALL MOUNTED DISCONNECT DETAIL**
 E2.0 NOT TO SCALE

FL#52458

ATP ENGINEERING SOUTH, FL
 SARASOTA, FLORIDA
 ENGR. BUSINESS #8908
 941-360-2181

DATE: _____

REV#	DESCRIPTION

DESOTO CENTER
MANATEE COUNTY GOVERNMENT
 600 301 BOULEVARD WEST
 BRADENTON, FLORIDA 34205
 IFAS# W1200286, WORK ASSIGNMENT #66

FEEDER SCHEDULES AND DETAILS LAYOUT

DRAWING TITLE: FEEDER SCHEDULES AND DETAILS LAYOUT

FILE: M.C. DeSoto Center

JOB NO.: 2012.63

DATE: 08/23/2012

PLOT SIZE: 1:1

DRAWN BY: CMD

CHECKED BY: JDC

SHEET No.: **E2.0**