NO.	FDOT ITEM NO.	DESCRIPTION	UNIT	QUANTITY
1	0101-1	Mobilization	LS	1
2	0102-1	MOT	LS	1
3	0104-6	Sand bags	LF	264
4	0104-10-3	Staked Silt Fence, Type III	LF	1,382
5	0104-11	Floting Turbidity Barrier Type III	LF	210
6	0110-1-1	Clearing & Grubbing	ACRE	4.00
A2 7	0110-3	Removal of Existing Structure (Rip-Rap)	LS	1
8	0120-1	Regular Excavation (Road, Pond & Parking)	CY	1,869
9	0120-1	Regular Excavation (Boardwalk & Sidewalk)	CY	67
10	0120-6	Embankment (Roadwork, Pond And Parking)	CY	1,311
11	0120-6	Embankment (Boardwalk & Sidewalk)	CY	85
A2 12	0120-72	9" Gravel Fill (Not To Exceed 1" Dia.)	CY	54
A2 13	0121-70	Concrete Slurry (Flowable Fill) 1"	CY	10
14	0160-4	12" Type B Stabilization (LBR 40)	SY	2,490
A2 15	0285-704	6" Bank Run Shell (Fill Parking Area)	SY	1,973
16	0285-705	14" Optional Base Group 5: Crushed Concrete	SY	205
17	0285-706	10" Optional Base Group 9: Limerock LBR 100	SY	2,272
18	0334-1-13	2" Superpave Asphalt Concrete, Traffic C, SP 12.5	TN	226
19	0337-7-32	1" Asphalt Concrete FC-9.5 , Traffic C, Rubber	TN	114
20	0400-2-5	Concrete Class II	CY	4
21	0415-1-5	Reinforcing Steel	LB	600.00
22	0425-1549	Ditch Bottom Inlet, Type D Modified	EA	3
23	0425-3-41	Junction Box, Drainage P-7	EA	1
24	0430-174-218	14"x23" ERCP	LF	200
25	0455-2	Timber Piling (10 in. diameter)	LF	784.00
	0470-1	Timber - 2x4 (Bracing/Blocking)	MB	0.748
A2		Timber - 2x6 (Railing/Decking)	MB	2.888
		Timber - 2x12 (Joists/Pile Caps)	MB	2.782
26		Timber - 4x4 (Posts)	MB	0.628
27	0514 -71 -2	Plastic Filter Fabric	SY	819
28	0515-2302	Pedestrian, Bicycle Railing, Aluminun Only,54" Picket Rail	LF	340
29	0520-2-4	Concrete Curb,Type D	LF	215
30	0520-2-9	Concrete Curb,Type X (Special)	LF	52
31	0522-1	6' Concrete Sidewalk	SY	332
32	0530-3-3	RipRap - Rubble	TN	1.5
A2 33	0530-3-4	Riprap , Rubble F&I Ditch Lining	TN	7
34	0542-70	Conc. Bumper Guard	EA	31
35	0550-10-212	Fencing (9 Gauge Galv. Wire)	LF	570
36	0570-1-2	Performance turf, sod	SY	5,752
37	0430-982-625	Mitered End Section, RCP Elliptical	EA	2
38	700-20-11	Stop sign (R1-1)	AS	1
39	700-20-11	Handicap sign 12" X 18"	AS	2
40	706-3	Retro-Reflective Pavement Markers	EA	109
41	711-11-111	Thermoplastic, Standard , White, Solid, 6"	NM	0.53
42	711-11-125	Thermoplastic, Standard , White, Solid, 24"	LF	24
43	711-11-131	Thermoplastic, Standard , White, Skip, 6" 6'-10'	GM	0.11
44	711-11-151	Thermoplastic, Standard , White, Skip, 6" 2'-4' Skip	LF	148
45	711-11-170	Thermoplastic, Standard , White, Arrow	EA	10
46	711-11-211	Thermoplastic, Standard , Yellow, Solid, 6"	NM	0.41
47	711-11-224	Thermoplastic, Standard , Yellow, Solid, 18"	LF	153
48	711-17	Thermoplastic, Remove Existing Thermoplastic Pavement Markings	SF	2,000
A2 49	MC1	Simpson HU 210 (or Equal)	EA	120
A2 50	MC2	Simpson DTT2 (or Equal)	EA	140
A2 51	MC3	Simpson LTT19 (or Equal)	EA	4
A2 52	MC4	Simpson ABE44 (or Equal)	EA	6
A2 53	MC5	Simpson H4 (or Equal)	EA	12
A2 54	MC6	1/2" SS304 Hilti Hit-HY150 Adhesive Anchors	EA	10
A2 55	MC7	Fastening Hardware Remainder (Bolts, Screws, Nails...)	LB	130
56	MC8	4x4 Wooden Parking stops 8' long	EA	34

MANATEE COUNTY
PUBLIC WORKS
DEPARTMENT

PERICO BAYOU PARKING AREA
ADDENDUM 2
QUANTITY SHEET

REVISION		DATE
	BY	DATE
SURVEYED	HYATT	10/09
DESIGNED		12/09
DRAWN		12/09
CHECKED		12/09

SCALE: N.T.S.

SEAL
APPROVED BY:

SIAMAK SHAHMIRZAD, P.E.
STATE OF FLORIDA P.E. # 42905
MANATEE COUNTY GOVERNMENT
PUBLIC WORKS DEPARTMENT
1112 26TH AVENUE EAST
BRADENTON, FL 34208

DATE

SHEET 7 OF 40

COPYRIGHT 2003 © MANATEE COUNTY GOVERNMENT