

MEMORANDUM



To: All Interested Bidders

Date: May 1, 2015

Subject: IFB#15-1244-OV, Fiddlers Green Lift Station
and Force Main Replacement
1312 91st St. Ct., N.W., Bradenton, FL
Project No.: 402-5133080
ADDENDUM #2

Bidders are hereby notified that this Addendum shall be acknowledged on page 00300-1 of the Bid Form and made a part of the above named bidding and contract documents. Bids submitted without Acknowledgement of the Addendum will be considered incomplete.

The following items are issued to add to, modify, and clarify the bid and contract documents. These items shall have the same force and effect as the original bidding document, and cost involved shall be included in the bid prices. Bids to be submitted on the specified bid date, shall conform to the additions and revisions listed herein.

The deadline to submit all inquiries concerning interpretation, clarification or additional information pertaining to this bid was April 20, 2015 at 5:00 pm. This deadline has been established to maintain fair treatment for all potential bidders, while maintaining the expedited nature of the Economic Stimulus that the contracting of this work may achieve.

Bidders Note 1:

Revised Bid Forms (A & B) revising the quantities of item nos. 13 and 14.
(4 total pages attached)

Bidders Note 2:

Engineer's clarification to Addendum No. 1:

Question 1: Response 4, if we are cutting in a new tee, what is the distance to the nearest upstream valve? We need to know the volume of raw sewage we will have to handle when we cut into the existing force main.

Response 1: The nearest upstream valve is approximately 740 LF to the west at the existing lift station. Please note, the existing 6" force main has a total length of approximately 3,653 LF. From the record drawings, the high point of the force main is approximately 2,665 LF downstream from the lift station. If the record drawings are 100% accurate, the proposed cut-in tee is at the first 750 LF of force main, this means there could be approximately 2,665 LF of existing 6" force main to generate raw sewage to be handled.

(Record Drawing of Sewer & Water Plan for the Loop T233 attached, 8 total pages)

Financial Management
Purchasing Division
1112 Manatee Ave W Suite 803, Bradenton, FL 34205
Phone number: (941)749-3014

May 1, 2015

IFB#15-1244-OV, Fiddlers Green Lift Station
and Force Main Replacement (Page 2 of 2)

ADDENDUM #2

Question 2: Response 8, does not directly answer the question regarding telemetry equipment, but if the current existing control panel houses the existing telemetry equipment and if we are to just relocate the existing control panel, then we will not need a new pump control panel correct? Plan Sheet 7 of 11, LIFT STATION PROPOSED CONDITION detail, shows a NEW CONTROL PANEL, are we to furnish and install a new pump control panel?

Response 2: Plan sheet 7 of 11 has been revised and is attached. The contractor shall be responsible for relocating the existing control panel, install new conduit and wiring to the wet well. The County will relocate the antenna after the contractor has relocated the control panel, the County shall be responsible for telemetry equipment and associated wiring. The County shall connect all wiring inside the relocated control panel.

Question 3: Response 9, if we are to exclude the cost of new pumps, what about base elbows, guide rail system, floats, lifting cables, hatch cover, etc., are we to furnish these?

Response 3: Yes, furnish and install. The contractor shall be responsible for furnishing all items associated with the new above ground lift stations and all items mentioned above with the following exceptions: the County will furnish and install the actual pumps, relocate the antenna & telemetry equipment and associated wiring; the Contractor shall relocate the existing control panel, install new conduit and wiring to wet well. Contractor shall furnish and install all items required to have a fully functioning, operating lift station, (lift chains are required, not cables). New landscaping and fencing will not be required.

If you have submitted a bid prior to receiving this addendum, you may request in writing that your original sealed bid be returned to your firm. All sealed bids received will be opened on the date stated.

Bids will be received at the Manatee County Purchasing Division, 1112 Manatee Avenue West, Suite 803, Bradenton, FL 34205 **May 12, 2015 at 3:00 PM.**

Sincerely yours,



Melissa M. Wendel, CPPO, Purchasing Official *for*
Manatee County Purchasing Division
Ov\Attachments via pdf:

Revised Bid Forms (A & B) (4 total pages)

Revised Plans (REF: Sheet 7, Pump information updated, 04/30/2015) (1 total pages)

Record Drawing of Sewer & Water Plan for the Loop (T233) (8 total pages)

BID FORM SECTION 00300 / SUBMIT IN DUPLICATE

INVITATION FOR BID #15-1244-OV / Addendum #2

Fiddlers Green Lift Station and Force Main Replacement

1312 91st St. Ct., N.W., Bradenton, FL / Project No.: 402-5133080

(Bid "A" - Based on Completion Time of 150 Calendar Days)

ITEM NO.	DESCRIPTION	U/M	QTY	UNIT PRICE	EXTENDED PRICE
	FURNISH AND INSTALL FORCE MAIN				
1	CURB	LF	30	\$	\$
2	ASPHALT PAVEMENT RESTORATION (BASE & 1 1/2" S-III)	SY	15	\$	\$
3	ASPHALT PAVEMENT RESTORATION (MILL & RESURFACE)	SY	235	\$	\$
4	SIDEWALK, CONCRETE (4" MIN. THICK)	SY	17	\$	\$
5	DRIVEWAY, CONCRETE (6" MIN. THICK) LIFT STATION	SY	20	\$	\$
6	SOD	SY	42	\$	\$
*7	ABANDON EXISTING 3" FM, GROUT FILL (Addendum #1)	CY	12	\$	\$
8	REMOVE EXISTING VALVE	EA	2	\$	\$
*9	4" PVC C-900 (DR-18), DIRECT BURY (Addendum #1)	LF	12	\$	\$
10	4" HDPE, DR-11, HDD	LF	1,100	\$	\$
11	FITTINGS, DI	LB	255	\$	\$
12	4" MJ TO HDPE PIPE ADAPTERS	EA	4	\$	\$
*13	4" GATE VALVE, MJ (Addendum #2) (Revise qty from 1 to 2)	EA	2	\$	\$
*14	6" X 4" Cut-In-Tee (Addendum #2) (Revise qty from 2 to 1)	EA	1	\$	\$
	SUBTOTAL CONSTRUCTION COST, FURNISH AND INSTALL FORCE MAIN				\$

BIDDER: _____

AUTHORIZED SIGNATURE: _____

00300-2
 Fiddlers Green Lift Station
 and Force Main
 Bid "A", Based on 150
 calendar completion time
 Addendum #2

BID FORM SECTION 00300 / SUBMIT IN DUPLICATE**INVITATION FOR BID #15-1244-OV / Addendum #2****Fiddlers Green Lift Station and Force Main Replacement****1312 91st St. Ct., N.W., Bradenton, FL / Project No.: 402-5133080****(Bid "A" - Based on Completion Time of 150 Calendar Days)**

ITEM NO.	DESCRIPTION	U/M	QTY	UNIT PRICE	EXTENDED PRICE
	FURNISH AND INSTALL LIFT STATION				
15	EXISTING LIFT STATION - COMPLETE ABANDONMENT & REMOVAL	LS	1	\$	\$
16	NEW 6' DIA. WET WELL AND ABOVE-GROUND VALVE ASSEMBLY	LS	1	\$	\$
17	BY-PASS PUMPING	LS	1	\$	\$
	SUBTOTAL CONSTRUCTION COST, FURNISH AND INSTALL LIFT STATION				\$
18	MOBILIZATION	LS	1		\$
19	MISCELLANEOUS WORK & CLEANUP	LS	1		\$
20	RECORD DRAWINGS	LS	1		\$
	TOTAL BASE BID - Based on Completion Time of 150 Calendar Days				\$
21	Contract Contingency Work (Used only with County Approval)	10% OF TOTAL BASE BID			\$
	TOTAL AWARD OFFER FOR BID with Contract Contingency - Bid "A" Based on a Completion Time of 150 Calendar Days (Addendum #2)				\$

BIDDER: _____

AUTHORIZED SIGNATURE: _____

00300-3
 Fiddlers Green Lift Station
 and Force Main
 Bid "A", Based on 150
 calendar completion time
 Addendum #2

BID FORM SECTION 00300 / SUBMIT IN DUPLICATE
INVITATION FOR BID #15-1244-OV / Addendum #2
Fiddlers Green Lift Station and Force Main Replacement
1312 91st St. Ct., N.W., Bradenton, FL / Project No.: 402-5133080
(Bid "B" - Based on Completion Time of 210 Calendar Days)

ITEM NO.	DESCRIPTION	U/M	QTY	UNIT PRICE	EXTENDED PRICE
	FURNISH AND INSTALL FORCE MAIN				
1	CURB	LF	30	\$	\$
2	ASPHALT PAVEMENT RESTORATION (BASE & 1 1/2" S-III)	SY	15	\$	\$
3	ASPHALT PAVEMENT RESTORATION (MILL & RESURFACE)	SY	235	\$	\$
4	SIDEWALK, CONCRETE (4" MIN. THICK)	SY	17	\$	\$
5	DRIVEWAY, CONCRETE (6" MIN. THICK) LIFT STATION	SY	20	\$	\$
6	SOD	SY	42	\$	\$
*7	ABANDON EXISTING 3" FM, GROUT FILL (Addendum #1)	CY	12	\$	\$
8	REMOVE EXISTING VALVE	EA	2	\$	\$
*9	4" PVC C-900 (DR-18), DIRECT BURY (Addendum #1)	LF	12	\$	\$
10	4" HDPE, DR-11, HDD	LF	1,100	\$	\$
11	FITTINGS, DI	LB	255	\$	\$
12	4" MJ TO HDPE PIPE ADAPTERS	EA	4	\$	\$
*13	4" GATE VALVE, MJ (Addendum #2) (Revise qty from 1 to 2)	EA	2	\$	\$
*14	6" X 4" Cut-In-Tee (Addendum #2) (Revise qty from 2 to 1)	EA	1	\$	\$
	SUBTOTAL CONSTRUCTION COST, FURNISH AND INSTALL FORCE MAIN				\$

BIDDER: _____

AUTHORIZED SIGNATURE: _____

00300-4
Fiddlers Green Lift Station
and Force Main
Bid "B", Based on 210
calendar completion time
Addendum #2

**BID FORM SECTION 00300 / SUBMIT IN DUPLICATE
INVITATION FOR BID #15-1244-OV / Addendum #2
Fiddlers Green Lift Station and Force Main Replacement
1312 91st St. Ct., N.W., Bradenton, FL / Project No.: 402-5133080**

(Bid "B" - Based on Completion Time of 210 Calendar Days)

ITEM NO.	DESCRIPTION	U/M	QTY	UNIT PRICE	EXTENDED PRICE
	FURNISH AND INSTALL LIFT STATION				
15	EXISTING LIFT STATION - COMPLETE ABANDONMENT & REMOVAL	LS	1	\$	\$
16	NEW 6' DIA. WET WELL AND ABOVE-GROUND VALVE ASSEMBLY	LS	1	\$	\$
17	BY-PASS PUMPING	LS	1	\$	\$
	SUBTOTAL CONSTRUCTION COST, FURNISH AND INSTALL LIFT STATION				\$
18	MOBILIZATION	LS	1		\$
19	MISCELLANEOUS WORK & CLEANUP	LS	1		\$
20	RECORD DRAWINGS	LS	1		\$
	TOTAL BASE BID - Based on Completion Time of 150 Calendar Days				\$
21	Contract Contingency Work (Used only with County Approval)	10% OF TOTAL BASE BID			\$
	TOTAL AWARD OFFER FOR BID with Contract Contingency - Bid "B" Based on a Completion Time of 210 Calendar Days (Addendum #2)				\$

BIDDER: _____

AUTHORIZED SIGNATURE: _____

00300-5
Fiddlers Green Lift Station
and Force Main
Bid "B", Based on 210
calendar completion time
Addendum #2