



Financial Management Department
Purchasing Division
1112 Manatee Ave W Suite 803
Bradenton, FL 34205
Phone: (941) 749-3074
www.myanatee.org

Email

March 15, 2016

TO: All Interested Bidders

SUBJECT: Invitation for Bid #16-1225DC
Master Lift Station (MLS) 12A Wetwell Rehabilitation
ADDENDUM #2

Bidders are hereby notified that this Addendum shall be acknowledged on the Bid Form and made a part of the above named bidding and contract documents.

1. Bid Opening is changed to March 24, 2016 at 3:30 P.M., same location.
2. The flow meter installation states to install the conduit from the new vault to the MLS building.

Question: Is the electrician supposed to pull and terminate wiring? If so where is the source to pull from? Does the county want a remote reader output for the flow meter? If so where does it get mounted/located?

Response: The Contractor shall install all conduit and wiring. The County will land the 4-20ma output to SCADA.

Conduit and control cable from the mag meter to the control head.

Conduit and 110vac to the breaker panel next to bathroom.

Conduit and shielded two pair cable to telemetry panel to provide 4-20 ma to SCADA.
Install remote meter on wall next to ATS switch gear (pictures available).

Conduit will be needed from the meter vault to a close proximity next to the telemetry cabinet to the flow meter control head. The control head supplies power to the mag meter in the ground. The control head that will be located inside the building next to the telemetry cabinet will then need 110vac conduit to the break either installed in out telemetry cabinet or MCC breaker panel. The last conduit will come out of the flow meter control head to the telemetry cabinet which will supply the 4-20mA telemetry output to our SCADA system.


Placement of the flow meter control head is not a problem as long as it is easily visible to the operators.

March 15, 2016

If you have submitted a bid prior to receiving this addendum you may request in writing that your original, sealed bid be returned to your firm. All sealed bids received will be opened on the date stated.

Bids will be received at Manatee County Purchasing, 1112 Manatee Avenue West, Suite 803, Bradenton, Florida 34205 until **March 24, 2016 at 3:30 P.M.**

Sincerely,



for Melissa M. Wendel, CPPO
Purchasing Official

/dcr

Attachments: Plan Sheet 2 (Add flow meter conduit and additional call-outs)