


MANATEE COUNTY GOVERNMENT

INTENT TO AWARD

ITQ NO./TITLE	18-R069400GL/Repair of Boardwalks in the Preserves	DATE POSTED	BCC AF 10/29 DS N/A	MCC N/A MBC N/A
PROCUREMENT REPRESENTATIVE	Grace E Lux	PROJECTED AWARD DATE	October 29, 2018	
DEPARTMENT/DIVISION	Financial Management/Procurement	AUTHORIZED BY DATE	 10/29/18 Chris Daley, Procurement Manager	

NOTICE OF INTENT TO AWARD

The Manatee County Procurement Division provides notice of its intent to award a contract with Billy Cahoon, LLC for the provision of Repair of Boardwalks in the Preserves .

ENABLING/REGULATING AUTHORITY

Manatee County Procurement Ordinance, Sec 2-26.

BACKGROUND/DISCUSSION

The Work required for this Invitation to Quote includes the furnishing of all equipment, labor, materials, supplies, and other components necessary to provide repairs or replacement of boardwalk boards and fasteners for sections of the boardwalk in the Robinson, Leffis Key and Emerson Point Preserves. .

The solicitation was advertised on September 18, 2018 on the Manatee County website and emailed directly to eight (8) firms thought to have the capability, cpacity, and experience to provide the necessary labor and material to perform the work that was the subject of this solicitation. Responses were received from the following firms:

Billy Cahoon, LLC, Bradenton, FL

EVALUATION RESULTS SUMMARY:

Billy Cahoon, LLC was the lowest responsive, responsible bidder(s). A bid tabulation of the results is attached to this Notice of Intent to Award.

The Procurement Division and the Parks & Natural Resources Department recommend award to Billy Cahoon, LLC .

ATTACHMENTS (List in order of attached)	Bid Tabulation	NAME OF FUNDING SOURCE	Infrastructure Sales Tax
COST	\$155,272.88	FUNDS VERIFIED	Yes

ITQ 18-R069400GL
REVISED ATTACHMENT C
ADDENDUM 1
BID FORM FOR
CONTRACT DEVELOPMENT FOR REPAIRS OF BOARDWALKS IN PRESERVES
EMERSON POINT BOARDWALK REPAIR

	Bid price
Task 1 Replace hardware Bridge 1 & 3	\$ 17,083.72
Task 2 Replace Guard rail Bridge 1 & 3	\$ 13,204.80
Task 3 Rebuild/replace guard rail/hand rail on tower stairs	\$ 12,298.04
Task 4 Replace tower platform decking and subfloor structure	\$ 12,688.67

Bidder: Billy Cahoon, LLC

Authorized Signature: 

Date: 10/18/2018

ITQ 18-R069400GL
REVISED ATTACHMENT C
ADDENDUM 1
BID FORM FOR
CONTRACT DEVELOPMENT FOR REPAIRS OF BOARDWALKS IN PRESERVES
LEFFIS KEY BOARDWALK REPAIR

	Bid price
Task 1: Replace all galvanized hardware and damaged wood on Boardwalk 1(165') and dispose of construction debris at designated disposal area.	\$ <u>16,272.30</u>
Task 2: Replace all galvanized hardware and damaged wood on Boardwalk 2(140')	\$ <u>13,806.80</u>
Task 3: Replace all galvanized hardware and damaged wood on Boardwalk 3(230')	\$ <u>22,682.60</u>

Bidder: Billy Cahoon, LLC

Authorized Signature: 

Date: 10/18/2018

ITQ 18-R069400GL
REVISED ATTACHMENT C
ADDENDUM 1
BID FORM FOR
CONTRACT DEVELOPMENT FOR REPAIRS OF BOARDWALKS IN PRESERVES
ROBINSON BOARDWALK REPAIR

Bid price

Task 1: (540' boardwalk): Making such preparations as are necessary including removing large stainless carriage bolts and rails to remove deck boards. Remove 3"x6" deck boards and flip 180 degrees to ensure less weathered surface is facing upwards while minimizing damage to railing structure. Boards should be re-fastened with minimum 4" #12 stainless steel Alloy 304, A2 wood screws using the same number as are removed and sunk to be beneath the walking surface of the wood. Also, replacement of 3"x8"x8' cross spars(x50) that brace boardwalk pilings including reinstallation of piling segment spacer while re-using stainless bolts.

\$ 30,547.80

Task 2: (150' bridge): Making such preparations as are necessary including removing large stainless carriage bolts and rails to remove deck boards. Remove 3"x6" deck boards and flip 180 degrees to ensure less weathered surface is facing upwards while minimizing damage to railing structure. Boards should be re-fastened with minimum 4" #12 stainless steel Alloy 304, A2 wood screws using the same number as are removed and sunk to be beneath the walking surface of the wood.

\$ 8,485.50

ITQ 18-R069400GL
REVISED ATTACHMENT C
ADDENDUM 1

**BID FORM FOR
CONTRACT DEVELOPMENT FOR REPAIRS OF BOARDWALKS IN PRESERVES
ROBINSON BOARDWALK REPAIR**

<p>Task 3: (95' bridge): Making such preparations as are necessary including removing large stainless carriage bolts and rails to remove deck boards. Remove 3"x6" deck boards and flip 180 degrees to ensure less weathered surface is facing upwards while minimizing damage to railing structure. Boards should be re-fastened with minimum 4" #12 stainless steel Alloy 304, A2 wood screws using the same number as are removed and sunk to be beneath the walking surface of the wood.</p>	<p>\$ <u>5,374.15</u></p>
<p>Task 4(50' Bridge): Making such preparations as are necessary including removing large stainless carriage bolts and rails to remove deck boards. Remove 3"x6" deck boards and flip 180 degrees to ensure less weathered surface is facing upwards while minimizing damage to railing structure. Boards should be re-fastened with minimum 4" #12 stainless steel Alloy 304, A2 wood screws using the same number as are removed and sunk to be beneath the walking surface of the wood. Also, replacement of 3"x8"x8' cross spars(x50) that brace boardwalk pilings including reinstallation of piling segment spacer while re-using stainless bolts.</p>	<p>\$ <u>2,828.50</u></p>

Bidder: Billy Cahoon, LLC

Authorized Signature: 

Date: 10/18/2018