



1112 Manatee Ave. West  
Bradenton, FL 34205  
[purchasing@mymanatee.org](mailto:purchasing@mymanatee.org)

## Solicitation Addendum

---

**Addendum No.:** 2  
**Solicitation No.:** 19-TA002974CD  
**Project No.:** 6076861  
**Solicitation Title:** Intersection Improvements, Cortez Road at 43<sup>rd</sup> Street West  
**Addendum Date:** May 30, 2019  
**Procurement Contact:** Chris Daley; [chris.daley@mymanatee.org](mailto:chris.daley@mymanatee.org)

---

**IFBC NO. 19-TA002974CD IS AMENDED AS SET FORTH HEREIN. RESPONSES TO QUESTIONS POSED BY PROSPECTIVE BIDDERS ARE PROVIDED BELOW. THIS ADDENDUM IS HEREBY INCORPORATED IN AND MADE A PART OF IFBC NO. 19-TA002974CD.**

**Replace:**

**APPENDIX I, BID PRICING FORM, PAGES APPENDIX I-2 THRU APPENDIX I-5**

Replace Appendix I, Bid Pricing Form, pages Appendix I-2 thru Appendix I-5 with REVISED pages Appendix I-2 thru Appendix I-5 issued with this Addendum 2. NOTE: Quantities for signing and marking bid items 25 and 26 were adjusted to match the quantities shown in the revised Signing and Marking Plans issued with Addendum 1.

**ENGINEER'S CLARIFICATIONS**

Coordination with SUNTRUST bank is needed before the construction for the removal of three parking spaces in county ROW. Please refer to Sheet 7.

**QUESTIONS AND RESPONSES:**

**Q1. Reference plan sheet 12, the note that reads "EXISTING CONCRETE BOX TO BE RELOCATED", what is this box and where is it being relocated to?**

R1. This is an abandoned pull box per Traffic Operation Dept. The Plan notes shall be changed as "EXISTING CONCRETE BOX TO BE REMOVED". Payment for this item is under Clearing & Grubbing.

**Q2. Reference plan sheet 7, at approximately station 200+80, the 2' METAL GUARDRAIL, what is the disposition of this guardrail, is it to be removed and disposed of or removed and reinstalled?**

R2. The Guardrail is out of the construction limit and to remain in place.

**Q3. Reference plan sheet 7, what is the extent of the clearing at the wooded area, back to the east right-of-way line or what? Please define.**

R3. The clearing limit shall follow the limit of construction as shown in the cross sections. Tree and bushes in the clear zone (6' for RRR project) shall also be removed.

**Q4. Reference plan sheet 8, it appears that a portion of the improvement work will be in the F.D.O.T. R/W, shouldn't there be an asphalt paving and base scenario for work in the F.D.O.T. right-of-way?**

R4. A portion of the work is in the FDOT right of way. The paving limit shall per the END PROJECT labeling on the Plan.

---

NOTE: Items that are ~~struck through~~ are deleted. Items that are underlined have been added or changed. All other terms and conditions remain as stated in the IFBC.

#### **End of Addendum**

#### **INSTRUCTIONS:**

Receipt of this addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the response being deemed non-responsive.

AUTHORIZED FOR RELEASE: Theresa Webb, Procurement Official